APPENDIX NO. 11—1897.

THE DUPLEX BASE APPARATUS, AND DIRECTIONS FOR ITS USE IN THE FIELD.

By WILLIAM EIMBECK, Assistant.

The Duplex is a bimetallic contact-slide apparatus consisting of two bars of precisely similar construction, each 5 metres in length.

It was constructed in the instrument shop of the Survey, after plans and specifications submitted by Assistant William Eimbeck. These plans and specifications were originally submitted in 1885, but no action was then taken. On invitation by a circular issued by the office in 1887, to consider the subject of a new 5-metre primary base apparatus, the original duplex scheme was resubmitted with the suggestion that it be referred for criticism of its merits to expert geodesists and others interested. To this suggestion the office acceded, and subsequently a number of copies of a preliminary report were sent out by the office. In reply several interesting and comprehensive letters were received, notably from Profs. J. B. Johnson, Charles A. Schott, R. S. Woodward, George Davidson, Simon Newcomb, and Dr. G. B. Gould; also from Gen. C. B. Comstock and Mr. M. S. Wheeler, assistant in the United States Corps of Engineers, Prof. J. H. Gore, Dr. Westphal, editor of Instrumentenkunde, et al. On the whole the criticisms of these eminent men were in every way encouraging. It was conceded that the principle was sound, and that if the construction should succeed in securing and maintaining equality in the mean temperatures of the components, the duplex scheme would unquestionably prove fruitful in good results.

The test of the principle by actual trial was favored and urged. Accordingly, in 1890, after a thorough inquiry into its merits, Dr. T. C. Mendenhall, then superintendent, authorized the construction of the new apparatus in accordance with the plans and specifications submitted as stated. It is proper, however, to remark in this connection that the detail in construction was in part worked out and designed by Mr. E. G. Fischer, chief mechanician of the Survey, to whose ingenuity, professional skill, and interest in the success of the duplex is also due the splendid workmanship in which it is executed.

As a matter of office routine, and as far as seemed expedient, every detail of construction was submitted to and passed upon by the Instrument Board of the Survey before execution was authorized. Shortly after completion of the apparatus, early in 1893, it was placed on exhibition at the World's Columbian Exposition at Chicago and later the Geodetic Conference, which convened at the office of the Survey in January, 1894, examined it and recommended that it be given a thorough and careful trial as soon as practicable. (See Proceedings Geodetic Conference, Appendix No. 9, p. 234, Coast and Geodetic Survey Report for 1893.)

The salient characteristics which distinguish the duplex from other bars are: (1) Its two disconnected tubular components (brass and steel); (2) the reversibility of the components; (3) its double metallic truss tubes, the inner one of which containing the components is reversible on its axis; (4) indication of the accumulated difference of length of the measures from the steel and brass components.

Excepting one component, which is of steel, the apparatus is wholly constructed of brass tubing of the smallest dimensions consistent with requisite strength and rigidity. Each one of the bars weighs 118 pounds. The flexure is constant.

The object of the introduction of these features of construction, especially the interchange of position of the components by reversal, is to promote uniformity in the distribution of heat, but particularly to insure equality in the mean thermic state of the components.

Inasmuch as the length of a metallic rod is at all times the surest index of its thermal condition, the preservation of equality in the mean temperatures of the components is unquestionably *the* important requisite upon which the efficiency of every bimetallic device mainly depends.

The duplex, although a bimetallic apparatus, is not a Borda thermometer. Having its components fixedly connected, the Borda device is a real thermometer, capable of indicating real temperature at all times; the duplex, on the other hand, having *disconnected* components, is not a thermometer, and does not therefore indicate actual temperatures at any time. Knowledge of the actual temperatures of the components is without importance. The total relative displacement or shift of the components with respect to one another during a measurement is all that is required for the reduction of the results of measure to the standard. As a composite apparatus the action of the duplex may therefore appropriately be considered without reference to temperatures, either real or inferential. It deals solely with expansions, the mechanically integrated differences in the lengths of its components and their ratio to one another, as more particularly explained further on.

Among further advantages which the duplex is assumed to possess over other bars may be mentioned the independence of its duplex and thermometric constants, and the uniformity of the projections of its steel and brass components from the truss tubes, which latter circumstance insures equality in their exposure and protection. Uniformity in the protection or exposure of the components from end to end is of the utmost importance in every bimetallic apparatus, and must be scrupulously satisfied if equality in their thermic states is to obtain at all times.

Moreover, if simultaneously used as a bimetallic and a thermometric apparatus, as was done in the Salt Lake base measure, the duplex will furnish three practically independent results from a single measure, which must and will agree if the constants experimentally derived from both the field and comparator measures are consistent. These results are: (1) The thermic measure from the steel component; (2) the thermic measure from the brass component (both in connection with the temperatures derived from the mercurial thermometers); (3) the differential expansions or duplex measure obtained from the steel and brass components conjointly. But the accordance of these three results proves not only the satisfactory behavior of the apparatus, but also the reliability of the execution of the measurement.

The following diagram of the duplex bar shows the arrangement of the components and the principal features of construction:



Fig. 1

The parallel components lie side by side in a plane normal transversely to the vertical plane, their centers 1⅛ inches or 2·80 centimetres apart.

For dimensions and detail of construction of the bars, see plates 3, 4, 5, and 6.

Each of the components is provided in the usual manner with a contact slide and screw, etc.* The components consist respectively of closed steel and brass tubing three-fourths of an inch in diameter, and cross-dimensioned as regards thickness of their walls, with due regard to the

* For full description of the contact slide, aligning telescope, and the trestles, etc., see account of "Perfected form of Contact-Slide Base Apparatus," by J. E. Hilgard, Appx. 17, Coast and Geodetic Survey Report for 1880, and account of Primary Base Apparatus, by C. A. Schott, Appx. 7, Coast and Geodetic Survey Report for 1892.

specific heat and conductivity of these metals. Their outer surfaces were nickel-plated in order to insure in each equal power for the absorption and emission of heat. The selection of steel and brass resulted from considerations of economy in construction, the ratio of the expansions of these metals being judged sufficiently sensitive.

The particular form of construction of the apparatus out of light brass tubing will, it is believed, insure the requisite degree of equability in its thermic behavior. This is essential to, and in fact necessary for, its complete success as a composite measure.

The mercurial thermometers, although entirely unnecessary, were provided for special purposes; for example, the determination of the coefficients of expansion. Each bar contains three symmetrically disposed thermometers, which if regularly used will render the duplex serviceable also as a thermometric measure.

The shifts or relative displacements of the components with respect to one another are determinable by, and follow directly from, the successive readings of the bar scales. While one set of scales would have sufficed for this purpose, yet for convenience and symmetry in construction a second set was provided. These are secured respectively near the rear and the front ends of the bars, as shown in the illustration.

To facilitate the making of the contacts between bars in the reversed as well as in the direct positions, both the upper and the nether faces of the contact slides are provided with a set of fiducial lines. The standard lengths of the bars rest upon the coincidence of both of these sets of lines with fixed lines on the bars. When the lines are set to coincidence, the lengths of the components are defined by the agate tips or terminals, horizontal knife edges at their rear ends, and flat or abutting surfaces of 2·5 millimetres diameter at their forward ends.*

As regards field procedure, the duplex differs from other contact bars in no essential particular, except in that it requires the making of two contacts for every bar laid, namely, the contacts between its double components in the sense "steel to steel" and "brass to brass." The alignment and inclination of the bars is effected and determined in the usual way by means of aligning telescopes and inclination sectors, as shown in the illustrations. The scales for relative shifts of the components require to be read twice, once at beginning and once at conclusion of the measurement of each whole or half section of a base, as the case may be. Scale readings are also required whenever "shift" is made to equalize the projecting ends of the components. During actual measurements it is advantageous to shift the brass and not the steel components, in order to leave the latter undisturbed in the truss tubes, thus insuring continuity in the measurements with the steel components.

Inasmuch as the bar scales relate the two components and determine their relative displacement, it will usually suffice during measurement to refer but one of them to the section or stop marks. The independent reference of both the components, however, will afford a check upon the scale readings.

Before referring the components at the start or conclusion of a measurement some advantage is gained by setting their agates even, i. e., tangent to a line normal to the axis of the bars, as in that case the transfer measures will be the same for both. This equality in the projections of the components from the truss tubes is readily and most accurately accomplished by means of reflections from a plane mirror.

Again, during use of the duplex it is convenient, on account of the central position of the aligning telescopes, to keep the axis of the bars in the line of measure. Still, unless the normal position of the sector transit is well assured, it is preferable and essential to accuracy in the transfer measures to place the bars slightly eccentric, so as to bring that component which is nearest to the sector in the line of measure.

Reversal of the components being a distinctive feature or principle of construction of the duplex, should never be neglected, either in field practice or in comparisons for standardization, if results of the highest attainable precision are sought. Without reversal of the components, especially during exposure of the bars to radiant heat, the equality in the mean temperatures of the components will in part be sacrificed, and as a consequence slight discrepancies or "lag" would undoubtedly develop and impair the precision of the measures.

* For an account of the standardization of the duplex bars by the Office of Standard Weights and Measures, see Report by Assistant Andrew Braid in the Coast and Geodetic Survey Report for 1896.

A reversal of the components is equivalent to change of face in the bars. The frequency of reversals will depend upon circumstances, but ordinarily two reversals during a day's work will suffice. It is, however, essential that these reversals be symmetrically disposed with reference to the subdivisions of the base or to each day's measurement.

Again, on account of the standardization, the measures of a line or section should always be made in equal extent with the bars in the positions of "face up" and "face down." The scales and verniers, being firmly secured to the components, turn with them on reversal, and appear in the windows of the truss tubes provided for the purpose. Through these windows, which are closed with glass planes to intercept the free circulation of the air, the scales are read. Shutters protect the windows against injury. The legends engraved upon these window shutters designate the position or face of the components within.

When in position "face up," the steel components of the bars are to the left looking in the direction of the measure, whereas when "face down" they will be to the right.

In the measurement of the Salt Lake base the components were reversed but twice each day, i. e., once at the middle point of each half-kilometre section, measured respectively in the morning and evening.

Inasmuch as during this measurement the duplex was on trial for general efficiency as a composite apparatus, systematic execution was important. Accordingly the mercurial thermometers were also regularly read, and the measurement of a section was carried out in strict conformity with the scheme of procedure shown in the following diagram of a kilometre section.*



Fig. 2

Each kilometre section, it will be noticed, was thus measured twice, once forward and once backward, noting in each, also, the measure at the half-kilometre point. The day's field work was restricted to the measurement of a single section in but one direction.

It will also be seen that the advantage which this particular arrangement of the field procedure affords, if methodically pursued, consists in furnishing results for the whole section free from the errors due to temperature defects in the components, whereas for the half section it exhibits them, if material, to their full extent, rates of temperature changes assumed to be equal. Measuring them under rising and falling temperatures without regard to system or plan, such as shown in the above diagram, although in general yielding results free from temperature errors, can furnish no results from which the precision of the measures or the thermic efficiency of the bars may with certainty be inferred.

The subjection of an apparatus to a thorough test for thermic efficiency is practicable only through systematic field procedure. The measuring of lines under like or similar temperature conditions will in general be productive of results entirely misleading as regards their accuracy.

The length of the Duplex bars is known in terms of the international prototype metre, No. 21, the standardization having been effected by comparisons upon the 50-metre comparator base at the United States Coast and Geodetic Survey Office, through the "Woodward" 5-metre standard bar No. 17, in melting ice.† The "Duplex constants" were determined independently of the thermometer readings, i. e., from the expansions direct, and the thermometric constants in the customary way.

* This mode of conducting measurements was proposed by the writer in 1885, twelve years ago, as part of the duplex scheme. I have but very recently noticed that the remeasurement of the Bonner base in 1892 was conducted after the same general plan. (See Die Neumessung Der Grundlinien, Geodetic Institute, Berlin, 1897.)

† See Appx. No. 8, Report 1892, The measurement of the Holton and St. Albans base lines, by R. S. Woodward et al., and Appx. No. 5, Report 1894, Report on the length of the Holton Base, by Assistant C. A. Schott.

For purposes of standardization this bar, in ice, is not only uncommonly convenient but invaluable.

In the matter of speed of measurements trial has demonstrated that the Duplex easily leads all other forms of measuring bars in use to-day. A speed of forty bars an hour, or, what is the same thing, a kilometre in five hours, is easily maintained. The necessity of making an extra contact for every duplex bar laid was found to cause no appreciable delay in the progress of the work.

The maximum speed attained in the Salt Lake base measure was at the rate of seventy bars an hour, which broke all previous records of base measurements with any other apparatus, not excepting the monometallic contact-slide bars of the Survey.

The time required in making contacts with the Duplex or any other apparatus is consumed chiefly in aligning and adjusting the bars for height, and not in establishing "coincidence" in the fiducial lines, which, as a rule, is a matter of but a few moments.

But, to illustrate the capacity of the Duplex for rapid work more fully, it may further be remarked that nineteen consecutive kilometre sections were measured in nineteen consecutive working days of five hours each, viz, from 10.30 o'clock a. m. to 5 o'clock p. m., with an hour and a half intermission after completion of first half kilometre, for the purpose of insuring rising and falling temperatures.

In point of accuracy of the field measures the Duplex exceeded expectations. Computed in the usual manner, from the difference in the two measures for the whole sections, it appears to have easily attained a relative precision of 1-5 000 000 part, both as a duplex and a thermometric apparatus. But, computed from the discrepancies in the measures for the half sections, which measures appear to be slightly affected by systematic error due to "lag," the precision reached makes a less favorable showing. The computations for the half sections remain as yet incomplete.

The crucial test for efficiency to which the Duplex was subjected in the Salt Lake base measure proved it to be practically free from "lag" or imperfect thermic behavior, although during the operations of the measurement the change of the temperature was at times wide and rapid.

Its superiority as an efficient field apparatus was thus satisfactorily established. The selection of metallic tubing in its construction was no mistake. Although tried under adverse field conditions it nevertheless maintained equality in the mean temperatures of its components with a surprising degree of precision.

Moreover, as regards manipulation it is safe to assert that the Duplex leads all others as a compact and convenient base apparatus, not easily deranged in its adjustments, and calculated to insure satisfactory results with bestowal of but ordinary precaution on the part of the observer. Used only as a duplex, without the thermometers, the bar is simplicity itself. Its great weight insures to it exceptional stability in field work.

As of interest also, it may finally be mentioned that, bearing in mind the mechanical construction, no accumulation of error results in the case of the Duplex from interruption or irregularity in the progress of measurements made with it, for the reason that each bar as it is brought into contact faithfully records in scale readings the precise thermic relations which obtain at the instant in the bar preserving the measure. In other forms of base bars this advantage is usually lost because of the impracticability, as a rule, of noting the temperatures of the bars at the instant of establishing contact.

But, as before intimated, the judicious adaptation of the field procedure in all cases to the particular needs of a primary apparatus will go far toward the complete elimination of this as well as other defects to which it may be liable.

To avoid complication in the construction no compensation is applied to preserve invariability in the distance of the rear end of the components from the fixed knife-edge bearing of the rear trestle. The error in measure which thus results from expansions during ordinary fluctuations of temperatures will usually be found inappreciable. In extreme cases, however, requiring correction it is readily computed from the known dimensions, the coefficients of expansion, and the temperatures of the bars at beginning and closing of the measurement in question. This correction is wholly independent of time or distance measured.

The components are securely held in an unchanging relation by the action of helix springs firmly keyed to the components and the reversing tubes. These springs placed within the component tubes cause the contact screws to bear hard at all times against the headpiece of the truss tubes.

Turning the contact screws moves the components forward or backward by the action of the helix springs. Uniformity in the contact pressure is insured by weak helix springs fitted in the sliding caps, as shown in the cross section of the bar. When properly supported at the quarter points, the axes of the reversing tubes are straight or without "sag," a condition which was effected by tentative adjustments of the diaphragms supporting them. On account of the accurate centering, accomplished by carefully executed, well-ground lathe work, these tubes reverse with perfect freedom of motion. By means of a detent they turn exactly half round, leaving the components always in a horizontal position. Carefully executed, the reversals will cause no sensible disturbance in the position of the bars. Upon this point, concerning which there seemed to be no end of apprehension in the minds of the hypercritical, the apparatus was thoroughly tested under the powerful microscope-micrometers of the office comparator and found to be absolutely secure against disturbance.

The diameter of the main truss tubes is 10·2 centimetres. The diameter of the reversing tubes is 6·7 centimetres. The thickness of the walls of these tubes is, respectively, 1·75 millimetres and 0·75 millimetre. The horizontal section shown in plate 3 is accurately drawn to scale.

The three mercurial thermometers project vertically through the double truss tube and are held in such a position as to place the centers of their bulbs midway between the components. The reversing tube is for this purpose pierced on opposite sides. The reversal of the components renders the temporary removal of the thermometers necessary. Though the bulbs of these delicate thermometers do not form immediate contact with the components, they are, nevertheless, supposed, on account of the construction, to accurately indicate the mean temperature common to both of them.

The bar scales, graduated to centimetres, read in the direction of the measure. By construction these scales are symmetrically arranged and fixed with reference to the ends of the steel components, and the verniers, similarly arranged, are firmly attached to the brass components.

When the components are of equal length and equally projecting, the four scales read approximately as follows:

	Centimetres.
Rear scale, bar No. 15	5
Front scale, bar No. 15	25
Rear scale, bar No. 16	45
Front scale, bar No. 16	65

The difference in these readings in the sense:

R. 16 minus R. 15, or F. 16 minus F. 15, is therefore 40 centimetres;

hence

R. 16 minus R. 15 = F. 16 minus F. 15.

In other words, the differences in the readings of the rear and the front scales of the two bars are necessarily always equal, irrespective of either the relative positions or the thermal condition of the components.

The particular difference in the scale readings, which corresponds to the normal, i. e., the equality state in the lengths of the components, has been designated, for distinction, the "normal scale reading," and which, on account of its importance, is to be regarded as an auxiliary constant of the apparatus. As at present adjusted, the normal readings differ slightly from the above values, being, respectively, 40·04 centimetres for the rear scales and 40·11 centimetres for the front scales. This slight discrepancy in the identity of the two readings, the result of imperfect adjustment of the verniers, is, however, without significance and can easily be removed by perfecting of the vernier adjustments.

These scale readings, though determinable in various ways, are readily ascertained from readings made when the components have equal length, i. e., when at the temperature of +25°·5 C, as indicated by the thermometers.

Again, since on account of the symmetrical arrangement the distances between the zeros of the scales or the zeros of the verniers (approximately 5 metres), though constantly varying in conformity with thermic changes, are necessarily always equivalent, respectively, to the lengths of the

steel and brass components, it is evident that, no matter what the thermic state of the bars may be, the following relations obtain:

R. 16 minus R. 15 = 40·04 centimetres + the difference, brass minus steel components;

F. 16 minus F. 15 = 40·11 centimetres + the difference, brass minus steel components;

where 40·04 and 40·11 centimetres are the present *normal* scale readings above referred to.

These two relations, it will be seen, are mainly useful in affording the means of ascertaining at any time the difference in the lengths of the steel and brass components.

Though it suffices for all ordinary purposes to depend upon the readings of either the rear or the front scales alone, yet in standardization measures, or when the greatest attainable precision is sought, it will be preferable to read both. For, since the rear and front scales must agree, the readings of both will not only furnish an excellent check, but it will enhance also the accuracy and trustworthiness of the differences.

In further explanation of the mode of action of the components, it may be pertinent to remark that during measurement with the duplex, "brass" will advance and will continue to advance upon "steel," temperatures *rising* or *falling*, so long as it remains longer than "steel." Inversely, "brass" will recede and will continue to recede upon "steel," temperatures *rising* or *falling*, so long as it remains shorter than "steel." That is to say, the scale readings during the advance of a measurement will $\binom{\text{increase}}{\text{decrease}}$, temperatures rising or falling so long as "brass" is $\binom{\text{longer}}{\text{shorter}}$ than "steel." The difference in the two measures, in the sense (B — S), will, therefore, be $\binom{\text{plus}}{\text{minus}}$ when the measure from "brass" is $\binom{\text{longer}}{\text{shorter}}$ than that from "steel." No change whatever in relative position or scale readings will take place so long as both the components maintain equal lengths.

From this mode of action of the duplex it is also evident that the difference in the two continuous measures from its components is determined by the first and last scale readings, corrected for intermediate shifts of the brass components. A verification of this all-important difference may be secured through the independent reference of the steel and brass components to the ground marks. For it is clear that the difference in the sums of the "set-ups" and "set-backs," corrected in the case of "brass" for intermediate shifts, is equivalent to the difference in the two measures found for each half or whole section of the base.

The duplex constants above alluded to are: (1) The length of the components in standard measure, when they are of equal length, and (2) the duplex coefficients, which depend upon the *ratio* of the expansions of brass and steel.

Assuming that these two constants, together with the difference in the measures from brass and steel $(B - S)$ are known, and disregarding the corrections for inclination, etc., the total length L for the n double bar lengths in standard measure may be computed by means of the following simple expression:

$$L = nl + \alpha_0 (B - S)$$

in which α_0 denotes the duplex coefficient for steel, l the duplex or equality length of the components in standard measure, and $(B - S)$, as before explained, the difference of first minus last scale reading of a measurement, corrected for the "set-ups" and "set-backs," and such other relative shifts of brass as were made for the purpose of equalizing the ends of the components.

The equations which express the lengths of the measures from the steel or the brass components in terms of their respective thermometric constants are, of course, of the usual form.

Hence the four equations expressive of the lengths L for n double bars measured with the duplex as a composite bar may, therefore, be written:

$$L = nl + \alpha_0 (B - S) \quad \text{duplex method from steel} \tag{1}$$

$$L = nl + \alpha_1 (B - S) \quad \text{duplex method from brass} \tag{2}$$

$$L = n \overset{\text{m}}{10} [1 + ds (t - \tau_0)] \quad \text{thermometric method from steel} \tag{3}$$

$$L = n \overset{\text{m}}{10} [1 + db (t - \tau_1)] \quad \text{thermometric method from brass} \tag{4}$$

and where α_0 and α_1 in equations (1) and (2) denote respectively the duplex coefficients for steel and brass, and ds, db, and τ_0, τ_1, and t in equations (3) and (4) the coefficients of expansion, the

standard temperatures and the observed mean thermometric temperatures respectively of the steel and brass components. The thermometric standard length of the components of bars Nos. 15 + 16 is 10 metres.

Since equations (1) and (2) reduce simultaneously to $L = nl$, when $B - S$ becomes zero (i. e., when the measures from brass and steel happen to be of equal length), it is evident that unless l be known in standard measure an additional corrective term would be requisite, which would render the computation of L by the duplex method unnecessarily complex. For this reason l is properly chosen a *constant* of the duplex. It is directly determinable from the expansions themselves, without regard to the thermometric temperatures of the bars.

Again, if in a measure obtained by the duplex $B - S$ turns out to be zero no correction whatever for temperature applies, since the length nl found is at once the true length in standard measure. The lengths of bars Nos. 15 and 16 are sensibly identical, viz, 5 metres.

Though the duplex coefficients (α_0 and α_1) are easily derived by elimination of $t - \tau$ from equations (3) and (4), it seemed nevertheless simpler and more appropriate to exclude the notion of temperatures entirely and to deduce them directly from the ratio of the expansions.

To this end let l denote, as before, the normal length of the components when of equal length, Δs and Δb the total expansions respectively of steel and brass for equal thermic conditions, then bearing in mind that these expansions vanish or change sign simultaneously, the length of the steel measure is obviously expressed by

$$nl + \Delta s = S \tag{5}$$

and the length of the brass measure by

$$nl + \Delta b = B \tag{6}$$

Subtracting (5) from (6) we have

$$\Delta b - \Delta s = B - S \tag{7}$$

the symbolic relation which subsists between the differences in the total expansions and the lengths in the two measures from brass and steel. That is to say, the difference in the total expansions and the difference in the lengths of the two measures are always equal.

Now this difference $B - S$, as before explained, is always known, being directly obtained from the scale readings of the apparatus, etc. Therefore, since in addition to this also the ratio of the expansions of the components $\frac{\Delta b}{\Delta s}$ is known, it is plain that the total expansions of either steel or brass measures themselves may be found from the relations:

$$\Delta b - \Delta s = \delta \tag{8}$$

$$\frac{\Delta b}{\Delta s} = m \tag{9}$$

which are necessarily true whatever the thermal condition of the apparatus or lengths of line measured with it may be. Therefore, solving with respect to Δs we have: $\Delta s\,(m - 1) = \delta$ and

$$\Delta s = \delta \frac{1}{m - 1} = \delta \alpha_0 \tag{10}$$

and with respect to Δb

$$\Delta b = \Delta s + \delta = \delta \left(\frac{1}{m - 1} + 1 \right) = \delta\,(\alpha_0 + 1) = \delta \alpha_1. \tag{11}$$

These two coefficients α_0 and α_1 differ always by a unit irrespective of the metals of the components. The latter is therefore of but little practical significance, except for the purposes of verification. The coefficient, α_0, for steel, however, on account of its importance, is properly regarded a constant of the duplex apparatus, and for convenience of distinction it has been called the "duplex coefficient." Substituting $B - S$ for δ the preceding corrections reduce to the form as given in the equations (1) and (2) on page 745.

Inasmuch as the ratio of the expansions $\frac{\Delta b}{\Delta s}$ is constant and independent of the length, it is obviously determinable from two or more measures of one or more fixed distances of *unknown* length, whereas the ratio of the thermometric coefficients of expansion, $\frac{db}{ds}$, although also equal to m, is determinable only from two or more measures of one or more fixed distances of *known* length. This noteworthy distinction results from the fact that db and ds are already related to a thermometric scale and a linear unit.

In practice, therefore, especially if using the bar simply as a duplex measure, we may even dispense with the determination of the coefficients of expansion in the ordinary way entirely, and instead determine the ratio of the expansions $\frac{\Delta b}{\Delta s}$ from the differences in the two measures of the sections of a base line. The coefficients thus deduced would unquestionably lead to a better agreement between the separate measures than those found in the usual way.

Hence, whenever such double measures as are suitable for the accurate determination of (m) are available, the standardization or recomparison of the duplex may be confined to the determination of the particular lengths of the components which they possess when of equal length.

In order to be perfectly consistent, the constants of length and the coefficients of expansion, independently determined from thermometric and differential expansion measures, must satisfy the relations:

$$l = 10^m + (10^m - l_b)\,\alpha_0$$

and

$$\frac{ds}{db - ds} = \frac{\Delta s}{\Delta b - \Delta s} = \alpha_0$$

which, from a practical point of view, affords a most convenient and rigorous verification of their trustworthiness. l_b represents the length of brass at the standard temperature (τ_0) of steel.

A further noteworthy fact concerning the duplex which it will be well to point out is, that on account of the difference in the expansions of its components *unequal* wear of the agate knives from "contact friction" will necessarily affect somewhat differently their duplex and their thermometric lengths. If, however, the wear of the knives of the steel and brass components chances to be *proportional* to their respective expansions, it will not change at all the duplex length.

Lastly, it may be stated that inasmuch as slight accidental errors of observations, other than those resulting from defective temperatures, necessarily affect the factor $B—S$, it is plain that the differential expansion results from the duplex measures can not in general be as accordant as the corresponding thermometric results from each component separately, provided the errors due to defective temperatures are properly eliminated in both systems. Hence, if in any composite apparatus thermically as perfect as the duplex the mercurial thermometers be assumed to give the mean temperatures of the components as accurately as the bimetallic device, then barring the existence of systematic temperature errors, the thermometrical result from each component singly will in general agree better than the results from the differential expansion method.

The inclination sectors are graduated and adjusted so as to read 20° when the components are horizontal. Error in the inclination from eccentricity in the sectors is provided against by two diametrically opposite verniers. The diameter of the sectors is 8 inches.

DIRECTIONS ON THE USE OF THE DUPLEX APPARATUS IN THE FIELD.

The use of the duplex in the field does not differ from that of other types of contact bars, except in so far as it requires the making of two contacts for every bar laid, namely, the contacts between its double components in the sense "steel" to "steel" and "brass" to "brass." In every other respect its manipulation is practically the same as that of the subsidiary monometallic apparatus in use on the Survey. The manner of reading the bar scales is a matter so simple as to require no special explanation.

The adjustments required by the duplex and the manner in which they may be perfected will be found fully set forth in Appendix No. 12 of this Report, Coast and Geodetic Survey, 1897, report on the Salt Lake base measure.

On starting a measurement, place the first bar upon the trestles, roughly align it and turn its components into position, "face up."* Next, set the contact slides to fiducial zero and make the agate knives normal to each other, i. e., normal to the axis of the bar, by means of the plane mirror provided for the purpose. Next, align the bar accurately and shift it at the same time so that its steel component will fall nearly vertically over the initial ground mark and in the line of measure.

Next, transfer the knife edge of *steel* to "ground" in the usual way by means of the sector transit and the centimetre scale. Brass having been previously set normal to steel, is necessarily related to ground the same as steel and need not therefore be referred. Next, read the thermometers, if required, the inclination sector and the bar scales. This will complete the laying of the first bar.†

Next, place the second bar on the trestle and roughly align it; turn the components "face up" and slide the bar backward into approximate contact with the rear bar.

Next, adjust rear end for height by raising (or lowering) the cradle bar of the rear trestle by means of the sliding wedge provided for the purpose and securely clamp it. Next, establish the preliminary contact by bodily sliding the bar backward, relieving it at the same time of its full weight in order to diminish the friction upon the rear trestle. Next, align the bar accurately by lateral shift upon the forward trestles until the aligning telescope bisects the line flag at the next section post ahead.

Lastly, establish the final contact between the components as quickly as possible by means of the contact screws, and at the same time read the mercurial thermometers, the inclination sectors, and the bar scales, which will complete the laying of the second bar.

Next, launch the rear bar, carry it forward, and place it into proper contact with the second bar, which now preserves the measure.

Next, read the thermometers and the inclination sectors, but not the scales, since readings of the latter are no longer required. Next, launch the rear (second) bar and carry it forward, and place it into contact with the third bar, and again read the thermometers and the sectors as before.

Next, launch the (third) bar, etc., and proceed as before explained to the end of the measure. The inclination sectors and the thermometers must be read for every bar laid.

At the conclusion of the measure it will be necessary to again read the scales of the last two bars laid, and transfer "front agate" of "steel" to "ground" in the same manner followed at the start, and to shift "brass" until the "front agates" of both the components are relatively even or normal. The shifts of "brass" thus occasioned must be determined by additional scale readings. Since the reversal of the components in nowise affects the continuity of the measure, verifications by scale readings may be disregarded. Scale readings taken at the beginning and closing of measurement will suffice, and will be all that is required to complete the measurement.

In establishing the preliminary contact by bodily sliding the bar backward or forward, which after some little practice is usually accomplished with surprising rapidity and precision, the utmost care and precaution should be observed to protect the agate knives against injury. For the transference of the components to "ground," place the centimetre scale horizontal, and reading in the direction of the measure, which, if its graduation be numbered from left to right, as is usually the case, will expose the face toward the left, looking in the direction of the measure. Hence, face the scale by setting the transit sector to the left, normal to the end of the bar to be referred, and about 25 or 30 feet distant from it. By placing it at the same time, also, at half the height of the bar above the ground, equality in distance and in definition of the sector telescope will be insured. A short-legged tripod, if available, will conveniently serve this latter purpose.

Never fail to check the transfer measures by pointings with the sector in both the direct and reversed positions.

As usually employed, a "set-up" is a quantity additive to and a "set-back" a quantity subtractive from the measure as obtained by the apparatus.

---

* The duplex bars are in the position designated "face up" when the steel component is to the leftward, looking in the direction of measure, and "face down" when steel is to the right.

† In executing the transference of the components to the ground marks, always place the sector transit on the same side of the line, the centimetre scale horizontal upon the section posts and parallel to the line of base. The graduated face of the scale should be placed so as to read in the direction of the measure.

Equalization of the projecting components, if required, should invariably be effected by shifting "brass," *never* "steel." Shifts of the steel components during operation would interrupt the continuity of the measure, and should therefore be scrupulously avoided.

On account of unavoidable shifts, the measures from "brass" are usually discontinuous and hence require to be corrected accordingly. Shift of the brass components must, therefore, be accompanied by scale readings. The records regarding these shifts should always be explicit and complete, so as to leave no question as to what was done.

General observations.—If, at the beginning or closing of a measurement, the precaution is taken to set the *components* of the first and last bars normal to each other, the reference of either one of them to the "ground" will suffice. If, however, it is found impracticable to set them normal, the components must be reversed and separately referred. To this end reverse the components (after having first removed the mercurial thermometers) to position "face up" or "face down," as may be required, in order to place each of them consecutively in the line of measure. These reversals should always be made with dispatch, and the thermometers quickly restored to their respective sockets in order to prevent changes in their indications from exposure.

Again, respecting the transference of the components to the "ground," if the *last bar* of the *preceding measure* is permitted to remain undisturbed upon its trestles—an advisable procedure—it will be found advantageous on resuming the measurement to refer its *blunt front agates* to "ground," and then to continue by bringing the agate knives of the *initial bar* of the contemplated measure into *contact with it.* Moreover, if instead of referring the last bar of a preceding measure in the usual way, it be shifted and set vertically over "ground," the reference measure for both the components will be the same, and zero.

This mode of resuming the measurements was adopted and uniformly followed in the Salt Lake base as soon as its advantages were recognized and fully established. It saves the setting and clamping of the contact slides at their fiducial zeros, and preserves the uniformity in their adjustments. The placing of the components accurately into the vertical of "ground" is most readily accomplished through the contact screw micrometers. To this end point upon "ground" with the transit and shift component into tangency with its spider line by means of the contact screw and note the micrometer. Repeat this with the sector in the reversed position and again note the reading of the micrometer. Next, set the contact screw to the mean of the micrometer readings, which will place the component vertically over "ground."

This method of adjusting the components into the vertical through "ground" is convenient, expeditious, and very accurate.

As a matter of convenience in the "set-up" and "set-back" measures it is well, before attempting the transference of the components to "ground," to set them normal.

Should alteration in the relative relation of the components become necessary at any time during the operation of measure, be particular to effect this by shifting "brass," *never* "steel."

The reading of the scales may be restricted to the rear set of the bars alone. The front scales if simultaneously read will, however, serve as a check upon the former. In the Salt Lake base measure, both the rear and front scales were regularly read.

When shifting "brass," with reference to "steel," determine its amount by scale readings.

The frequency of reversal of the components will depend upon circumstances. Two reversals during a day, one each at the middle points of the morning and afternoon measures, will, as a rule, suffice.

Begin each measure of the half sections in position "face up" and conclude with "face down," reversing the components at the middle of the measures.

To prevent undue or irregular heating of the projecting components while adjusting position or establishing contacts, wear a suitable glove with the tips of the fingers clipped off.

To obviate the necessity of frequent shifts of "brass" during measure under extreme temperature conditions, it is suggested to set "brass" *ahead* or *back* of "steel" *one-half* the amount it is likely to recede or advance. An approximate temperature will suffice for this.

To readily lay off the normal directions required for setting the sector transits when plumbing to the "ground," a parallel ruler of suitable dimensions laid flat upon the projecting components and gently pressed against the headpiece of the truss tube will prove convenient. For, since these headpieces are accurately fitted by lathe work, the edges of the ruler, if placed as set

forth, will point in a direction normal to the axis of the truss tubes. Hence, tilting the ruler downward a little, the setting up of the sector in the range of the outer edge of the ruler at the required distance will insure to it a position normally opposite the end of the components.

The trestles.—In setting the trestles endeavor to secure a uniform grade parallel to ground, without reference to the inclination of the preceding bar. Effect this whenever the nature of the ground permits by adjusting the cradle bars so that on sighting over the tops, respectively, of the rollers and knife edges they coincide with a line touching the distant horizón. Adherence to this mode of setting the trestles will insure not only nearly uniform, but also the least, inclinations consistent with the profile of the ground.

To secure the proper spacing for setting the rear trestles, measure the required distance, not from the *preceding front trestles*, but from the *black band* which marks the point of support at the forward end of the measuring bar. The position of the forward trestle is then readily and accurately located by measuring from the knife edge of the rear trestle, if placed as explained. Their firm and stable setting upon hard ground is materially expedited by providing their legs with suitable cleats for forcing them well into the ground by aid of the foot. Always clamp the trestles and cradle bars securely as soon as the bars are approximately aligned and properly adjusted for height and for contact.

Be careful not to break or shear off the bulbs of the mercurial thermometers during reversals of the components. Always remove them, therefore, before reversal and restore them to their respective sockets as quickly as possible thereafter.

To reduce the "set-up" and "set-back" measures to a minimum, which is of some advantage, it is suggested to subdivide the base line into regular sections by a tape measure or chain standardized to the same temperature as the base apparatus, disregarding the corrections for either temperature or grades of the site. (The duplex is of standard length at the temperature of 25°·3 Centigrade, very nearly. The components are practically of equal length when at 25°·5 Centigrade, as indicated by the three-bar thermometers.) As a valuable auxiliary in the preparation of a base, set and accurately align stakes 2 by 4 inches in size at every 50 metres. They will prove convenient in many ways, particularly in affording a control of the alignment, as well as of the progress of the measure. In the Salt Lake base measure these stakes contributed very materially toward maintaining the temper and spirit of the operatives throughout the day.

In setting the section and half-section posts, be particular to place their tops level as well as flush with the ground, and their outer edges parallel to the direction of the base. Through the centers of the bolts which define the sections draw a heavy pencil line in the direction of the base. Attention to these details, though seemingly unimportant, will be found of much assistance in quickly orienting and adjusting the centimetre scales for the transferrences during the measurement, or in accurately flagging out the base for the alignment of the apparatus. In ranging out the line, place short flags at the half section and long flags at the whole section stones, to the end that the tops of the latter may be seen projecting over the tops of the former if the site be sufficiently plane. Set the flags truly vertical, and secure them by appropriate bracing. By using slender flags the accurate alignment of the bars may be easily maintained during measure by closely keeping in their range without regard to the state of the adjustment of the aligning telescopes.

On account of the great weight of the duplex bars (118 pounds each) which insures to them exceptional stability, even under exposure to a high wind, it was found necessary, for greater security and safety in establishing the preliminary contacts, to somewhat check the free and easy gliding tendency of the strongly inclining bars by slightly clamping the roller of the front trestles.* The making of the preliminary contacts is at best hazardous, requiring constant care and precaution to shield and protect the agates against damage and the bars against displacement. To this end the contact slides should be held back with the forefinger in such a way as to take up a sudden lurch, should it inadvertently occur, in order to protect the agates from injury. At all events this method of making the preliminary contacts, which was successfully practiced in the Salt Lake base measure, proved very effective, in proof of which it may be stated that although 4 600 bars were laid and 9 200 single contacts made, not a single mishap occurred that resulted in injury to the agates.

* To be able to slide the bars at all it is necessary, while making the preliminary contacts, to diminish the friction upon the knife-edge bearings by lifting the rear ends of the bars.

The measurement.—If practicable, measure always a kilometre section a day in the same direction; the first half during the morning hours, under rising temperature, and the second half during the afternoon hours, under falling temperature.

To satisfactorily secure this end it is suggested to take up the measurement as late as possible in the morning and to continue it to as late an hour as practicable in the afternoon. If a measurement be carried forward at a speed of 40 bars an hour, a speed which, after some little practice, is easily maintained, the measure of each half kilometre section will seldom require more than two hours and a half. Hence, the hour of commencing the day's measurement may therefore be conveniently set at 11 o'clock a. m., and continued until 5.30 p. m., with an hour and a half intermission after completion of the first half kilometre.

The complete and systematic measurement of a base by half kilometre sections, as explained, affords many advantages. It simplifies the operations, insures similarity and symmetry in the measures of each whole section, and obviates the necessity of frequent settings of as well as transferences to special stop marks.

The trestles, if used for the support of the apparatus during measurement, should be portable and convenient of manipulation while setting and adjusting them to grade. They should easily adapt themselves to peculiarities of the ground and at the same time afford ample stability. The trestles used in the Salt Lake measurement filled these requisites satisfactorily, except as regards their stability, in which particular they proved deficient on account of the flexibility of the cradle standards under the horizontal thrust caused by the contact pressure between the double components of the duplex apparatus.*

Since it was apprehended that the errors in the section measures which thus resulted from the displacements of the bars through contact pressure might prove large enough to require correction, the flexure in the cradle uprights was subsequently carefully determined at Washington under the powerful microscopes of the office comparator base.

Although it may be conceded, in view of the experience so far had with the duplex, that its construction out of light brass tubing qualifies it for accurate measurement, without further protection save the ordinary felt jacketing which covers its truss tubes at present, it is nevertheless recommended that whenever practicable additional shelter be provided. The shelter sled used in the Salt Lake base—a simple frame structure covered with canvas, and traveling on runners—proved very effective and convenient. Being light in weight, it was easily drawn over the ground by a pair of horses, and thus enabled the party to pursue its work without interruption in spite of rain and high winds. Not an hour's time was lost from either unfavorable weather or undue exposure of the operatives to the burning sun of the desert during the whole term of the work. Closed down and securely guyed to the ground it served to protect the apparatus during nights and on Sundays, and permitted the bars to remain on the trestles in position ready to continue the measure on the following day.

Although for primary geodetic work—i. e., in connection with triangulation of superior fundamental character—it will be advisable and, indeed, necessary always to measure a base line twice, once in each direction, even if for no other purpose than to find the precision of the final measure, it is nevertheless confidently believed, in view of the exceptional degree of precision of the duplex (viz, one five-millionth part), that if simultaneously used as a thermometric and a bimetallic measure the three (independent) results from a single carefully executed measurement will insure a precision quite sufficient for trigonometric work of a subsidiary character, such as is requisite for a trigonometric survey of a limited locality, as, for example, a State. Judged by the results obtained in the case of the Salt Lake base this belief seems well borne out, for the results from the two measurements of that base do not differ more than 2 millimetres, indicating a precision of the single measure hardly attainable by any other apparatus hitherto employed, even from a double measurement of a base, and surpassing the limit of accuracy usually reached in the determination of the constants of the apparatus of the ordinary construction at present in use.

The necessity of conscientious verification of every measure or observation appertaining to and calculated in any way to contribute toward the reliability of the measurement or the completeness of the record thereof will readily suggest itself to the careful and responsible observer. Under favorable circumstances the cost of making a single measurement with the duplex, after the

* These trestles were never designed for the duplex, but belong to the monometallic bars Nos. 13 and 14.

manner pursued in the Salt Lake base, will probably not exceed a hundred dollars ($100) per kilometre, inclusive of the necessary expenses for preliminary preparations. That is to say, in consideration of its simplicity, convenience, and speed in manipulation, measuring with the duplex will cost neither more nor less than will measuring with the present monometallic apparatus of the Survey.

The field party employed in the Salt Lake base measure, including an extra driver and a men's mess cook, consisted of nineteen persons, with six horses and two wagons. It lived in camp, and was organized with the view of providing against interruption of the measurement from sickness, etc.

For diagrams illustrating the plan of measurement, as well as for forms of record and computations, etc., see Appendix No. 12, Report on the Salt Lake Base Measure, 1897.

The mode of the standardization of the duplex apparatus, together with special investigations concerning the flexure instability of the trestles, will be found explained in Appendix No. 12, Coast and Geodetic Survey Report, 1897, entitled Report on the Salt Lake Base Measure. These trestles, it should be borne in mind, belonging to the monometallic contact bars Nos. 13 and 14 of the Survey, were never intended for the duplex. They were used only because no other more rigid and suitable trestles were available at the time.



DUPLEX BARS IN CONTACT—FACE DOWN.



VIEW OF DUPLEX BARS, WITH ALIGNING TELESCOPE SIGHTING IN DIRECTION OF MEASUREMENT.



DUPLEX BAR No. 15 ON ITS TRESTLES.

THE DUPLEX BASE APPARATUS

Designed by Wm Eimbeck, Assistant



A and C Contact Slides
B . S Brass & Steel Components
D . E Contact Screws
F Truss Tube Head
G Truss Tube
H Reversing Tube Head
K Reversing Tube
M Reversing Tube Collar
N Diaphragms supporting Reversing Tube
O Guide Diaphragms for the Components

THE NORRIS PETERS CO., PHOTO-LITHO., WASHINGTON, D. C.

APPENDIX NO. 12, 1897.

REPORT ON THE MEASUREMENT OF THE SALT LAKE BASE LINE, IN UTAH.

By WILLIAM EIMBECK, Assistant.

6585——48

Blank page retained for pagination

APPENDIX NO. 12—1897.

REPORT ON THE MEASUREMENT OF THE SALT LAKE BASE LINE, IN UTAH.

By WILLIAM EIMBECK, Assistant.

The question of the location of a primary base of verification within the thirty-ninth parallel triangulation in Utah had received much attention in connection with the development and execution of that triangulation through eastern Nevada and Utah. The extent and scope of the geometric figures of this triangulation are exceptional and without a precedent in practical geodesy.

Measured along the central parallel, for example, the main chain lying between the Yolo and El Paso base lines is approximately 1,680 kilometres in extent, and is composed of but eight distinct trigonometric figures, containing not less than 10 lines of 230 kilometres average length. The longest one of these, stretching eastwardly from "Ellen Peak" across the delta of the Green River to "Uncompahgre Peak," is nearly 300 kilometres in extent. As regards heights, the triangulation is no less remarkable. Traversing the mountains at an average elevation of about 11 000 feet, it culminates, on crossing the Continental Divide, in central Colorado, at an elevation of 14 300 feet above the sea.

Though executed in every phase or feature with the utmost care and the very best of instrumental appliances, yet, on account of its unprecedented scale and the consequent problematical character of its final results, the measurement of a fundamental base near its middle meridian was deemed desirable, and, indeed, necessary, and was therefore decided upon as far back as 1883.

For the location of such a base the broad and open valleys of central Utah afforded special advantages. Their easy accessibility and their settled condition or state of cultural development adapted them most admirably for the measurement.

Accordingly, with that object in view, the preliminary examination of these valleys was begun in 1884 in the vicinity of Mount Nebo. It was thence carried into the Juab and Sanpete valleys and the open plains about Oasis and Deseret. Later on, in 1887 and 1888, the reconnaissance was extended into the basin of Utah Lake, and thence northward to the valley of the Jordan River and Great Salt Lake. The immediate outcome of this exhaustive reconnaissance was the discovery of many highly favorable base-line sites, notably those situated in the Juab, Sanpete, and Salt Lake valleys. A few of these sites, though favorable for measurement, had to be abandoned on account of the inelegance and inadequacy of the expansions of the trigonometric nets necessary to connect them with the main scheme.

But the verification and support of the linear element of the thirty-ninth parallel triangulation was not the only object it was sought to accomplish through the *location* of this base. The connection of the astronomical longitudes at Salt Lake and Ogden cities was also to be considered. These two important astronomical stations, which had served also as principal points of departure in the geographical exploration surveys within the mountains of the West, required intimate connection with the main work of the parallel.

Again, the height of the base above the level of the ocean was another question of moment, which claimed consideration. In a geodetic work of the precision and general refinement of the Rocky Mountain and Nevada sections of the transcontinental arc, it seemed manifestly inexpedient to depend for the elevation of one of its fundamental bases upon the trigonometrically determined

heights without verification by reliable spirit levels, especially in view of the circumstance that the heights of the Utah stations, largely derived from lines of uncommon length, were brought over a thousand kilometres from the ocean. In view of this it was obviously much to be questioned whether the heights could be regarded as possessed of that degree of precision deemed needful for the reduction of the proposed Salt Lake base. On the other hand, the transcontinental levels of the Union and Central Pacific, and other railways centering at Ogden, brought over from the seas, were the only lines of spirit levels at present available. The connection of the base site by spirit levels with the elevation of the railway crossing at Ogden was, therefore, regarded as necessary.

In consideration of the above and the desirability also of an extension of the triangulation in Utah along the 112th meridian, as a link essential to a comprehensive trigonometric survey of the United States,* the main chain was subsequently expanded over the basin of the Great Salt Lake by a single quadrilateral. This elegant figure hinging upon the line "Nebo-Ibepah" is the largest quadrilateral in the whole work, and covers an area of nearly 10 300 square miles. The central station "Deseret" was introduced in order to facilitate the geodetic connection of the astronomical stations referred to, as well as the base line situated between Ogden and Salt Lake City. For the convenient and effective connection of these latter points, and particularly for the extension of the triangulation to the northward into Idaho, this quadrilateral figure will prove of much value.

Upon thorough consideration of the merits and demerits of the several sites from time to time reported, it was finally decided, in view of the reasons above set forth, to adopt and measure the base line situated upon the shores of the lake, near Hooper, unquestionably the most eligible and satisfactory site found that seemed well suited for economical connection and measurement, notwithstanding the fact that its connecting net extends in large part over the waters of Great Salt Lake. For illustration of the base net see pl. 1.

General location.—As will be seen from the accompanying triangulation sketches, the base line is situated upon the flat lands extending along the eastern shore of the Great Salt Lake, from the mouth of the Weber River to Farmington. Its northern end is located upon the grounds of Mr. Cato Love, at South Hooper, and its southern end opposite Kaysville, within school section 16, township 3 north, range 2 west of the Salt Lake principal meridian of the Utah land surveys. The approximate length of this base is 11·2 kilometres. The site is smooth and nearly level, excepting a slight swell near its middle at Beard's Point. The principal constituent of the soil is sand intermixed with loam. The southern half is alkaline, and being covered in part with a salt grass, and sage brush is used for pasturage purposes throughout the year. The three northern kilometres of the line pass through well irrigated, cultivated fields.

During the dry season (summer and fall) the ground is hard and admirably adapted for base-line measurement with apparatus supported by trestles. There are some farm improvements at various points along the site, but a slight change in location resulted in clearing it of every consequential obstruction, excepting at the stackyard of Mr. Beard, where a couple of grain stacks had to be removed to make passageway for the shelter-sled. Among the minor obstructions which could not be avoided may be mentioned twenty-eight barbed-wire fences, a railroad embankment, a turnpike embankment, some deep furrows, and numerous water ditches. The two largest of the latter had to be bridged over. Each of the twenty-eight wire fences had to be taken down and replaced once in each measurement.

Though the provisional location and trace of this site had been made and decided upon before I entered upon the occupation of "Waddoup" and "Antelope" triangulation stations, to Assistant J. J. Gilbert is due the credit for final location. Under my direction Assistant Gilbert prepared the site for measurement, perpetuated its terminals by substantial stone and brick monuments, and executed a complete topographical survey.

The brick piers at south and north base—that is, the permanent surface monuments which mark the position of the base—were built with the view to serve also as pedestals for the 20-inch theodolite used in observing the triangulation net. These piers were carried to a height of 9 feet in order to lift the instrument above the stratum of superheated and boiling atmosphere, a condition that seemed to prevail over the barren flat lands of the Salt Lake Valley at nearly all hours on sunny days.

* See Proceedings of Geodetic Conference, App. No. 9, Report 1893, p. 360. Report, Committee on the Measurement of Arcs.

Salt Lake Base Net, Utah, 1896.



THE HARRIS & EWING CO. PHOTO-LITHO., WASHINGTON, D.C.

The base, divided into eleven sections, was accurately traced by stakes set firmly in the ground. At every kilometre from south base a prismoidal stone 20 inches in length was firmly planted by packing the ground solidly around it. In the centers of these stones, dressed down to 5 by 5 inches square, were inserted §-inch copper bolts secured in place by sulphur. Fine cross lines (+) cut normal to the direction of the base defined the exact section points.

Half-kilometre posts were subsequently provided for the exclusive purpose, as will appear farther on, of subjecting the Duplex to a thorough test with respect to its behavior as a thermically perfect field measure. These posts consist of 4 by 4 Oregon fir 20 inches in length firmly planted in the ground. Ordinary 2-inch wood screws, with notch set normal to the base, mark the exact division points. The faces of all these posts and stones were placed accurately level, and flush with the ground. Heavy pencil lines drawn across the tops of these posts and kilometre stones in the line of the base served to accurately flag out the base in advance of the measurement, and to orient the centimetre scales for the "set-up" and "set-back" measures. The base was ranged out by 2 by 2 inch flag poles 7 and 10 feet in length, marked at their tops by a black and white band, set true to line, and secured in a vertical position by appropriate bracing. The shorter 7-foot flags were set up at the half-kilometre posts and the projecting 10-foot flags at the kilometre stones. The "range" thus established afforded a convenient means of controlling the direction of the measure without the aid of *adjusted* aligning telescopes. No grading of the line whatever was required. Although slightly rough in places, the clearing away of sage and grease brush and of some sunflowers was all that was needed to put the site in condition for measurement. Some little plowing and ditching was also necessary in order to drain off pools of water that had accumulated in places from flowing wells or overflowing irrigation ditches.

The convexity in the profile of the base necessitated the erection of 70-foot scaffold signals at its terminals in order to establish intervisibility between north and south base. The brick piers, on account of their dimensions and finish, it was found impracticable to carry higher than originally built.

Height of the base.—To determine the profile of the base, Assistant Gilbert ran a simultaneous double line of spirit-levels from south to north base, and after the completion of the base measurement the connection with tide water was completed by running similar levels to "bench mark" Hooper, situated 4 miles to the westward on the eastern shore of the Great Salt Lake. The height of this bench mark was determined in 1887 by lines of levels run in opposite directions from the crossing of the Union Pacific and Utah Southern Railways at Ogden, Utah.

The "Hooper" bench is the northern one of a pair of benches established in 1887, by means of which the transcontinental railway levels at Ogden were carried across the waters of the Great Salt Lake to the "Grantsville" bench, thence by reciprocal zenith distances to the summit of Deseret peak, the central station of the great quadrilateral which spans the basin of Great Salt Lake. A verification of the height of the base above the ocean, thus found from the railway levels, is assured through the hypsometric work of the transcontinental triangulation which rests upon a very complete and comprehensive series of zenith distances directly connecting with the mean tide water at the Straits of Karquines, California, and the height of Colorado Springs, in Colorado, as derived from the Coast Survey lines of precise levels.

MEASUREMENT OF THE BASE.

Having given in the above a brief account of the preliminary preparations, before passing to a description of the measurement of the base, it is deemed expedient for the convenience of the reader to preface it with the following condensed description of the Duplex apparatus:

BASE APPARATUS.*

The Duplex.—On the survey the duplex is known as "Base Bars Nos. 15 and 16." It is a bimetallic contact-slide apparatus, consisting of two precisely similar bars wholly constructed of metallic tubing of the smallest dimensions consistent with requisite strength and rigidity. The important characteristics which distinguish it from other forms of bars are: (1) Its two disconnected tubular components; (2) the reversibility of these components; (3) its double metallic

* For detailed account of the duplex base apparatus, see Appendix No. 11.

truss-tubes, the inner one of which carrying the components is reversible on its axis; (4) the summation, during use, of the minute differences of length of its components and the indication of the sum total of these differences. The components consist respectively of steel and brass tubing of ¾-inch outer diameter, with walls proportioned in thickness to the specific heat and conductivity of these metals. Their surfaces are nickel-plated in order to insure to them equal power for absorption and emission of heat.

The object of the adoption of the tubular form of construction, and the principle of reversal of the components, is to secure uniformity in the distribution of temperature, or more particularly equality in the mean temperatures of the components, the important requisite upon which the success of every bimetallic scheme unquestionably chiefly depends. Each bar, 5 metres in length, is protected by light jacketing against sudden changes of temperature, and weighs 118 pounds. The flexure of the bars is constant. The components are provided in the usual manner with three mercurial thermometers each. These theremometers mainly serve to convert the apparatus into a thermometric measure. Their bulbs are placed centrally between the components without, however, forming a metallic contact with them.

To facilitate the making of the contacts in either of the reversed or the direct positions of the components, both the upper and nether faces of the contact slides are provided with a set of fiducial lines. The lengths of the components, as defined by these lines, are sensibly the same for both faces. The reversal of the components is equivalent to a change of face.

The relative displacement of the components, and the shifts of "brass" during a measurement, for equalization of their projections, are determined as to amount by the successive readings of the bar-scales. For this purpose each bar is provided with two sets of scales and verniers. The scales are firmly attached to the steel components, and the verniers to the brass components. The scales are 12 centimetres in length, and read directly to tenths of a millimetre. Being symmetrically placed with respect to the agate terminals of the components, the distance between the *zeros* of corresponding *scales*, or of corresponding *verniers*, is always the same respectively as the lengths of the steel and brass components. Hence, the differences in the readings of the two rear and the two front scales, diminished by their "*normal readings*," will be equal to the difference in the lengths of the steel and brass components.

The "normal scale reading" is that which obtains when the components have equal lengths, i. e., when at a temperature of approximately 25°·5 C. This normal scale reading, 40·075 centimetres, may be regarded as an auxiliary constant of the duplex, by means of which the accumulated scale differences may be corrected, if necessary, for one or two extra bar lengths.

A further advantage of the duplex consists in the independence of its principal constants, namely, the standard lengths of its steel and brass components, the thermometric coefficients of expansions of these components, and the so-called differential bimetallic or "duplex coefficient."

This latter coefficient being dependent solely on the *ratio of the expansions* of brass and steel, without reference to either temperature or *definite* lengths, is obviously deducible either from adequate measures made in the field or special standardization experiments upon the comparator base. In certain favorable contingencies preference should be given to the determination of this coefficient from suitable *field* measures. In general, therefore, no special series of observations will be requisite for the determination of this important coefficient.

If simultaneously used both as a bimetallic and a thermometric apparatus, the duplex will furnish three practically independent results from a single operation of measure, which must and will agree if the constants referred to are *consistent*. These are the two thermometric results, one each from the steel and brass components, and the duplex or differential expansion measure from both the components conjointly.

In the matter of manipulation in the field the duplex differs from the ordinary monometallic bar in nothing, except that it requires the making of two contacts for every bar laid, i. e., the contacts between its double components in the sense "steel to steel," "brass to brass."

On account of compactness of construction the duplex proved in this first trial to be not only a portable but also a most convenient field measure, not easily deranged in its adjustments. If used only as a duplex without thermometers, the apparatus is simplicity itself. Interruption or irregularity in the progress of measurement in no way affects its results. Manipulated with but ordinary precaution, it is certain to furnish satisfactory results.

Standardization.—Before being shipped to the field, in June, 1896, the new bars were standardized under authority of the Office of Standard Weights and Measures, and their principal constants were determined from a series of 32 comparative measures with the Woodward 5-metre standard bar No. 17, in melting ice, upon the 50-metre comparator line recently established in the grounds of the Coast and Geodetic Survey Office in Washington, D. C.*

Later in the year, after completion of the base measure and the return of the duplex to the office in November, it was again compared with the Woodward standard through 32 similar measures upon the office comparator. This recomparison, undertaken mainly with the view of ascertaining whether the lengths of the bars had sustained change from wear of the agates, was conducted by the writer under instructions from the Superintendent, in strict conformity with the mode of procedure followed in the base measure. Accordingly, the thirty-two comparative measures were made in four groups of eight symmetrically arranged measures each. In each group the eight measures were made with the components alternately in the positions "face up" and "face down," the change of face being effected by a reversal of the components after completion of each forward and backward measure.

On completion of the second group of eight measures, executed as regards position of the faces in the obverse order, the duplex bars were turned end for end and the remaining sixteen measures, arranged in two groups of similar measures, were executed by measuring in the reversed direction Throughout this restandardization the duplex apparatus was handled with the utmost care, and the components were accurately aligned and, after completion of each forward and backward measure, were systematically reversed. The thermometers and the scales were also carefully read and verified by two observers, and in order to secure the most favorable temperature conditions each of the four groups was executed during the afternoon hours of the day. For standard lengths these experiments were regularly preceded each day by a double measurement of the comparator base with the standard bar No. 17, in melting ice. The minute expansions in the truss tubes, for which no compensation is provided in the construction, were eliminated by executing every return measure backward; that is, without turning the duplex bars end for end.

In order to properly relate the two series of comparative measures between the duplex and the office standard No. 17 through the ground marks which define the terminals of the comparator base, the end microscope-micrometers, before being pointed upon the duplex components, were invariably first referred to these marks by means of the Repsold cut-off cylinder. Such cut-off references were required at every reversal of the components and the microscope-micrometers were pointed directly either upon the well-focused agate knives or centrally between the direct and reflected images of spider lines stretched for the purpose across the plane-faced front agates. The necessary illumination for these micrometric pointings was effected through reflections from the metallic scale of the Repsold cut-off cylinder in horizontal position.

On completion of the restandardization of the duplex, an exhaustive investigation was undertaken to determine the flexure relations of the trestles. It had been noticed while in the field that the *cradle arms* of these trestles were much too slender and flexible to effectually withstand the push or thrust caused by the double contact pressure of the duplex without sensibly yielding to it, and that an investigation of the matter was, therefore, desirable. With this object in view the bars, supported by the trestles in the usual manner, were placed under the comparator microscopes and the flexure of the cradle arms carefully measured for thrusts of various intensities and lengths of arms. The thrusts by weights were applied and measured in both directions. As was to be expected, the results of this novel and somewhat comprehensive series of experiments show: (1) That the flexure at any length of arm is proportional to the intensity of the thrust; (2) that with respect to length of arm above the base of the cradle, the observed flexure proved to be approximately proportional to the square of the length of arm.

Thus it was found, for example, that while the elastic yield at the head of the trestles was always *nil*, at a point three-fifths of the length up the arms of the cradle, i. e., the estimated average height at which the bars were supported in the field, the flexure due to contact pressure was five microns. Supported at the tops of the cradle arms, the flexure from the same pressure proved to be equivalent to twenty microns.

* See Report Office of Standard Weights and Measures, by Andrew Braid, Assistant, page 2, Coast and Geodetic Survey Report for 1896. The length of this standard bar is very accurately known in terms of the International Prototype Metre No. 21.

For verification the tension of the helix springs of the contact slides was subsequently determined by means of a delicate spring balance. Thus determined, the flexures from contact pressure and the flexures caused by weights were found to agree. The weights applied in these experiments by means of a pulley and cord were one-half, one, and two kilogrammes. It must be conceded that the magnitude of the observed flexures exceeded expectation and that they could not be disregarded. It was made evident, also, that the duplex apparatus, in consequence of its double contact pressure, required supports of greater stability than is afforded by the trestles used—trestles, by the way, which belong to the monometallic subsidiary bars of the Survey, and were never intended for the duplex.

Next, investigations were also made relative to the uncertainty of making contacts and transferring the components to the ground marks. From eighty contacts noted, twenty for each of the four components, it was found that the probable error of estimating a coincidence of the fiducial lines is $\pm 2^{\mu}\cdot 8$. From twenty measures for transferring the agate knives to ground, using the same centimetre scale and sector transit employed in the field, the probable error of a single transferrence was found to be ± 85 microns.

These investigations were very materially simplified by the use of the contact screw micrometers with which the components of the duplex apparatus are provided. The division value of these micrometers is directly derivable from ten or more revolutions of the screw heads measured upon the bar scales.*

These special investigations of the duplex were concluded finally by observations for the determination of the wear of the agate knives from contact friction. That the knife edges had become somewhat blunted was plainly discernible. The average amount of wear as computed from carefully measured widths of the contact *surfaces*, together with angles of the knife edges, was found to be $8^{\mu}\cdot 0$. In other words, assuming the knife edges to have been perfect when issued from the shop, it seemed established that the combined length of the two bars (Nos. 15 and 16) had shortened by about 16 microns during use. Including the standardization experiments 26·3 kilometres had in all been measured with the duplex. In the computation of the corrections for this wear it was assumed that it was proportional to the *area* of contact surface, or, which is the same thing, that the *volume* lost by wear was directly proportional to the number of contacts. Hence, the $\frac{1}{26\cdot 3}$ part of the whole cubical contents lost was worn away during the measurement of each kilometre.

Adjustments.—Like other contact-slide measures the duplex requires two principal adjustments: (1) That of the inclination sectors; (2) that of the aligning telescopes.

The inclination sectors.—The sector arcs are divided from 0° to 40° and read to 10″ by two diametrically opposite verniers. Properly adjusted, the verniers read exactly 20° when the components are horizontal. This adjustment is conveniently made by means of an ordinary wye level placed at a point about 25 metres distant from, and nearly at right angles to, the centre of the bar and at the same elevation. When the bars have thus been placed in a truly horizontal position the sectors, whose verniers have previously been set to the proper reading, are adjusted so that their level bubbles assume a central position. This adjustment should be frequently verified.

The aligning telescopes.—The adjustment of the aligning telescopes consists chiefly in making their sight lines parallel to the axis of the reversing tube. In the absence of more convenient means this adjustment may be effected as follows: Select an even and nearly level piece of ground, and after having placed the bars upon the trestles adjust the aligning telescopes for collimation; next, with the aid of the sector transit, range out, in a straight and approximately level line on the ground or upon posts, three nails, viz, one near each end of the apparatus and the third about 75 metres distant ahead upon a fence post or other convenient object; next, stretch a cord between the two near nails, which cord, if proper care has been taken, will be accurately in the line fixed by the three nails; next, having set the knives and rollers of the trestles level and to proper elevation, shift the axes of the bars accurately into the vertical plane through the stretched cord by means of suitable plummets; next, set the axes of the aligning telescopes horizontal and,

* The heads of these micrometers are divided into twenty-five divisions. From a series of measures of full turns upon the bar scales the value of one division was found $= 25^{\mu}\cdot 4$.

without disturbing anything, adjust them in azimuth until they bisect the distant nail. This, if properly done, completes the adjustment, and will insure parallelism between the sight lines of the aligning telescopes and the axes of rotation of the reversing tubes. The lathe centres in the head-pieces of the truss tubes will serve the purpose of placing the bars in the vertical plane through the stretched cord. Although it was found that this adjustment, as well as that of the inclination sectors, proved to be uncommonly permanent during the Salt Lake base measure, they were, nevertheless, tested a number of times and kept under control by the range afforded by the line flags at the section posts. It should also be remarked that inasmuch as the plane of collimation of the telescopes falls centrally between the two parallel components, in order to keep either one of them in the line of measure it is necessary to point the aligning telescope a little out of the centre. In the base measure, steel, when "face up," was kept in the line of measure, which was accomplished by directing the pointings five-eighths inch to the right of centres of the line flag poles.*

Sector transit.—The sector transit used in referring the components to the ground marks was always set up on the left side of the line, looking in the direction of the measurement. This required the centimetre scales to be placed so as to read in the direction of the measure, which is desirable.

The sector transit was, of course, always placed normal to the end of the bar to be referred, approximately 30 feet distant from it, and, to insure equal definition, at about half the elevation of the bar above the ground. This latter condition was accomplished by means of a short-legged tripod provided for the purpose. The adjustments for collimation and horizontality and verticality of the axes of the sector were accurately made and controlled throughout the measurement. The pointings upon the agates of the components and the centimetre scales were always twice made, i. e., once in the direct and once in the reversed position of the transit.

The normal direction of the transit was determined in the following simple manner: A parallel ruler, 2½ inches in width and about 10 inches in length, was placed flat upon the projecting components and gently pressed against the end face of the truss tubes. Tilting the ruler slightly downward and sighting along its outer edge, the center of the sector tripod was ranged into this line and set up at the desired distance. It should be remarked that inasmuch as the headpieces of the truss tubes were fitted by lathe work, their faces are necessarily normal to the axis of the truss tubes. Pointed upon with the sectors placed as above explained, reversals of the components, when set to normal position by the mirror, brought out no perceptible discrepancies. This method of placing the sector transit at a normal direction, which is peculiar only to the duplex, was found to be so convenient and expeditious that it was exclusively employed as soon as recognized.

"Set-ups" and "set-backs."—In referring the agates of the components to the ground marks, a "set-up" is a quantity additive to, and a "set-back" a quantity subtractive from, the measure obtained by means of the base apparatus. The shifts of brass upon steel for the purpose of equalizing the ends of the components belong to the same category. They affect the measure from brass in either the additive or the subtractive way, according as the readings of the scales are thereby increased or decreased.

The "set-ups" and "set-backs" were measured by means of 10-centimetre scale, Coast and Geodetic Survey, No. 190, the graduations of which on investigation by the Office had been found to be free from appreciable error.

Placed horizontally upon the section bolts and parallel to the line of measure, the scale faces the sector transit and the graduations increase in the direction of the measurement. This latter circumstance proved an excellent safeguard against confusion or mistakes in noting the "set-ups" and "set-backs," which were made with the utmost care and were verified in every instance to obviate possible mistakes.

Scales and scale readings.—As before explained, the scales of the duplex are centimetre scales, firmly attached to the steel components, whereas the verniers, which are adjustable, are secured to and carried by the brass components. These scales, etc., of which each bar has two sets, are graduated to millimetres and read directly to tenths. The hundredths are determinable by estimation. The scales are 12 centimetres in length, and to avoid confusion in the readings are differently numbered. Thus, for example, when the rear scale of bar No. 15 reads

* If the sector transit be always set accurately normal to the line of measure, which is easily done in the case of the duplex, it will be simpler and preferable to keep the centres or axes of the bars in the line of measure.

5 centimetres the rear scale of bar No. 16 reads 45 centimetres, etc. The graduation of the scales increases from rear toward front, or, which is the same thing, in the direction of the measurement. Hence, if during measurement "brass" advances upon the "steel" the scale readings increase; if "brass" recedes the scale readings decrease. Brass obviously will $\left\{\begin{matrix}\text{advance}\\ \text{recede}\end{matrix}\right\}$ upon steel so long as it is $\left\{\begin{matrix}\text{longer}\\ \text{shorter}\end{matrix}\right\}$ than steel.

The difference in the scale readings of successive bars, diminished by the normal difference, is equivalent to the difference in the lengths of the steel and brass components. The lengths of the two bars 15 and 16 are sensibly equal, viz, 5 metres each.

For the reduction of the scale differences from 99 to 100 bars, or from 1 to 2 bars, as the case may be, a knowledge of the *normal* difference in scale readings is required. This auxiliary constant is determinable in various ways, as, for example, from the scale readings when the brass and steel components are of equal length. The components of the two bars (15 + 16) have equal length when at the mean temperature + 25°·5 C., as indicated by the mercurial thermometers.

The normal differences in the scale readings depend upon the adjustment of the verniers. This adjustment may be made very secure and practically invariable. As at present adjusted these differential readings are for the rear scales R 16 − R 15 = 40·04 centimetres and for the front scales F 16 − F 15 = 40·11 centimetres.*

The plane mirror.—For the convenient and expeditious reference of the components to the ground marks, it is essential that they project normally from the truss tubes. A simple means by which they may be made normal is an ordinary plane mirror. If held in a vertical position and gently pressed against the agates of the components their ends will obviously be normal to each other when they, and their reflected images, appear in straight lines, i. e., as prolongations of each other. Therefore, if upon trial it be found that they appear at an angle, shift "brass" (never "steel"), by means of the contact screw, until they do appear straight, which may be accurately judged, in the absence of special provision, by the projecting stems of the thermometers. The entire reliability of this process was abundantly tested and established by pointings with the sector transit, at a normal position, and reversals of the components. Reflections repeated after reversal of the components also afford an accurate check.

The trestles.—The wooden trestles which were used in the Salt Lake base measure belong to subsidiary monometallic bars, Coast and Geodetic Survey, Nos. 13 and 14. The foot plates, provided to give greater stability to the trestles when crossing soft or yielding ground, were not used, as the ground along the Salt Lake base site, being thoroughly sunbaked, afforded all needful stability without them.

The setting of a continuous series of trestles is a task beset by many trials and difficulties, requiring close and unremitting attention to secure the proper conditions of alignment, distance, grade, and stability, all of which are essential and requisite, and must always be promptly and satisfactorily secured if neither speed nor the accuracy of the measure is to be sacrificed.

The line of the trestles is maintained by the range of the bars themselves; their distance or position is fixed by measures, not from the last trestle set but from the black bands around the bars.

In order to insure at once the most advantageous gradients compatible with the profile of the site, clamp the cradle bars at an elevation such that their bearing edges coincide with or touch the horizontal line defined (or fixed) by sighting tangent to the roller or knife edges of the preceding trestles and the distant horizon line in the direction of the base. In other words, set each successive trestle to an average uniform gradient irrespective of the incidental inclination of the preceding bar. For, so set, the bars on being placed upon them will also be parallel to the ground and in position ready for approximate contact.

The rapid and stable setting of the trestles was greatly facilitated by providing each trestle leg with a cleat, bolted to it just above the iron ferrule at its foot.

To adjust, bring the cradle bearings to a horizontal position by means of a carpenter's level,

* The effect of reversal of the components upon the mean scale readings is but trifling and may usually be disregarded. From a series of readings made for the purpose the discrepancy was found to be for bar 15, "face-up," − "face-down," = + 0·0024 millimetres, and for bar 16, "face-up," − "face-down," = − 0·0084 millimetres.

or similar instrument, clamp securely, and, with a screwdriver, loosen one end of the block carrying the embedded level, bring the bubble to the center, and tighten screw. Reverse and correct to true center.

When arranged in a line and set horizontal with the small spirit levels embedded in cradle bars, the top edges of the knives and rollers should be parallel. Test this by glancing over the tops of them. If on so doing it appears that one or more of the rollers or knives are materially out of parallelism, correct them by approximately raising (or lowering) the particular bars, and then adjust the levels accordingly. Although it is desirable, when set by means of these levels, that the cradle bearings be horizontal, it is not essential that they be accurately so. It will suffice if they are parallel among themselves. Also oil all screw bolts so as to clamp easily, and firmly secure the cradle arms by tightening the screws underneath the head pieces of the trestles, etc.

Field Procedure.—On the morning of the third day of September, after a careful adjustment of the inclination sectors and the aligning telescopes, at camp, the duplex was hauled to North Base on the laps of six men appropriately seated in an ordinary freight wagon, and the first measurement of the base began there in the afternoon.

The entire measurement of the base was carried out with the bars supported and maintained in position by the ordinary field trestles above described.

For the protection of the apparatus and party during the measurement, a light canvas-covered sled, a movable structure traveling on runners, was provided.*

The base line was measured twice, once in each direction. It was divided into eleven sections, each a kilometre in length, excepting the eleventh, which has a length of 1·2 kilometres. Each section, therefore, contained an even number of bar lengths. They are consecutively numbered from I to XI.

To obviate the inconvenience of referring the measuring bars to the permanent end marks of the base inclosed in the hollow brick piers, two posts 5 inches in diameter and 3 feet long were placed in the line of the base, just outside of the piers, or approximately 0·8 metre distant from the permanent surface monuments. The exact line points were marked by copper bolts provided with fine cross lines. These subsections, designated "A" and "B," were directly measured with a 3 meter fractional bar, once at the start and again at the finish, respectively, of the first and second measurement of the base with the apparatus.

The modus operandi pursued in the measurement was the following: The trestles having been previously arranged in appropriate position and securely clamped, the first bar (No. 16 in this instance) was placed upon them, and accurately aligned in such a manner that the steel component fell in the line of measure, its rear end approximately vertical over the ground mark at "B." Next, a transit sector was placed to the eastward of "B," about thirty feet distant and at right angles to the line of measure, and the agate knife-edge of "steel," set to fiducial zero, plumbed down in the usual manner by noting the scale readings for both the knife-edge and the ground mark; next, the bar scales and the mercurial thermometers were read, the latter quickly lifted from their seats, and the components reversed. This reversal brought the brass component into the line of measure. On setting the contact slide of "brass" to coincidence of its fiducial lines, its knife was immediately referred to "ground" in precisely the same manner as was the steel component. Next, the scales and the thermometers were provisionally read, the latter removed, and the components reversed back. This restored the bar to its direct or first position, and a final reading of the inclination sectors, the scales, and the thermometers, completed the laying of the first duplex bar in the Salt Lake base measure.

Next, the trestles having been arranged and set to grade beforehand, the second bar, 15 in this instance, was placed in approximate alignment and its rear end adjusted to proper height by means of the wedges, and the trestles firmly clamped. Next an approximate contact was effected by a backward sliding of the whole bar upon the trestles and the final alignment of its forward end by lateral shifting and telescope pointings upon the line flags ahead. Next, the contacts between the components, "steel to steel" and "brass to brass," were made perfect by means of the contact screws, and the laying of this second bar was completed by noting the readings of its

* For detailed description and illustrations see further on.

scales, thermometers, and its inclination sectors. Next, on command "ready launch," the first rear bar (16) was withdrawn, carried forward by two men, and, under guidance of the proper officers,* was placed upon the next pair of trestles and approximately aligned. Next, after having accurately adjusted its rear end for height by the wedges of the cradle, the bar was again bodily slid backward into approximate contact, which, after final alignment by telescope pointings, was properly perfected in the usual way by means of the contact screws. The readings of the inclination sector and the thermometers, simultaneously with making the final contacts, completed the laying of the third bar. Next, at command as before, the second bar (15) was launched, carried forward and placed upon the trestles, etc., as before explained. At the same time the shelter sled was drawn forward a bar's length by a pair of horses, in order to keep the apparatus and party well sheltered from the burning sun.

Inasmuch as during this first measurement the duplex was on trial for general efficiency as a composite apparatus, neither care nor precaution were spared to insure precision in the execution of every detail essential to the operation. Thus the thermometers of the bars were regularly read as soon as each was successively laid. The scale readings, however, as being of no further importance, were discontinued after the laying of the second bar.

At the beginning of a measurement the scale readings of the first two bars laid, together with the "set-up" or "set-back" measures for the brass and steel components at the starting point, are all that is required in addition to their temperatures and inclinations, for the three independent results it was the aim to secure in this measurement.

The general plan of measurement which was methodically pursued in the base measure is illustrated in the following diagram of a kilometre section:†



Fig. 2

Each kilometre section, it will be seen, was measured twice, once forward and once backward, as before explained. Each measurement was executed in a day, during particular hours in the morning and evening. The half-kilometre points were introduced into the measure for the exclusive purpose of testing the new apparatus for thermal behavior. Being at the middle of each section, they also served conveniently for the midday stops. The daily measures were regularly referred to these points, and caused no extra work or delay whatever in the adopted routine duty of the work.

For testing the behavior of base apparatus under field conditions, the series of half-kilometre measures, arranged and executed as shown, affords peculiar advantages, chiefly on account of reversal of the second measure in direction, that each half section is thus measured once in the morning under rising temperatures and again in the afternoon under falling temperatures, or vice versa, as the case may be, while the whole sections are measured under as similar temperature conditions as obtain during the same hours of the two different days.

This was the plan of measurement followed and the object sought. Unquestionably the plan is thorough, and if methodically pursued under favorable weather conditions is bound to bring to light the thermic faults of a bar, however insignificant they may be.

The difference in the measures thus obtained under favorable weather conditions will be nil

* The officer making the contacts in the meantime remained at his place or position, in order to protect the rear trestle and bar from being struck or accidentally disturbed in any way by the men while carrying the bar and trestles forward.

† This method of conducting the measurements of base lines was proposed by me in 1885, as part of the duplex scheme, for the express purpose of testing the thermal efficiency of base apparatuses. Only very recently I have noticed that the remeasurement of the "Bonner Base" in 1892 was executed after the same general plan. See "Die Neumessung der Grundlinien, etc.," by the Prussian Geodetic Institute, Berlin, 1897.

for the whole (daily) sections, no matter what the character of the apparatus, whereas for the half sections they will be of appreciable magnitude and of a systematic nature, i. e., their algebraic signs will regularly alternate, unless the apparatus used chances to be thermically perfect, in which case the differences in question would obviously also be zero. Hence, the differences in the measures for the half sections, if appreciable and alternating in their signs, will be systematic in character, and on that account will be mainly significant in so far as they exhibit or serve to determine the thermal characteristics of the apparatus employed; for example, in the case of the duplex, whether it be equally efficient as a bimetallic and as a thermometric apparatus. On the other hand, the *daily* results from the *whole* sections can contribute nothing toward a satisfactory solution as regards the question of either the thermal perfection of the apparatus or the reliability of the results in "*normal*" measure.

The movable shelter.—This valuable adjunct, which was used in the base measure for the protection of both the party and the apparatus, consisted, as before stated, of a large canvas-covered sled traveling on runners. It was a "double-ender," 56 feet in length, 12 feet in width, and 9 feet in height at the ridge line of its arched roof. Framed out of Oregon fir of the lightest permissible dimensions, it was bolted together into a rectangular-shaped open truss in such a manner as to convert its posts and diagonals, respectively, into ties and struts. By this means the framework of the truss was sufficiently strengthened to retain its shape, no matter whether supported at the middle, as when crossing a dike or embankment, or at the two ends, as when crossing a broad ditch or sharp depression in the ground. During the measurement this sled was drawn along over the undisturbed natural ground by two horses. Weighing not over 3,000 pounds, it glided easily over ditch, furrow, or railway embankment, answering its purpose admirably. It occasioned no delays, and as for simplicity, convenience, and cheapness it would be difficult to construct a movable shelter more effective or complete. The cost of the material used in its construction, as lumber, carriage bolts, nails, and canvas covering, did not exceed $65.

During measurement the two ends of the sled were always kept open. The side curtains were usually so regulated by reefing as to prevent the sun's rays from striking the apparatus, but not to interfere with the free circulation of the air. During hours when the wind was too strong the side curtains were lowered enough to prevent it from striking the apparatus. In short, the sled afforded every desirable protection against the burning heat of the desert, etc., and so enabled the party to pursue the measurement of the base uninterruptedly at all times. Only on one occasion, during very high wind, did it become necessary to discontinue the work on account of the danger of overturning the sled.

Its utility and beneficent effects, not only upon the results of measure but upon the health and temper of the party, can not be easily overestimated. It is much to be doubted whether without the comforts and protection which this sled afforded the party would have been able to measure nineteen kilometre sections in nineteen consecutive working days, as it actually did. Not less than two days' time were saved on account of rainy weather. It more than saved its cost in time alone. The advantages that are secured through the employment of such a sled are so many and so pronounced that no important base measurement should be executed without a similar movable shelter.

The first measurement of the Salt Lake base was brought to a finish on the 17th day of September. The return measurement was started next day and concluded on the 3d of October.

General summary.—In the beginning of the measurements the transferences of the rear ends of the bars were effected by clamping the contact slides of the components to the fiducial zeros. Each component was independently referred to "ground," i. e., without prior attempt at equalization of their projections from the truss tubes by means of the mirror. The sector transit was always set up on the left, looking in the direction of the measure, normal to the end of the bar and about 30 feet distant from it. The pointings upon the agates of the components were always made double, i. e., once with the transit in the direct and once in the reversed positions, each accurately leveled. The graduations of the scales, placed always so as to increase in the direction of the measure, served admirably to prevent confusion in the "set-up" and "set-back" measures.

Except for the "set-ups" and "set backs," the measures of the sections from "steel" are continuous. The equalization of the projecting components was effected, whenever necessary, by

shifting of "brass." "Steel" was never changed. The measures from the brass components are therefore not continuous, but require correction for "shifts." As to amount, these "shifts" are equal, of course, to the differences of the accompanying scale readings. To obviate as much as was practicable the "shifts" occasioned by excessive relative displacement, "brass" was always set ahead or back of "steel" one-half the quantity it was likely to lose or gain on "steel" in any contemplated measure. Close attention to this useful expedient resulted largely, if not wholly, in the prevention of the "shifts," excepting the few measures that were made during the extremes of the temperatures of the field season, where it was unavoidable. The extra "shifts" required in the Salt Lake base measure were but few.

Throughout the measurement of the base the steel and brass components were independently referred to the section posts. This was judged desirable in order to render the individual results from steel and brass as independent as possible. Ordinarily the reference of steel alone suffices.

A preliminary measurement of the northern fraction of section XI was made with the view of affording the operatives of the party an opportunity to familiarize themselves with their respective duties, and to gain practice in the manipulation of the new apparatus. Naturally during this first attempt at measuring with the new apparatus progress was slow. The party lacked training and familiarity with the working of the mechanical details of the bars, and the mode of the field procedure had not yet been sufficiently developed and systematized. This practice measurement was not used in determining the final length of the base.

Though during nights the thermometers were taken from their sockets and securely packed away in a box lined with cotton batting, the bars themselves were left on the trestles in order to keep them out of the chilly or frosty air that usually collects upon the flat lands about the Great Salt Lake during the early morning hours in quiet bright weather.

For the better protection of the apparatus during nights, before quitting the field of work the canvas curtains of the shelter sled were dropped and tied to the runners, and the sled well secured to the ground by stakes and guys. The watchman who was left in charge was permitted to swing his hammock and live within the sled thus closed down.

Each morning, after having replaced the mercurial thermometers in their regular order and tested the adjustments of the inclination sectors, the measurement was resumed by accurately aligning bar 16, the first bar of the contemplated measure, and by placing the knife-edge of its steel component, set to fiducial zero, in the vertical line passing through the "night stone," and then proceeding in the same manner as before described.

In order to preserve regularity in the methods of execution, the measurements of the half sections were invariably begun with the components in position "face up," i.e., "steel" in the line of measure.

The principle of reversal of the duplex components was regularly observed by turning the components once at the middle point of each measure or at the quarter-section points.

Though the uniform practice in the Salt Lake base measure was to always read the bar scales in connection with the reversals, it is, nevertheless, obvious that it was entirely unnecessary to do so, for on account of construction and precision in workmanship, reversals of the components in nowise affect the continuity of their measures.

Simultaneously with these reversals occasion was taken, whenever required on account of the temperature of the day, to equalize the projecting components by shifting "brass" by means of the contact screws. The magnitudes of these shifts were determined by a special set of scale readings.

On completion of the measurement of the third kilometre, sufficient training and experience in the handling of the new apparatus had been acquired by the party to easily measure at the rate of 40 bars an hour, or a kilometre section in five hours. Moreover, as the real needs of the new apparatus, calculated to insure dispatch and accuracy, were being better understood, some modifications in the methods of procedure were introduced. For example, in order to strictly conform to the adopted plan of measurement, and to save the time and labor required to establish temporary line points, the first half of every kilometre section was completely measured in the morning and the second half in the afternoon of each day. A further modification which was adopted consisted in regularly equalizing the ends of the components of the first and last bars

of the half-kilometre measures by the mirror before attempting their transference to the ground marks. This, it will be seen, saved the independent reference of the brass component to "ground;" that is to say, on finishing the measure of a half section, "brass" was shifted forward or backward until normal with front of "steel." Reference of either "steel" or "brass" to ground was then made in the usual manner. For a check, the components were occasionally reversed and "steel" tested by transit pointings. But it should be remarked in this connection that on account of reversal of the components midway of the half-kilometre measures they are always in the reverse position at its end, i. e., "face down," and "brass" in the line of measure.

On resuming the measurement after the noon rest or in the morning, the components having previously been turned to the position "face up" and "steel" placed in the line of measure, the front end of "steel" of bar 15, the last bar of the preceding measure,* was always placed vertically over "ground" by means of the contact screw micrometer. To this end "ground" was picked up by transit pointings and "steel" brought into contact with vertical spider lines by means of the contact screw. A satisfactory contact having thus been effected, the reading of the contact screw micrometer was noted. Next the transit was reversed, leveled, and "ground" again picked up and brought to the height of "steel." If this second pointing proved imperfect, as was usually the case, on account of axis inclination, "steel" was again moved by the contact screw until in apparent tangency with the spider line of the transit and the micrometer reading noted the second time. Next the micrometer was set to the mean reading and "steel" assumed to be truly vertical over "ground." Next, by application of the plane mirror pressed gently against "steel," "brass" was shifted forward or backward until the direct and reflected images of the bar seemed in the straight line, and the front agates of the components were then assumed to be normal to the axis of the bar. The knife agates of bar No. 16, the *first* bar of the proposed *new* measure, were then brought into contact in the usual way with "*front*" of bar No. 15, placed as above explained, and the clamping of the contact slides to zero and the separate plumbing of "brass" to "ground" were thus obviated. In this first position bar No. 15 merely served to start the measure. The scale readings required at this juncture are those of the next two bars, i. e., Nos. 16 and 15, or the first two bars of the new measure.

With regard to ascertaining the total "shift" of "brass" for each half or whole section, i. e., for each 100 or 200 bars, from the scale readings direct and without necessity of reduction, it is suggested to carry the measure of each half section one bar beyond the section posts, or, better still, to read the scales of bar No. 15 after having been placed in position as just above explained for the beginning of a new measurement, as it will save the time of laying the extra bar.

These expedients were practiced in the Salt Lake base measure with much success. Should either of these prove at any time impracticable, as is not unlikely, then the relative total shift of "brass" upon "steel," as derived from the first and last scale readings for every $100-1=99$ bars, may be reduced to 100 bars by applying as a correction the difference between the actual scale readings of the last two bars laid and the corresponding "*normal difference*," namely, 40·075 centimeters, as before explained.

In order to insure ease and freedom in the longitudinal sliding of the bars, the "creases" in the rear bearing plates of the bars and the knife edges of the rear trestle were removed. The friction due to the great weight of the bars insures to them ample stability against slip on account of inclination without the former. As before stated, there is nothing in the whole operation which promotes speed of measurement so effectively as does rapidity in establishing the preliminary contact by the sliding of the bars bodily upon the trestles.

During progress of the base measurement the shelter sled, drawn by a pair of horses, was regularly hauled forward simultaneously with the launching of the rear bar, and while it and its trestles were being carried forward by the men. After a few days of training the sled moved along with remarkable precision and steadiness, starting at the instant of launching the rear bar, and stopping usually within a foot of the desired position at the ringing of a bell.

* In the Salt Lake base the measurement of each whole or half section commenced with bar No. 16 and finished with No. 15. The setting of the blunt front ends of the components normal to one another by means of the mirror is a matter much more readily accomplished than the setting of the contract slides to fiducial zero. In fact, this method was found to be so convenient, accurate, and expeditious that its adoption and practice in connection with the duplex is recommended.

The distribution of the operatives who participated in the Salt Lake base measure, together with the positions of the trestles and the bars under the sled during measurement, is shown in Plate No. 3. The sled, as before stated, proved a most admirable and valuable adjunct in the base measurement. On account of the numerous furrows and water ditches which crossed the base line, a shelter mounted on wheels could not have answered nearly as well.

The organization of the party, as given under the head of "Personnel of the party," exactly suited the needs of effective and uninterrupted handling of the duplex in the progress of the base measure. After thorough training its movements were characterized by a swing and precision of action more complete and more rhythmical than were perhaps ever before attained, certainly never excelled, by a base-measuring party. To fully appreciate this it must be borne in mind that the party broke all previous records by carrying the measure forward (by means of the ordinary field trestles) at the unprecedented rate of 70 bars per hour.

As of interest also, in conveying a clear conception of the magnitude of the work accomplished in the Salt Lake base measure, it may be remarked that 9,400 trestles were set on the natural ground and 4,700 bars laid.

The trestles used certainly possess considerable range of adaptability to peculiarities of the ground, but the cradle arms were found to be too weak and flexible for the double contact pressure of the duplex, notwithstanding they were always thoroughly clamped.

The setting of the trestles during an accurate and rapidly progressing measurement is a matter of much consequence. There is considerable knack, good judgment, and unbounded perseverance associated with it. To set a series of trestles at once to a uniform grade and with the needful stability is a task, if well performed, worthy of the highest recognition and acknowledgment.

In setting these 9,400 trestles of the base measure a creditable work was done. Judged by the grade corrections, which do not average as much as 3 centimetres per kilometre, it is very much to be questioned whether a better or more uniform series were ever before set than the series of 9,400 trestles of the Salt Lake base measure; in view of which it seems but fair to state that this creditable performance is due to the perseverance, the skill, and good judgment of Assistant H. P. Ritter of the Survey, and C. S. Wilkes, a civil engineer acting as foreman of the party.

The range of free motion in the contact slides, about 8 millimetres, practically renders the making of the approximate contacts largely a matter of chance. That is to say, on placing a new bar by sliding it bodily it is as likely that it will be laid too close as not close enough to the preceding one in position. The secret of rapid measurement—that is, the knack by which perfect contact is most readily effected—was found to consist in first establishing an approximate contact between the consecutive bars by sliding the bars bodily upon the trestles (partially relieved of their full bearing upon the rear trestles in order to diminish friction), after which "final contact" is quickly effected by a turn or two of the contact screws. But the utmost care must be exercised in thus bringing about the approximate contact to shield the agate knives against injury, which is perhaps most easily effected by pushing the contact slides back and placing the forefinger of the left hand in front of them. A sudden lurch or slip of the bar, should it inadvertently occur, may thus result in a "gentle squeeze" of the finger, but it will protect and save the agates from injury.

In the base measure this expedient was steadily practiced, and after some little experience had been gained final contact between the bars was established with surprising rapidity. It became quite evident, in fact, that the time required for bringing a bar into position is expended not in effecting precision of contact but in aligning the bars and adjusting their rear ends to proper height. To perfect the coincidence in the fiducial lines by means of the contact screws is, as a rule, a matter of but a few moments. The necessity of having to make two contacts for every bar placed thus proved to be neither an inconvenience nor a drawback as regarded the speed of measure with the duplex.

For the purpose of studying the behavior of the duplex with reference to the fluctuations of the temperatures of the air, three thermometers were regularly read every half hour during the measurement. For protection against radiant heat, etc., these were suspended on the shady

The Salt Lake Base Measure, Utah, 1896

Diagram showing the Disposition of the Party and the Apparatus, during Measurement, under the Shelter Sled



Personnel of the Party.

No. 1 Einbeck, Contacts.	*No. 8 Hand, Launching and carrying the Bars forward*
" 2 Gilbert, Inclin. Sectors & Thermo's.	*" 9 " " " " " " "*
" 3 Welker, Aligning, Thermo's; Scales.	*" 10 " Carrying released Trestles forward, etc.*
" 4 Ritter, Spacing & Aligning Trestles.	*" 11 " " " " " " "*
" 5 Yates, Recorder & Records.	*" 12 " Aiding in setting & adjusting Trestles.*
" 6 Lynch, Air Thermo's & Conductor of Sled.	*" 13 " " " " " " "*
" 7 Wilkes, Foreman & Rear Trestles.	*" 14 Driver of the Shelter Sled.*
	" 15 Hand setting aligning flags & opening wire Fences.

The Rear Bar was launched, the Trestles picked up and all carried forward. Simultaneously with starting up the Sled and moving it forward 5 Metres.

THE HOBBS PETERS CO. PHOTO-LITHO. WASHINGTON D.C.

side, within the shelter sled, about 6½ feet above the ground. A comparative examination of these temperatures demonstrated that the bar temperatures followed the fluctuations of the air temperatures very closely, seldom deviating therefrom by more than a couple of degrees, even during periods of rapid change. Thus the differences in the *mean* temperatures of the air and apparatus for each one of the two measurements of the base, for example, did not exceed 0°.4 C., the mean air temperature being the lower in both cases.

Since the reversal of the components requires the temporary removal of the thermometers from the bars, in order to prevent material change in their indications from exposure to the open air between times, the reversals were usually executed with dispatch and the thermometers immediately restored to their respective sockets.

The entire reliability of every observation—as the shifts of the brass components, scale readings, or "set-up" measure, etc.—which in any way entered into or affected the base measurement, was the subject of constant concern, and was accomplished, it is believed, through persistent watchfulness and independent verification, as far as necessary, by different observers. Nothing, in short, was left undone that in any manner seemed calculated to contribute to the completeness and the accuracy of the measurement or the record thereof. The relative shifts of the brass components, affecting as they do the continuity of the measure, were noted and controlled with especial care.

Inasmuch as a speed of 40 bars an hour easily admits of measuring a kilometre section in five hours, the time for daily measurement may be so chosen as to insure, in general, both rising and falling temperatures every day. In the Salt Lake base the daily measurements were therefore taken up as a rule at 10.30 in the morning and concluded at about 5 o'clock in the afternoon. By reducing the midday stop for rest to an hour, from 2 until 3 o'clock, the resumption of the measurement in the morning may safely be deferred until 11.30 and the afternoon measures may be continued until 5.30. There can be no question that the practicability of so timing and conducting the operations in the field as to insure measures for each of the half sections of the base under falling as well as rising temperatures has been fully established.

It may finally be remarked that measuring bars, whether thermically perfect or imperfect, will each give results entirely consistent in themselves, whether used under constant or variable temperature conditions, provided the latter be not too dissimilar. A mere agreement of the results of measure is therefore not to be accepted as positive proof of their reliability. In all such cases the question as to the *normal lengths* of a measure, or of the *thermal efficiency* of the apparatus, is liable to remain wholly obscure and indeterminate. In other words, the precision as well as the reliability of the results of measure, and the thermal perfection of the bar with which obtained, is satisfactorily determinable only by a mode of measuring either the same as or similar to that followed in the Salt Lake base measure.

Measuring a base line to an equal extent under rising and falling temperatures without regard to any such particular plan or method, while it will probably yield a true length for a *whole* base, can furnish no data from which the precision of the resulting measure may be with certainty inferred.

As the practical outcome of or the experience gained in the Salt Lake base measure, it may be safely asserted that, assuming a settled mode of field procedure and ordinary familiarity with the principles of its construction and action, the duplex will be found so simple and reliable an apparatus that if manipulated with but ordinary care its employment is bound to insure results of exceptional precision and reliability.

Referring now to the provisional results of this carefully measured base line, as given below, it will be seen that, in so far as their agreement seems qualified to bear out the preceding observations or to establish the thermic characteristics of the duplex apparatus, they leave no question as to its uncommon perfection both as a bimetallic and thermometric apparatus. The small differences in the measures for half sections, although not yet fully reduced and investigated, prove this beyond a reasonable doubt.

As computed from the results for the whole sections, both from the duplex and thermometric measures, the average relative precision attained is 1-5,000,000th part, which is as great as that obtainable by the Woodward 5-metre bar No. 17 in melting ice, and greater than that yet attained by any other field apparatus hitherto constructed and tried, either in this country or abroad.

Although the cost of measuring with the duplex can not be definitely estimated, being as a rule largely contingent on circumstances beyond control, it will nevertheless be useful to indicate that, owing to simplicity of its construction, portability, ease, and rapidity of manipulation, it can neither be essentially greater nor less than the cost of measuring with the monometallic apparatus of the Survey or metallic tapes and thermometers. Thus, for example, in the present case, in which, as we have seen, fully 23 kilometres were measured in twenty-three working days, i. e., within thirty days, inclusive of Sundays and days lost on account of unfavorable weather, etc., the total cost of the measurement of the base, including preparations, signals, marking, etc., but excluding pay and transportation of the five regular Coast Survey officers, was at the rate of about $100 per kilometre, single measure.

The personnel of the base-measuring party included the following officers:

William Eimbeck, Assistant and chief of party. Contacts between the duplex components and scale readings.

J. J. Gilbert, Assistant, rear bar alignments, inclination sectors, thermometers, transferences, and field computations;

P. A. Welker, Assistant, front bar alignments, thermometers, sector transit, inclination sectors, and verification of bar scales;

H. P. Ritter, Assistant, front trestles and transference of the bars to the ground marks;

Charles C. Yates, Assistant, keeper of the records and assisting in the field computations;

Buford Lynch, air thermometers and miscellaneous;

C. S. Wilkes, civil engineer, rear trestles and adjustment of the inclination sectors;

Certainly, in view of the exceptional success achieved in the Salt Lake base measure, etc., credit is due to these gentlemen for their able and untiring support.

In the restandardization of the duplex at Washington, I had the valuable assistance of the following officers, namely:

P. A. Welker, W. I. Vinal, G. R. Putnam, R. L. Faris, and Chas. C. Yates, Assistants, and L. A. Fischer, Adjuster of the office of Standard Weights and Measures, and E. G. Fischer, Chief Mechanician of the Coast and Geodetic Survey.

The shelter sled referred to on page 765 was constructed by Assistant J. J. Gilbert in conformity with general suggestions made by the writer. The substitution of the ordinary sled runners for wheels, such as were used on the Yolo shelter carriage, proved in every way a success. The actual execution of the measurement of the base under the protection of this sled required fifteen persons.

The practicability of constructing equally efficient measuring bars, in conformity with either the thermometric or the bimetallic type, seems fully demonstrated by the remarkable accordance of the results obtained in this measurement. Moreover, if it be borne in mind that the Duplex yields from every single measurement *three* separate results, whose degree of concordance establishes not only their entire trustworthiness but throws also much light upon the thermal behavior of the apparatus and the care with which it was manipulated during the measurement, it would seem to be warranted to assign to it first place among the accepted base apparatus of the day. No other bars hitherto used in geodetic work can lay claim, in my judgment, to so unique and practically significant a distinction.