MICROGRAPHIA:

OR SOME

Physiological Descriptions

OF

MINUTE BODIES

MADE BY

MAGNIFYING GLASSES.

WITH

OBSERVATIONS and INQUIRIES thereupon.

By *R. HOOKE*, Fellow of the ROYAL SOCIETY.

Non possis oculo quantum contendere Linceus,
Non tamen idcirco contemnas Lippus inungi. Horat. Ep. Lib. 1.



LONDON, Printed for *James Allestry*, Printer to the ROYAL SOCIETY, and are to be sold at his Shop, at the *Rose* and *Crown* in *Duck-Lane*. MDCLXVII.

National Oceanic and Atmospheric Administration

Rare Books from 1600-1800

ERRATA NOTICE

One or more conditions of the original document may affect the quality of the image, such as:

Discolored pages
Faded or light ink
Binding intrudes into the text

This has been a co-operative project between the NOAA Central Library, the Climate Database Modernization Program, National Climate Data Center (NCDC) and the NOAA 200th Celebration. To view the original document, please contact the NOAA Central Library in Silver Spring, MD at (301) 713-2607 x124 or at Library.Reference@noaa.gov

HOV Services
Imaging Contractor
12200 Kiln Court
Beltsville, MD 20704-1387
April 14, 2008

By the Council of the Royal Society of *London* for Improving of Natural Knowledge.

Ordered, *That the Book written by* Robert Hooke, *M. A. Fellow of this Society, Entitled,* Micrographia, or ſome Phyſiological Deſcriptions of Minute Bodies, made by Magnifying Glaſſes, with Obſervations and Inquiries thereupon, *Be Printed by* John Martyn, *and* James Alleſtry, *Printers to the ſaid Society.*

Novem. 23.
1664.

BROUNCKER. *P. R. S.*

OB
H752

QH
271
H66
1667

TO THE KING.

SIR,

I Do here most humbly lay this *small* Present at *Your Majesties* Royal feet. And though it comes accompany'd with two *disadvantages*, the *meanness* of the *Author*, and of the *Subject*; yet in both I am *incouraged* by the *greatness* of your *Mercy* and your *Knowledge*. By the *one* I am taught, that you can

 forgive

forgive the moſt *preſumptuous Offendors:* And by the *other*, that you will not *eſteem* the leaſt work of *Nature*, or *Art*, unworthy your *Obſervation.* Amidſt the many *felicities* that have accompani'd *your Majeſties* happy *Reſtauration* and *Government*, it is none of the leaſt conſiderable, that *Philoſophy* and *Experimental Learning* have *proſper'd* under your *Royal Patronage.* And as the calm proſperity of your Reign has given us the *leiſure* to follow theſe *Studies* of *quiet* and *retirement*, ſo it is juſt, that the *Fruits* of them ſhould, by way of *acknowledgement*, be return'd to *your Majeſty.* There are, Sir, ſeveral other of your Subjects, of your *Royal Society*, now buſie about *Nobler* matters: The *Improvement* of *Manufactures* and *Agriculture*, the *Increaſe* of *Commerce*, the *Advantage* of *Navigation*: In all which they are *aſsiſted* by *your Majeſties Incouragement* and *Example.* Amidſt all thoſe

greater

greater Designs, I here presume to bring in that which is more *proportionable* to the *smalness* of my Abilities, and to offer some of the *least* of all *visible things*, to that *Mighty King*, that has *establisht an Empire* over the best of all *Invisible things* of this World, the *Minds* of Men.

Your Majesties most humble

and most obedient

Subject and Servant,

ROBERT HOOKE.

TO THE

ROYAL SOCIETY.

AFter my *Addreſs* to our *Great Founder* and *Patron*, I could not but think my ſelf oblig'd, in conſideration of thoſe *many Ingagements* you have laid upon me, to offer theſe my *poor Labours* to this MOST ILLUSTRIOUS ASSEMBLY. YOU have been pleas'd formerly to accept of theſe rude *Draughts*. I have ſince added to them ſome *Deſcriptions*, and ſome *Conjectures* of my own. And therefore, together with YOUR *Acceptance*, I muſt alſo beg YOUR *pardon*. The Rules YOU have preſcrib'd YOUR ſelves in YOUR Philoſophical Progreſs do ſeem the beſt that have ever yet been practis'd. And particularly that of avoiding *Dogmatizing*, and the *eſpouſal* of any *Hypotheſis* not ſufficiently grounded and confirm'd by *Experiments*. This way ſeems the moſt excellent, and may preſerve both *Philoſophy* and *Natural Hiſtory* from its former *Corruptions*. In ſaying which, I may ſeem to condemn my own Courſe in this Treatiſe; in which there may perhaps be ſome *Expreſſions*, which may ſeem more *poſitive* then YOUR Preſcriptions will permit: And though I deſire to have them underſtood only as *Conjectures* and *Quæries* (which YOUR Method does not altogether diſallow) yet if even in thoſe I have exceeded, 'tis fit that I ſhould declare, that it was not done by YOUR Directions. For it is moſt unreaſonable, that YOU ſhould undergo the *imputation* of the *faults* of my *Conjectures*, ſeeing YOU can receive ſo *ſmall advantage* of reputation by the *ſleight Obſervations* of

YOUR moſt humble and
moſt faithful Servant

ROBERT HOOKE.

THE PREFACE.

IT is the great prerogative of Mankind above other Creatures, that we are not only able to behold *the works of Nature, or barely to* ſuſtein *our lives by them, but we have alſo the power of* conſidering, comparing, altering, aſſiſting, *and* improving *them to various uſes. And as this is the peculiar priviledge of humane Nature in general, ſo is it capable of being ſo far advanced by the helps of Art, and Experience, as to make ſome Men excel others in their Obſervations, and Deductions, almoſt as much as they do Beaſts. By the addition of ſuch* artificial Inſtruments *and* methods, *there may be, in ſome manner, a reparation made for the miſchiefs, and imperfection, mankind has drawn upon it ſelf, by negligence, and intemperance, and a wilful and ſuperſtitious deſerting the Preſcripts and Rules of Nature, whereby every man, both from a deriv'd corruption, innate and born with him, and from his breeding and converſe with men, is very ſubject to ſlip into all ſorts of errors.*

The only way which now remains for us to recover ſome degree of thoſe former perfections, ſeems to be, by rectifying the operations of the Senſe, *the* Memory, *and* Reaſon, *ſince upon the evidence, the* ſtrength, *the* integrity, *and the* right correſpondence *of all theſe, all the light, by which our actions are to be guided, is to be renewed, and all our command over things is to be eſtabliſht.*

It is therefore moſt worthy of our conſideration, to recollect their ſeſeveral defects, that ſo we may the better underſtand how to ſupply them, and by what aſſiſtances we may inlarge *their power, and* ſecure *them in performing their particular duties.*

As for the actions of our Senſes, *we cannot but obſerve them to be in*

many

many particulars much outdone by those of other Creatures, and when at best, to be far short of the perfection they seem capable of: And these infirmities of the Senses arise from a double cause, either from the disproportion of the Object to the Organ, *whereby an infinite number of things can never enter into them, or else from* error in the Perception, *that many things, which come within their reach, are not received in a right manner.*

The like frailties are to be found in the Memory; *we often let many things* slip away *from us, which deserve to be retain'd; and of those which we treasure up, a great part is either* frivolous *or* false; *and if good, and substantial, either in tract of time* obliterated, *or at best so* overwhelmed *and buried under more frothy notions, that when there is need of them, they are in vain sought for.*

The two main foundations being so deceivable, it is no wonder, that all the succeeding works which we build upon them, of arguing, concluding, defining, judging, and all the other degrees of Reason, are lyable to the same imperfection, being, at best, either vain, or uncertain: So that the errors of the understanding *are answerable to the two other, being defective both in the quantity and goodness of its knowledge; for the limits, to which our thoughts are confi nd, are small in respect of the vast extent of Nature it self; some parts of it are* too large *to be comprehended, and some* too little *to be perceived. And from thence it must follow, that not having a full sensation of the Object, we must be very lame and imperfect in our conceptions about it, and in all the propositions which we build upon it; hence we often take the* shadow *of things for the* substance, *small* appearances *for good* similitudes, similitudes *for* definitions; *and even many of those, which we think to be the most solid definitions, are rather expressions of our own misguided apprehensions then of the true nature of the things themselves.*

The effects of these imperfections are manifested in different ways, according to the temper and disposition of the several minds of men, some they incline to gross ignorance *and stupidity, and others to a* presumptuous imposing *on other mens Opinions, and a* confident dogmatizing *on matters, whereof there is no assurance to be given.*

Thus

Thus all the uncertainty, and mistakes of humane actions, proceed either from the narrowness and wandring of our Senses, *from the slipperiness or delusion of our* Memory, *from the confinement or rashness of our* Understanding, *so that 'tis no wonder, that our power over natural causes and effects is so slowly improv'd, seeing we are not only to contend with the obscurity and* difficulty of the things *whereon we work and think, but even the* forces of our own minds *conspire to betray us.*

These being the dangers in the process of humane Reason, the remedies of them all can only proceed from the real, *the* mechanical, *the* experimental *Philosophy, which has this advantage over the Philosophy of* discourse *and* disputation, *that whereas that chiefly aims at the subtilty of its Deductions and Conclusions, without much regard to the first ground-work, which ought to be well laid on the Sense and Memory; so this intends the right ordering of them all, and the making them serviceable to each other.*

The first thing to be undertaken in this weighty work, is a watchfulness over the failings *and an* inlargement of the dominion, *of the Senses.*

To which end it is requisite, first, That there should be a scrupulous *choice, and a* strict examination, *of the reality, constancy, and certainty of the Particulars that we admit: This is the first rise whereon truth is to begin, and here the most severe, and most impartial diligence, must be imployed; the storing up of all, without any regard to evidence or use, will only tend to darkness and confusion. We must not therefore esteem the riches of our Philosophical treasure by the* number *only, but chiefly by the* weight; *the most* vulgar *Instances are not to be neglected, but above all, the most* instructive *are to be entertain'd; the footsteps of Nature are to be trac'd, not only in her* ordinary course, *but when she seems to be put to her shifts, to make many* doublings *and* turnings, *and to use some kind of art in indeavouring to avoid our discovery.*

The next care to be taken, in respect of the Senses, is a supplying of their infirmities with Instruments, *and, as it were, the adding of* artificial Organs *to the* natural; *this in one of them has been of late years*

accom-

accomplisht with prodigious benefit to all sorts of useful knowledge, by the invention of Optical Glasses. By the means of Telescopes, *there is nothing so* far distant *but may be represented to our view; and by the help of* Microscopes, *there is nothing so* small, *as to escape our inquiry; hence there is a new visible World discovered to the understanding. By this means the Heavens are open'd, and a vast number of new Stars, and new Motions, and new Productions appear in them, to which all the antient Astronomers were utterly Strangers. By this the Earth it self, which lyes so neer us, under our feet, shews quite a new thing to us, and in every* little particle *of its matter, we now behold almost as great a variety of Creatures, as we were able before to reckon up in the whole* Universe *it self.*

It seems not improbable, but that by these helps the subtilty of the composition of Bodies, the structure of their parts, the various texture of their matter, the instruments and manner of their inward motions, and all the other possible appearances of things, may come to be more fully discovered; all which the antient Peripateticks *were content to comprehend in two general and (unless further explain'd) useless words of* Matter *and* Form. *From whence there may arise many admirable advantages, towards the increase of the* Operative, *and the* Mechanick *Knowledge, to which this Age seems so much inclined, because we may perhaps be inabled to discern all the secret workings of Nature, almost in the same manner as we do those that are the productions of Art, and are manag'd by Wheels, and Engines, and Springs, that were devised by humane Wit.*

In this kind I here present to the World my imperfect Indeavours; which though they shall prove no other way considerable, yet, I hope, they may be in some measure useful to the main Design of a reformation *in Philosophy, if it be only by shewing, that there is not so much requir'd towards it, any strength of* Imagination, *or exactness of* Method, *or depth of* Contemplation (*though the addition of these, where they can be had, must needs produce a much more perfect composure*) *as a* sincere Hand, *and a* faithful Eye, *to examine, and to record, the things themselves as they appear.*

And

And I beg my Reader, to let me take the boldness to assure him, that in this present condition of knowledge, a man so qualified, as I have indeavoured to be, only with resolution, and integrity, and plain intentions of imploying his Senses *aright, may venture to compare the reality and the usefulness of his services, towards the true Philosophy, with those of other men, that are of much stronger, and more acute* speculations, *that shall not make use of the same method by the Senses.*

The truth is, the Science of Nature has been already too long made only a work of the Brain *and the* Fancy: *It is now high time that it should return to the plainness and soundness of* Observations *on* material *and* obvious *things. It is said of great Empires, That* the best way to preserve them from decay, is to bring them back to the first Principles, and Arts, on which they did begin. *The same is undoubtedly true in Philosophy, that by wandring far away into* invisible Notions, *has almost quite destroy'd it self, and it can never be recovered, or continued, but by returning into the same* sensible paths, *in which it did at first proceed.*

If therefore the Reader expects from me any infallible Deductions, or certainty of Axioms, *I am to say for my self, that those stronger Works of Wit and Imagination are above my weak Abilities; or if they had not been so, I would not have made use of them in this present Subject before me: Whereever he finds that I have ventur'd at any small Conjectures, at the causes of the things that I have observed, I beseech him to look upon them only as* doubtful Problems, *and* uncertain ghesses, *and not as unquestionable Conclusions, or matters of unconfutable Science; I have produced nothing here, with intent to bind his understanding to an* implicit *consent; I am so far from that, that I desire him, not absolutely to rely upon these Observations of my eyes, if he finds them contradicted by the future Ocular Experiments of sober and impartial Discoverers.*

As for my part, I have obtained my end, if these my small Labours shall be thought fit to take up some place in the large stock of natural Observations, *which so many hands are busie in providing. If I have contributed the* meanest foundations *whereon others may raise nobler*

Superstructures, *I am abundantly satisfied; and all my ambition is, that I may serve to the great Philosophers of this Age, as the makers and the grinders of my Glasses did to me; that I may prepare and furnish them with some* Materials, *which they may afterwards* order *and* manage *with better skill, and to far greater advantage.*

The next remedies in this universal cure of the Mind are to be applyed to the Memory, *and they are to consist of such Directions as may inform us, what things are best to be* stor'd up *for our purpose, and which is the best way of so* disposing *them, that they may not only be* kept in safety, *but ready and convenient, to be at any time* produc'd *for use, as occasion shall require. But I will not here prevent my self in what I may say in another Discourse, wherein I shall make an attempt to propose some Considerations of the manner of compiling a Natural and Artificial History, and of so ranging and registring its Particulars into Philosophical Tables, as may make them most useful for the raising of* Axioms *and* Theories.

The last indeed is the most hazardous *Enterprize, and yet the most* necessary; *and that is, to take such care that the* Judgment *and the* Reason *of Man (which is the third Faculty to be repair'd and improv'd) should receive such assistance, as to avoid the dangers to which it is by nature most subject. The Imperfections, which I have already mention'd, to which it is lyable, do either belong to the* extent, *or the* goodness *of its knowledge; and here the difficulty is the greater, least that which may be thought a* remedy *for the one should prove* destructive *to the other, least by seeking to inlarge our Knowledge, we should render it weak and uncertain; and least by being too scrupulous and exact about every Circumstance of it, we should confine and streighten it too much.*

In both these the middle wayes are to be taken, nothing is to be omitted, *and yet every thing to pass a* mature deliberation: *No* Intelligence *from Men of all Professions, and quarters of the World, to be* slighted, *and yet all to be so* severely examin'd, *that there remain no room for doubt or instability; much* rigour *in admitting, much* strictness *in comparing, and above all, much* slowness *in debating, and*

shyness

shyness *in determining, is to be practised. The* Understanding *is to* order *all the inferiour services of the lower Faculties; but yet it is to do this only as a* lawful Master, *and not as a* Tyrant. *It must not* incroach *upon their Offices, nor take upon it self the employments which belong to either of them. It must* watch *the irregularities of the Senses, but it must not go before them, or* prevent *their information. It must* examine, range, *and* dispose *of the bank which is laid up in the Memory; but it must be sure to make* distinction *between the* sober *and* well collected heap, *and the* extravagant Idea's, *and* mistaken Images, *which there it may sometimes light upon. So many are the* links, *upon which the true Philosophy depends, of which, if any one be* loose, *or* weak, *the whole* chain *is in danger of being dissolv'd; it is to* begin *with the Hands and Eyes, and to* proceed *on through the Memory, to be* continued *by the Reason; nor is it to stop there, but to* come about *to the Hands and Eyes again, and so, by a* continual passage round *from one Faculty to another, it is to be maintained in life and strength, as much as the body of man is by the* circulation *of the blood through the several parts of the body, the Arms, the Fat, the Lungs, the Heart, and the Head.*

If once this method were followed with diligence and attention, there is nothing that lyes within the power of human Wit (or which is far more effectual) of human Industry, which we might not compass; we might not only hope for Inventions to equalize those of Copernicus, Galileo, Gilbert Harvy, *and of others, whose Names are almost lost, that were the Inventors of* Gun-powder, *the* Seamans Compass, Printing, Etching, Graving, Microscopes, &c. *but multitudes that may far exceed them: for even those discoveries seem to have been the products of some such method, though but imperfect; What may not be therefore expected from it if thoroughly prosecuted?* Talking *and* contention of Arguments *would soon be turn'd into* labours; *all the fine* dreams *of Opinions, and* universal metaphysical natures, *which the luxury of subtil Brains has devis'd, would quickly vanish, and give place to* solid Histories, Experiments *and* Works. *And as at first, mankind* fell *by* tasting *of the forbidden Tree of Knowledge, so we, their Posterity, may be in part* restor'd

by

by the same way, not only by beholding *and* contemplating, *but by* tasting *too those fruits of Natural knowledge, that were never yet forbidden.*

From hence the World may be assisted with variety *of Inventions,* new *matter for Sciences may be* collected, *the* old improv'd, *and their* rust *rubb'd away; and as it is by the benefit of Senses that we receive all our Skill in the works of Nature, so they also may be wonderfully benefited by it, and may be guided to an easier and more exact performance of their Offices; 'tis not unlikely, but that we may find out wherein our Senses are deficient, and as easily find wayes of repairing them.*

The Indeavours of Skilful men have been most conversant about the assistance of the Eye, and many noble Productions have followed upon it; and from hence we may conclude, that there is a way open'd for advancing the operations, not only of all the other Senses, but even of the Eye it self; that which has been already done ought not to content us, but rather to incourage us to proceed further, and to attempt greater things in the same and different wayes.

'Tis not unlikely, but that there may be yet invented several other helps for the eye, as much exceeding those already found, as those do the bare eye, such as by which we may perhaps be able to discover living Creatures *in the Moon, or other Planets, the* figures *of the compounding Particles of matter, and the particular* Schematisms *and* Textures *of Bodies.*

And as Glasses *have highly promoted our* seeing, *so 'tis not improbable, but that there may be found many* Mechanical Inventions *to improve our other Senses, of* hearing, smelling, tasting, touching. *'Tis not impossible to hear a* whisper *a* furlongs *distance, it having been already done; and perhaps the nature of the thing would not make it more impossible, though that furlong should be ten times multiply'd. And though some famous Authors have affirm'd it impossible to hear through the* thinnest plate *of* Muscovy-glass; *yet I know a way, by which 'tis easie enough to hear one speak through a* wall a yard thick. *It has not been yet thoroughly examin'd, how far* Otocousticons *may be improv'd, nor what other wayes there may be of* quickning *our hearing, or* conveying *sound through* other bodies *then the* Air: *for that that is not the only* medium, *I can assure the Reader, that I have, by the help of a* distended wire, *propagated*

gated the sound to a very considerable distance in an instant, *or with as seemingly quick a motion as that of light, at least, incomparably swifter then that, which at the same time was propagated through the Air; and this not only in a straight line, or direct, but in one bended in many angles.*

Nor are the other three so perfect, but that diligence, attention, *and many* mechanical contrivances, *may also highly improve them. For since the sense of* smelling *seems to be made by the* swift passage *of the* Air (impregnated *with the steams and* effluvia *of several odorous Bodies) through the grisly* meanders *of the Nose whose surfaces are* cover'd *with a very sensible* nerve, *and* moistned *by a* transudation *from the* processus mamillares *of the Brain, and some adjoyning* glandules, *and by the moist* steam *of the* Lungs, *with a Liquor convenient for the reception of those* effluvia *and by the adhesion and mixing of those steams with that liquor, and thereby affecting the nerve, or perhaps by insinuating themselves into the juices of the brain, after the same manner, as I have in the following Observations intimated, the parts of Salt to pass through the skins of Effs, and Frogs. Since, I say, smelling seems to be made by some such way, 'tis not improbable, but that some contrivance, for making a great quantity of Air pass quick through the Nose, might as much promote the sense of smelling, as the any wayes hindring that passage does dull and destroy it. Several tryals I have made, both of hindring and promoting this sense, and have succeeded in some according to expectation; and indeed to me it seems capable of being improv'd, for the judging of the constitutions of many Bodies. Perhaps we may thereby also judge (as other Creatures seem to do) what is wholsome, what poyson; and in a word, what are the specifick properties of Bodies.*

There may be also some other mechanical wayes found out, of sensibly perceiving the effluvia *of Bodies; several Instances of which, were it here proper, I could give of Mineral steams and exhalations; and it seems not impossible, but that by some such wayes improved, may be discovered, what Minerals lye buried under the Earth, without the trouble to dig for them; some things to confirm this Conjecture may be found in* Agricola, *and other Writers of Minerals, speaking of the Vegetables that are apt to thrive, or pine, in those steams.*

 Whether

Whether also those steams, which seem to issue out of the Earth, and mix with the Air (and so to precipitate some aqueous *Exhalations, wherewith 'tis impregnated), may not be by some way detected before they produce the effect, seems hard to determine; yet something of this kind I am able to discover, by an Instrument I contriv'd to shew all the minute variations in the pressure of the Air; by which I constantly find, that before, and during the time of rainy weather, the pressure of the Air is less, and in* dry weather, *but especially when an* Eastern Wind *(which having past over vast tracts of Land is heavy with Earthy Particles) blows, it is much more, though these changes are varied according to very odd Laws.*

The Instrument is this. I prepare a pretty capaceous Bolt-head A B, with a small stem about two foot and a half long D C; upon the end of this D I put on a small bended Glass, or brazen *Syphon* D E F (open at D, E and F, but to be closed with cement at F and E, as occasion serves) whose stem F should be about six or eight inches long, but the bore of it not above half an inch diameter, and very even; these I fix very strongly together by the help of very hard Cement, and then fit the whole Glass A B C D E F into a long Board, or Frame, in such manner, that almost half the head A B may lye buried in a concave Hemisphere cut into the Board R S; then I place it so on the Board R S, as is exprest in the first Figure of the first Scheme; and fix it very firm and steady in that posture, so as that the weight of the *Mercury* that is afterwards to be put into it, may not in the least shake or stir it; then drawing a line X Y on the Frame R T, so that it may divide the ball into two equal parts, or that it may pass, as 'twere, through the center of the ball. I begin from that, and divide all the rest of the Board towards U T into inches, and the inches between the 25 and the end E (which need not be above two or three and thirty inches distant from the line X Y) I subdivide into Decimals; then stopping the end F with soft Cement, or soft Wax, I invert the Frame, placing the head downwards, and the Orifice E upwards; and by it, with a small Funnel, I fill the whole Glass with Quicksilver; then by stopping the small Orifice E with my finger, I oftentimes erect and invert the whole Glass and Frame, and thereby free the Quicksilver and Glass from all the bubbles or parcels of lurking Air; then inverting it as before, I fill it top full with clear and well strain'd Quicksilver, and having made ready a small ball of pretty hard Cement, by heat made very soft, I press it into the hole E, and thereby stop it very fast; and to secure this Cement from flying out afterward, I bind over it a piece of Leather, that is spread over in the inside with Cement, and wound about it whilst the Cement is hot: Having thus fastned it, I gently erect again the Glass after this manner: I first let the Frame down edge-wayes, till the edge R V touch the Floor, or ly horizontal; and then in that edging posture raise the end R S; this I do, that if there chance to be any Air hidden in the small Pipe E, it may ascend into the Pipe F, and not into the Pipe D C: Having thus erected it, and hung it by the hole Q, or fixt it perpendicularly by any other means, I open the end F,

and

and by a ſmall *Syphon* I draw out the *Mercury* ſo long, till I find the ſurface of it AB in the head to touch exactly the line XY; at which time I immediately take away the *Syphon*, and if by chance it be run ſomewhat below the line XY, by pouring in gently a little *Mercury* at F, I raiſe it again to its deſired height, by this contrivance I make all the ſenſible riſing and falling of the *Mercury* to be viſible in the ſurface of the *Mercury* in the Pipe F, and ſcarce any in the head AB. But becauſe there really is ſome ſmall change of the upper ſurface alſo, I find by ſeveral Obſervations how much it riſes in the Ball, and falls in the Pipe F, to make the diſtance between the two ſurfaces an inch greater then it was before; and the meaſure that it falls in the Pipe is the length of the inch by which I am to mark the parts of the Tube F, or the Board on which it lyes, into inches and Decimals: Having thus juſtned and divided it, I have a large Wheel MNOP, whoſe outmoſt limb is divided into two hundred equal parts; this by certain ſmall Pillars is fixt on the Frame RT, in the manner expreſt in the Figure. In the middle of this, on the back ſide, in a convenient frame, is placed a ſmall Cylinder, whoſe circumference is equal to twice the length of one of thoſe diviſions, which I find anſwer to an inch of aſcent, or deſcent, of *Mercury*: This Cylinder I, is movable on a very ſmall Needle, on the end of which is fixt a very light Index KL, all which are ſo pois'd on the Axis, or Needle, that no part is heavier then another: Then about this Cylinder is wound a ſmall Clew of Silk, with two ſmall ſteel Bullets at each end of it GH; one of theſe, which is ſomewhat the heavier, ought to be ſo big, as freely to move to and fro in the Pipe F; by means of which contrivance, every the leaſt variation of the height of the *Mercury* will be made exceeding viſible by the motion to and fro of the ſmall Index KL.

But this is but one way of diſcovering the effluvia *of the Earth mixt with the Air; there may be perhaps many others, witneſs the* Hygroſcope, *an Inſtrument whereby the watery ſteams volatile in the Air are diſcerned, which the Noſe it ſelf is not able to find. This I have deſcrib'd in the following Tract in the Deſcription of the Beard of a wild Oat. Others there are, may be diſcovered both by the Noſe, and by other wayes alſo. Thus the* ſmoak *of burning* Wood *is* ſmelt, ſeen, *and ſufficiently* felt *by the eyes: The* fumes *of burning* Brimſtone *are* ſmelt *and diſcovered alſo by the deſtroying the Colours of Bodies, as by the* whitening of a red Roſe: *And who knows, but that the Induſtry of man, following this method, may find out wayes of improving this ſenſe to as great a degree of perfection as it is in any Animal, and perhaps yet higher.*

'Tis not improbable alſo, but that our taſte *may be very much improv'd, either by* preparing *our taſt for the Body, as, after eating* bitter *things,* Wine, *or other* Vinous liquors, *are more ſenſibly taſted; or elſe by* pre-

paring

paring *Bodies for our taſt; as the diſſolving of Metals with acid Liquors, make them taſtable, which were before altogether inſipid; thus* Lead *becomes* ſweeter *then Sugar, and* Silver *more* bitter *then Gall,* Copper *and* Iron *of moſt* loathſome *taſts. And indeed the buſineſs of this ſenſe being to diſcover the preſence of diſſolved Bodies in Liquors put on the Tongue, or in general to diſcover that a fluid body has ſome ſolid body diſſolv'd in it, and what they are; whatever contrivance makes this diſcovery improves this ſenſe. In this kind the mixtures of Chymical Liquors afford many Inſtances; as the ſweet Vinegar that is impregnated with Lead may be diſcovered to be ſo by the affuſion of a little of an* Alcalizate ſolution: *The bitter liquor of* Aqua fortis *and* Silver *may be diſcover'd to be charg'd with that Metal, by laying in it ſome plates of Copper: 'Tis not improbable alſo, but there may be multitudes of other wayes of diſcovering the parts diſſolv'd, or diſſoluble in liquors; and what is this diſcovery but a kind of* ſecundary taſting.

'Tis not improbable alſo, but that the ſenſe of feeling *may be highly improv'd, for that being a ſenſe that judges of the more* groſs *and* robuſt motions *of the* Particles *of* Bodies, *ſeems capable of being improv'd and aſſiſted very many wayes. Thus for the diſtinguiſhing of* Heat *and* Cold, *the* Weather-glaſs *and* Thermometer, *which I have deſcrib'd in this following Treatiſe, do exceedingly perfect it; by each of which the leaſt variations of heat or cold, which the moſt Acute ſenſe is not able to diſtinguiſh, are manifeſted This is oftentimes further promoted alſo by the help of* Burning-glaſſes, *and the like, which collect and unite the radiating heat. Thus the* roughneſs *and* ſmoothneſs *of a Body is made much more ſenſible by the help of a* Microſcope, *then by the moſt* tender *and* delicate Hand. *Perhaps, a Phyſitian might, by ſeveral other* tangible *proprieties, diſcover the conſtitution of a Body as well as by the* Pulſe. *I do but inſtance in theſe, to ſhew what poſſibility there may be of many others, and what probability and hopes there were of finding them, if this method were followed; for the Offices of the five Senſes being to detect either the* ſubtil *and* curious Motions *propagated through all* pellucid *or perfectly* homogeneous *Bodies; Or the more* groſs *and* vibrative Pulſe *communicated through the* Air *and all other convenient* mediums, *whether fluid or ſolid: Or the*

effluvia

effluvia *of Bodies* diſſolv'd *in the* Air ; *Or the* particles *of bodies* diſſolv'd *or* diſſoluble *in* Liquors, *or the more* quick *and* violent ſhaking motion *of* heat *in all or any of theſe: whatſoever does any wayes promote any of theſe kinds of* criteria, *does afford a way of improving ſome one ſenſe. And what a multitude of theſe would a diligent Man meet with in his inquiries? And this for the helping and promoting the* ſenſitive faculty *only.*

Next, as for the Memory, *or* retentive faculty, *we may be ſufficiently inſtructed from the* written Hiſtories *of* civil actions, *what great aſſiſtance may be afforded the Memory, in the committing to writing things obſervable in* natural operations. *If a Phyſitian be therefore accounted the more able in his Faculty, becauſe he has had long experience and practice, the remembrance of which, though perhaps very imperfect, does regulate all his after actions: What ought to be thought of that man, that has not only a perfect* regiſter *of his own experience, but is grown* old *with the experience of many hundreds of years, and many thouſands of men.*

And though of late, men, beginning to be ſenſible of this convenience, have here and there regiſtred and printed ſome few Centuries, *yet for the moſt part they are ſet down very lamely and imperfectly, and, I fear, many times not ſo truly, they ſeeming, ſeveral of them, to be deſign'd more for* Oſtentation *then* publique uſe: *For, not to inſtance, that they do, for the moſt part, omit thoſe Experiences they have made, wherein their Patients have miſcarried, it is very eaſie to be perceiv'd, that they do all along* hyperbolically extol *their own Preſcriptions, and viliſie thoſe of others. Notwithſtanding all which, theſe kinds of Hiſtories are generally eſteem'd uſeful, even to the ableſt Phyſitian.*

What may not be expected from the rational *or* deductive Faculty *that is furniſht with ſuch* Materials, *and thoſe ſo readily* adapted, *and rang'd for uſe, that in a moment, as 'twere, thouſands of Inſtances, ſerving for the* illuſtration, determination, *or* invention, *of almoſt any inquiry, may be* repreſented *even to the ſight? How neer the nature of* Axioms *muſt all thoſe* Propoſitions *be which are examin'd before ſo many* Witneſſes? *And how difficult will it be for any, though never ſo ſubtil an error in Philoſophy, to* ſcape *from being diſcover'd, after it has indur'd the* touch, *and ſo many other* tryals?

 What

What kind of mechanical way, and physical invention also is there requir'd, that might not this way be found out? The Invention *of a way to find the* Longitude *of places is easily perform'd, and that to as great* perfection *as is desir'd, or to as great an* accuratenes *as the* Latitude *of places can be found at Sea; and perhaps yet also to a greater certainty then that has been hitherto found, as I shall very speedily freely manifest to the world. The way of* flying *in the Air seems principally unpracticable, by reason of the* want of strength *in* humane muscles; *if therefore that could be suppli'd, it were, I think, easie to make twenty contrivances to perform the office of* Wings: *What Attempts also I have made for the supplying that Defect, and my successes therein, which, I think, are wholly new, and not inconsiderable, I shall in another place relate.*

'Tis not unlikely also, but that Chymists, *if they followed this method, might find out their so much sought for* Alkahest. *What an* universal Menstruum, *which dissolves all sorts of* Sulphureous Bodies, *I have discover'd (which has not been before taken notice of as such) I have shewn in the sixteenth Observation.*

What a prodigious variety of Inventions in Anatomy *has this latter Age afforded, even in our own Bodies, in the very* Heart, *by which we live, and the* Brain, *which is the seat of our knowledge of other things? witness all the excellent Works of* Pecquet, Bartholinus, Billius, *and many others; and at home, of Doctor* Harvy, *Doctor* Ent, *Doctor* Willis, *Doctor* Glisson. *In* Celestial Observations *we have far exceeded all the Antients, even the* Chaldeans *and* Egyptians *themselves, whose* vast Plains, high Towers, *and* clear Air, *did not give them so great advantages over us, as we have over them by our* Glasses. *By the help of which, they have been very much outdone by the famous* Galileo, Hevelius, Zulichem; *and our own Countrymen, Mr.* Rook, *Doctor* Wren, *and the great Ornament of our Church and Nation, the* Lord Bishop of Exeter. *And to say no more in* Aerial Discoveries, *there has been a wonderful progress made by the* Noble Engine *of* the most Illustrious Mr. Boyle, *whom it becomes me to mention with all honour, not only as my particular Patron, but as the* Patron *of* Philosophy *it self; which he every day* increases *by his* Labours, *and* adorns *by his* Example.

The

The good ſucceſs of all theſe great Men, *and many others, and the now ſeemingly great* obvioufneſs *of moſt of their and divers other Inventions, which from the beginning of the world have been, as 'twere, trod on, and yet not minded till theſe laſt* inquiſitive *Ages (an Argument that there may be yet behind multitudes of the like) puts me in mind to recommend ſuch Studies, and the proſecution of them by ſuch methods, to the* Gentlemen *of our Nation, whoſe* leiſure *makes them fit to* undertake, *and the* plenty *of their fortunes to* accompliſh, *extraordinary things in this way. And I do not only propoſe this kind of* Experimental Philoſophy *as a matter of high* rapture *and* delight *of the mind, but even as a* material *and* ſenſible Pleaſure. *So vaſt is the* variety of Objects *which will come under their Inſpections, ſo many* different wayes *there are of* handling *them, ſo great is the* ſatisfaction *of* finding *out* new things, *that I dare compare the* contentment *which they will injoy, not only to that of* contemplation, *but even to that which moſt men prefer of* the very Senſes themſelves.

And if they will pleaſe to take any incouragement from ſo mean and ſo imperfect endeavours as mine, upon my own experience, I can aſſure them, without arrogance, That there has not been any inquiry or Problem in Mechanicks, *that I have hitherto propounded to my ſelf, but by a certain method (which I may on ſome other opportunity explain) I have been able preſently to examine the poſſibility of it; and if ſo, as eaſily to excogitate divers wayes of performing it: And indeed it is poſſible to do as much by* this method *in* Mechanicks, *as by* Algebra *can be perform'd in* Geometry. *Nor can I at all doubt, but that the ſame method is as applicable to* Phyſical Enquiries, *and as likely to find and reap thence as plentiful a crop of Inventions; and indeed there ſeems to be no ſubject ſo barren, but may with this good husbandry be highly improv'd.*

Toward the proſecution of this method in Phyſical Inquiries, *I have here and there* gleaned *up an* handful *of Obſervations, in the collection of moſt of which I made uſe of* Microſcopes, *and ſome other* Glaſſes *and* Inſtruments *that improve the ſenſe; which way I have herein taken, not that there are not multitudes of uſeful and pleaſant Obſervables, yet uncollected, obvious enough without the helps of Art, but only to promote the uſe of Mechanical helps for the Senſes, both in the ſurveying the already viſible World,*

World, and for the discovery of many others hitherto unknown, and to make us, with the great Conqueror, to be affected that we have not yet overcome one World when there are so many others to be discovered, every considerable improvement of Telescopes *or* Microscopes *producing new Worlds and* Terra-Incognita's *to our view.*

The Glasses I used were of our English make, but though very good of the kind, yet far short of what might be expected, could we once find a way of making Glasses Elliptical, or of some more true shape; for though both Microscopes, *and* Telescopes, *as they now are, will magnifie an Object about a thousand thousand times bigger then it appears to the naked eye; yet the Apertures of the Object-glasses are so very small, that very few Rays are admitted, and even of those few there are so many false, that the Object appears* dark *and* indistinct: *And indeed these inconveniences are such, as seem inseparable from Spherical Glasses, even when most exactly made; but the way we have hitherto made use of for that purpose is so imperfect, that there may be perhaps ten wrought before one be made tolerably good, and most of those ten perhaps every one differing in goodness one from another, which is an Argument, that the way hitherto used is, at least, very uncertain. So that these Glasses have a double defect; the one, that very few of them are exactly true wrought; the other, that even of those that are best among them, none will admit a sufficient number of Rayes to magnifie the Object beyond a determinate bigness. Against which Inconveniences the only Remedies I have hitherto met with are these.*

First, for *Microscopes* (where the Object we view is near and within our power) the best way of making it appear bright in the Glass, is to cast a great quantity of light on it by means of *convex glasses*, for thereby, though the aperture be very small, yet there will throng in through it such multitudes, that an Object will by this means indure to be magnifi'd as much again as it would be without it. The way for doing which is this. I make choice of some Room that has only one window open to the South, and at about three or four foot distance from this Window, on a Table, I place my *Microscope*, and then so place either a round Globe of Water, or a very deep clear *plano convex* Glass (whose convex side is turn'd towards the Window) that there is a great quantity of Rayes collected and thrown upon the Object: Or if the Sun shine, I place a small piece of oyly Paper very near the Object, between that and the light; then with a good large Burning-Glass I so collect and throw the Rayes on the Paper, that there may be a very great quantity of light pass through it to the Object; yet I so proportion that light, that it

may

may not singe or burn the Paper. Instead of which Paper there may be made use of a small piece of Looking-glass plate, one of whose sides is made rough by being rubb'd on a flat Tool with very fine sand, this will, if the heat be leisurely cast on it, indure a much greater degree of heat, and consequently very much augment a convenient light. By all which means the light of the Sun, or of a Window, may be so cast on an Object, as to make it twice as light as it would otherwise be without it, and that without any inconvenience of glaring, which the immediate light of the Sun is very apt to create in most Objects; for by this means the light is so equally diffused, that all parts are alike inlightned; but when the immediate light of the Sun falls on it, the reflexions from some few parts are so vivid, that they drown the appearance of all the other, and are themselves also, by reason of the inequality of light, indistinct, and appear only radiant spots.

But because the light of the Sun, and also that of a Window, is in a continual variation, and so many Objects cannot be view'd long enough by them to be throughly examin'd; besides that, oftentimes the Weather is so dark and cloudy, that for many dayes together nothing can be view'd: And because also there are many Objects to be met with in the night, which cannot so conveniently be kept perhaps till the day, therefore to procure and cast a sufficient quantity of light on an Object in the night, I thought of, and often used this, Expedient.

I procur'd me a small Pedestal, such as is describ'd in the fifth Figure of the first *Scheme* on the small Pillar A B, of which were two movable Armes C D, which by means of the Screws E F, I could fix in any part of the Pillar; on the undermost of these I plac'd a pretty large Globe of Glass G, fill'd with exceeding clear Brine, stopt, inverted, and fixt in the manner visible in the Figure; out of the side of which Arm proceeded another Arm H, with many joynts; to the end of which was fastned a deep plain *Convex glass* I, which by means of this Arm could be moved to and fro, and fixt in any posture. On the upper Arm was placed a small Lamp K, which could be so mov'd upon the end of the Arm, as to be set in a fit posture to give light through the Ball: By means of this Instrument duly plac'd, as is exprest in the Figure, with the small flame of a Lamp may be cast as great and convenient a light on the Object as it will well indure; and being always constant, and to be had at any time, I found most proper for drawing the representations of those small Objects I had occasion to observe.

None of all which ways (though much beyond any other hitherto made use of by any I know) do afford a sufficient help, but after a certain degree of magnifying, they leave us again in the lurch. Hence it were very desirable, that some way were thought of for making the Object-glass of such a Figure as would conveniently bear a large Aperture.

As for Telescopes, *the only improvement they seem capable of, is the increasing of their length; for the Object being remote, there is no thought of giving it a greater light then it has; and therefore to augment the Aperture, the Glass must be ground of a very large sphere; for, by that*

 meanis,

means, the longer the Glaſs be, the bigger aperture will it bear, if the Glaſſes be of an equal goodneſs in their kind. Therefore a ſix will indure a much larger Aperture then a three foot Glaſs; and a ſixty foot Glaſs will proportionably bear a greater Aperture then a thirty, and will as much excel it alſo as a ſix foot does a three foot, as I have experimentally obſerv'd in one of that length made by Mr. Richard Reives *here at* London, *which will bear an Aperture above three inches over, and yet make the Object proportionably big and diſtinct; whereas there are very few thirty foot Glaſſes that will indure an Aperture of more then two inches over. So that for* Teleſcopes, *ſuppoſing we had a very ready way of making their Object Glaſſes of exactly ſpherical Surfaces, we might, by increaſing the length of the Glaſs, magnifie the Object to any aſſignable bigneſs. And for performing both theſe, I cannot imagine any way more eaſie, and more exact, then by this following Engine, by means of which, any Glaſſes, of what length ſoever, may be ſpeedily made. It ſeems the moſt eaſie, becauſe with one and the ſame Tool may be with care ground an Object Glaſs, of any length or breadth requiſite, and that with very little or no trouble in fitting the Engine, and without much skill in the Grinder. It ſeems to be the moſt exact, for to the very laſt ſtroke the Glaſs does regulate and rectifie the Tool to its exact Figure; and the longer or more the Tool and Glaſs are wrought together, the more exact will both of them be of the deſir'd Figure. Further, the motions of the Glaſs and Tool do ſo croſs each other, that there is not one point of eithers Surface, but has thouſands of croſs motions thwarting it, ſo that there can be no kind of Rings or Gutters made either in the Tool or Glaſs.*

The contrivance of the Engine is, only to make the ends of two large *Mandrils* ſo to move, that the Centers of them may be at any convenient diſtance aſunder, and that the *Axis* of the *Mandrils* lying both in the ſame plain produc'd, may meet each other in any aſſignable Angle; both which requiſites may be very well perform'd by the Engine deſcrib'd in the third Figure of the firſt *Scheme*: where A B ſignifies the Beam of a Lath fixt perpendicularly or Horizontally, C D the two Poppet heads, fixt at about two foot diſtance, E F an Iron *Mandril*, whoſe tapering neck F runs in an adapted tapering braſs Collar; the other end E runs on the point of a Screw G; in a convenient place of this is faſtned H a pully Wheel, and into the end of it, that comes through the Poppet head C, is ſcrewed a Ring of a hollow *Cylinder* K, or ſome other conveniently ſhap'd Tool, of what wideneſs ſhall be

be thought most proper for the cize of Glasses, about which it is to be imploy'd: As, for Object glasses, between twelve foot and an hundred foot long, the Ring may be about six inches over, or indeed somewhat more for those longer Glasses. It would be convenient also, and not very chargeable, to have four or five several Tools; as one for all Glasses between an inch and a foot, one for all Glasses between a foot and ten foot long, another for all between ten and an hundred, a fourth for all between a hundred and a thousand foot long; and if Curiosity shall ever proceed so far, one for all lengths between a thousand and ten thousand foot long; for indeed the principle is such, that supposing the *Mandrils* well made, and of a good length, and supposing great care be used in working and polishing them, I see no reason, but that a Glass of a thousand, nay of ten thousand foot long, may be as well made as one of ten; for the reason is the same, supposing the *Mandrils* and Tools be made sufficiently strong, so that they cannot bend; and supposing the Glass, out of which they are wrought, be capable of so great a regularity in its parts as to refraction: this hollow *Cylinder* K is to contain the Sand, and by being drove round very quick to and fro by means of a small Wheel, which may be mov'd with ones foot, serves to grind the Glass: The other *Mandril* is shap'd like this, but it has an even neck instead of a taper one, and runs in a Collar, that by the help of a Screw, and a joynt made like M in the Figure, it can be still adjustned to the wearing or wasting neck: into the end of this *Mandril* is screwed a Chock N, on which with Cement or Glew is fastned the piece of Glass Q that is to be form'd; the middle of which Glass is to be plac'd just on the edge of the Ring, and the Lath O P is to be set and fixt (by means of certain pieces and screws, the manner whereof will be sufficiently evidenc'd by the Figure) in such an Angle as is requisite to the forming of such a Sphere as the Glass is design'd to be of; the geometrical ground of which being sufficiently plain, though not heeded before, I shall, for brevities sake, pass over. This last *Mandril* is to be made (by means of the former, or some other Wheel) to run round very swift also, by which two cross motions the Glass cannot chuse (if care be us'd) but be wrought into a most exactly spherical Surface.

But because we are certain, from the Laws of refraction *(which I I have experimentally found to be so, by an Instrument I shall presently describe) that* the lines of the angles of Incidence are proportionate to the lines of the angles of Refraction, *therefore if Glasses could be made of those kind of Figures, or some other, such as the most incomparable* Des Cartes *has invented, and demonstrated in his Philosophical and Mathematical Works, we might hope for a much greater perfection of Opticks then can be rationally expected from spherical ones; for though,* cæteris paribus, *we find, that the larger the* Telescope *Object Glasses are, and the shorter those of the* Microscope, *the better they magnifie, yet both of them,*

beside

besides such determinate dimensions, are by certain inconveniences rendred unuseful; for it will be exceeding difficult *to make and* manage *a Tube above an* hundred foot long, *and it will be as difficult to* inlighten *an Object less then an hundred part of an inch distant from the Object Glass.*

I have not as yet made any attempts of that kind, though I know two or three wayes, which, as far as I have yet considered, seem very probable, and may invite me to make a tryal as soon as I have an opportunity, of which I may hereafter perhaps acquaint the world. In the Interim, I shall describe the Instrument I even now mention'd, by which the refraction *of all kinds of Liquors may be most exactly measur'd, thereby to give the curious an opportunity of making what further tryals of that kind they shall think requisite to any of their intended tryals; and to let them see that the laws of Refraction are not only notional.*

The Instrument consisted of five Rulers, or long pieces placed together, after the manner exprest in the second Figure of the first *Scheme*, where A B denotes a straight piece of wood about six foot and two inches long, about three inches over, and an inch and half thick, on the back side of which was hung a small plummet by a line stretcht from top to bottom, by which this piece was set exactly upright, and so very firmly fixt; in the middle of this was made a hole or center, into which one end of a hollow cylindrical brass Box C C, fashion'd as I shall by and by describe, was plac'd, and could very easily and truly be mov'd to and fro; the other end of this Box being put into, and moving in, a hole made in a small arm D D; into this box was fastned the long Ruler E F, about three foot and three or four inches long, and at three foot from the above mention'd Centers P P was a hole E, cut through, and cross'd with two small threads, and at the end of it was fixt a small sight G, and on the back side of it was fixt a small Arm H, with a Screw to fix it in any place on the Ruler L M; this Ruler L M was mov'd on the Center B (which was exactly three foot distance from the middle Center P) and a line drawn through the middle of it L M, was divided by a Line of cords into some sixty degrees, and each degree was subdivided into minutes, so that putting the cross of the threads in E upon any part of this divided line, I presently knew what Angle the two Rules A B and E F made with each other, and by turning the Screw in H, I could fix them in any position. The other Ruler also R S was made much after the same manner, only it was not fixt to the hollow cylindrical Box, but, by means of two small brass Armes or Ears, it mov'd on the Centers of it; this also, by means of the cross threads in the hole S, and by a Screw in K, could be fastned on any division of another line of cords of the same radius drawn on N O. And so by that means, the Angle made by the two Rulers, A B and R S, was also known. The Brass box C C in the middle was shap'd very much like the Figure X, that is, it was a cylindrical Box stopp'd close at either end, off of which a part both of the sides and bottomes was cut out, so

that

that the Box, when the Pipe and that was joyned to it, would contain the Water when fill'd half full, and would likewise, without running over, indure to be inclin'd to an Angle, equal to that of the greatest refraction of Water, and no more, without running over. The Ruler E F was fixt very fast to the Pipe V, so that the Pipe V directed the length of the Ruler E F, and the Box and Ruler were mov'd on the Pin T T, so as to make any desirable Angle with the Ruler A B. The bottom of this Pipe V was stop'd with a small piece of exactly plain Glass, which was plac'd exactly perpendicular to the Line of direction, or *Axis* of the Ruler E F. The Pins also T T were drill'd with small holes through the *Axis*, and through those holes was stretcht and fastned a small Wire. There was likewise a small Pipe of Tin loosly put on upon the end of V, and reaching down to the sight G; the use of which was only to keep any false Rayes of light from passing through the bottom of V, and only admitting such to pass as pierced through the sight G: All things being placed together in the manner describ'd in the Figure; that is, the Ruler A B being fixt perpendicular, I fill'd the Box C C with Water, or any other Liquor, whose refraction I intended to try, till the Wire passing through the middle of it were just covered: then I moved and fixt the Ruler F E at any assignable Angle, and placed the flame of a Candle just against the sight G; and looking through the sight I, I moved the Ruler R S to and fro, till I perceived the light passing through G to be covered, as 'twere, or divided by the dark Wire passing through P P: then turning the Screw in K, I fixt it in that posture: And through the hole S, I observed what degree and part of it was cut by the cross threads in S. And this gave me the Angle of Inclination, A P S answering to the Angle of Refraction B P E: for the surface of the Liquor in the Box will be alwayes horizontal, and consequently A B will be a perpendicular to it; the Angle therefore A P S will measure, or be the Angle of Inclination in the Liquor; next E P B must be the Angle of Refraction, for the Ray that passes through the sight G, passes also perpendicularly through the Glass *Diaphragme* at F, and consequently also perpendicularly through the lower surface of the Liquor contiguous to the Glass, and therefore suffers no refraction till it meet with the horizontal surface of the Liquor in C C, which is determined by the two Angles.

By means of this Instrument I can with little trouble, *and a very small quantity of any* Liquor, *examine, most accurately, the* refraction *of it, not only for one inclination, but for all; and thereby am inabled to make very accurate Tables; several of which I have also experimentally made, and find, that* Oyl of Turpentine *has a much greater Refraction then* Spirit of Wine, *though it be* lighter; *and that* Spirit of Wine *has a greater Refraction then* Water, *though it be lighter also; but that* salt Water *also has a greater Refraction then* fresh, *though it be* heavier: *but* Allum water *has a less refraction then common* Water, *though heavier also. So that it seems, as to the* refraction *made in a Liquor, the* speci-

 fick

fick gravity *is of no efficacy. By this I have alſo found, that look what* proportion *the* Sine *of the Angle of one* Inclination *has to the* Sine *of the Angle of* Refraction, *correſpondent to it, the ſame* proportion *have all the* Sines *of other Inclinations to the* Sines *of their appropriate Refractions.*

My way for meaſuring how much a Glaſs magnifies an Object, plac'd at a convenient diſtance from my eye, is this. Having rectifi'd the *Microſcope*, to ſee the deſir'd Object through it very diſtinctly, at the ſame time that I look upon the Object through the Glaſs with one eye, I look upon other Objects at the ſame diſtance with my other bare eye; by which means I am able, by the help of a *Ruler* divided into inches and ſmall parts, and laid on the *Pedeſtal* of the *Microſcope*, to caſt, as it were, the magnifi'd appearance of the Object upon the Ruler, and thereby exactly to meaſure the Diameter it appears of through the Glaſs, which being compar'd with the Diameter it appears of to the naked eye, will eaſily afford the quantity of its magnifying.

The *Microſcope*, which for the moſt part I made uſe of, was ſhap'd much like that in the ſixth Figure of the firſt *Scheme*, the Tube being for the moſt part not above ſix or ſeven inches long, though, by reaſon it had four Drawers, it could very much be lengthened, as occaſion required; this was contriv'd with three Glaſſes; a ſmall Object Glaſs at A, a thinner Eye Glaſs about B, and a very deep one about C: this I made uſe of only when I had occaſion to ſee much of an Object at once; the middle Glaſs conveying a very great company of radiating Pencils, which would go another way, and throwing them upon the deep Eye Glaſs. But when ever I had occaſion to examine the ſmall parts of a Body more accurately, I took out the middle Glaſs, and only made uſe of one Eye Glaſs with the Object Glaſs, for always the fewer the Refractions are, the more bright and clear the Object appears. And therefore 'tis not to be doubted, but could we make a *Microſcope* to have one only refraction, it would, *ceteris paribus*, far excel any other that had a greater number. And hence it is, that if you take a very clear piece of a broken *Venice* Glaſs, and in a Lamp draw it out into very ſmall hairs or threads, then holding the ends of theſe threads in the flame, till they melt and run into a ſmall round Globul, or drop, which will hang at the end of the thread; and if further you ſtick ſeveral of theſe upon the end of a ſtick with a little ſealing Wax, ſo as that the threads ſtand upwards, and then on a Whetſtone firſt grind off a good part of them, and afterward on a ſmooth Metal plate, with a little Tripoly, rub them till they come to be very ſmooth; if one of theſe be fixt with a little ſoft Wax againſt a ſmall needle hole, prick'd through a thin Plate of Braſs, Lead, Pewter, or any other Metal, and an Object, plac'd very near, be look'd at through it, it will both magnifie and make ſome Objects more diſtinct then any of the great *Microſcopes*. But becauſe theſe, though exceeding eaſily made, are yet very troubleſome to be us'd, becauſe of their ſmalneſs, and the nearneſs of the Object; therefore to prevent both theſe, and yet have only two Refractions, I provided me a Tube of Braſs, ſhap'd much like that in the fourth Figure of the firſt *Scheme*; into the ſmaller end of this I fixt with Wax a good *plano convex*

vex Object Glass, with the convex side towards the Object, and into the bigger end I fixt also with wax a pretty large plano *Convex* Glass, with the *convex* side towards my eye, then by means of the small hole by the side, I fill'd the intermediate space between these two Glasses with very clear Water, and with a Screw stopp'd it in; then putting on a Cell for the Eye, I could perceive an Object more bright then I could when the intermediate space was only fill'd with Air, but this, for other inconveniences, I made but little use of.

My way for fixing both the Glass and Object to the Pedestal most conveniently was thus: Upon one side of a round Pedestal A B, in the sixth Figure of the first *Scheme*, was fixt a small Pillar C C, on this was fitted a small Iron Arm D, which could be mov'd up and down, and fixt in any part of the Pillar, by means of a small Screw E; on the end of this Arm was a small Ball fitted into a kind of socket F, made in the side of the Brass Ring G, through which the small end of the Tube was screw'd; by means of which contrivance I could place and fix the Tube in what posture I desir'd (which for many Observations was exceeding necessary) and adjusten it most exactly to any Object.

For placing the Object, I made this contrivance; upon the end of a small brass Link or Staple H H, I so fastned a round Plate I I, that it might be turn'd round upon its Center K, and going pretty stiff, would stand fixt in any posture it was set; on the side of this was fixt a small Pillar P, about three quarters of an inch high, and through the top of this was thrust a small Iron pin M, whose top just stood over the Center of the Plate; on this top I fixt a small Object, and by means of these contrivances I was able to turn it into all kind of positions, both to my Eye and the Light; for by moving round the small Plate on its center, I could move it one way, and by turning the Pin M, I could move it another way, and this without stirring the Glass at all, or at least but very little: the Plate likewise I could move to and fro to any part of the Pedestal (which in many cases was very convenient) and fix it also in any Position, by means of a Nut N, which was screw'd on upon the lower part of the Pillar C C. All the other Contrivances are obvious enough from the draught, and will need no description

Now though this were the Instrument I made most use of, yet I have made several other Tryals with other kinds of Microscopes, *which both for* matter *and* form *were very different from common spherical Glasses. I have made a* Microscope *with one piece of Glass, both whose surfaces were* plains. *I have made another only with a* plano concave, *without any kind of reflection, divers also by means of* reflection. *I have made others of* Waters, Gums, Resins, Salts, Arsenick, Oyls, *and with divers other* mixtures *of* watery *and* oyly Liquors. *And indeed the subject is capable of a great variety; but I find generally none more useful then that which is made with* two Glasses, *such as I have already describ'd.*

What

What the things are I obſerv'd, the following deſcriptions will manifeſt; in brief, they were either exceeding ſmall Bodies, *or* exceeding ſmall Pores, *or* exceeding ſmall Motions, *ſome of each of which the Reader will find in the following Notes, and ſuch, as I preſume, (many of them at leaſt) will be* new, *and perhaps not leſs* ſtrange: *Some* ſpecimen *of each of which Heads the Reader will find in the ſubſequent delineations, and indeed of ſome more then I was willing there ſhould be; which was occaſioned by my firſt Intentions to print a much greater number then I have ſince found time to compleat. Of ſuch therefore as I had, I ſelected only ſome few of every Head, which for ſome particulars ſeem'd moſt obſervable, rejecting the reſt as ſuperfluous to the preſent Deſign.*

What each of the delineated Subjects are, the following deſcriptions annext to each will inform, of which I ſhall here, only once for all, add, That in divers of them the Gravers have pretty well follow'd my directions and draughts; and that in making of them, I indeavoured (as far as I was able) firſt to diſcover the true appearance, and next to make a plain repreſentation of it. This I mention the rather, becauſe of theſe kind of Objects there is much more difficulty to diſcover the true ſhape, then of thoſe viſible to the naked eye, the ſame Object ſeeming quite differing, in one poſition to the Light, from what it really is, and may be diſcover'd in another. And therefore I never began to make any draught before by many examinations in ſeveral lights, and in ſeveral poſitions to thoſe lights, I had diſcover'd the true form. For it is exceeding difficult in ſome Objects, to diſtinguiſh between a prominency *and a* depreſſion, *between a* ſhadow *and a* black ſtain, *or a* reflection *and a* whiteneſs in the colour. *Beſides, the tranſparency of moſt Objects renders them yet much more difficult then if they were* opacous. *The Eyes of a Fly in one kind of light appear almoſt like a Lattice, drill'd through with abundance of ſmall holes; which probably may be the Reaſon, why the Ingenious* Dr. Power *ſeems to ſuppoſe them ſuch. In the Sunſhine they look like a Surface cover'd with golden Nails; in another poſture, like a Surface cover'd with Pyramids; in another with Cones; and in other poſtures of quite other ſhapes; but that which exhibits the beſt, is the Light collected on the Object, by thoſe means I have already deſcrib'd.*

And

And this was undertaken in prosecution of the Design which the ROYAL SOCIETY *has propos'd to it self. For the Members of the Assembly having before their eys so many* fatal *Instances of the errors and falshoods, in which the greatest part of mankind has so long wandred, because they rely'd upon the strength of humane Reason alone, have begun anew to correct all* Hypotheses *by sense, as Seamen do their* dead Reckonings *by* Cœlestial Observations; *and to this purpose it has been their principal indeavour to* enlarge *&* strengthen *the* Senses *by* Medicine, *and by such* outward Instruments *as are proper for their particular works. By this means they find some reason to suspect, that those effects of Bodies, which have been commonly attributed to* Qualities, *and those confess'd to be* occult, *are perform'd by the small* Machines *of Nature, which are not to be discern'd without these helps, seeming the meer products of* Motion, Figure, *and* Magnitude; *and that the* Natural Textures, *which some call the* Plastick faculty, *may be made in* Looms, *which a greater perfection of Opticks may make discernable by these Glasses; so as now they are no more puzzled about them, then the vulgar are to conceive, how* Tapestry *or* flowred Stuffs *are woven. And the ends of all these Inquiries they intend to be the* Pleasure *of Contemplative minds, but above all, the* ease and dispatch *of the labours of mens hands. They do indeed neglect no opportunity to bring all the* rare *things of Remote Countries within the compass of their knowledge and practice. But they still acknowledg their* most useful *Informations to arise from* common *things, and from* diversifying *their most* ordinary *operations upon them. They do not wholly reject Experiments of meer* light *and* theory; *but they principally aim at such, whose Applications will* improve and facilitate *the present way of* Manual Arts. *And though some men, who are perhaps taken up about less honourable Employments, are pleas'd to censure their proceedings, yet they can shew more* fruits *of their first three years, wherein they have assembled, then any other* Society *in* Europe *can for a much larger space of time. 'Tis true, such undertakings as theirs do commonly meet with small incouragement, because men are generally rather taken with the* plausible *and* discursive, *then the* real *and the solid part of Philosophy; yet by the good fortune of their institution, in an Age of all others the most* inquisitive, *they have been assisted by the* contribution *and* presence *of very many of the chief* Nobility *and* Gentry,

 and

and others, who are some of the most considerable *in their several Professions. But that that yet farther convinces me of the* Real esteem *that the more* serious *part of men have of this* Society, *is, that several* Merchants, *men who act in earnest (whose Object is* meum & tuum, *that great* Rudder *of humane affairs) have adventur'd considerable sums of* Money, *to put in practice what some of our Members have contrived, and have continued* stedfast *in their good opinions of such Indeavours, when not one of a hundred of the vulgar have believed their undertakings feasable. And it is also fit to be added, that they have one advantage peculiar to themselves, that very many of their number are* men of Converse and Traffick; *which is a good Omen, that their attempts will bring Philosophy from* words *to* action, *seeing the men of Business have had so great a share in their first foundation.*

And of this kind I ought not to conceal one particular Generosity, *which more nearly concerns my self. It is the* munificence *of* Sir John Cutler, *in endowing a Lecture for the promotion of* Mechanick Arts, *to be governed and directed by This* Society. *This* Bounty *I mention for the* Honourableness *of the thing it self, and for the expectation which I have of the* efficacy *of the* Example; *for it cannot now be objected to them, that their Designs will be esteemed* frivolous *and* vain, *when they have such a* real Testimony *of the* Approbation *of a* Man *that is such an* eminent Ornament *of this renowned City, and one, who, by the* Variety, *and the* happy Success, *of his negotiations, has given evident proofs, that he is not easie to be deceiv'd. This Gentleman has well observ'd, that the* Arts *of life have been too long* imprison'd *in the dark shops of Mechanicks themselves, & there* hindred from growth, *either by ignorance, or self-interest: and he has bravely* freed *them from these* inconveniences: *He hath not only obliged* Tradesmen, *but* Trade *it self: He has done a work that is worthy of* London, *and has taught the chief City of Commerce in the world the right way how Commerce is to be improv'd. We have already seen many other great signs of Liberality and a large mind, from the same hand: For by his* diligence *about the* Corporation for the Poor; *by his honorable* Subscriptions *for the rebuilding of St.* Paul's; *by his chearful* Disbursement *for the replanting of* Ireland, *and by many other such* publick works, *he has shewn by what means he indeavours to* establish *his Memory; and now by this last gift he has done that, which became one of the* wisest Citizens

of

of our Nation to accomplish, seeing one of the wisest of our Statesmen, the Lord Verulam, *first propounded it.*

But to return to my Subject, from a digression, which, I hope, my Reader will pardon me, seeing the Example is so rare that I can make no more such digressions. If these my first Labours shall be any wayes useful to inquiring men, I must attribute the incouragement and promotion of them to a very Reverend *and* Learned Person, *of whom this ought in justice to be said,* That there is scarce any one Invention, which this Nation has produc'd in our Age, but it has some way or other been set forward by his assistance. *My Reader, I believe, will quickly ghess, that it is* Dr. Wilkins *that I mean. He is indeed a man born for the* good *of* mankind, *and for the* honour *of his* Couutry. *In the* sweetness *of whose* behaviour, *in the* calmness *of his* mind, *in the* unbounded goodness *of his* heart, *we have an evident Instance, what the true and the* primitive unpassionate Religion *was, before it was* sowred *by particular* Factions. *In a word, his* Zeal *has been so* constant *and* effectual *in advancing all good and profitable* Arts, *that as one of the Antient* Romans *said of* Scipio, That he thanked God that he was a *Roman*; because whereever *Scipio* had been born, there had been the seat of the Empire of the world: *So may I thank God, that* Dr. Wilkins *was an* Englishman, *for whereever he had lived, there had been the chief Seat of* generous Knowledge *and* true Philosophy. *To the truth of this, there are so many worthy men living that will subscribe, that I am confident, what I have here said, will not be look'd upon, by any ingenious Reader, as a* Panegyrick, *but only as a* real testimony.

By the Advice of this Excellent man *I first set upon this Enterprise, yet still came to it with much* Reluctancy, *because I was to follow the footsteps of so eminent a Person as* Dr. Wren, *who was the first that attempted any thing of this nature; whose original draughts do now make one of the Ornaments of that great Collection of Rarities in the* Kings Closet. *This* Honor, *which his first beginnings of this kind have receiv'd, to be admitted into the most famous place of the world, did not so much* incourage, *as the* hazard *of coming after* Dr. Wren *did* affright *me; for of him I must affirm, that, since the time of* Archimedes, *there scarce ever met in one man, in so*

great

great a perfection, such a Mechanical Hand, *and so* Philosophical *a* Mind.

But at last, being assured both by Dr. Wilkins, *and* Dr. Wren *himself, that he had given over his intentions of prosecuting it, and not finding that there was any else design'd the pursuing of it, I set upon this undertaking, and was not a little incourag'd to proceed in it, by the Honour the* Royal Society *was pleas'd to favour me with, in approving of those draughts (which from time to time as I had an opportunity of describing) I presented to them. And particularly by the Incitements of divers of those Noble and excellent Persons of it, which were my more especial Friends, who were not less urgent with me for the publishing, then for the prosecution of them.*

After I had almost compleated these Pictures and Observations (having had divers of them ingraven, and was ready to send them to the Press) I was inform'd, that the Ingenious Physitian Dr. Henry Power *had made several* Microscopical *Observations, which had I not afterwards, upon our interchangably viewing each others Papers, found that they were for the most part differing from mine, either in the Subject it self, or in the particulars taken notice of; and that his design was only to print Observations without Pictures, I had even then* suppressed *what I had so far proceeded in. But being further* excited *by several of my Friends, in complyance with their opinions, that it would not be unacceptable to several inquisitive Men, and hoping also, that I should thereby discover something New to the World, I have at length cast in my Mite, into the vast Treasury of* A Philosophical History. *And it is my* hope, *as well as* belief, *that these my* Labours *will be no more comparable to the* Productions *of many other* Natural Philosophers, *who are now every where busie about* greater *things; then my* little Objects *are to be compar'd to the greater and more beautiful* Works of Nature, *A Flea, a Mite, a Gnat, to an Horse, an Elephant, or a Lyon.*

SOME


Schem: I.
Fig: I.
Fig: 2.
Fig: 3.


Fig: 4.
Fig: 5.
Fig: 6.

MICROGRAPHIA,

OR SOME

Physiological Descriptions

OF

MINUTE BODIES,

MADE BY

MAGNIFYING GLASSES;

WITH

OBSERVATIONS and INQUIRIES thereupon.

Observ. I. *Of the Point of a sharp small Needle.*

AS in *Geometry*, the most natural way of beginning is from a Mathematical *point*; so is the same method in Observations and *Natural history* the most genuine, simple, and instructive. We must first endevour to make *letters*, and draw *single* strokes true, before we venture to write whole *Sentences*, or to draw large *Pictures*. And in *Physical* Enquiries, we must endevour to follow Nature in the more *plain* and *easie* ways she treads in the most *simple* and *uncompounded bodies*, to trace her steps, and be acquainted with her manner of walking there, before we venture our selves into the multitude of *meanders* she has in *bodies of a more complicated* nature; lest, being unable to distinguish and judge of our way, we quickly lose both *Nature* our Guide, and *our selves* too, and are left to wander in the *labyrinth* of groundless opinions; wanting both *judgment*, that *light*, and *experience*, that *clew*, which should direct our proceedings. *Schem.* 2. *Fig.* 1.

We will begin these our Inquiries therefore with the Observations of Bodies of the most *simple nature* first, and so gradually proceed to those of a more *compounded* one. In prosecution of which method, we shall begin with a *Physical point*; of which kind the *Point of a Needle* is commonly reckon'd for one; and is indeed, for the most part, made so sharp, that the naked eye cannot distinguish any parts of it: It very easily pierces, and makes its way through all kind of bodies softer then it self: But if view'd with a very good *Microscope*, we may find that the *top* of a Needle (though as to the

 sense

ſenſe very *ſharp*) appears a *broad*, *blunt*, and very *irregular* end; not reſembling a Cone, as is imagin'd, but onely a piece of a tapering body, with a great part of the top remov'd, or deficient. The Points of Pins are yet more blunt, and the Points of the moſt curious Mathematital Inſtruments do very ſeldome arrive at ſo great a ſharpneſs; how much therefore can be built upon demonſtrations made onely by the productions of the Ruler and Compaſſes, he will be better able to conſider that ſhall but view thoſe *points* and *lines* with a *Microſcope*.

Now though this point be commonly accounted the ſharpeſt (whence when we would expreſs the ſharpneſs of a point the moſt *ſuperlatively*, we ſay, As ſharp as a Needle) yet the *Microſcope* can afford us hundreds of Inſtances of Points many thouſand times ſharper: ſuch as thoſe of the *hairs*, and *briſtles*, and *claws* of multitudes of *Inſects*; the *thorns*, or *crooks*, or *hairs* of *leaves*, and other ſmall vegetables; nay, the ends of the *ſtiriæ* or ſmall *parallelipipeds* of *Amianthus*, and *alumen plumoſum*; of many of which, though the Points are ſo ſharp as not to be viſible, though view'd with a *Microſcope* (which magnifies the Object, in bulk, above a million of times) yet I doubt not, but were we able *practically* to make *Microſcopes* according to the *theory* of them, we might find hills, and dales, and pores, and a ſufficient bredth, or expanſion, to give all thoſe parts elbow-room, even in the blunt top of the very Point of any of theſe ſo very ſharp bodies. For certainly the *quantity* or extenſion of any body may be *Diviſible in infinitum*, though perhaps not the *matter*.

But to proceed: The Image we have here exhibited in the firſt Figure, was the top of a ſmall and very ſharp Needle, whoſe point *a a* nevertheleſs appear'd through the *Microſcope* above a quarter of an inch broad, not round nor flat, but *irregular* and *uneven*; ſo that it ſeem'd to have been big enough to have afforded a hundred armed Mites room enough to be rang'd by each other without endangering the breaking one anothers necks, by being thruſt off on either ſide. The ſurface of which, though appearing to the naked eye very ſmooth, could not nevertheleſs hide a multitude of holes and ſcratches and ruggedneſſes from being diſcover'd by the *Microſcope* to inveſt it, ſeveral of which inequalities (as A, B, C, ſeem'd *holes* made by ſome ſmall ſpecks of *Ruſt*; and D ſome *adventitious body*, that ſtuck very cloſe to it) were *caſual*. All the reſt that roughen the ſurface, were onely ſo many marks of the rudeneſs and bungling of *Art*. So unaccurate is it, in all its productions, even in thoſe which ſeem moſt neat, that if examin'd with an organ more acute then that by which they were made, the more we ſee of their *ſhape*, the leſs appearance will there be of their *beauty*: whereas in the works of *Nature*, the deepeſt Diſcoveries ſhew us the greateſt Excellencies. An evident Argument, that he that was the Author of all theſe things, was no other then *Omnipotent*; being able to include as great a variety of parts and contrivances in the yet ſmalleſt Diſcernable Point, as in thoſe vaſter bodies (which comparatively are called alſo Points) ſuch as the *Earth*, *Sun*, or *Planets*. Nor need it ſeem ſtrange that the Earth it ſelf may be by an *Analogie* call'd a Phyſical Point: For as its body, though now

ſo


1/10 pollicis Ang: or of an inch
Fig: 1 a
D
C
b
b
b
1/16 poll: Ang: or of an inch
Fig: 2: a
a

p: 2.

Sch. II.

so near us as to fill our eys and fancies with a sense of the vastness of it, may by a little Distance, and some convenient *Diminishing* Glasses, be made vanish into a scarce visible Speck, or Point (as I have often try'd on the *Moon*, and (when not too bright) on the *Sun* it self.) So, could a Mechanical contrivance succesfully answer our *Theory*, we might see the least spot as big as the Earth it self; and Discover, as also conjectures, as great a variety of bodies in the *Moon*, or *Planets*, as in the *Earth*. *Des Cartes Diop ch. 10. § 9.*

But leaving these Discoveries to future Industries, we shall proceed to add one Observation more of a *point* commonly so call'd, that is, the mark of a *full stop*, or *period*. And for this purpose I observed many both *printed* ones and *written*; and among multitudes I found *few* of them more *round* or *regular* then this which I have delineated in the third figure of the second Scheme, but *very many* abundantly *more disfigur'd*; and for the most part if they seem'd equally round to the eye, I found those points that had been made by a *Copper-plate*, and Roll-press, to be as misshapen as those which had been made with *Types*, the most curious and smothly *engraven strokes* and *points*, looking but as so many *furrows* and *holes*, and their *printed impressions*, but like *smutty daubings* on a matt or uneven floor with a blunt extinguisht brand or stick's end. And as for *points* made with a *pen* they were much *more rugged* and *deformed*. Nay, having view'd certain pieces of exceeding curious writing of the kind (one of which in the bredth of a *two-pence* compris'd *the Lords prayer, the Apostles Creed, the ten Commandments, and about half a dozen verses besides of the Bible*, whose *lines* were so *small* and *near together*, that I was unable to *number* them with my *naked eye*, a very ordinary *Microscope*, I had then about me, inabled me to see that what the Writer of it had asserted was *true*, but withall discover'd of what pitifull *bungling scribbles* and *scrawls* it was compos'd, *Arabian* and *China characters* being almost as well shap'd; yet thus much I must say for the Man, that it was for the most part *legible* enough, though in some places there wanted a good *fantsy* well *preposest* to help one through. If this manner of *small writing* were made *easie* and *practicable* (and I think I know such a one, but have never yet made tryal of it, whereby one might be inabled to write *a great deale* with *much ease*, and *accurately* enough in a very *little roome*) it might be of very good use to convey *secret Intelligence* without any danger of *Discovery* or *mistrusting*. But to come again to the point. The *Irregularities* of it are caused by three or four *coadjutors*, one of which is, the *uneven surface* of the *paper*, which at best appears no smother then a very course piece of *shag'd cloth*, next the *irregularity of the Type* or *Ingraving*, and a third is the *rough Daubing* of the *Printing-Ink* that lies upon the instrument that makes the impression, to all which, add the *variation* made by the Different *lights* and *shadows*, and you may have sufficient reason to ghess that a *point* may appear much more *ugly* then *this*, which I have here presented, which though it appear'd through the *Microscope gray*, like a great splatch of *London* dirt, about three inches over; yet to the *naked eye* it was *black*, and no bigger then that in the midst of the Circle A. And could I have

found

found Room in this Plate to have inserted an O you should have seen that the *letters* were not more distinct then the *points* of Distinction, nor a *drawn circle* more exactly *so*, then we have now shown a *point* to be a *point*.

Observ. II. *Of the Edge of a Razor.*

Schem. 2. *Fig.* 2. THe sharpest *Edge* hath the same kind of affinity to the sharpest *Point* in Physicks, as a *line* hath to a *point* in Mathematicks; and therefore the Treaty concerning this, may very properly be annexed to the former. A Razor doth appear to be a Body of a very neat and curious aspect, till more closely viewed by the *Microscope*, and there we may observe its very Edge to be of all kind of shapes, except what it should be. For examining that of a very sharp one, I could not find that any part of it had any thing of sharpness in it; but it appear'd a rough surface of a very considerable bredth from side to side, the narrowest part not seeming thinner then the back of a pretty thick Knife. Nor is't likely that it should appear any otherwise, since as we just now shew'd that a *point* appear'd a *circle*, 'tis rational a *line* should be a *parallelogram*.

Now for the drawing this second Figure (which represents a part of the Edge about half a quarter of an inch long of a Razor well set) I so plac'd it between the Object-glass & the light that there appear'd a reflection from the very Edge, represented by the white line *a b c d e f*. In which you may perceive it to be somewhat sharper then elsewhere about *d*, to be indented or pitted about *b*, to be broader and thicker about *c*, and unequal and rugged about *e*, and pretty even between *a b* and *e f*. Nor was that part of the Edge *g h i k* so smooth as one would imagine so smooth bodies as a Hone and Oyl should leave it; for besides those multitudes of scratches, which appear to have raz'd the surface *g h i k*, and to cross each other every way which are not half of them exprest in the Figure, there were several great and deep scratches, or furrows, such as *g h* and *i k*, which made the surface yet more rugged, caus'd perhaps by some small Dust casually falling on the Hone, or some harder or more flinty part of the Hone it self. The other part of the Razor *l l*, which is polish'd on a grinding-stone, appear'd much rougher then the other, looking almost like a plow'd field, with many parallels, ridges, and furrows, and a cloddy, as 'twere, or an uneven surface: nor shall we wonder at the roughnesses of those surfaces, since even in the most curious wrought Glasses for *Microscopes*, and other Optical uses, I have, when the Sun has shone well on them, discover'd their surface to be variously raz'd or scratched, and to consist of an infinite of small broken surfaces, which reflect the light of very various and differing colours. And indeed it seems impossible by Art to cut the surface of any hard and brittle body smooth, since *Putte*, or even the most curious *Powder* that can be made use of, to polish such a body, must consist of little hard rough particles, and each of them must cut its way, and consequently leave some kind of gutter or

furrows

furrow behind it. And though Nature does seem to do it very readily in all kinds of fluid bodies, yet perhaps future observators may discover even these also rugged; it being very probable, as I elsewhere shew, that fluid bodies are made up of small solid particles variously and strongly mov'd, and may find reason to think there is scarce a surface *in rerum naturâ* perfectly smooth. The black spot *m n*, I ghess to be some small speck of rust, for that I have oft observ'd to be the manner of the working of Corrosive Juyces. To conclude, this Edge and piece of a Razor, if it had been really such as it appear'd through the *Microscope*, would scarcely have serv'd to cleave wood, much less to have cut off the hair of beards, unless it were after the manner that *Lucian* merrily relates *Charon* to have made use of, when with a Carpenters Axe he chop'd off the beard of a sage Philosopher, whose gravity he very cautiously fear'd would indanger the oversetting of his Wherry.

Observ. III. *Of fine Lawn, or Linnen Cloth.*

THis is another product of Art, A piece of the finest Lawn I was able to get, so curious that the threads were scarce discernable by the naked eye, and yet through an ordinary *Microscope* you may perceive what a goodly piece of *coarse Matting* it is; what proportionable cords each of its threads are, being not unlike, both in shape and size, the bigger and coarser kind of *single Rope-yarn*, wherewith they usually make *Cables*. That which makes the Lawn so transparent, is by the *Microscope*, nay by the naked eye, if attentively viewed, plainly enough evidenced to be the multitude of square holes which are left between the threads, appearing to have much more hole in respect of the intercurrent parts then is for the most part left in a *lattice-window*, which it does a little resemble, onely the crossing parts are round and not flat. *Schem. 15. Fig. 3.*

These threads that compose this fine contexture, though they are as small as those that constitute the finer sorts of Silks, have notwithstanding nothing of their glossie, pleasant, and lively reflection. Nay, I have been informed both by the Inventor himself, and several other eye-witnesses, that though the flax, out of which it is made, has been (by a singular art, of that excellent Person, and Noble Vertuoso, M. *Charls Howard*, brother to the *Duke of Norfolk*) so curiously dress'd and prepar'd, as to appear both to the eye and the touch, full as *fine* and as *glossie*, and to receive all kinds of colours, as well as Sleave-Silk; yet when this Silken Flax is twisted into threads, it quite loseth its former luster, and becomes as plain and base a thread to look on, as one of the same bigness, made of common Flax.

The reason of which odd *Phenomenon* seems no other then this; that though the curiously dreſt Flax has its parts so exceedingly small, as to equallize, if not to be much smaller then the clew of the Silk-worm, especially in thinness, yet the differences between the figures of the constituting filaments are so great, and their substances so various, that whereas

 those

those of the *Silk* are *small, round, hard, transparent*, and to their bigness proportionably *stiff*, so as each filament preserves its proper *Figure*, and consequently its vivid *reflection* intire, though twisted into a thread, if not too hard; those of Flax are *flat, limber, softer*, and *less transparent*, and in twisting into a thread they joyn, and lie so close together, as to lose their own, and destroy each others particular reflections. There seems therefore three Particulars very requisite to make the so dreſt Flax appear Silk also when spun into threads. First, that the substance of it should be made more *clear* and *transparent*, Flax retaining in it a kind of opacating brown, or yellow; and the parts of the whitest kind I have yet observ'd with the *Microscope* appearing white, like flaw'd Horn or Glass, rather then clear, like clear Horn or Glass. Next that, the filaments should each of them be *rounded*, if that could be done, which yet is not so very necessary, if the first be perform'd, and this third, which is, that each of the small filaments be *stifned*; for though they be square, or flat, provided they be *transparent* and stiff, much the same appearances must necessarily follow. Now, though I have not yet made trial, yet I doubt not, but that both these proprieties may be also induc'd upon the Flax, and perhaps too by one and the same Expedient, which some trials may quickly inform any ingenious attempter of, who from the use and profit of such an Invention, may find sufficient argument to be prompted to such Inquiries. As for the *tenacity* of the substance of Flax, out of which the thread is made, it seems much inferiour to that of Silk, the one being a *vegetable*, the other an *animal* substance. And whether it proceed from the better concoction, or the more homogeneous constitution of *animal* substances above those of *vegetables*, I do not here determine; yet since I generally find, that *vegetable* substances do not equalize the *tenacity* of *animal*, nor these the *tenacity* of some purified *mineral* substances; I am very apt to think, that the *tenacity* of bodies does not proceed from the *hamous*, or *hooked* particles, as the *Epicureans*, and some modern *Philosophers* have imagin'd; but from the more exact *congruity* of the constituent parts, which are contiguous to each other, and so bulky, as not to be easily separated, or shatter'd, by any small pulls or concussion of heat.

Observ. IV. *Of fine waled Silk, or Taffety.*

Schem. 3. *Fig.* 1. THis is the appearance of a piece of very fine Taffety-riband in the bigger magnifying Glass, which you see exhibits it like a very convenient substance to make Bed-matts, or Door-matts of, or to serve for Bee-hives, Corn-scuttles, Chairs, or Corn-tubs, it being not unlike that kind of work, wherewith in many parts in *England*, they make such Utensils of Straw, a little wreathed, and bound together with thongs of Brambles. For in this Contexture, each little filament, fiber, or clew of the Silk-worm, seem'd about the bigness of an ordinary Straw, as appears by the little irregular

Fig: 1



Fig: 3

Fig: 4

A

Fig: 2

C

D



B

regular pieces, *a b*, *c d*, and *e f*; The *Warp*, or the thread that ran crossing the Riband, appear'd like a single Rope of an Inch Diameter; but the *Woof*, or the thread that ran the length of the Riband, appear'd not half so big. Each Inch of six-peny-broad Riband appearing no less then a piece of Matting Inch and half thick, and twelve foot square; a few yards of this, would be enough to floor the long Gallery of the *Loure* at *Paris*. But to return to our piece of Riband: It affords us a not unpleasant object, appearing like a bundle, or wreath, of very clear and transparent *Cylinders*, if the Silk be white, and curiously ting'd; if it be colour'd, each of those small horney *Cylinders* affording in some place or other of them, as vivid a reflection, as if it had been sent from a *Cylinder* of Glass or Horn. In-so-much, that the reflections of Red, appear'd as if coming from so many *Granates*, or *Rubies*. The lovelines of the colours of Silks above those of hairy Stuffs, or Linnen, consisting as I else-where intimate, chiefly in the transparency, and vivid reflections from the *Concave*, or inner surface of the *transparent Cylinder*, as are also the colours of Precious Stones; for most of the reflections from each of these *Cylinders*, come from the *Concave* surface of the air, which is as 'twere the foil that incompasses the *Cylinder*. The colours with which each of these *Cylinders* are ting'd, seem partly to be superficial, and sticking to the out-sides of them; and partly, to be imbib'd, or sunck into the substance of them: for Silk, seeming to be little else then a dried thread of Glew, may be suppos'd to be very easily relaxt, and softened, by being steeped in warm, nay in cold, if penetrant, juyces or liquors. And thereby those tinctures, though they tinge perhaps but a small part of the substance, yet being so highly impregnated with the colour, as to be almost black with it, may leave an impression strong enough to exhibite the desir'd colour. A pretty kinde of artificial Stuff I have seen, looking almost like transparent Parchment, Horn, or Ising-glass, and perhaps some such thing it may be made of, which being transparent, and of a glutinous nature, and easily mollified by keeping in water, as I found upon trial, had imbib'd, and did remain ting'd with a great variety of very vivid colours, and to the naked eye, it look'd very like the substance of the Silk. And I have often thought, that probably there might be a way found out, to make an artificial glutinous composition, much resembling, if not full as good, nay better, then that Excrement, or whatever other substance it be out of which, the Silk-worm wire-draws his clew. If such a composition were found, it were certainly an easie matter to find very quick ways of drawing it out into small wires for use. I need not mention the use of such an Invention, nor the benefit that is likely to accrue to the finder, they being sufficiently obvious. This hint therefore, may, I hope, give some Ingenious inquisitive Person an occasion of making some trials, which if successfull, I have my aim, and I suppose he will have no occasion to be displeas'd.

Obſerv. V. *Of watered Silks, or Stuffs.*

Schem. 3. Fig. 2. THere are but few *Artificial* things that are worth obſerving with a *Microſcope*; and therefore I ſhall ſpeak but briefly concerning them. For the Productions of art are ſuch rude miſ-ſhapen things, that when view'd with a *Microſcope*, there is little elſe obſervable, but their deformity. The moſt curious Carvings appearing no better then thoſe rude *Ruſſian* Images we find mention'd in *Purchas*, where three notches at the end of a Stick, ſtood for a face. And the moſt ſmooth and burniſh'd ſurfaces appear moſt rough and unpoliſht: So that my firſt Reaſon why I ſhall add but a few obſervations of them, is, their miſ-ſhapen form; and the next, is their uſeleſsneſs. For why ſhould we trouble our ſelves in the examination of that form or ſhape (which is all we are able to reach with a *Microſcope*) which we know was deſign'd for no higher a uſe, then what we were able to view with our naked eye? Why ſhould we endeavour to diſcover myſteries in that which has no ſuch thing in it? And like *Rabbins* find out *Caballiſms*, and *ænigmâs* in the Figure, and placing of Letters, where no ſuch thing lies hid: whereas in *natural* forms there are ſome ſo ſmall, and ſo curious, and their deſign'd buſineſs ſo far remov'd beyond the reach of our ſight, that the more we magnify the object, the more excellencies and myſteries do appear; And the more we diſcover the imperfections of our ſenſes, and the Omnipotency and Infinite perfections of the great Creatour. I ſhall therefore onely add one or two Obſervations more of *artificial* things, and then come to the Treaty concerning ſuch matters as are the Productions of a more curious Workman. One of theſe, ſhall be that of a piece of water'd Silk, repreſented in the ſecond Figure of the third *Scheme*, as it appear'd through the leaſt magnifying Glaſs. *A B.* ſignifying the long way of the Stuff, and *C D* the broad way. This Stuff, if the right ſide of it be looked upon, appears to the naked eye, all over ſo waved, undulated, or grain'd, with a curious, though irregular variety of brighter and darker parts, that it adds no ſmall gracefulneſs to the Gloſs of it. It is ſo known a propriety, that it needs but little explication; but it is obſervable, which perhaps every one has not conſidered, that thoſe parts which appear the darker part of the wave, in one poſition to the light, in another appears the lighter, and the contrary; and by this means the undulations become tranſient, and in a continual change, according as the poſition of the parts in reſpect of the incident beams of light is varied. The reaſon of which odd *phænomena*, to one that has but diligently examin'd it even with his naked eye, will be obvious enough. But he that obſerves it with a *Microſcope*, may more eaſily perceive what this *Proteus* is, and how it comes to change its ſhape. He may very eaſily perceive, that it proceeds onely from the variety of the *Reflections* of light, which is caus'd by the various *ſhape of the Particles*, or little protuberant parts of the thread that compoſe the ſurface; and that thoſe parts of the waves that appear

appear the brighter, throw towards the eye a multitude of ſmall reflections of light, whereas the darker ſcarce afford any. The reaſon of which reflection, the *Microſcope* plainly diſcovers, as appears by the Figure. In which you may perceive, that the brighter parts of the ſurface conſiſt of an abundance of large and ſtrong reflections, denoted by *a, a, a, a, a,* &c. for the ſurfaces of thoſe threads that run the *long way*, are by the Mechanical proceſs of watering, *creas'd* or *angled* in another kind of poſture then they were by the weaving: for by the weaving they are onely *bent round* the warping threads; but by the watering, they are *bent with an angle, or elbow*, that is in ſtead of lying, or being bent *round* the threads, as in the third Figure, *a, a, a, a, a,* are about *b, b, b* (*b, b, b* repreſenting the ends, as 'twere, of the croſs threads, they are bent about) they are creas'd on the top of thoſe threads, with an *angle*, as in the fourth Figure, and that with all imaginable variety; ſo that, whereas before they reflected the light onely from one point of the round ſurface, as about *c, c, c,* they now when water'd, reflect the beams from more then half the whole ſurface, as *de, de, de,* and in other poſtures they return no reflections at all from thoſe ſurfaces. Hence in one poſture they compoſe the brighter parts of the waves, in another the darker. And theſe reflections are alſo varied, according as the particular parts are variouſly bent. The reaſon of which creaſing we ſhall next examine; and here we muſt fetch our information from the Mechaniſm or manner of proceeding in this operation; which, as I have been inform'd, is no other then this.

They double all the Stuff that is to be water'd, that is, they creaſe it juſt through the middle of it, the whole length of the piece, leaving the right ſide of the Stuff inward, and placing the two edges, or ſilvages juſt upon one another, and, as near as they can, place the wale ſo in the doubling of it, that the wale of the one ſide may lie very near parallel, or even with the wale of the other; for the nearer that poſture they lie, the greater will the watering appear; and the more obliquely, or acroſs to each other they lie, the ſmaller are the waves. Their way for folding it for a great wale is thus: they take a Pin, and begin at one ſide of the piece in any wale, and ſo moving it towards the other ſide, thereby direct their hands to the oppoſite ends of the wale, and then, as near as they can, place the two oppoſite ends of the ſame wale together, and ſo double, or fold the whole piece, repeating this enquiry with a Pin at every yard or two's diſtance through the whole length; then they ſprinkle it with water, and fold it the longways, placing between every fold a piece of Paſtboard, by which means all the wrong ſide of the water'd Stuff becomes flat, and with little wales, and the wales on the other ſide become the more protuberant; whence the creaſings or angular bendings of the wales become the more perſpicuous. Having folded it in this manner, they place it with an interjacent Paſtboard into an hot Preſs, where it is kept very violently preſt, till it be dry and ſtiff; by which means, the wales of either contiguous ſides leave their own impreſſions upon each other, as is very manifeſt by the ſecond Figure, where 'tis obvious enough, that the wale of the piece *A B C D* runs parallel between the pricked lines *ef, ef, ef,* and as

manifest to discern the impressions upon these wales, left by those that were prest upon them, which lying not exactly parallel with them, but a little athwart them, as is denoted by the lines of, *o o o o*, *gh*. *gh*, *gh*, between which the other wales did lie parallel; they are so variously, and irregularly creas'd that being put into that shape when wet, and kept so till they be drie, they so set each others threads, that the Moldings remain almost as long as the Stuff lasts.

Hence it may appear to any one that attentively considers the Figure, why the parts of the wale *a*, *a*, *a*, *a*, *a*, *a*, should appear bright; and why the parts *b*, *b*, *b*, *b*, *b*, *b*, should appear shadowed, or dark; why some, as *d*, *d*, *d*, *d*, *d*, *d*, should appear partly light, and partly dark: the varieties of which reflections and shadows are the only cause of the appearance of watering in Silks, or any other kind of Stuffs.

From the variety of reflection, may also be deduc'd the cause why a small breez or gale of wind ruffling the surface of a smooth water, makes it appear black; as also, on the other side, why the smoothing or burnishing the surface of whitened Silver makes it look black; and multitudes of other phænomena might hereby be solv'd, which are too many to be here insisted on.

Observ. VI. *Of small Glass Canes.*

Schem. 4. THat I might be satisfi'd, whether it were not possible to make an *Artificial* pore as *small* as any *Natural* I had yet found, I made several attemps with small *glass pipes*, melted in the flame of a Lamp, and then very *suddenly* drawn out into a great length. And, by *that means*, without much difficulty, I was able to draw some almost as small as a *Cobweb*, which yet, with the *Microscope*, I could plainly perceive to be *perforated*, both by looking on the *ends* of it, and by looking on it *against the light*; which was much the *easier way* to determine whether it were solid or perforated; for, taking a small pipe of glass, and closing one end of it, then filling it *half full* of water, and holding it *against the light*, I could, by this means, very easily find what was the *differing aspect* of a *solid* and a *perforated* piece of glass; and so easily distinguish, without seeing either end, whether any *Cylinder* of glass I look'd on, were a *solid stick*, or a *hollow cane*. And by this means, I could also presently judge of any small *filament* of glass, whether it were *hollow* or *not*, which would have been exceeding tedious to examine by looking on the end. And many such like ways I was fain to make use of, in the examining of divers other particulars related in this Book, which would have been no easie task to have determined meerly by the more common way of looking on, or viewing the Object. For, if we consider first, the very *faint light* wherewith the object is enlightened, whence many particles appear *opacous*, which when more enlightned, appear very *transparent*, so that I was fain to *determine* its *transparency* by one glass, and its *texture* by another Next, the *unmanageableness* of most *Objects*, by reason of


Fig. 2.
Fig. 3.
Figura
Quarta.
Fig: 5.
Fig: 6.
Fig: Z
Fig: Y
Fig: X
Fig: &.

of their *smalness*, 3. The *difficulty of finding* the desired point, and of *placing* it so, as to reflect the *light conveniently* for the Inquiry. Lastly, ones being able to view it but with *one eye* at once, they will appear no small *obstructions*, nor are they easily *remov'd* without many *contrivances*. But to proceed, I could not find that water, or some *deeply ting'd* liquors would in small ones rise so high as one would expect; and the *highest* I have found it yet rise in any of the pipes I have try'd, was to 21 *inches* above the level of the water in the vessel: for though I found that in the small pipes it would *nimbly enter* at first, and run about 6 or 7 *inches* upwards; yet I found it then to move upwards *so slow*, that I have not yet had the *patience* to observe it above that height of 21 *inches* (and that was in a pretty *large Pipe*, in comparison of those I formerly mentioned; for I could observe the *progress* of a *very deep ting'd liquor* in it with my *naked eye*, without much trouble; whereas many of the *other pipes* were so *very small*, that unless in a *convenient posture* to the light, I could not perceive *them*:) But 'tis very probable, that a greater *patience* and *assiduity* may discover the liquors to *rise*, at least to remain *suspended*, at heights that I should be loath now even to *ghess* at, if at least there be any *proportion* kept between the height of the ascending liquor, and the *bigness of the holes* of the pipes.

An Attempt for the Explication of this Experiment.

My Conjecture, *That the unequal height of the surfaces of the water, proceeded from the greater pressure made upon the water by the Air without the Pipes* A B C, *then by that within them*; I shall endeavour to confirm from the truth of the two following *Propositions*: Schem. 4. Fig. 1.

The first of which is, *That an unequal pressure of the incumbent Air, will cause an unequal height in the water's Surfaces.*

And the second is, *That in this experiment there is such an unequal pressure.*

That the first is true, the following *Experiment* will evince. For if you take any Vessel so contrived, as that you can at pleasure either *increase* or *diminish* the *pressure* of the Air upon this or that part of the *Superficies* of the *water*, the *equality* of the height of those parts will presently be *lost*; and that part of the *Superficies* that sustains the *greater pressure*, will be *inferior* to that which undergoes the *less*. A fit Vessel for this purpose, will be an inverted Glass *Syphon*, such an one as is described in the *Sixth Figure*. For if into it you put Water enough to fill it as high as *A B*, and gently blow in at *D*, you shall *depress* the Superficies *B*, and thereby *raise* the opposite Superficies *A* to a *considerable height*, and by gently *sucking* you may produce clean *contrary* effects.

Next, That there is such an *unequal pressure*, I shall prove from this, *That there is a much greater incongruity of Air to Glass, and some other Bodies, then there is of Water to the same.*

By *Congruity, I mean a property of a fluid Body, whereby any part of it is readily united with any other part, either of it self, or of any other similar, fluid, or solid body: And by Incongruity a property of a fluid, by which it is hindred from uniting with any dissimilar, fluid, or solid Body.*

This last property, any one that hath been observingly conversant about fluid Bodies, cannot be ignorant of. For (not now to mention several *Chymical Spirits* and *Oyls*, which will *very hardly*, if at *all*, be brought to *mix* with one another; insomuch that there may be found some 8 or 9, or more, several distinct Liquors, which *swimming* one upon another, will not presently *mix*) we need seek no further for Examples of this kind in *fluids*, then to observe the *drops of rain* falling through the *air*, and the *bubbles of air* which are by any means conveyed under the surface of the *water*; or a drop of common *Sallet Oyl* swimming upon water. In all which, and many more examples of this kind that might be enumerated, the *incongruity* of two *fluids* is easily discernable. And as for the *Congruity* or *Incongruity* of Liquids, with several kinds of *firm* Bodies, they have long since been taken notice of, and called by the Names of *Drineſs* and *Moiſture* (though these two names are not comprehensive enough, being commonly used to signifie only the adhering or not adhering of *water* to some other *solid Bodies*) of this kind we may observe that *water* will more readily *wet some woods* then *others*; and that *water*, let fall upon a *Feather*, the whiter side of a *Colwort*, and some other leaves, or upon almost any *dusty*, *unctuous*, or *resinous* superficies, will not *at all adhere* to them, but easily *tumble off* from them, like a solid *Bowl*; whereas, if dropt upon *Linnen*, *Paper*, *Clay*, *green Wood*, &c. it will not be taken off, without leaving some part of it behind *adhering* to them. So *Quick-silver*, which will very *hardly* be brought to *stick* to any *vegetable body*, will *readily adhere* to, and *mingle* with, several clean *metalline bodies*.

And that we may the better finde what the *cause* of *Congruity* and *Incongruity* in bodies is, it will be requisite to consider, First, what is the *cause* of *fluidness*; And this, *I conceive*, to be nothing else but a certain *pulse* or *shake* of *heat*; for Heat being nothing else but a very *brisk* and *vehement agitation* of the parts of a body (as I have elswhere made *probable*) the parts of a body are thereby made so *loose* from one another, that they easily *move any way*, and become *fluid*. That I may explain this a little by a gross Similitude, let us suppose a dish of sand set upon some body that is very much *agitated*, and shaken with some *quick* and *strong vibrating motion*, as on a *Millstone* turn'd round upon the under stone very violently whilst it is empty; or on a very stiff *Drum*-head, which is vehemently or very nimbly beaten with the Drumsticks. By this means, the sand in the dish, which before lay like a *dull* and unactive body, becomes a perfect *fluid*; and ye can no sooner make a *hole* in it with your finger, but it is immediately *filled up again*, and the upper surface of it *level'd*. Nor can you *bury* a *light body*, as a piece of Cork under it, but it presently *emerges* or *swims* as 'twere on the top; nor can you lay a *heavier* on the top of it, as a piece of Lead, but it is immediately *buried*

in

in Sand, and (as 'twere) sinks to the bottom. Nor can you make a *hole* in the side of the Dish, but the sand shall *run out* of it to a *level*, not an *obvious property* of a fluid body, as such, but this dos *imitate*; and all this meerly caused by the vehement *agitation* of the conteining vessel; for by this means, *each* sand becomes to have a *vibrative* or *dancing* motion, so as no other heavier body can *rest* on it, unless *sustein'd* by some other on either side: Nor will it suffer any Body to be *beneath* it, unless it be a *heavier* then it self. Another Instance of the strange *loosening* nature of a violent jarring Motion, or a strong and nimble vibrative one, we may have from a piece of *iron* grated on very strongly with a *file*: for if into that a pin be *screw'd* so firm and hard, that though it has a convenient head to it, yet it can by no means be *unscrew'd* by the fingers; if, I say, you attempt to unscrew this whilst *grated on by the file*, it will be found to undoe and turn very *easily*. The first of these Examples manifests, how a body actually *divided* into small parts, becomes a *fluid*. And the latter manifests by what means the agitation of heat so easily *loosens* and *unties* the parts of *solid* and *firm* bodies. Nor need we suppose heat to be any thing else, besides such a motion; for supposing we could *Mechanically* produce such a one *quick* and *strong* enough, we need not spend *fuel* to *melt* a body. Now, that I do not speak this altogether groundless, I must refer the Reader to the Observations I have made upon the shining sparks of Steel, for there he shall find that *the same* effects are produced upon small chips or parcels of Steel by the *flame*, and by *a quick and violent motion*; and if the body of *steel* may be thus melted (as I there shew it may) I think we have little reason to doubt that almost *any other* may not also. Every Smith can inform one how quickly both his *File* and the *Iron* grows *hot* with *filing*, and if you *rub* almost any two *hard* bodies together, they will do the same: And we know, that a sufficient degree of heat causes *fluidity*, in some bodies much sooner, and in others later; that is, the parts of the body of some are so *loose* from one another, and so *unapt to cohere*, and so *minute* and *little*, that a very *small* degree of agitation keeps them always in the *state of fluidity*. Of this kind, I suppose, the *Æther*, that is the *medium* or *fluid* body, in which all other bodies do as it were swim and move; and particularly, the *Air*, which seems nothing else but a kind of *tincture* or *solution* of terrestrial and aqueous particles *dissolv'd* into it, and agitated by it, just as the *tincture* of *Cocheneel* is nothing but some finer *dissoluble* parts of that Concrete lick'd up or *dissolv'd* by the *fluid* water. And from this Notion of it, we may easily give a more Intelligible reason how the Air becomes so capable of *Rarefaction* and *Condensation*. For, as in *tinctures*, one grain of some *strongly tinging* substance may *sensibly* colour some *hundred thousand* grains of *appropriated* Liquors, so as every *drop* of it has its proportionate share, and be sensibly ting'd, as I have try'd both with *Logwood* and *Cocheneel*: And as some few grains of *Salt* is able to infect as great a quantity, as may be found by *præcipitations*, though not so easily by the *sight* or *taste*; so the *Air*, which seems to be but as 'twere a *tincture* or *saline substance*, *dissolv'd and agitated by the fluid and agil Æther*, may disperse

perſe and *expand* it ſelf into a *vaſt ſpace*, if it have room enough, and infect, as it were, every part of that ſpace. But, as on the other ſide, if there be but ſome *few grains* of the liquor, it may *extract all* the colour of the tinging ſubſtance, and may *diſſolve* all the Salt, and thereby become *much more impregnated* with thoſe ſubſtances, ſo may *all* the air that ſufficed in a *rarify'd ſtate* to fill ſome *hundred thouſand* ſpaces of Æther, be compris'd in only *one*, but in a poſition proportionable *denſe*. And though we have not yet found out ſuch *ſtrainers* for Tinctures and Salts as we have for the Air, being yet unable to *ſeparate* them from their diſſolving liquors by any kind of *filtre*, without *præcipitation*, as we are able to *ſeparate* the Air from the Æther by *Glaſs*, and ſeveral other bodies. And though we are yet unable and ignorant of the ways of *præcipitating* Air out of the Æther as we can Tinctures, and Salts out of ſeveral *diſſolvents*; yet neither of theſe ſeeming *impoſſible* from the nature of the things, nor ſo *improbable* but that ſome happy future induſtry may find out ways to effect them; nay, further, ſince we find that Nature *does really perform* (though by what means we are not certain) both theſe actions, namely, by *præcipitating* the Air in Rain and Dews, and by ſupplying the Streams and Rivers of the World with freſh water, *ſtrain'd* through ſecret ſubterraneous Caverns: And ſince, that in very many other *proprieties* they do ſo exactly *ſeem* of the *ſame nature*; till further obſervations or tryals do inform us of the *contrary*, we may *ſafely enough conclude* them of the *ſame kind*. For it ſeldom happens that any two natures have ſo many properties *coincident* or the *ſame*, as I have obſerv'd Solutions and Air to have, and to be *different* in the reſt. And therefore I think it neither *impoſſible*, *irrational*, nay nor *difficult* to be able to *predict* what is *likely* to happen in other particulars alſo, beſides thoſe which *Obſervation* or *Experiment* have declared thus or thus; eſpecially, if the *circumſtances* that do often very much conduce to the variation of the effects be duly *weigh'd* and *conſider'd*. And indeed, were there not a *probability* of this, our *inquiries* would be *endleſs*, our *tryals vain*, and our greateſt *inventions* would be nothing but the meer *products* of *chance*, and not of *Reaſon*; and, like *Mariners* in an Ocean, deſtitute both of a *Compaſs* and the ſight of the *Celeſtial guids*, we might indeed, *by chance*, Steer *directly* towards our deſired Port, but 'tis *a thouſand to one* but we *miſs* our aim. But to proceed, we may hence alſo give a plain reaſon, how the Air comes to be *darkned* by *clouds*, &c. which are nothing but a kind of *precipitation*, and how thoſe *precipitations* fall down in *Showrs*. Hence alſo could I very eaſily, and I think truly, deduce the cauſe of the curious *ſixangular figures* of Snow, and the appearances of *Haloes*, *&c.* and the ſudden *thickning* of the Sky with Clouds, and the *vaniſhing* and *diſappearing* of thoſe Clouds again; for all theſe things may be very eaſily *imitated* in a *glaſs of liquor*, with ſome ſlight *Chymical preparations* as I have often try'd, and may ſomewhere elſe more largely relate, but have not now time to ſet them down. But to proceed, there are other bodies that conſiſt of particles more *Groſs*, and of a more *apt* figure for *coheſion*, and this requires a *ſomewhat greater* agitation; ſuch, I ſuppoſe ☿. *fermented vinous*

Spirits

Spirits, several *Chymical Oils*, which are much of kin to those Spirits, &c. Others yet require a *greater*, as *water*, and so others *much greater*, for almost infinite degrees: For, I suppose there are very *few* bodies in the world that may not be made *aliquatenus* fluid, by *some* or *other* degree of agitation or heat.

Having therefore in short set down my Notion of a Fluid body, I come in the next place to consider what *Congruity* is; and this, as I said before, being a *Relative property* of a fluid, whereby it may be said to be *like* or *unlike* to this or that other body, whereby it *does* or *does not mix* with this or that body. We will again have recourse to our former Experiment, though but a rude one; and here if we mix in the dish *several kinds* of sands, some of *bigger*, others of *less* and finer bulks, we shall find that by the agitation the *fine sand* will *eject* and *throw out* of it self all those *bigger* bulks of small *stones* and the like, and those will be *gathered* together all into *one* place; and if there be *other* bodies in it of other natures, those also will be *separated* into a place by themselves, and *united* or *tumbled* up together. And though this do not come up to the *highest property* of *Congruity*, which is a *Cohæsion* of the parts of the fluid together, or a kind of *attraction* and *tenacity*, yet this does as 'twere *shadow* it out, and somewhat resemble it; for just after the same manner, I suppose the *pulse* of heat to *agitate* the small parcels of matter, and those that are of a *like bigness*, and *figure*, and *matter*, will *hold*, or *dance* together, and those which are of a *differing* kind will be *thrust* or *shov'd* out from between them; for particles that are all *similar*, will, like so many *equal musical strings equally stretcht*, vibrate together in a kind of *Harmony* or *unison*; whereas others that are *dissimilar*, upon what account soever, unless the disproportion be otherwise counter-ballanc'd, will, like so many *strings out of tune* to those unisons, though they have the same agitating *pulse*, yet make quite *differing* kinds of *vibrations* and *repercussions*, so that though they may be both mov'd, yet are their *vibrations* so *different*, and so *untun'd*, as 'twere to each other, that they *cross* and *jar* against each other, and consequently, *cannot agree* together, but *fly back* from each other to their similar particles. Now, to give you an instance how the *disproportion* of some bodies in one respect, may be *counter-ballanc'd* by a *contrary disproportion* of the same body in another respect, whence we find that the subtil *vinous spirit* is *congruous*, or does readily *mix* with *water*, which in many properties is of a very *differing nature*, we may consider that a *unison* may be made either by two *strings* of the same *bigness*, *length*, and *tension*, or by two strings of the same *bigness*, but of *differing length*, and a *contrary differing tension*; or 3*ly*. by two strings of *unequal length* and *bigness*, and of a *differing tension*, or of *equal length*, and *differing bigness* and *tension*, and several other such varieties. To which *three properties* in *strings*, will correspond *three proprieties* also in *sand*, or the *particles* of bodies, their *Matter* or *Substance*, their *Figure* or *Shape*, and their *Body* or *Bulk*. And from the *varieties* of these *three*, may arise *infinite varieties* in fluid bodies, though all agitated by the *same pulse* or *vibrative* motion. And there may be as many ways of making Harmonies

and

and Discords with these, as there may be with *musical strings*. Having therefore seen what is the cause of Congruity or Incongruity, those relative properties of fluids, we may, from what has been said, very easily collect, what is the *reason* of those Relative proprieties also between *fluid bodies* and *solid*; for since all bodies consist of *particles* of such a *Substance*, *Figure*, and *Bulk*; but in some they are *united* together more *firmly* then to be *loosened* from each other by every *vibrative* motion (though I imagine that there is no body in the world, but that some degree of agitation may, as I hinted before, agitate and loosen the particles so as to make them fluid) those *cohering* particles may *vibrate* in the same manner almost as those that are *loose* and become *unisons* or *discords*, as I may so speak, to them. Now that the *parts* of all *bodies*, though never so *solid*, do yet *vibrate*, I think we need go no further for proof, then that *all* bodies have some *degrees* of *heat* in them, and that there has not been yet found any thing *perfectly cold*: Nor can I believe indeed that there is any such thing in Nature, as a body whose particles are at *rest*, or *lazy* and *unactive* in the great *Theatre* of the *World*, it being quite *contrary* to the grand *Oeconomy* of the Universe. We see therefore what is the reason of the *sympathy* or uniting of some bodies together, and of the *antipathy* or flight of others from each other: For *Congruity* seems nothing else but a *Sympathy*, and *Incongruity* an *Antipathy* of bodies; hence *similar* bodies once *united* will not *easily part*, and *dissimilar* bodies once *disjoyn'd* will not *easily unite* again; from hence may be very easily deduc'd the reason of the *suspension* of *water* and *Quick-silver* above their usual *station*, as I shall more at large anon shew.

These properties therefore (alwayes the concomitants of fluid bodies) produce these following visible *Effects*:

First, They *unite* the parts of a fluid to its *similar* Solid, or keep them *separate* from its *dissimilar*. Hence *Quick-silver* will (as we noted before) *stick* to *Gold*, *Silver*, *Tin*, *Lead*, &c. and *unite* with them: but *roul* off from *Wood*, *Stone*, *Glass*, &c. if never so little scituated out of its *horizontal level*; and *water* that will *wet salt* and *dissolve* it, will *slip* off from *Tallow*, or the like, without at all *adhering*; as it may likewise be observed to do upon a *dusty* superficies. And next they cause the parts of *homogeneal fluid* bodies readily to *adhere* together and *mix*, and of *heterogeneal*, to be exceeding *averse* thereunto. Hence we find, that *two* small *drops* of *water*, on any superficies they can roul on, will, if they chance to touch each other, *readily unite* and *mix* into one 3d *drop*: The like may be observed with two small *Bowls* of *Quick-silver* upon a Table or Glass, provided their surfaces be not *dusty*; and with two drops of *Oyl* upon fair water, *&c.* And further, *water* put unto *wine*, *salt water*, *vinegar*, *spirit* of *wine*, or the like, does immediately (especially if they be shaken together) *disperse* it self all over them. Hence, on the contrary, we also find, that *Oyl of Tartar* poured upon *Quick-silver*, and *Spirit of Wine* on that *Oyl*, and *Oyl of Turpentine* on that *Spirit*, and *Air* upon that *Oyl*, though they be stopt closely up into a Bottle, and *shaken* never so much, they will by no means long suffer any of their bigger parts to be *united* or in-

cluded

cluded within any of the other Liquors(by which recited Liquors,may be plainly enough represented the four *Peripatetical Elements*, and the more subtil *Æther* above all.) From this property'tis, that a drop of *water* does not mingle with, or vanish into *Air*, but is *driven* (by that Fluid equally protruding it on every side) and forc't into as little a space as it can possibly be contained in, namely, into a *Round Globule*. So likewise a little *Air* blown under the *water*, is *united* or thrust into a *Bubble* by the ambient water. And a parcel of *Quick-silver* enclosed with *Air*, *Water*, or almost any other *Liquor*, is *formed* into a *round Ball*.

Now the cause why all these included Fluids, newly mentioned, or as many others as are wholly included within a heterogeneous fluid, are not *exactly* of a *Spherical Figure* (seeing that if caused by these Principles only, it could be of no other) must proceed from some other kind of *pressure* against the two opposite flatted sides. This *adventitious* or *accidental pressure* may proceed from *divers causes*, and accordingly must *diversifie* the Figure of the included heterogeneous fluid: For seeing that a body may be included either with a fluid only, or only with a solid, or partly with a fluid, and partly with a solid, or partly with one fluid, and partly with another; there will be found a very great variety of the terminating *surfaces*, much differing from a *Spherical*, according to the various resistance or pressure that belongs to each of these encompassing bodies.

Which Properties may in general be deduced from two heads, *viz. Motion*, and *Rest*. For, either this Globular Figure is altered by a *natural Motion*, such as is *Gravity*; or a *violent*, such as is any *accidental motion* of the fluids, as we see in the *wind* ruffling up the water,and the *purlings* of *Streams*, and *foaming* of *Catarracts*, and the like. Or thirdly, By the *Rest*, *Firmness* and *Stability* of the ambient *Solid*. For if the including *Solid* be of an *angular* or any other *irregular* Form, the included *fluid* will be near of the *like*,as a Pint-*Pot* full of *water*,or a *Bladder* full of *Air*. And next, if the including or included fluid have a greater *gravity* one than another,then will the *globular* Form be depreſt into an *Elliptico-spherical*: As if, for example, we suppose the Circle *A B C D*, in the *fourth Figure*, to represent a *drop of water*, *Quick-silver*, or the like, included with the *Air* or the like, which supposing there were no *gravity* at all in either of the *fluids*, or that the *contained* and *containing* were of the *same weight*, would be *equally compreſt* into an exactly *spherical* body (the ambient fluid *forcing equally* against every side of it.) But supposing either a greater *gravity* in the included, by reason whereof the parts of it being *preſt* from *A* towards *B*, and thereby the whole put into *motion*, and that *motion* being *hindred* by the *resistance* of the *subjacent* parts of the ambient, the *globular* Figure *A D B C* will be *depreſt* into the *Elliptico-spherical*, *E G F H*. For the side *A* is *detruded* to *E* by the *Gravity*, and *B* to *F* by the *resistance* of the subjacent medium: and therefore *C* must necessarily be thrust to *G*; and *D* to *H*. Or else, supposing a greater *gravity* in the *ambient*, by whose more then ordinary *pressure* against the under side of the included globule; *B* will be forced to *F*, and by its *resistance* of

the motion *upwards*, the side *A* will be *depreſt* to *E*, and therefore *C* being thruſt to *G* and *D* to *H*; the *globular* Figure by this means alſo will be made an *Elliptico-ſpherical*. Next if a fluid be included *partly* with one, and *partly* with another fluid, it will be found to be ſhaped *diverſly*, according to the proportion of the *gravity* and *incongruity* of the 3 *fluids* one to another: As in the *ſecond Figure*, let the upper *M M M* be *Air*, the middle *L M N O* be common *Oyl*, the lower *O O O* be *Water*, the *Oyl* will be form'd, not into a *ſpherical* Figure, ſuch as is repreſented by the *pricked Line*, but into ſuch a Figure as L M N O, whoſe ſide L M N will be of a flatter *Elliptical* Figure, by reaſon of the great diſproportion between the *Gravity* of *Oyl* and *Air*, and the ſide L O M of a rounder, becauſe of the ſmaller difference between the weight of *Oyl* and *Water*. Laſtly, The *globular* Figure will be changed, if the *ambient* be partly *fluid* and partly *ſolid*. And here the termination of the incompaſſed *fluid* towards the incompaſſing is ſhap'd according to the proportion of the congruity or incongruity of the *fluids* to the *ſolids*, and of the gravity and incongruity of the *fluids* one to another. As ſuppoſe the ſubjacent *medium* that hinders an included fluids deſcent, be a *ſolid*, as let K I, in the *fourth Figure*, repreſent the ſmooth ſuperficies of a *Table*; E G F H, a parcel of *running Mercury*; the ſide G F H will be more flatted, according to the proportion of the incongruity of the *Mercury* and *Air* to the *Wood*, and of the *gravity* of *Mercury* and *Air* one to another; The ſide G E H will likewiſe be a little more depreſt by reaſon the ſubjacent parts are now at reſt, which were before in motion.

Or further in the *third Figure*, let A I L D repreſent an including *ſolid* medium of a cylindrical ſhape (as ſuppoſe a ſmall *Glaſs Jar*) Let F G E M M repreſent a contain'd *fluid*, as water; this towards the bottom and ſides, is figured according to the concavity of the *Glaſs*: But its upper *Surface*, (which by reaſon of its gravity, (not conſidering at all the Air above it, and ſo neither the congruity or incongruity of either of them to the Glaſs) ſhould be terminated by part of a *Sphere* whoſe diameter ſhould be the ſame with that of the earth, which to our ſenſe would appear a ſtraight *Line*, as F G E, Or which by reaſon of its having a greater congruity to Glaſs than Air has, (not conſidering its Gravity) would be thruſt into a *concave Sphere*, as C H B, whoſe diameter would be the ſame with that of the concavity of the Veſſel:) Its upper Surface, I ſay, by reaſon of its having a greater gravity then the Air, and having likewiſe a greater congruity to Glaſs then the Air has, is terminated, by a *concave Elliptico-ſpherical* Figure, as C K B. For by its congruity it eaſily conforms it ſelf, and adheres to the Glaſs, and conſtitutes as it were one containing body with it, and therefore ſhould thruſt the contained Air on that ſide it touches it, into a *ſpherical* Figure, as B H C, but the motion of Gravity depreſſing a little the Corners B and C, reduces it into the aforeſaid Figure C K B. Now that it is the greater congruity of one of the two *contiguous fluids*, then of the other, to the containing *ſolid*, that cauſes the ſeparating ſurfaces to be thus or thus figured: And that it is not becauſe this or that figurated ſurface is more proper, natural, or peculiar to

one

one of these fluid bodies, then to the other, will appear from this, that the same *fluids* will by being put into differing *solids*, change their *surfaces*. For the same water, which in a Glass or wooden Vessel will have a concave surface upwards, and will rise higher in a smaller then a greater Pipe, the same water, I say, in the same Pipes greased over or oyled, will produce quite contrary effects; for it will have a *protuberant* and *convex* surface upwards, and will not rise so high in small, as in bigger Pipes: Nay, in the very same solid Vessel, you may make the very same two contiguous *Liquids* to alter their Surfaces; for taking a small Wine-glass, or such like Vessel, and pouring water gently into it, you shall perceive the *surface* of the water all the way *concave*, till it rise even with the top, when you shall find it (if you gently and carefully pour in more) to grow very *protuberant* and *convex*; the reason of which is plain, for that the *solid* sides of the containing body are no longer extended, to which the water does more readily adhere then the air; but it is henceforth to be included with air, which would reduce it into a *hemisphere*, but by reason of its *gravity*, it is flatted into an *Oval*. *Quicksilver* also which to *Glass* is more incongruous then *Air* (and thereby being put into a *Glass-pipe*, will not adhere to it, but by the more *congruous air* will be forced to have a very *protuberant* surface, and to rise higher in a greater then a lesser Pipe) this *Quicksilver* to clean *Metal*, especially to *Gold*, *Silver*, *Tin*, *Lead*, &c. *Iron* excepted, is more *congruous* then *Air*, and will not only stick to it, but have a *concave* Surface like *water*, and rise higher in a less, then in a greater Pipe.

In all these Examples it is evident, that there is an *extraordinary* and *adventitious force*, by which the *globular* Figure of the contained *heterogeneous* fluid is altered; neither can it be imagined, how it should otherwise be of any other Figure then *Globular*: For being by the *heterogeneous* fluid equally *protruded* every way, whatsoever part is *protuberant*, will be thereby *depreſt*. From this cause it is, that in its effects it does very much resemble a *round Spring* (such as a *Hoop*.) For as in a *round Spring* there is required an additional *pressure* against two opposite sides, to reduce it into an *Oval* Form, or to force it in between the sides of a *Hole*, whose *Diameter* is less then that of the *Spring*, there must be a considerable force or *protrusion* against the *concave* or inner side of the *Spring*; So to alter this *spherical* constitution of an included fluid body, there is required more pressure against opposite sides to reduce it into an *Oval*; and, to press it into an *Hole* less in *Diameter* then it self, it requires a greater *protrusion* against all the other sides. What degrees of force are requisite to reduce them into longer and longer *Ovals*, or to press them into less and less *holes*, I have not yet experimentally calculated; but thus much by experiment I find in general, that there is alwayes required a greater pressure to close them into longer *Ovals*, or protude them into smaller *holes*. The necessity and reason of this, were it requisite, I could easily explain: but being not so necessary, and requiring more room and time then I have for it at present, I shall here omit it; and proceed to shew, that this may be presently found true, if Experiment be made with a

round Spring (the way of making which trials is *obvious* enough.) And with the fluid bodies of *Mercury, Air, &c*, the way of trying which, will be somewhat more difficult; and therefore I shall in brief describe it. He therefore that would try with *Air*, must first be provided of a *Glass-pipe*, made of the shape of that in the *fifth Figure*, whereof the side A B, represents a straight *Tube* of about three foot long, C, represents another part of it, which consists of a *round Bubble*; so ordered, that there is left a *passage* or *hole* at the top, into which may be fastened with *cement* several *small Pipes* of determinate *cylindrical* cavities: as let the *hollow* of

F.	be	$\frac{1}{4}$	of an inch.
G.		$\frac{1}{6}$	
H.		$\frac{1}{8}$	
I.		$\frac{1}{12}$	
K.		$\frac{1}{16}$	
L.		$\frac{1}{24}$	
M.		$\frac{1}{32}$	
&c.			

There may be added as many more, as the Experimenter shall think fit, with holes continually decreasing by known quantities, so far as his senses are able to help him; I say, so far, because there may be made *Pipes* so small that it will be impossible to perceive the *perforation* with ones naked eye, though by the help of a *Microscope*, it may easily enough be perceived: Nay, I have made a *Pipe* perforated from end to end, so small, that with my naked eye I could very hardly see the body of it, insomuch that I have been able to knit it up into a knot without breaking: And more accurately examining one with my *Microscope*, I found it not so big as a sixteenth part of one of the smaller hairs of my head which was of the smaller and finer sort of hair, so that sixteen of these *Pipes* bound faggot-wise together, would but have equalized one single hair; how small therefore must its *perforation* be? It appearing to me through the *Microscope* to be a proportionably *thick-sided Pipe*.

To proceed then, for the trial of the Experiment, the Experimenter must place the *Tube* A B, perpendicular, and fill the *Pipe* F (cemented into the hole E) with water, but leave the *bubble* C full of *Air*, and then gently pouring in water into the Pipe A B, he must observe diligently how high the water will rise in it before it protrude the *bubble* of Air C, through the narrow passage of F, and denote exactly the height of the *Cylinder* of water, then cementing in a second Pipe as G, and filling it with water; he may proceed as with the former, denoting likewise the height of the *Cylinder* of water, able to protrude the *bubble* C through the passage of G, the like may he do with the next *Pipe*, and the next, *&c.* as far as he is able: then comparing the several heights of the *Cylinders*, with the several *holes* through which each *Cylinder* did force the *air* (having due regard to the *Cylinders* of water in the small *Tubes*) it will be very easie to determine, what force is requisite to press the *Air* into such and such *a hole*, or (to apply it to our present experiment) how

how much of the pressure of the *Air* is taken off by its ingress into smaller and smaller *holes*. From the application of which to the entring of the *Air* into the bigger *hole* of the *Vessel*, and into the smaller *hole* of the *Pipe*, we shall clearly find, that there is a greater pressure of the air upon the water in the *Vessel* or greater *pipe*, then there is upon that in the lesser *pipe*: For since the pressure of the *air* every way is found to be equal, that is, as much as is able to press up and sustain a *Cylinder* of *Quicksilver* of two foot and a half high, or thereabouts; And since of this pressure so many more degrees are required to force the *Air* into a smaller then into a greater *hole* that is full of a more congruous fluid. And lastly, since those degrees that are requisite to press it in, are thereby taken off from the *Air* within, and the *Air* within left with so many degrees of pressure less then the *Air* without; it will follow, that the *Air* in the less *Tube* or *pipe*, will have less pressure against the superficies of the *water* therein, then the *Air* in the bigger: which was the minor Proposition to be proved.

The Conclusion therefore will necessarily follow, *viz.* That *this unequal pressure of the Air caused by its ingress into unequal holes, is a cause sufficient to produce this effect, without the help of any other concurrent*; and therefore is probably the principal (if not the only) cause of these *Phænomena*.

This therefore being thus explained, there will be divers *Phænomena* explicable thereby, as, the rising of *Liquors* in a *Filtre*, the rising of *Spirit of Wine, Oyl, melted Tallow, &c.* in the *Week* of a *Lamp*, (though made of small *Wire, Threeds* of *Asbestus, Strings* of *Glass*, or the like) the rising of *Liquors* in a *Spunge*, piece of *Bread, Sand, &c.* perhaps also the ascending of the *Sap* in *Trees* and *Plants*, through their small, and some of them *imperceptible pores*, (of which I have said more, on another occasion) at least the passing of it out of the earth into their roots. And indeed upon the consideration of this Principle, multitudes of other uses of it occurr'd to me, which I have not yet so well examined and digested as to propound for *Axioms*, but only as *Queries* and *Conjectures* which may serve as *hints* toward some further *discoveries*.

As first, Upon the consideration of the *congruity* and *incongruity* of Bodies, as to *touch*, I found also the like *congruity* and *incongruity* (if I may so speak) as to the *Transmitting* of the *Raies* of Light: For as in this regard, *water* (not now to mention other Liquors) seems nearer of affinity to *Glass* then *Air*, and *Air* then *Quicksilver*: whence an *oblique Ray* out of *Glass*, will pass into *water* with very little *refraction* from the *perpendicular*, but none out of *Glass* into *Air*, excepting a *direct*, will pass without a very great refraction from the perpendicular, nay any oblique Ray under thirty degrees, will not be admitted into the Air at all. And *Quicksilver* will neither admit oblique or direct, but reflects all; seeming, as to the transmitting of the Raies of Light, to be of a quite differing constitution, from that of *Air, Water, Glass, &c.* and to resemble most those opacous and strong reflecting bodies of Metals: So also as to the property of cohesion or congruity, Water seems to keep the same order, being more

more congruous to Glass then Air, and Air then Quicksilver.

A Second thing (which was hinted to me, by the consideration of the included fluids globular form, caused by the protrusion of the ambient heterogeneous fluid) was, whether the *Phænomena* of gravity might not by this means be explained, by supposing the *Globe* of Earth, Water, and Air to be included with a *fluid*, heterogeneous to all and each of them, so subtil, as not only to be every where *interspersed* through the *Air*, (or rather the *air* through it) but to *pervade* the bodies of *Glass*, and even the *closest Metals*, by which means it may endeavour to *detrude* all earthly bodies as far from it as it can; and partly thereby, and partly by other of its properties may move them towards the Center of the Earth. Now that there is some such fluid, I could produce many Experiments and Reasons, that do seem to prove it: But because it would ask some time and room to set them down and explain them, and to consider and answer all the Objections (many whereof I foresee) that may be alledged against it; I shall at present proceed to other *Queries*, contenting my self to have here only given a hint of what I may say more elswhere.

A Third *Query* then was, Whether the *heterogeneity* of the *ambient fluid* may not be accounted a *secondary cause* of the *roundness* or *globular form* of the *greater bodies* of the world, such as are those of the *Sun*, *Stars*, and *Planets*, the *substance* of each of which seems altogether *heterogeneous* to the *circum-ambient fluid æther*? And of this I shall say more in the Observation of the Moon.

A Fourth was, Whether the *globular form* of the *smaller parcels* of matter here upon the *Earth*, as that of *Fruits*, *Pebbles*, or *Flints*, *&c.* (which seem to have been a *Liquor* at first) may not be caused by the *heterogeneous ambient fluid*. For thus we see that melted *Glass* will be naturally formed into a *round Figure*; so likewise any small Parcel of any *fusible body*, if it be perfectly enclosed by the *Air*, will be driven into a *globular* Form; and, when cold, will be found a *solid Ball*. This is plainly enough manifested to us by their way of making *shot* with the *drops of Lead*; which being a very pretty curiosity, and known but to a very few, and having the liberty of publishing it granted me, by that *Eminent Virtuoso* Sir *Robert Moray*, who brought in this Account of it to the *Royal Society*, I have here transcribed and inserted.

To make small shot of different sizes; Communicated by his Highness *P. R.*

TAke Lead out of the Pig what quantity you please, melt it down, stir and clear it with an iron Ladle, gathering together the blackish parts that swim at top like scum, and when you see the colour of the clear Lead to be greenish, but no sooner, strew upon it Auri-

pigmentum

pigmentum *powdered according to the quantity of Lead, about as much as will lye upon a half Crown piece will serve for eighteen or twenty pound weight of some sorts of Lead; others will require more, or less. After the* Auripigmentum *is put in, stir the Lead well, and the* Auripigmentum *will flame: when the flame is over, take out some of the Lead in a Ladle having a lip or notch in the brim for convenient pouring out of the Lead, and being well warmed amongst the melted Lead, and with a stick make some single drops of Lead trickle out of the Ladle into water in a Glass, which if they fall to be round and without tails, there is* Auripigmentum *enough put in, and the temper of the heat is right, otherwise put in more. Then lay two bars of Iron (or some more proper Iron-tool made on purpose) upon a Pail of water, and place upon them a round Plate of Copper, of the size and figure of an ordinary large Pewter or Silver Trencher, the hollow whereof is to be about three inches over, the bottom lower then the brims about half an inch, pierced with thirty, forty, or more small holes; the smaller the holes are, the smaller the shot will be; and the brim is to be thicker then the bottom, to conserve the heat the better.*

The bottom of the Trencher being some four inches distant frum the water in the Pail, lay upon it some burning Coles, to keep the Lead melted upon it. Then with the hot Ladle take Lead off the Pot where it stands melted, and pour it softly upon the burning Coles over the bottom of the Trencher, and it will immediately run through the holes into the water in small round drops. Thus pour on new Lead still as fast as it runs through the Trencher till all be done; blowing now and then the Coles with hand-Bellows, when the Lead in the Trencher cools so as to stop from running.

Whilst one pours on the Lead, another must, with another Ladle, thrusted four or five inches under water in the Pail, catch from time to time some of the shot, as it drops down, to see the size of it, and whether there be any faults in it. The greatest care is to keep the Lead upon the Trencher in the right degree of heat; if it be too cool, it will not run through the Trencher, though it stand melted upon it; and this is to

be

be helped by blowing the Coals a little, or pouring on new Lead that is hotter: but the cooler the Lead, the larger the Shot; and the hotter, the smaller; when it is too hot, the drops will crack and fly; then you must stop pouring on new Lead, and let it cool; and so long as you observe the right temper of the heat, the Lead will constantly drop into very round Shot, without so much as one with a tail in many pounds.

When all is done, take your Shot out of the Pail of water, and put it in a Frying-pan over the fire to dry them, which must be done warily, still shaking them that they melt not; and when they are dry you may separate the small from the great, in Pearl Sives made of Copper or Lattin let into one another, into as many sizes as you please. But if you would have your Shot larger then the Trencher makes them, you may do it with a Stick, making them trickle out of the Ladle, as hath been said.

If the Trencher be but toucht a very little when the Lead stops from going through it, and be not too cool, it will drop again, but it is better not to touch it at all. At the melting of the Lead take care that there be no kind of Oyl, Grease, or the like, upon the Pots, or Ladles, or Trencher.

The Chief cause of this Globular Figure of the Shot, seems to be the Auripigmentum; *for, as soon as it is put in among the melted Lead, it loses its shining brightness, contracting instantly a grayish film or skin upon it, when you scum it to make it clean with the Ladle. So that when the Air comes at the falling drop of the melted Lead, that skin constricts them every where equally: but upon what account, and whether this be the true cause, is left to further disquisition,*

Much after this same manner, when the Air is exceeding cold through which it passes, do we find the drops of Rain, falling from the Clouds, congealed into round Hail-stones by the freezing Ambient.

To which may be added this other known Experiment, That if you gently let fall a drop of *water* upon small *sand* or *dust*, you shall find, as it were, an artificial *round stone* quickly generated. I cannot upon this occasion omit the mentioning of the strange kind of *Grain*, which I have observed in a *stone* brought from *Kettering* in *Northamptonshire*, and therefore called by Masons *Kettering-Stone*; of which see the Description.

Which

Which brings into my mind what I long ſince obſerved in the fiery Sparks that are ſtruck out of a Steel. For having a great deſire to ſee what was left behind, after the Spark was gone out, I purpoſely ſtruck fire over a very white piece of Paper, and obſerving diligently where ſome conſpicuous ſparks went out, I found a very little black ſpot no bigger then the point of a Pin, which through a *Microſcope* appeared to be a perfectly round Ball, looking much like a poliſht ball of Steel, inſomuch that I was able to ſee the Image of the window reflected from it. I cannot here ſtay (having done it more fully in another place) to examine the particular Reaſons of it, but ſhall only hint, that I imagine it to be ſome ſmall parcel of the Steel, which by the violence of the motion of the ſtroke (moſt of which ſeems to be impreſt upon thoſe ſmall parcels) is made ſo glowing hot, that it is melted into a *Vitrum*, which by the ambient Air is thruſt into the form of a Ball.

A Fifth thing which I thought worth Examination was, Whether the motion of all kind of Springs, might not be reduced to the Principle whereby the included *heterogeneous fluid* ſeems to be moved; or to that whereby two Solids, as Marbles, or the like, are thruſt and kept together by the *ambient fluid*.

A Sixth thing was, Whether the Riſing and Ebullition of the Water out of Springs and Fountains (which lie much higher from the Center of the Earth then the Superficies of the Sea, from whence it ſeems to be derived) may not be explicated by the riſing of Water in a ſmaller Pipe: For the Sea-water being ſtrained through the Pores or Crannies of the Earth, is, as it were, included in little Pipes, where the preſſure of the Air has not ſo great a power to reſiſt its riſing: But examining this way, and finding in it ſeveral difficulties almoſt irremovable, I thought upon a way that would much more naturally and conceivably explain it, which was by this following Experiment: I took a Glaſs-Tube, of the form of that deſcribed in the ſixth Figure, and chuſing two *heterogeneous fluids*, ſuch as Water and Oyl, I poured in as much Water as filled up the Pipes as high as A B, then putting in ſome Oyl into the Tube A C, I depreſt the ſuperficies A of the Water to E, and B I raiſed to G, which was not ſo high perpendicularly as the ſuperficies of the Oyl F, by the ſpace F I, wherefore the proportion of the gravity of theſe two Liquors was as G H to F E.

This Experiment I tried with ſeveral other Liquors, and particularly with freſh Water and Salt (which I made by diſſolving Salt in warm Water) which two though they are nothing heterogeneous, yet before they would perfectly mix one with another, I made trial of the Experiment: Nay, letting the Tube wherein I tried the Experiment remain for many dayes, I obſerved them not to mix; but the ſuperficies of the freſh was rather more then leſs elevated above that of the Salt. Now the proportion of the gravity of Sea-water, to that of River-water, according to *Stevinus* and *Varenius*, and as I have ſince found pretty true by making trial my ſelf, is as 46. to 45. that is, 46. Ounces of the ſalt Wa-

ter will take up no more room then 45. of the fresh. Or reciprocally 45 pints of salt-water weigh as much as 46 of fresh.

But I found the proportion of Brine to fresh Water to be near 13 to 12: Supposing therefore G H M to represent the Sea, and F I the height of the Mountain above the Superficies of the Sea, F M a Cavern in the Earth, beginning at the bottom of the Sea, and terminated at the top of the Mountain, L M the Sand at the bottom, through which the Water is as it were strained, so as that the fresher parts are only permitted to transude, and the saline kept back; if therefore the proportion of G M to F M be as 45 to 46, then may the Cylinder of Salt-water G M make the Cylinder of Fresh-water to rise as high as E, and to run over at N. I cannot here stand to examine or confute their Opinion, who make the depth of the Sea, below its Superficies, to be no more perpendicularly measured then the height of the Mountains above it: 'Tis enough for me to say, there is no one of those that have asserted it, have experimentally known the perpendicular of either; nor shall I here determine, whether there may not be many other causes of the separation of the fresh water from the salt, as perhaps some parts of the Earth through which it is to pass, may contain a Salt, that mixing and uniting with the Sea-salt, may precipitate it; much after the same manner as the *Alkalizate* and *Acid Salts* mix and precipitate each other in the preparation of *Tartarum Vitriolatum*. I know not also whether the exceeding cold (that must necessarily be) at the bottom of the Water, may not help towards this separation, for we find, that warm Water is able to dissolve and contain more Salt, then the same cold; insomuch that Brines strongly impregnated by heat, if let cool, do suffer much of their Salt to subside and crystallize about the bottom and sides. I know not also whether the exceeding pressure of the parts of the Water one against another, may not keep the Salt from descending to the very bottom, as finding little or no room to insert it self between those parts, protruded so violently together, or else squeeze it upwads into the superiour parts of the Sea, where it may more easily obtain room for it self, amongst the parts of the Water, by reason that there is more heat and less pressure. To this Opinion I was somewhat the more induced by the relations I have met with in *Geographical Writers*, of drawing fresh Water from the bottom of the Sea, which is salt above. I cannot now stand to examine, whether this natural perpetual motion may not artificially be imitated: Nor can I stand to answer the Objections which may be made against this my Supposition: As, First, How it comes to pass, that there are sometimes salt Springs much higher then the Superficies of the Water? And, Secondly, Why Springs do not run faster and slower, according to the varying height made of the Cylinder of Sea-water, by the ebbing and flowing of the Sea?

As to the First, In short, I say, the fresh Water may receive again a saline Tincture near the Superficies of the Earth, by passing through some salt *Mines*, or else many of the saline parts of the Sea may be kept back, though not all.

And

And as to the Second, The same *Spring* may be fed and supplyed by divers *Caverns*, coming from very far distant parts of the *Sea*, so as that it may in one place be *high*, in another *low water*; and so by that means the *Spring* may be equally supply'd at all times. Or else the *Cavern* may be so straight and narrow, that the water not having so ready and free passage through it, cannot upon so short and quick mutations of pressure, be able to produce any sensible effect at such a distance. Besides that, to confirm this *hypothesis*, there are many *Examples* found in *Natural Historians*, of *Springs* that do ebb and flow like the Sea: As particularly, those recorded by the Learned *Camden*, and after him by *Speed*, to be found in this *Island*: One of which, they relate to be on the Top of a Mountain, by the small Village *Kilken* in *Flintshire*, *Maris æmulus qui statis temporibus suas evomit & resorbet Aquas*; Which at certain times riseth and falleth after the manner of the Sea. A Second in *Caermardenshire*, near *Caermarden*, at a place called *Cantred Bichan*; *Qui (ut scribit Giraldus) naturali die bis undis deficiens, & toties exuberans, marinas imitatur instabilitates*; That twice in four and twenty hours ebbing and flowing, resembleth the unstable motions of the Sea. The *Phænomena* of which two may be easily made out, by supposing the *Cavern*, by which they are fed, to arise from the bottom of the next Sea. A Third, is a Well upon the River *Ogmore* in *Glamorganshire*, and near unto *Newton*, of which *Camden* relates himself to be certified, by a Letter from a Learned Friend of his that observed it, *Fons abest hinc, &c.* The Letter is a little too long to be inserted, but the substance is this; That this Well ebbs and flows quite contrary to the flowing and ebbing of the Sea in those parts: for 'tis almost empty at Full Sea, but full at Low water. This may happen from the Channel by which it is supplied, which may come from the bottom of a Sea very remote from those parts, and where the Tides are much differing from those of the approximate shores. A Fourth, lies in *Westmorland*, near the River *Loder*; *Qui instar Euripi sæpius in die reciprocantibus undis fluit & refluit*, which ebbs and flows many times a day. This may proceed from its being supplyed from many Channels, coming from several parts of the Sea, lying sufficiently distant asunder to have the times of High-water differing enough one from the other; so as that whensoever it shall be High water over any of those places, where these Channels begin, it shall likewise be so in the Well; but this is but a supposition.

A Seventh *Query* was, Whether the *dissolution* or mixing of several bodies, whether fluid or solid, with saline or other Liquors, might not partly be attributed to this Principle of the congruity of those bodies and their dissolvents? As of Salt in Water, Metals in several *Menstruums*, Unctuous Gums in Oyls, the mixing of Wine and Water, *&c.* And whether *precipitation* be not partly made from the same Principle of Incongruity? I say *partly*, because there are in some Dissolutions, some other Causes concurrent.

I shall lastly make a much more seemingly strange and unlikely *Query*; and that is, Whether this Principle, well examined and explained, may

not be found a *co-efficient* in the most considerable Operations of Nature? As in those of *Heat*, and *Light*, and consequently, of *Rarefaction* and *Condensation*, *Hardness*, and *Fluidness*, *Perspicuity* and *Opacousness*, *Refractions* and *Colours*, *&c.* Nay, I know not whether there may be many things done in Nature, in which this may not (be said to) have a Finger? This I have in some other passages of this Treatise further enquired into and shewn, that as well *Light* as *Heat* may be caused by *corrosion*, which is applicable to *congruity*, and consequently all the rest will be but *subsequents*: In the mean time I would not willingly be guilty of that *Error*, which the thrice Noble and Learned *Verulam* justly takes notice of, as such, and calls *Philosophiæ Genus Empiricum*, *quod in paucorum Experimentorum Angustiis & Obscuritate fundatum est.* For I neither conclude from one single Experiment, nor are the Experiments I make use of, all made upon one Subject: Nor wrest I any Experiment to make it *quadrare* with any preconceiv'd Notion. But on the contrary, I endeavour to be conversant in divers kinds of Experiments, and all and every one of those Trials, I make the Standards or Touchstones, by which I try all my former Notions, whether they hold out in weight, and measure, and touch, *&c.* For as that Body is no other then a Counterfeit Gold, which wants any one of the Proprieties of Gold, (such as are the Malleableness, Weight, Colour, Fixtness in the Fire, Indissolubleness in *Aqua fortis*, and the like) though it has all the other; so will all those Notions be found to be false and deceitful, that will not undergo all the Trials and Tests made of them by Experiments. And therefore such as will not come up to the desired *Apex* of Perfection, I rather wholly reject and take new, then by piecing and patching, endeavour to retain the old, as knowing such things at best to be but lame and imperfect. And this course I learned from Nature; whom we find neglectful of the old Body, and suffering its Decaies and Infirmities to remain without repair, and altogether sollicitous and careful of perpetuating the *Species* by new *Individuals*. And it is certainly the most likely way to erect a glorious Structure and Temple to *Nature*, such as she will be found (by any *zealous Votary*) to reside in; to begin to build a new upon a sure Foundation of Experiments.

But to digress no further from the consideration of the *Phænomena*, more immediately explicable by this Experiment, we shall proceed to shew, That, as to the rising of Water in a *Filtre*, the reason of it will be manifest to him, that does take notice, that a *Filtre* is constituted of a great number of small long solid bodies, which lie so close together, that the Air in its getting in between them, doth lose of its pressure that it has against the *Fluid* without them, by which means the Water or Liquor not finding so strong a resistance between them as is able to counter-ballance the pressure on its superficies without, is raised upward, till it meet with a pressure of the Air which is able to hinder it. And as to the Rising of Oyl, melted Tallow, Spirit of Wine, *&c.* in the Week of a Candle or Lamp, it is evident, that it differs in nothing from the former, save only in this; that in a *Filtre* the Liquor descends and runs away by another part; and in the Week the Liquor is dispersed and carried away by the Flame;

Flame; something there is ascribable to the Heat, for that it may rarifie the more volatil and spirituous parts of those combustible Liquors, and so being made lighter then the Air, it may be protruded upwards by that more ponderous fluid body in the Form of Vapours; but this can be ascribed to the ascension of but a very little, and most likely of that only which ascends without the Week. As for the Rising of it in a Spunge, Bread, Cotton, *&c.* above the superficies of the subjacent Liquor; what has been said about the *Filtre* (if considered) will easily suggest a reason, considering that all these bodies abound with small holes or pores.

From this same Principle also (*viz. the unequal pressure of the Air against the unequal superficies of the water*) proceeds the cause of the accession or incursion of any floating body against the sides of the containing Vessel, or the *appropinquation* of two floating bodies, as *Bubbles, Corks, Sticks, Straws, &c.* one towards another. As for instance, Take a Glass-jar, such as A B in the seventh *Figure*, and filling it pretty near the top with water, throw into it a small round piece of Cork, as C, and plunge it all over in water, that it be wet, so as that the water may rise up by the sides of it, then placing it any where upon the superficies, about an inch, or one inch and a quarter from any side, and you shall perceive it by degrees to make *perpendicularly* toward the nearest part of the side, and the nearer it approaches, the faster to be moved; the reason of which *Phænomenon* will be found no other then this, that the Air has a greater pressure against the middle of the *superficies*, then it has against those parts that approach nearer, and are *contignous* to the sides. Now that the pressure is greater, may (as I shewed before in the explication of the third *Figure*) be evinced from the flatting of the water in the middle, which arises from the gravity of the under *fluid*: for since, as I shewed before, if there were no gravity in the under *fluid*, or that it were equal to that of the upper, the terminating Surface would be *Spherical*, and since it is the additional pressure of the gravity of water that makes it so flat, it follows, that the pressure upon the middle must be greater then towards the sides. Hence the Ball having a stronger pressure against that side of it which respects the middle of the *superficies*, then against that which respects the *approximate* side, must necessarily move towards that part, from whence it finds least resistance, and so be *accelerated*, as the resistance decreases. Hence the more the water is raised under that part of its way it is passing above the middle, the faster it is moved: And therefore you will find it to move faster in E then in D, and in D then in C. Neither could I find the floating substance to be moved at all, until it were placed upon some part of the *Superficies* that was sensibly elevated above the height of the middle part. Now that this may be the true cause, you may try with a blown Bladder, and an exactly round Ball upon a very smooth side of some pliable body, as *Horn* or *Quicksilver*. For if the Ball be placed under a part of the Bladder which is upon one side of the middle of its pressure, and you press strongly against the Bladder, you shall find the Ball moved from the middle towards the sides.

Having

Having therefore shewn the reason of the motion of any float towards the sides, the reason of the incursion of any two floating bodies will easily appear: For the rising of the water against the sides of either of them, is an Argument sufficient, to shew the pressure of the Air to be there less, then it is further from it, where it is not so much elevated; and therefore the reason of the motion of the other toward it, will be the same as towards the side of the Glass; only here from the same reason, they are mutually moved toward each other, whereas the side of the Glass in the former remains fixt. If also you gently fill the Jar so full with water, that the water is *protuberant* above the sides, the same piece of Cork that before did hasten towards the sides, does now fly from it as fast towards the middle of the Superficies; the reason of which will be found no other then this, that the pressure of the Air is stronger against the sides of the Superficies G and H, then against the middle I; for since, as I shewed before, the Principle of congruity would make the terminating Surface Spherical, and that the flatting of the Surface in the middle is from the abatement of the waters pressure outwards, by the contrary indeavour of its gravity; it follows that the pressure in the middle must be less then on the sides; and therefore the consecution will be the same as in the former. It is very odd to one that considers not the reason of it, to see two floating bodies of wood to approach each other, as though they were indued with some magnetical vigour; which brings into my mind what I formerly tried with a piece of Cork or such like body, which I so ordered, that by putting a little stick into the same water, one part of the said Cork would approach and make toward the stick, whereas another would discede and fly away, nay it would have a kind of verticity, so as that if the *Æquator* (as I may so speak) of the Cork were placed towards the stick, if let alone, it would instantly turn its appropriate Pole toward it, and then run a-tilt at it: and this was done only by taking a dry Cork, and wetting one side of it with one small stroak; for by this means gently putting it upon the water, it would depress the superficies on every side of it that was dry, and therefore the greatest pressure of the Air, being near those sides caused it either to chase away, or else to fly off from any other floating body, whereas that side only, against which the water ascended, was thereby able to attract.

It remains only, that I should determine how high the Water or other Liquor may by this means be raised in a smaller Pipe above the Superficies of that without it, and at what height it may be sustained: But to determine this, will be exceeding difficult, unless I could certainly know how much of the Airs pressure is taken off by the smalness of such and such a Pipe, and whether it may be wholly taken off, that is, whether there can be a hole or pore so small, into which Air could not at all enter, though water might with its whole force; for were there such, 'tis manifest, that the water might rise in it to some five or six and thirty English Foot high. I know not whether the capillary Pipes in the bodies of small Trees, which we call their *Microscopical pores*, may not be such; and whether the congruity of the sides of the Pore may not yet draw the juyce

even

even higher then the Air was able by its bare pressure to raise it: For, Congruity is a principle that not only unites and holds a body joyned to it, but, which is more, attracts and draws a body that is very near it, and holds it above its usual height.

And this is obvious even in a drop of water suspended under any Similar or Congruous body: For, besides the ambient pressure that helps to keep it sustein'd, there is the Congruity of the bodies that are contiguous. This is yet more evident in Tenacious and Glutinous bodies; such as Gummous Liquors, Syrups, Pitch, and Rosin melted, *&c.* Tar, Turpentine, Balsom, Bird-lime, *&c.* for there it is evident, that the Parts of the tenacious body, as I may so call it, do stick and adhere so closely together, that though drawn out into long and very slender Cylinders, yet they will not easily relinquish one another; and this, though the bodies be *aliquatenus* fluid, and in motion by one another; which, to such as consider a fluid body only as its parts are in a confused irregular motion, without taking in also the congruity of the parts one among another, and incongruity to some other bodies, does appear not a little strange. So that besides the incongruity of the ambient fluid to it, we are to consider also the congruity of the parts of the contein'd fluid one with another.

And this Congruity (that I may here a little further explain it) is both a Tenaceous and an Attractive power; for the Congruity, in the Vibrative motions, may be the cause of all kind of attraction, not only Electrical, but Magnetical also, and therefore it may be also of Tenacity and Glutinousness. For, from a perfect congruity of the motions of two distant bodies, the intermediate fluid particles are separated and droven away from between them, and thereby those congruous bodies are, by the incompassing mediums, compell'd and forced neerer together; wherefore that attractiveness must needs be stronger, when, by an immediate contact, they are forc'd to be exactly the same: As I shew more at large in my *Theory* of the *Magnet*. And this hints to me the reason of the suspension of the *Mercury* many inches, nay many feet, above the usual station of 30 inches. For the parts of *Quick-silver*, being so very similar and congruous to each other, if once united, will not easily suffer a divulsion: And the parts of water, that were any wayes *heterogeneous*, being by *exantlation* or rarefaction exhausted, the remaining parts being also very similar, will not easily part neither. And the parts of the Glass being solid, are more difficultly disjoyn'd; and the water, being somewhat similar to both, is, as it were, a medium to unite both the *Glass* and the *Mercury* together. So that all three being united, and not very dissimilar, by means of this contact, if care be taken that the Tube in erecting be not shogged, the *Quicksilver* will remain suspended, notwithstanding its contrary indeavour of Gravity, a great height above its ordinary Station; but if this immediate Contact be removed, either by a meer separation of them one from another by the force of a shog, whereby the other becomes imbodied between them, and licks up from the surface some agil parts, and so hurling them makes them air; or else

by

by ſome ſmall heterogeneous agil part of the Water, or Air, or Quick-ſilver, which appears like a bubble, and by its jumbling to and fro there is made way for the *heterogeneous Æther* to obtrude it ſelf between the Glaſs and either of the other Fluids, the Gravity of *Mercury precipitates* it downward with very great violence; and if the Veſſel that holds the reſtagnating *Mercury* be convenient, the *Mercury* will for a time *vibrate* to and fro with very large *reciprocations*, and at laſt will remain kept up by the preſſure of the external Air at the height of neer thirty inches. And whereas it may be objected, that it cannot be, that the meer imbodying of the *Æther* between theſe bodies can be the cauſe, ſince the *Æther* having a free paſſage alwayes, both through the Pores of the Glaſs, and through thoſe of the Fluids, there is no reaſon why it ſhould not make a ſeparation at all times whilſt it remains ſuſpended, as when it is violently diſ-joyned by a ſhog. To this I anſwer, That though the *Æther* paſſes between the Particles, that is, through the Pores of bodies, ſo as that any chaſme or ſeparation being made, it has infinite paſſages to admit its entry into it, yet ſuch is the tenacity or attractive virtue of Congruity, that till it be overcome by the meer ſtrength of Gravity, or by a ſhog aſſiſting that Conatus of Gravity, or by an agil Particle, that is like a leaver agitated by the *Æther*; and thereby the parts of the congruous ſubſtances are ſeparated ſo far aſunder, that the ſtrength of congruity is ſo far weakened, as not to be able to reunite them, the parts to be taken hold of being removed out of the attractive Sphere, as I may ſo ſpeak, of the congruity; ſuch, I ſay, is the tenacity of congruity, that it retains and holds the almoſt contiguous Particles of the Fluid, and ſuffers them not to be ſeparated, till by meer force that attractive or retentive faculty be overcome: But the ſeparation being once made beyond the Sphere of the attractive activity of congruity, that virtue becomes of no effect at all, but the *Mercury* freely falls downwards till it meet with a reſiſtance from the preſſure of the *ambient* Air, able to reſiſt its gravity, and keep it forced up in the Pipe to the height of about thirty inches.

Thus have I gently raiſed a Steel *pendulum* by a Loadſtone to a great Angle, till by the ſhaking of my hand I have chanced to make a ſeparation between them, which is no ſooner made, but as if the Loadſtone had retained no attractive virtue, the *Pendulum* moves freely from it towards the other ſide. So vaſt a difference is there between the attractive virtue of the *Magnet* when it acts upon a contiguous and upon a disjoyned body: and much more muſt there be between the attractive virtues of congruity upon a contiguous and disjoyned body; and in truth the attractive virtue is ſo little upon a body disjoyned, that though I have with a *Microſcope* obſerved very diligently, whether there were any extraordinary *protuberance* on the ſide of a drop of water that was exceeding neer to the end of a green ſtick, but did not touch it, I could not perceive the leaſt; though I found, that as ſoon as ever it toucht it the whole drop would preſently unite it ſelf with it; ſo that it ſeems an abſolute contact is requiſite to the exerciſing of the tenacious faculty of congruity.

Obſerv.

Obſerv. VII. *Of ſome* Phænomena *of Glaſs drops.*

THeſe *Glaſs Drops* are ſmall parcels of coarſe green Glaſs taken out of the Pots that contain the *Metal* (as they call it) in fuſion, upon the end of an Iron Pipe; and being exceeding hot, and thereby of a kind of ſluggiſh fluid Conſiſtence, are ſuffered to drop from thence into a Bucket of cold Water, and in it to lye till they be grown ſenſibly cold.

Some of theſe I broke in the open air, by ſnapping off a little of the ſmall ſtem with my fingers, others by cruſhing it with a ſmall pair of Plyers; which I had no ſooner done, then the whole bulk of the drop flew violently, with a very brisk noiſe, into multitudes of ſmall pieces, ſome of which were as ſmall as duſt, though in ſome there were remaining pieces pretty large, without any flaw at all, and others very much flaw'd, which by rubbing between ones fingers was eaſily reduced to duſt; theſe diſperſed every way ſo violently, that ſome of them pierced my skin. I could not find, either with my naked Eye, or a *Microſcope*, that any of the broken pieces were of a regular figure, nor any one like another, but for the moſt part thoſe that flaw'd off in large pieces were prettily branched.

The ends of others of theſe drops I nipt off whilſt all the bodies and ends of them lay buried under the water, which, like the former, flew all to pieces with as brisk a noiſe, and as ſtrong a motion.

Others of theſe I tried to break, by grinding away the blunt end, and though I took a ſeemingly good one, and had ground away neer two thirds of the Ball, yet would it not fly to pieces, but now and then ſome ſmall rings of it would ſnap and fly off, not without a brisk noiſe and quick motion, leaving the Surface of the drop whence it flew very prettily branched or creaſed, which was eaſily diſcoverable by the *Microſcope*. This drop, after I had thus ground it, without at all impairing the remnant that was not ground away, I cauſed to fly immediately all into ſand upon the nipping off the very tip of its ſlender end.

Another of theſe drops I began to grind away at the ſmaller end, but had not worn away on the ſtone above a quarter of an inch before the whole drop flew with a brisk crack into ſand or ſmall duſt; nor would it have held ſo long, had there not been a little flaw in the piece that I ground away, as I afterwards found.

Several others of theſe drops I covered over with a thin but very tuff skin of *Icthyocolla*, which being very tough and very tranſparent, was the moſt convenient ſubſtance for theſe tryals that I could imagine, having dipt, I ſay, ſeveral of theſe drops in this tranſparent Glue whilſt hot, and ſuffering them to hang by a ſtring tied about the end of them till they were cold, and the skin pretty tough; then wrapping all the body of the

drop (leaving out only the very tip) in fine supple Kids-leather very closely, I nipped off the small top, and found, as I expected, that notwithstanding this skin of Glue, and the close wrapping up in Leather, upon the breaking of the top, the drop gave a crack like the rest, and gave my hand a pretty brisk impulse: but yet the skin and leather was so strong as to keep the parts from flying out of their former posture; and, the skin being transparent, I found that the drop retained exactly its former figure and polish, but was grown perfectly opacous and all over flaw'd, all those flaws lying in the manner of rings, from the bottom or blunt end, to the very top or small point. And by several examinations with a *Microscope*, of several thus broken, I found the flaws, both within the body of the drop, and on the outward surface, to lye much in this order.

Let A B in the Figure X of the fourth Scheme represent the drop cased over with *Ichyocolla* or *Isinglass*, and (by being ordered as is before prescribed) crazed or flawed into pieces, but by the skin or case kept in its former figure, and each of its flawed parts preserved exactly in its due posture; the outward appearance of it somewhat plainly to the naked eye, but much more conspicuous if viewed with a small sens appeared much after this shape. That is, the blunt end B for a pretty breadth, namely, as far as the Ring C C C seemed irregularly flawed with divers clefts, which all seemed to tend towards the Center of it, being, as I afterwards found, and shall anon shew in the description of the figure Y, the Basis, as it were, of a Cone, which was terminated a little above the middle of the drop; all the rest of the Surface from C C C to A was flawed with an infinite number of small and parallel Rings, which as they were for the most part very round, so were they very thick and close together, but were not so exactly flaw'd as to make a perfect Ring, but each circular part was by irregular cracks flawed likewise into multitudes of irregular flakes or tiles; and this order was observed likewise the whole length of the neck,

Now though I could not so exactly cut this *conical Body* through the *Axis*, as is represented by the figure Y; yet by *anatomizing*, as it were, of several, and taking notice of divers particular circumstances, I was informed, that could I have artificially divided a flaw'd drop through the *Axis* or *Center*, I should with a *Microscope* have found it to appear much of this form, where A signifies the *Apex*, and B the blunt end, C C the Cone of the Basis, which is terminated at T the top or end of it, which seems to be the very middle of the blunt end, in which, not only the conical body of the Basis C C is terminated, but as many of the parts of the drop as reach as high as D D.

And it seemed to be the head or beginning of a Pith, as it were, or a a part of the body which seemed more spungy then the rest, and much more irregularly flawed, which from T ascended by E E, though less visible, into the small neck towards A. The Grain, as it were, of all the flaws, that from all the outward Surface A D C C D A, was much the same, as is represented by the black strokes that meet in the middle D T, D T, D E, D E, &c.

Nor

Nor is this kind of Grain, as I may call it, peculiar to Glass drops thus quenched; for (not to mention *Coperas-stones*, and divers other *Marchasites* and *Minerals*, which I have often taken notice of to be in the very same manner flaked or grained, with a kind of Pith in the middle;) I have observed the same in all manner of cast Iron, especially the coarser sort, such as Stoves, and Furnaces, and Backs, and Pots are made of: For upon the breaking of any of those Substances it is obvious to observe, how from the out-sides towards the middle, there is a kind of Radiation or Grain much resembling this of the Glass-drop; but this Grain is most conspicuous in Iron-bullets, if they be broken: the same *Phænomena* may be produced by casting *regulus* of *Antimony* into a Bullet-mold, as also with *Glass of Antimony*, or with almost any such kind of *Vitrified substance*, either cast into a cold Mold or poured into Water.

Others of these Drops I heat red hot in the fire, and then suffered them to cool by degrees. And these I found to have quite lost all their *fulminating* or flying quality, as also their hard, brittle and springy texture; and to emerge of a much softer temper, and much easier to be broken or snapt with ones finger; but its strong and brittle quality was quite destroyed, and it seemed much of the same consistence with other green Glass well nealed in the Oven.

The Figure and bigness of these for the most part was the same with that of the Figure Z; that is, all the surface of them was very smooth and polisht, and for the most part round, but very rugged or knobbed about D, and all the length of the stem was here and there pitted or flatted. About D, which is at the upper part of the drop under that side of the stem which is concave, there usually was made some one or more little Hillocks or Prominences. The drop it self, before it be broken, appears very transparent, and towards the middle of it, to be very full of small Bubbles, of some kind of aerial substance, which by the refraction of the outward surface appear much bigger then really they are; and this may be in good part removed, by putting the drop under the surface of clear Water, for by that means most part of the refraction of the convex Surface of the drop is destroyed, and the bubbles will appear much smaller. And this, by the by, minds me of the appearing magnitude of the *aperture* of the *iris*, or *pupil* of the eye, which though it appear, and be therefore judged very large, is yet not above a quarter of the bigness it appears of, by the *lenticular* refraction of the *Cornea*.

The cause of all which *Phænomena* I imagine to be no other then this, That the Parts of the Glass being by the excessive heat of the fire kept off and separated one from another, and thereby put into a kind of sluggish fluid consistence, are suffered to drop off with that heat or agitation remaining in them, into cold Water; by which means the outsides of the drop are presently cool'd and *crusted*, and are thereby made of a loose texture, because the parts of it have not time to settle themselves leisurely together, and so to lie very close together: And the innermost parts of the drop, retaining still much of their former heat and agitations, remain

of a loose texture also, and, according as the cold strikes inwards from the bottom and sides, are quenched, as it were, and made rigid in that very posture wherein the cold finds them. For the parts of the *crust* being already hardened, will not suffer the parts to shrink any more from the outward Surface inward; and though it shrink a little by reason of the small parcels of some Aerial substances dispersed through the matter of the Glass, yet that is not neer so much as it appears (as I just now hinted;) nor if it were, would it be sufficient for to consolidate and condense the body of Glass into a *tuff* and close *texture*, after it had been so excessively rarified by the heat of the glass-Furnace.

But that there may be such an expansion of the aerial substance contained in those little *blebbs* or bubbles in the body of the drop, this following Experiment will make more evident.

Take a small Glass-Cane about a foot long, seal up one end of it *hermetically*, then put in a very small bubble of Glass, almost of the shape of an Essence-viol with the open mouth towards the sealed end, then draw out the other end of the Pipe very small, and fill the whole Cylinder with water, then set this Tube by the Fire till the Water begin to boyl, and the Air in the bubble be in good part rarified and driven out, then by sucking at the smalling Pipe, more of the Air or vapours in the bubble may be suck'd out, so that it may sink to the bottom; when it is sunk to the bottom, in the flame of a Candle, or Lamp, nip up the slender Pipe and let it cool: whereupon it is obvious to observe, first, that the Water by degrees will subside and shrink into much less room: Next, that the Air or vapours in the Glass will expand themselves so, as to buoy up the little Glass: Thirdly, that all about the inside of the Glass-pipe there will appear an infinite number of small bubbles, which as the Water grows colder and colder will swell bigger and bigger, and many of them buoy themselves up and break at the top.

From this *Disceding* of the heat in Glass drops, that is, by the quenching or cooling Irradiations propagated from the Surface upwards and inwards, by the lines C T, C T, D T, D E, *&c.* the bubbles in the drop have room to expand themselves a little, and the parts of the Glass contract themselves; but this operation being too quick for the sluggish parts of the Glass, the contraction is performed very unequally and irregularly, and thereby the Particles of the Glass are bent, some one way, and some another, yet so as that most of them draw towards the Pith or middle T E E E, or rather from that outward: so that they cannot *extricate* or unbend themselves, till some part of T E E E be broken and loosened, for all the parts about that are placed in the manner of an Arch, and so till their hold at T E E E be loosened they cannot fly asunder, but uphold, and shelter, and fix each other much like the stones in a Vault, where each stone does concurre to the stability of the whole Fabrick, and no one stone can be taken away but the whole Arch falls. And wheresoever any of those radiating wedges D T D, *&c.* are removed, which are the component parts of this Arch, the whole Fabrick presently falls to pieces;

pieces; for all the Springs of the several parts are set at liberty; which immediately extricate themselves and fly asunder every way; each part by its spring contributing to the darting of it self and some other contiguous part. But if this drop be heat so hot as that the parts by degrees can unbend themselves, and be settled and annealed in that posture, and be then suffered gently to subside and cool; The parts by this nealing losing their springiness, constitute a drop of a more soft but less brittle texture, and the parts being not at all under a flexure, though any part of the middle or Pith T E E E be broken, yet will not the drop at all fly to pieces as before.

This Conjecture of mine I shall indeavour to make out by explaining each particular Assertion with *analogous* Experiments: The Assertions are these.

First, That the parts of the Glass, whilst in a fluid Consistence and hot, are more rarified, or take up more room, then when hard and cold.

Secondly, That the parts of the drop do suffer a twofold contraction.

Thirdly, That the dropping or quenching the glowing metal in the Water makes it of a hard, springing, and rarified texture.

Fourthly, That there is a flexion or force remaining upon the parts of the Glass thus quenched, from which they indeavour to extricate themselves.

Fifthly, That the Fabrick of the drop, that is able to hinder the parts from extricating themselves, is *analogus* to that of an Arch.

Sixthly, That the sudden flying asunder of the parts proceeds from their springiness.

Seventhly, That a gradual heating and cooling does anneal or reduce the parts of Glass to a texture that is more loose, and easilier to be broken, but not so brittle.

That the first of these is true may be gathered from this, That *Heat is a property of a body arising from the motion or agitation of its parts*; and therefore whatever body is thereby toucht must necessarily receive some part of that motion, whereby its parts will be shaken and agitated, and so by degrees free and extricate themselves from one another, and each part so moved does by that motion *exert* a *conatus* of *protruding* and displacing all the adjacent Particles. Thus Air included in a vessel, by being heated will burst it to pieces. Thus have I broke a Bladder held over the fire in my hand, with such a violence and noise, that it almost made me deaf for the present, and much surpassed the noise of a Musket: The like have I done by throwing into the fire small glass Bubbles hermetically sealed, with a little drop of Water included in them. Thus Water also, or any other Liquor, included in a convenient vessel, by being warmed, manifestly expands it self with a very great violence, so as to break the strongest vessel, if when heated it be narrowly imprisoned in it.

This

This is very manifest by the *sealed Thermometers*, which I have, by several tryals, at last brought to a great certainty and tenderness: for I have made some with stems above four foot long, in which the expanding Liquor would so far vary, as to be very neer the very top in the heat of Summer, and prety neer the bottom at the coldest time of the Winter. The Stems I use for them are very thick, straight, and even Pipes of Glass, with a very small *perforation*, and both the head and body I have made on purpose at the Glass-house, of the same metal whereof the Pipes are drawn: these I can easily in the flame of a Lamp, urged with the blast of a pair of Bellows, seal and close together, so as to remain very firm, close and even; by this means I joyn on the body first, and then fill both it and a part of the stem, proportionate to the length of the stem and the warmth of the season I fill it in with the best rectified *Spirit of Wine* highly *ting'd* with the lovely colour of *Cocheneel*, which I deepen the more by pouring some drops of common *Spirit of Urine*, which must not be too well rectified, because it will be apt to make the Liquor to curdle and stick in the small perforation of the stem. This Liquor I have upon tryal found the most tender of any spirituous Liquor, and those are much more sensibly affected with the variations of heat and cold then other more flegmatick and ponderous Liquors, and as capable of receiving a deep tincture, and keeping it, as any Liquor whatsoever; and (which makes it yet more acceptable) is not subject to be frozen by any cold yet known. When I have thus filled it, I can very easily in the forementioned flame of a Lamp seal and joyn on the head of it.

Then, for graduating the stem, I fix that for the beginning of my division where the surface of the liquor in the stem remains when the ball is placed in common distilled water, that is so cold that it just begins to freeze and shoot into flakes; and that mark I fix at a convenient place of the stem, to make it capable of exhibiting very many degrees of cold, below that which is requisite to freeze water: the rest of my divisions, both above and below this (which I mark with a [0] or nought) I place according to the Degrees of *Expansion*, or *Contraction* of the Liquor in proportion to the bulk it had when it indur'd the newly mention'd freezing cold. And this may be very easily and accurately enough done by this following way; Prepare a Cylindrical vessel of very thin plate Brass or Silver, A B C D of the figure Z; the Diameter A B of whose cavity let be about two inches, and the depth B C the same; let each end be cover'd with a flat and smooth plate of the same substance, closely soder'd on, and in the midst of the upper cover make a pretty large hole E F, about the bigness of a fifth part of the Diameter of the other; into this fasten very well with cement a straight and even Cylindrical pipe of Glass, E F G H, the Diameter of whose cavity let be exactly one tenth of the Diameter of the greater Cylinder. Let this pipe be mark'd at G H with a Diamant, so that G from E may be distant just two inches, or the same height with that of the cavity of the greater Cylinder, then divide the length E G exactly into 10 parts, so the capacity of the hollow of each of these divisions will be $\frac{1}{1000}$ part of the capacity of the greater Cylinder.

der. This vessel being thus prepared, the way of marking and graduating the *Thermometers* may be very easily thus performed:

Fill this Cylindrical vessel with the same liquor wherewith the *Thermometers* are fill'd, then place both it and the *Thermometer* you are to *graduate*, in water that is ready to be frozen, and bring the surface of the liquor in the *Thermometer* to the first marke or [o]; then so proportion the liquor in the Cylindrical vessel, that the surface of it may just be at the lower end of the small glass-Cylinder; then very gently and gradually warm the water in which both the *Thermometer* and this Cylindrical vessel stand, and as you perceive the ting'd liquor to rise in both stems, with the point of a Diamond give several marks on the stem of the *Thermometer* at those places, which by comparing the expansion in both Stems, are found to correspond to the divisions of the cylindrical vessel; and having by this means marked some few of these divisions on the Stem, it will be very easie by these to mark all the rest of the Stem; and accordingly to assign to every division a proper character.

A *Thermometer*, thus marked and prepared, will be the fittest Instrument to make a Standard of heat and cold that can be imagined. For being sealed up, it is not at all subject to variation or wasting, nor is it liable to be changed by the varying pressure of the Air, which all other kind of *Thermometers* that are open to the Air are liable to. But to proceed.

This property of Expansion with Heat, and Contraction with Cold, is not peculiar to Liquors only, but to all kind of solid Bodies also, especially Metals, which will more manifestly appear by this Experiment.

Take the Barrel of a Stopcock of Brass, and let the Key, which is well fitted to it, be riveted into it, so that it may slip, and be easily turned round, then heat this Cock in the fire, and you will find the Key so swollen, that you will not be able to turn it round in the Barrel; but if it be suffered to cool again, as soon as it is cold it will be as movable, and as easie to be turned as before.

This Quality is also very observable in *Lead*, *Tin*, *Silver*, *Antimony*, *Pitch*, *Rosin*, *Bees-wax*, *Butter*, and the like; all which, if after they be melted you suffer gently to cool, you shall find the parts of the upper Surface to subside and fall inwards, losing that plumpness and smoothness it had whilst in fusion. The like I have also observed in the cooling of *Glass of Antimony*, which does very neer approach the nature of Glass.

But because these are all Examples taken from other materials then Glass, and argue only, that possibly there may be the like property also in Glass, not that really there is; we shall by three or four Experiments indeavour to manifest that also.

And the First is an Observation that is very obvious even in these very drops, to wit, that they are all of them terminated with an unequal or irregular Surface, especially about the smaller part of the drop, and the whole length of the stem; as about D, and from thence to A, the whole Surface, which would have been round if the drop had cool'd leisurely, is, by being quenched hastily, very irregularly flatted and pitted; which

I

I ſuppoſe proceeds partly from the Waters unequally cooling and preſſing the parts of the drop, and partly from the ſelf-contracting or ſubſiding quality of the ſubſtance of the Glaſs: For the vehemency of the heat of the drop cauſes ſuch ſudden motions and bubbles in the cold Water, that ſome parts of the Water bear more forcibly againſt one part then againſt another, and conſequently do more ſuddenly cool thoſe parts to which they are contiguous.

A Second Argument may be drawn from the Experiment of cutting Glaſſes with a hot Iron. For in that Experiment the top of the Iron heats, and thereby rarifies the parts of the Glaſs that lie juſt before the crack, whence each of thoſe agitated parts indeavouring to expand its ſelf and get elbow-room, thruſts off all the reſt of the contiguous parts, and conſequently promotes the crack that was before begun.

A Third Argument may be drawn from the way of producing a crack in a ſound piece or plate of Glaſs, which is done two wayes, either Firſt, by ſuddenly heating a piece of Glaſs in one place more then in another. And by this means *Chymiſts* uſually cut off the necks of Glaſs-bodies, by two kinds of Inſtruments, either by a glowing hot round Iron-Ring, which juſt incompaſſes the place that is to be cut, or elſe by a *Sulphur'd* Threed, which is often wound about the place where the ſeparation is to be made, and then fired. Or Secondly, A Glaſs may be cracked by cooling it ſuddenly in any place with Water, or the like, after it has been all leiſurely and gradually heated very hot. Both which *Phænomena* ſeem manifeſtly to proceed from the *expanſion* and contraction of the parts of the Glaſs, which is alſo made more probable by this circumſtance which I have obſerved, that a piece of common window-glaſs being heated in the middle very ſuddenly with a live Coal or hot Iron, does uſually at the firſt crack fall into pieces, whereas if the Plate has been gradually heated very hot, and a drop of cold Water and the like be put on the middle of it, it only flaws it, but does not break it aſunder immediately.

A Fourth Argument may be drawn from this Experiment; Take a Glaſs-pipe, and fit into it a ſolid ſtick of Glaſs, ſo as it will but juſt be moved in it. Then by degrees heat them whilſt they are one within another, and they will grow ſtiffer, but when they are again cold, they will be as eaſie to be turned as before. This Expanſion of Glaſs is more manifeſt in this Experiment.

Take a ſtick of Glaſs of a conſiderable length, and fit it ſo between the two ends or ſcrews of a Lath, that it may but juſt eaſily turn, and that the very ends of it may be juſt toucht and ſuſteined thereby; then applying the flame of the Candle to the middle of it, and heating it hot, you will preſently find the Glaſs to ſtick very faſt on thoſe points, and not without much difficulty to be convertible on them, before that by removing the flame for a while from it, it be ſuffered to cool, and en y ou will find it as eaſie to be turned round as at the firſt.

From all which Experiments it is very evident, that all thoſe Bodies, and particularly Glaſs, ſuffers an Expanſion by Heat, and that a very conſiderable

siderable one, whilst they are in a state of Fusion. For *Fluidity*, as I elsewhere mention, *being nothing but an effect of a very strong and quick shaking motion, whereby the parts are, as it were, loosened from each other, and consequently leave an interjacent space or vacuity*; it follows, that all those shaken Particles must necessarily take up much more room then when they were at rest, and lay quietly upon each other. And this is further confirmed by a Pot of *boyling Alabaster*, which will manifestly rise a sixth or eighth part higher in the Pot, whilst it is boyling, then it will remain at, both before and after it be boyled. The reason of which odd *Phænomenon* (to hint it here only by the way) is this, that there is in the curious powder of Alabaster, and other calcining Stones, a certain watery substance, which is so fixt and included with the solid Particles, that till the heat be very considerable they will not fly away; but after the heat is increased to such a degree, they break out every way in vapours, and thereby so shake and loosen the small corpusles of the Powder from each other, that they become perfectly of the nature of a fluid body, and one may move a stick to and fro through it, and stir it as easily as water, and the vapours burst and break out in bubbles just as in boyling water, and the like; whereas, both before those watery parts are flying away, and after they are quite gone; that is, before and after it have done boyling, all those effects cease, and a stick is as difficultly moved to and fro in it as in sand, or the like. Which Explication I could easily prove, had I time; but this is not a fit place for it.

To proceed therefore, I say, that the dropping of this expanded Body into cold Water, does make the parts of the Glass suffer a double contraction: The first is, of those parts which are neer the Surface of the Drop. For Cold, as I said before, contracting Bodies, that is, *by the abatement of the agitating faculty the parts falling neerer together*; the parts next adjoying to the Water must needs lose much of their motion, and impart it to the Ambient-water (which the Ebullition and commotion of it manifests) and thereby become a solid and hard crust, whilst the innermost parts remain yet fluid and expanded; whence, as they grow cold also by degrees, their parts must necessarily be left at liberty to be condensed, but because of the hardness of the outward crust, the contraction cannot be admitted that way; but there being many very small, and before inconspicuous, bubbles in the substance of the Glass, upon the subsiding of the parts of the Glass, the agil substance contained in them has liberty of expanding it self a little, and thereby those bubbles grow much bigger, which is the second Contraction. And both these are confirmed from the appearance of the Drop it self: for as for the outward parts, we see, first, that it is irregular and shrunk, as it were, which is caused by the yielding a little of the hardened Skin to a Contraction, after the very outmost Surface is settled; and as for the internal parts, one may with ones naked Eye perceive abundance of very conspicuous bubbles, and with the *Microscope* many more.

The Consideration of which Particulars will easily make the Third Position probable, that is, that the parts of the drop will be of a very hard, though of a rarified Texture; for if the outward parts of the Drop, by reason of its hard crust, will indure very little Contraction, and the agil Particles, inclu-

ded in those bubbles, by the losing of their agitation, by thedecrease of the Heat,lose also most part of their Spring and Expansive power;it follows (the withdrawing of the heat being very sudden) that the parts must be left in a very loose Texture, and by reason of the implication of the parts one about another,which from their sluggishnes and glutinousnes I suppose to be much after the manner of the sticks in a Thorn-bush,or a Lock of Wool;It will follow, I say, that the parts will hold each other very strongly together,and indeavour to draw each other neerer together, and consequently their Texture must be very hard and stiff, but very much rarified.

And this will make probable my next Position, That *the parts of the Glass are under a kind of tension or flexure,out of which they indeavour to extricate and free themselves*,and thereby all the parts draw towards the Center or middle, and would, if the outward parts would give way, as they do when the outward parts cool leisurely (as in baking of Glasses) contract the bulk of the drop into a much less compass. For since,as I proved before,the Internal parts of the drop, when fluid,were of a very rarified Texture,and,as it were,tos'd open like a Lock of Wool,and if they were suffered leisurely to cool, would be again prest, as it were,close together: And since that the heat,which kept them bended and open, is removed, and yet the parts not suffered to get as neer together as they naturally would; It follows,that the Particles remain under a kind of *tension* and *flexure*, and consequently have an indeavour to free themselves from that *bending* and *distension*, which they do, as soon as either the tip be broken, or as soon as by a leisurely heating and cooling, the parts are nealed into another posture.

And this will make my next Position probable,that *the parts of the Glass drops are contignated together in the form of an Arch*,and cannot any where yield or be drawn inwards,till by the removing of some one part of it(as it happens in the removing one of the stones of an Arch)the whole Fabrick is shatter'd,and falls to pieces,and each of the Springs is left at liberty,suddenly to extricate it self: for since I have made it probable,that the internal parts of the Glass have a contractive power inwards, and the external parts are incapable of such a Contraction,and the figure of it being spherical;it follows,that the superficial parts must bear against each other, and keep one another from being condens'd into a less room, in the same manner as the stones of an Arch conduce to the upholding each other in that Figure.And this is made more probable by another Experiment which was communicated to me by an excellent Person,whose extraordinary Abilities in all kind of Knowledg, especially in that of Natural things,and his generous Disposition in communicating,incouraged me to have recourse to him on many occasions. The Experiment was this: Small Glass-balls (about the bigness of that represented in the *Figure &c.*) would,upon rubbing or scratching the inward Surface, fly all insunder, with a pretty brisk noise; whereas neither before nor after the inner Surface had been thus scratcht, did there appear any flaw or crack. And putting the pieces of one of those broken ones together again, the flaws appeared much after the manner of the black lines on the Figure, *&c.* These Balls were small, but exceeding thick bubbles of Glass, which being crack'd off from the *Puntilion*.whilst very hot, and so suffered to cool without nealing them in the

the Oven over the Furnace, do thereby (being made of white Glass, which cools much quicker then green Glass, and is thereby made much brittler) acquire a very *porous* and very brittle *texture*: so that if with the point of a Needle or Bodkin, the inside of any of them be rubbed prety hard, and then laid on a Table, it will, within a very little while, break into many pieces with a brisk noise, and throw the parts above a span asunder on the Table: Now though the pieces are not so small as those of a *fulminating* drop, yet they as plainly shew, that the outward parts of the Glass have a great *Conatus* to fly asunder, were they not held together by the *tenacity* of the parts of the inward Surface: for we see as soon as those parts are crazed by hard rubbing, and thereby their tenacity spoiled, the springiness of the more outward parts quickly makes a divulsion, and the broken pieces will, if the concave Surface of them be further scratcht with a Diamond, fly again into smaller pieces.

From which preceding considerations it will follow Sixthly, That the sudden flying asunder of the parts as soon as this Arch is any where disordered or broken, proceeds from the springing of the parts; which, indeavouring to *extricate* themselves as soon as they get the liberty, they perform it with such a quickness, that they throw one another away with very great violence: for the Particles that compose the Crust have a *Conatus* to lye further from one another, and therefore as soon as the external parts are loosened they dart themselves outward with great violence, just as so many Springs would do, if they were detained and fastened to the body, as soon as they should be suddenly loosened; and the internal parts drawing inward, they contract so violently, that they rebound back again and fly into multitude of small shivers or sands. Now though they appear not, either to the naked Eye, or the *Microscope*, yet I am very apt to think there may be abundance of small flaws or cracks, which, by reason the strong reflecting Air is not got between the *contiguous* parts, appear not. And that this may be so, I argue from this, that I have very often been able to make a crack or flaw, in some convenient pieces of Glass, to appear and disappear at pleasure, according as by pressing together, or pulling asunder the contiguous parts, I excluded or admitted the strong reflecting Air between the parts: And it is very probable, that there may be some Body, that is either very rarified Air, or something *analogous* to it, which fills the bubbles of these drops; which I argue, first, from the roundness of them, and next, from the vivid reflection of Light which they exhibite: Now though I doubt not, but that the Air in them is very much rarified, yet that there is some in them, to such as well consider this Experiment of the disappearing of a crack upon the *extruding* of the Air, I suppose it will seem more then probable.

The Seventh and last therefore that I shall prove, is, *That the gradual heating and cooling of these so extended bodies does reduce the parts of the Glass to a looser and softer temper.* And this I found by heating them, and keeping them for a prety while very red hot in a fire; for thereby I found them to grow a little lighter, and the small Stems to be very easily broken and snapt any where, without at all making the drop fly; whereas

before they were so exceeding hard, that they could not be broken without much difficulty; and upon their breaking the whole drop would fly in pieces with very great violence. The Reason of which last seems to be, that the leisurely heating and cooling of the parts does not only wast some part of the Glass it self, but ranges all the parts into a better order, and gives each Particle an opportunity of *relaxing* its self, and consequently neither will the parts hold so strongly together as before, nor be so difficult to be broken: The parts now more easily yielding, nor will the other parts fly in pieces, because the parts have no bended Springs. The *relaxation* also in the temper of hardned Steel, and hammered Metals, by nealing them in the fire, seems to proceed from much the same cause. For both by quenching suddenly such Metals as have *vitrid* parts interspers'd, as Steel has, and by hammering of other kinds that do not so much abound with them, as Silver, Brass, *&c.* the parts are put into and detained in a bended posture, which by the agitation of Heat are shaken, and loosened, and suffered to unbend themselves.

Observ. VIII. *Of the fiery Sparks struck from a Flint or Steel.*

Schem. 5. IT is a very common Experiment, by striking with a Flint against a Steel, to make certain fiery and shining Sparks to fly out from between those two compressing Bodies. About eight years since, upon casually reading the Explication of this odd *Phænomenon*, by the most Ingenious *Des Cartes*, I had a great desire to be satisfied, what that Substance was that gave such a shining and bright Light: And to that end I spread a sheet of white Paper, and on it, observing the place where several of these Sparks seemed to vanish, I found certain very small, black, but glistering Spots of a movable Substance, each of which examining with my *Miscrocope*, I found to be a small round *Globule*; some of which, as they looked prety small, so did they from their Surface yield a very bright and strong reflection on that side which was next the Light; and each look'd almost like a prety bright Iron-Ball, whose Surface was prety regular, such as is represented by the Figure A. In this I could perceive the Image of the Window prety well, or of a Stick, which I moved up and down between the Light and it. Others I found, which were, as to the bulk of the Ball, prety regularly round, but the Surface of them, as it was not very smooth, but rough, and more irregular, so was the reflection from it more faint and confused. Such were the Surfaces of B. C. D. and E. Some of these I found cleft or cracked, as C, others quite broken in two and hollow, as D. which seemed to be half the hollow shell of a Granado, broken irregularly in pieces. Several others I found of other shapes; but that which is represented by E, I observed to be a very big Spark of Fire, which went out upon one side of the Flint that I struck fire withall, to which

which it ſtuck by the root F, at the end of which ſmall Stem was faſtened-on a *Hemiſphere*, or half a hollow Ball, with the mouth of it open from the ſtemwards, ſo that it looked much like a Funnel, or an old faſhioned Bowl without a foot. This night, making many tryals and obſervations of this Experiment, I met, among a multitude of the Globular ones which I had obſerved, a couple of Inſtances, which are very remarkable to the confirmation of my *Hypotheſis*.

And the Firſt was of a pretty big Ball faſtened on to the end of a ſmall ſliver of Iron, which *Compoſitum* ſeemed to be nothing elſe but a long thin chip of Iron, one of whoſe ends was melted into a ſmall round Globul; the other end remaining unmelted and irregular, and perfectly Iron.

The Second Inſtance was not leſs remarkable then the Firſt; for I found, when a Spark went out, nothing but a very ſmall thin long ſliver of Iron or Steel, unmelted at either end. So that it ſeems, that ſome of theſe Sparks are the ſlivers or chips of the Iron *vitrified*, Others are only the ſlivers melted into Balls without vitrification, And the third kind are only ſmall ſlivers of the Iron, made red-hot with the violence of the ſtroke given on the Steel by the Flint.

He that ſhall diligently examine the *Phænomena* of this Experiment, will, I doubt not, find cauſe to believe, that the reaſon I have heretofore given of it, is the true and genuine cauſe of it, namely, That *the Spark appearing ſo bright in the falling, is nothing elſe but a ſmall piece of the Steel or Flint, but moſt commonly of the Steel, which by the violence of the ſtroke is at the ſame time ſever'd and heat red-hot, and that ſometimes to ſuch a degree, as to make it melt together into a ſmall Globule of Steel; and ſometimes alſo is that heat ſo very intenſe, as further to melt it and vitrifie it; but many times the heat is ſo gentle, as to be able to make the ſliver only red hot, which notwithſtanding falling upon the tinder* (that is only a very curious ſmall Coal made of the ſmall threads of Linnen burnt to coals and char'd) *it eaſily ſets it on fire.* Nor will any part of this *Hypotheſis* ſeem ſtrange to him that conſiders, Firſt, that either hammering, or filing, or otherwiſe violently rubbing of Steel, will preſently make it ſo hot as to be able to burn ones fingers. Next, that the whole force of the ſtroke is exerted upon that ſmall part where the Flint and Steel firſt touch: For the Bodies being each of them ſo very hard, the puls cannot be far communicated, that is, the parts of each can yield but very little, and therefore the violence of the concuſſion will be *exerted* on that piece of Steel which is cut off by the Flint. Thirdly, that the filings or ſmall parts of Steel are very apt, as it were, to take fire, and are preſently red hot, that is, there ſeems to be a very *combuſtible ſulphureous* Body in Iron or Steel, which the Air very readily preys upon, as ſoon as the body is a little violently heated.

And this is obvious in the filings of Steel or Iron caſt through the flame of a Candle; for even by that ſudden *tranſitus* of the ſmall chips of Iron, they are heat red hot, and that *combuſtible ſulphureous* Body is preſently prey'd upon and devoured by the *aereal* incompaſſing *Menſtruum*, whoſe office in this Particular I have ſhewn in the Explication of Charcole.

And

And in prosecution of this Experiment, having taken the filings of Iron and Steel, and with the point of a Knife cast them through the flame of a Candle, I observed where some conspicuous shining Particles fell, and looking on them with my *Microscope*, I found them to be nothing else but such round Globules, as I formerly found the Sparks struck from the Steel by a stroke to be, only a little bigger; and shaking together all the filings that had fallen upon the sheet of Paper underneath, and observing them with the *Microscope*, I found a great number of small Globules, such as the former, though there were also many of the parts that had remained untoucht, and rough filings or chips of Iron. So that, it seems, Iron does contain a very *combustible sulphureous* Body, which is, in all likelihood, one of the causes of this *Phænomenon*, and which may be perhaps very much concerned in the business of its hardening and tempering: of which somewhat is said in the Description of *Muscovy-glass*.

So that, these things considered, we need not trouble our selves to find out what kind of Pores they are, both in the Flint and Steel, that contain the *Atoms of fire*, nor how those *Atoms* come to be hindred from running all out, when a dore or passage in their Pores is made by the concussion: nor need we trouble our selves to examine by what *Prometheus* the Element of Fire comes to be fetcht down from above the Regions of the Air, in what Cells or Boxes it is kept, and what *Epimetheus* lets it go: Nor to consider what it is that causes so great a conflux of the atomical Particles of Fire, which are said to fly to a flaming Body, like Vultures or Eagles to a putrifying Carcass, and there to make a very great pudder. Since we have nothing more difficult in this *Hypothesis* to conceive, first, as to the kindling of Tinder, then how a large Iron-bullet, let fall red or glowing hot upon a heap of Small-coal, should set fire to those that are next to it first: Nor secondly, is this last more difficult to be explicated, then that a Body, as Silver for Instance, put into a weak *Menstruum*, as unrectified *Aqua fortis* should, when it is put in a great heat, be there dissolved by it, and not before; which *Hypothesis* is more largely explicated in the Description of Charcoal. To conclude, we see by this Instance, how much Experiments may conduce to the regulating of *Philosophical notions*. For if the most Acute *Des Cartes* had applied himself experimentally to have examined what substance it was that caused that shining of the falling Sparks struck from a Flint and a Steel, he would certainly have a little altered his *Hypothesis*, and we should have found, that his Ingenious Principles would have admitted a very plausible Explication of this *Phænomenon*; whereas by not examining so far as he might, he has set down an Explication which Experiment do's contradict.

But before I leave this Description, I must not forget to take notice of the Globular form into which each of these is most curiously formed. And this *Phænomenon*, as I have elsewhere more largely shewn, proceeds from a propriety which belongs to all kinds of fluid Bodies more or less, and is caused by the Incongruity of the Ambient and included Fluid, which so acts and modulates each other, that they acquire, as neer as is possible,


Fig: x.
D
Fig: 1.
B
E
C
A
F
Fig: 3.
G
E E E
C
B
Fig: 2.
A
D
C

possible, a *sperical* or *globular* form, which propriety and several of the *Phænomena* that proceed from it, I have more fully explicated in the sixth Observation.

One Experiment, which does very much illustrate my present Explication, and is in it self exceeding pretty, I must not pass by: And that is a way of making small *Globules* or *Balls* of Lead, or Tin, as small almost as these of Iron or Steel, and that exceeding easily and quickly, by turning the filings or chips of those Metals also into perfectly round *Globules*. The way, in short, as I received it from the *Learned Physitian Doctor* I. G. is this;

Reduce the Metal you would thus shape, into exceeding fine filings, the finer the filings are, the finer will the Balls be: *Stratifie* these filings with the fine and well dryed powder of quick Lime in a *Crucible* proportioned to the quantity you intend to make: When you have thus filled your *Crucible*, by continual *stratifications* of the filings and powder, so that, as neer as may be, no one of the filings may touch another, place the *Crucible* in a *gradual fire*, and by degrees let it be brought to a heat big enough to make all the filings, that are mixt with the quick Lime, to melt, and no more; for if the fire be too hot, many of these filings will joyn and run together; whereas if the heat be proportioned, upon washing the Lime-dust in fair Water, all those small filings of the Metal will subside to the bottom in a most curious powder, consisting all of exactly round *Globules*, which, if it be very fine, is very excellent to make Hour-glasses of.

Now though quick Lime be the powder that this direction makes choice of, yet I doubt not, but that there may be much more convenient ones found out, one of which I have made tryal of, and found very effectual; and were it not for discovering, by the mentioning of it, another Secret, which I am not free to impart, I should have here inserted it.

Observ. IX. *Of the Colours observable in Muscovy Glass, and other thin Bodies.*

MOscovy-glass, or *Lapis specularis*, is a Body that seems to have as many Curiosities in its Fabrick as any common Mineral I have met with: for first, It is transparent to a great thickness: Next, it is compounded of an infinite number of thin flakes joyned or generated one upon another so close & smooth, as with many hundreds of them to make one smooth and thin Plate of a transparent flexible substance, which with care and diligence may be slit into pieces so exceedingly thin as to be hardly perceivable by the eye, and yet even those, which I have thought the thinnest, I have with a good *Microscope* found to be made up of many other Plates, yet thinner; and it is probable, that, were our *Microscopes* much

much better, we might much further discover its divisibility. Nor are these flakes only regular as to the smoothness of their Surfaces; but thirdly, In many Plates they may be perceived to be terminated naturally with edges of the figure of a *Rhomboeid*. This Figure is much more conspicuous in our English talk, much whereof is found in the Lead Mines, and is commonly called *Spar*, and *Kauck*, which is of the same kind of substance with the *Selenitis*, but is seldom found in so large flakes as that is, nor is it altogether so tuff, but is much more clear and transparent, and much more curiously shaped, and yet may be cleft and flak'd like the other *Selenitis*. But fourthly, this stone has a property, which in respect of the *Microscope*, is more notable, and that is, that it exhibits several appearances of Colours, both to the naked Eye, but much more conspicuously to the *Microscope*; for the exhibiting of which, I took a piece of *Muscovy-glass*, and splitting or cleaving it into thin Plates, I found that up and down in several parts of them I could plainly perceive several white specks or flaws, and others diversly coloured with all the Colours of the *Rainbow*; and with the *Microscope* I could perceive, that these Colours were ranged in rings that incompassed the white speck or flaw, and were round or irregular, according to the shape of the spot which they terminated; and the position of Colours, in respect of one another, was the very same as in the *Rainbow*. The consecution of those Colours from the middle of the spot outward being Blew, Purple, Scarlet, Yellow, Green, Blew, Purple, Scarlet, and so onwards, sometimes half a score times repeated, that is, there appeared six, seven, eight, nine or ten several coloured rings or lines, each incircling the other, in the same manner as I have often seen a very *vivid Rainbow* to have four or five several Rings of Colours, that is, accounting all the Gradations between Red and Blew for one: But the order of the Colours in these Rings was quite contrary to the primary or innermost *Rainbow*, and the same with those of the secondary or outermost Rainbow; these coloured Lines or *Irises*, as I may so call them, were some of them much brighter then others, and some of them also very much broader, they being some of them ten, twenty, nay, I believe, neer a hundred times broader then others; and those usually were broadish which were neerest the center or middle of the flaw. And oftentimes I found, that these Colours reacht to the very middle of the flaw, and then there appeared in the middle a very large spot, for the most part, all of one colour, which was very vivid, and all the other Colours incompassing it, gradually ascending, and growing narrower towards the edges, keeping the same order, as in the *secundary Rainbow*, that is, if the middle were Blew, the next incompassing it would be a Purple, the third a Red, the fourth a Yellow, *&c.* as above; if the middle were a Red, the next without it would be a Yellow, the third a Green, the fourth a Blew, and so onward. And this order it always kept whatsoever were the middle Colour.

There was further observable in several other parts of this Body, many Lines or Threads, each of them of some one peculiar Colour, and those so exceedingly bright and vivid, that it afforded a very pleasant object

through

through the *Microscope*. Some of these *threads* I have observed also to be pieced or made up of several short lengths of differently coloured *ends* (as I may so call them) as a line appearing about two inches long through the *Microscope*, has been compounded of about half an inch of a Peach colour, $\frac{1}{8}$ of a lovely Grass-green, $\frac{3}{4}$ of an inch more of a bright Scarlet, and the rest of the line of a Watchet blew. Others of them were much otherwise coloured; the variety being almost infinite. Another thing which is very observable, is, that if you find any place where the colours are very broad and conspicuous to the naked eye, you may, by pressing that place with your finger, make the colours change places, and go from one part to another.

There is one *Phænomenon* more, which may, if care be used, exhibit to the beholder, as it has divers times to me, an exceeding pleasant, and not less instructive Spectacle; And that is, if curiosity and diligence be used, you may so split this admirable Substance, that you may have pretty large Plates (in comparison of those smaller ones which you may observe in the Rings) that are perhaps an $\frac{1}{8}$ or a $\frac{1}{6}$ part of an inch over, each of them appearing through the *Microscope* most curiously, intirely, and uniformly adorned with some one vivid colour: this, if examined with the *Microscope*, may be plainly perceived to be in all parts of it equally thick. Two, three, or more of these lying one upon another, exhibit oftentimes curious compounded colours, which produce such a *Compositum*, as one would scarce imagine should be the result of such *ingredients*: As perhaps a *faint yellow* and a *blew* may produce a very *deep purple*. But when anon we come to the more strict examination of these *Phænomena*, and to inquire into the causes and reasons of these productions, we shall, I hope, make it more conceivable how they are produced, and shew them to be no other then the natural and necessary effects arising from the peculiar union of concurrent causes.

These *Phænomena* being so various, and so truly admirable, it will certainly be very well worth our inquiry, to examine the causes and reasons of them, and to consider, whether from these causes demonstratively evidenced, may not be deduced the true causes of the production of all kind of Colours. And I the rather now do it, instead of an Appendix or Digression to this History, then upon the occasion of examining the Colours in Peacocks, or other Feathers, because this Subject, as it does afford more variety of particular Colours, so does it afford much better wayes of examining each circumstance. And this will be made manifest to him that considers, first, that this laminated body is more simple and regular then the parts of Peacocks feathers, this consisting only of an indefinite number of plain and smooth Plates, heaped up, or *incumbent* on each other. Next, that the parts of this body are much more manageable, to be divided or joyned, then the parts of a Peacocks feather, or any other substance that I know. And thirdly, because that in this we are able from a colourless body to produce several coloured bodies, affording all the variety of Colours imaginable: And several others, which the subsequent Inquiry will make manifest.

To begin therefore, it is manifest from several circumstances, that the material cause of the *apparition* of these several Colours, is some *Laminæ* or Plate of a transparent or pellucid body of a thickness very determinate and proportioned according to the greater or less refractive power of the *pellucid* body. And that this is so, abundance of Instances and particular Circumstances will make manifest.

As *first*, if you take any small piece of the *Muscovy-glass*, and with a Needle, or some other convenient Instrument, cleave it oftentimes into thinner and thinner *Laminæ*, you shall find, that till you come to a determinate thinness of them, they shall all appear transparent and colourless, but if you continue to split and divide them further, you shall find at last, that each Plate, after it comes to such a determinate thickness, shall appear most lovely ting'd or imbued with a determinate colour. If *further*, by any means you so flaw a pretty thick piece, that one part does begin to cleave a little from the other, and between those two there be by any means gotten some pellucid *medium*, those *laminated* pellucid bodies that fill that space, shall exhibit several Rainbows or coloured Lines, the colours of which will be disposed and ranged according to the various thicknesses of the several parts of that Plate. That this is so, is yet *further* confirmed by this Experiment.

Take two small pieces of ground and polisht Looking-glass-plate, each about the bigness of a shilling, take these two dry, and with your fore-fingers and thumbs press them very hard and close together, and you shall find, that when they approach each other very near, there will appear several *Irises* or coloured Lines, in the same manner almost as in the *Muscovy-glass*; and you may very easily change any of the Colours of any part of the interposed body, by pressing the Plates closer and harder together, or leaving them more lax; that is, a part which appeared coloured with a red, may be presently ting'd with a yellow, blew, green, purple, or the like, by altering the appropinquation of the terminating Plates. Now that air is not necessary to be the interposed body, but that any other transparent fluid will do much the same, may be tryed by wetting those approximated Surfaces with Water, or any other transparent Liquor, and proceeding with it in the same manner as you did with the Air; and you will find much the like effect, only with this difference, that those compreſt bodies, which differ most, in their refractive quality, from the compressing bodies, exhibit the most strong and vivid tinctures. Nor is it necessary, that this *laminated* and *ting'd* body should be of a fluid substance, any other substance, provided it be thin enough and transparent, doing the same thing: this the *Laminæ* of our *Muscovy-glass* hint; but it may be confirm'd by multitudes of other Instances.

And first, we shall find, that even Glass it self may, by the help of a Lamp, be blown thin enough to produce these *Phænomena* of Colours: which *Phænomena* accidentally happening, as I have been attempting to frame small Glasses with a Lamp, did not a little surprize me at first, having never heard or seen any thing of it before; though afterwards comparing it with the *Phænomena*, I had often observed

observed in those Bubbles which Children use to make with Soap-water, I did the less wonder; especially when upon Experiment I found, I was able to produce the same *Phænomena* in thin Bubbles made with any other transparent Substance. Thus have I produced them with Bubbles of *Pitch*, *Rosin*, *Colophony*, *Turpentine*, *Solutions* of several *Gums*, as *Gum-Arabick* in water; any *glutinous* Liquor, as *Wort*, *Wine*, *Spirit of Wine*, *Oyl of Turpentine*, *Glare of Snails*, &c.

It would be needless to enumerate the several Instances, these being enough to shew the generality or universality of this propriety. Only I must not omit, that we have instances also of this kind even in metalline Bodies and animal; for those several Colours which are observed to follow each other upon the polisht surface of hardned Steel, when it is by a sufficient degree of heat gradually tempered or softened, are produced from nothing else but a certain thin *Lamina* of a *vitrum* or *vitrified* part of the Metal, which by that degree of heat, and the concurring action of the ambient Air, is driven out and fixed on the surface of the Steel.

And this hints to me a very probable (at least, if not the true) cause of the hardning and tempering of Steel, which has not, I think, been yet given, nor, that I know of, been so much as thought of by any. And that is this, that the hardness of it arises from a greater proportion of a vitrified Substance interspersed through the pores of the Steel. And that the tempering or softning of it arises from the proportionate or smaller parcels of it left within those pores. This will seem the more probable, if we consider these Particulars.

First, That the pure parts of Metals are of themselves very *flexible* and *tuff*; that is, will indure bending and hammering, and yet retain their continuity.

Next, That the Parts of all vitrified Substances, as all kinds of Glass, the *Scoria* of Metals, *&c.* are very hard, and also very brittle, being neither *flexible* nor *malleable*, but may by hammering or beating be broken into small parts or powders.

Thirdly, That all Metals (excepting Gold and Silver, which do not so much with the bare fire, unless assisted by other saline Bodies) do more or less *vitrifie* by the strength of fire, that is, are corroded by a saline Substance, which I elsewhere shew to be the true cause of fire; and are thereby, as by several other *Menstruums*, converted into *Scoria*; And this is called, *calcining* of them, by Chimists. Thus Iron and Copper by heating and quenching do turn all of them by degrees into *Scoria*, which are evidently *vitrified* Substances, and unite with Glass, and are easily *fusible*; and when cold, very hard, and very brittle.

Fourthly, That most kind of *Vitrifications* or *Calcinations* are made by Salts, uniting and incorporating with the metalline Particles. Nor do I know any one *calcination* wherein a *Saline* body may not, with very great probability, be said to be an agent or coadjutor.

Fifthly, That Iron is converted into Steel by means of the incorporation of certain salts, with which it is kept a certain time in the fire.

Sixthly, That any Iron may, in a very little time, be *case hardned*, as the Trades-men call it, by casing the iron to be hardned with clay, and putting between the clay and iron a good quantity of a mixture of *Urine*, *Soot*, *Sea-salt*, and *Horses hoofs* (all which contein great quantities of Saline bodies) and then putting the case into a good strong fire, and keeping it in a considerable degree of heat for a good while, and afterwards heating, and quenching or cooling it suddenly in cold water.

Seventhly, That all kind of vitrify'd substances, by being suddenly cool'd, become very hard and brittle. And thence arises the pretty *Phænomena* of the Glass Drops, which I have already further explained in its own place.

Eighthly, That those metals which are not so apt to vitrifie, do not acquire any hardness by quenching in water, as Silver, Gold, &c.

These considerations premis'd, will, I suppose, make way for the more easie reception of this following Explication of the *Phænomena* of hardned and temper'd Steel. That Steel is a substance made out of Iron, by means of a certain proportionate *Vitrification* of several parts, which are so curiously and proportionately mixt with the more tough and unalter'd parts of the Iron, that when by the great heat of the fire this vitrify'd substance is melted, and consequently rarify'd, and thereby the pores of the Iron are more open, if then by means of dipping it in cold water it be suddenly cold, and the parts hardned, that is, stay'd in that same degree of *Expansion* they were in when hot, the parts become very hard and brittle, and that upon the same account almost as small parcels of glass quenched in water grow brittle, which we have already explicated. If after this the piece of Steel be held in some convenient heat, till by degrees certain colours appear upon the surface of the brightned metal, the very hard and brittle tone of the metal, by degrees relaxes and becomes much more tough and soft; namely, the action of the heat does by degrees loosen the parts of the Steel that were before streached or set *atilt* as it were, and stayed open by each other, whereby they become relaxed and set at liberty, whence some of the more brittle interjacent parts are thrust out and melted into a thin skin on the surface of the Steel, which from no colour increases to a deep Purple, and so onward by these *gradations* or consecutions, *White*, *Yellow*, *Orange*, *Minium*, *Scarlet*, *Purple*, *Blew*, *Watchet*, &c. and the parts within are more conveniently, and proportionately mixt; and so they gradually subside into a texture which is much better proportion'd and closer joyn'd, whence that rigidnesse of parts ceases, and the parts begin to acquire their former *ductilness*.

Now, that 'tis nothing but the vitrify'd metal that sticks upon the surface of the colour'd body, is evident from this, that if by any means it be scraped and rubb'd off, the metal underneath it is white and clear; and if it be kept longer in the fire, so as to increase to a considerable thickness, it may, by blows, be beaten off in flakes. This is further confirm'd by this observable, that that Iron or Steel will keep longer from rusting which is covered with this vitrify'd case: Thus also Lead will, by degrees, be

all

all turn'd into a litharge; for that colour which covers the top being scum'd or shov'd aside, appears to be nothing else but a litharge or vitrify'd Lead.

This is observable also in some sort, on Brass, Copper, Silver, Gold, Tin, but is most conspicuous in Lead: all those Colours that cover the surface of the Metal being nothing else, but a very thin vitrifi'd part of the heated Metal.

The other Instance we have, is in Animal bodies, as in Pearls, Mother of Pearl-shels, Oyster-shels, and almost all other kinds of stony shels whatsoever. This have I also sometimes with pleasure observ'd even in Muscles and Tendons. Further, if you take any glutinous substance and run it exceedingly thin upon the surface of a smooth glass or a polisht metaline body, you shall find the like effects produced: and in general, wheresoever you meet with a transparent body thin enough, that is terminated by reflecting bodies of differing refractions from it, there will be a production of these pleasing and lovely colours.

Nor is it necessary, that the two *terminating* Bodies should be both of the same kind, as may appear by the *vitrified Laminæ* on *Steel*, *Lead*, and other Metals, one surface of which *Laminæ* is contiguous to the surface of the Metal, the other to that of the Air.

Nor is it necessary, that these colour'd *Laminæ* should be of an even thickness, that is, should have their edges and middles of equal thickness, as in a Looking-glass-plate, which circumstance is only requisite to make the Plate appear all of the same colour; but they may resemble a *Lens*, that is, have their middles thicker then their edges; or else a *double concave*, that is, be thinner in the middle then at the edges; in both which cases there will be various coloured rings or lines, with differing consecutions or orders of Colours; the order of the first from the middle outwards being Red, Yellow, Green, Blew, *&c.* And the latter quite contrary.

But further, it is altogether necessary, that the Plate, in the places where the Colours appear, should be of a determinate thickness: First, It must not be more then such a thickness, for when the Plate is increased to such a thickness, the Colours cease; and besides, I have seen in a thin piece of *Muscovy-glass*, where the two ends of two Plates, which appearing both single, exhibited two distinct and differing Colours; but in that place where they were united, and constituted one double Plate (as I may call it) they appeared transparent and colourless. Nor, Secondly, may the Plates be *thinner* then such a determinate *size*; for we alwayes find, that the very outmost Rim of these flaws is terminated in a white and colourless Ring.

Further, in this Production of Colours there is no need of a determinate Light of such a bigness and no more, nor of a determinate position of that Light, that it should be on this side, and not on that side; nor of a terminating shadow, as in the Prisme, and Rainbow, or Water-ball: for we find, that the Light in the open Air, either in or out of the Sun-beams, and within a Room, either from one or many Windows, produces much

the

the same effect: only where the Light is brightest, there the Colours are most *vivid*. So does the light of a Candle, collected by a Glass-ball. And further, it is all one whatever side of the coloured Rings be towards the light; for the whole Ring keeps its proper Colours from the middle outwards in the same order as I before related, without varying at all, upon changing the position of the light.

But above all it is most observable, that here are all kind of Colours generated in a *pellucid* body, where there is properly no such refraction as *Des Cartes* supposes his *Globules* to acquire a *verticity* by: For in the plain and even Plates it is manifest, that the second refraction (according to *Des Cartes* his Principles in the *fifth Section of the eighth Chapter of his Meteors*) does regulate and restore the supposed *turbinated Globules* unto their former uniform motion. This Experiment therefore will prove such a one as our *thrice excellent Verulam* calls *Experimentum Crucis*, serving as a Guide or Land-mark, by which to direct our course in the search after the true cause of Colours. Affording us this particular negative Information, that for the production of Colours there is not necessary either a great refraction, as in the Prisme; nor Secondly, a determination of Light and shadow, such as is both in the Prisme and Glass-ball. Now that we may see likewise what affirmative and positive Instruction it yields, it will be necessary, to examine it a little more particularly and strictly; which that we may the better do, it will be requisite to premise somewhat in general concerning the nature of Light and Refraction.

And first for Light, it seems very manifest, that there is no luminous Body but has the parts of it in motion more or less.

First, That all kind of *fiery burning Bodies* have their parts in motion, I think, will be very easily granted me. That the *spark* struck from a Flint and Steel is in a rapid agitation, I have elsewhere made probable. And that the Parts of *rotten Wood*, *rotten Fish*, and the like, are also in motion, I think, will as easily be conceded by those, who consider, that those parts never begin to shine till the Bodies be in a state of putrefaction; and that is now generally granted by all, to be caused by the motion of the parts of putrifying bodies. That the *Bononian stone* shines no longer then it is either warmed by the Sun-beams, or by the flame of a Fire or of a Candle, is the general report of those that write of it, and of others that have seen it. And that heat argues a motion of the internal parts, is (as I said before) generally granted.

But there is one Instance more, which was first shewn to the *Royal Society* by Mr. *Clayton* a worthy Member thereof, which does make this Assertion more evident then all the rest: And that is, That a *Diamond* being *rub'd*, *struck*, or *heated* in the dark, shines for a pretty while after, so long as that motion, which is imparted by any of those Agents, remains (in the same manner as a Glass, rubb'd, struck, or (by a means which I shall elsewhere mention) heated, yields a sound which lasts as long as the *vibrating* motion of that *sonorous* body) several Experiments made on which Stone, are since published in a Discourse of Colours, by the truly honou-

honourable Mr. *Boyle*. What may be said of those *Ignes fatui* that appear in the night, I cannot so well affirm, having never had the opportunity to examine them my self, nor to be inform'd by any others that had observ'd them: And the relations of them in Authors are so imperfect, that nothing can be built on them. But I hope I shall be able in another place to make it at least very probable, that there is even in those also a Motion which causes this effect. That the shining of *Sea-water* proceeds from the same cause, may be argued from this, That it shines not till either it be beaten against a Rock, or be some other wayes broken or agitated by Storms, or Oars, or other *percussing* bodies. And that the Animal *Energyes* or Spirituous *agil* parts are very active in *Cats eyes* when they shine, seems evident enough, because their eyes never shine but when they look very intensly either to find their prey, or being hunted in a dark room, when they seek after their adversary, or to find a way to escape. And the like may be said of the shining *Bellies of Gloworms*, since 'tis evident they can at pleasure either increase or extinguish that Radiation.

It would be somewhat too long a work for this place *Zetetically* to examine, and positively to prove, what particular kind of motion it is that must be the efficient of Light; for though it be a motion, yet 'tis not every motion that produces it, since we find there are many bodies very violently mov'd, which yet afford not such an effect; and there are other bodies, which to our other senses, seem not mov'd so much, which yet shine. Thus Water and quick-silver, and most other liquors heated, shine not; and several hard bodies, as Iron, Silver, Brass, Copper, Wood, *&c.* though very often struck with a hammer, shine not presently, though they will all of them grow exceeding hot; whereas rotten Wood, rotten Fish, Sea water, Gloworms, *&c.* have nothing of tangible heat in them, and yet (where there is no stronger light to affect the Sensory) they shine some of them so Vividly, that one may make a shift to read by them.

It would be too long, I say, here to insert the discursive progress by which I inquir'd after the proprieties of the motion of Light, and therefore I shall only add the result.

And, First, I found it ought to be exceeding *quick*, such as those motions of *fermentation* and *putrefaction*, whereby, certainly, the parts are exceeding nimbly and violently mov'd; and that, because we find those motions are able more minutely to shatter and divide the body, then the most violent heats or *menstruums* we yet know. And that fire is nothing else but such a *dissolution* of the Burning body, made by the most *universal menstruum* of all *sulphureous bodies*, namely, the Air, we shall in an other place of this Tractate endeavour to make probable. And that, in all extreamly hot shining bodies, there is a very quick motion that causes Light, as well as a more robust that causes Heat, may be argued from the celerity wherewith the bodyes are dissolv'd.

Next, it must be a *Vibrative motion*. And for this the newly mention'd *Diamond* affords us a good argument; since if the motion of the parts did not

not return, the Diamond must after many rubbings decay and be wasted: but we have no reason to suspect the latter, especially if we consider the exceeding difficulty that is found in cutting or wearing away a Diamond. And a Circular motion of the parts is much more improbable, since, if that were granted, and they be suppos'd irregular and Angular parts, I see not how the parts of the Diamond should hold so firmly together, or remain in the same sensible dimensions, which yet they do. Next, if they be *Globular*, and mov'd only with a *turbinated* motion, I know not any cause that can impress that motion upon the *pellucid medium*, which yet is done. Thirdly, any other *irregular* motion of the parts one amongst another, must necessarily make the body of a fluid consistence, from which it is far enough. It must therefore be a *Vibrating* motion.

And Thirdly, That it is a very *short vibrating motion*, I think the instances drawn from the shining of Diamonds will also make probable. For a Diamond being the hardest body we yet know in the World, and consequently the least apt to yield or bend, must consequently also have its *vibrations* exceeding short.

And these, I think, are the three principal proprieties of a motion, requisite to produce the effect call'd Light in the Object.

The next thing we are to consider, is the way or manner of the *trajection* of this motion through the interpos'd pellucid body to the eye: And here it will be easily granted,

First, That it must be a body *susceptible* and *impartible* of this motion that will deserve the name of a Transparent. And next, that the parts of such a body must be *Homogeneous*, or of the same kind. Thirdly, that the constitution and motion of the parts must be such, that the appulse of the luminous body may be communicated or propagated through it to the greatest imaginable distance in the least imaginable time; though I see no reason to affirm, that it must be in an instant: For I know not any one Experiment or observation that does prove it. And, whereas it may be objected, That we see the Sun risen at the very instant when it is above the sensible Horizon, and that we see a Star hidden by the body of the Moon at the same instant, when the Star, the Moon, and our Eye are all in the same line; and the like Observations, or rather suppositions, may be urg'd. I have this to answer, That I can as easily deny as they affirm; for I would fain know by what means any one can be assured any more of the Affirmative, then I of the Negative. If indeed the propagation were very slow, 'tis possible something might be discovered by Eclypses of the Moon; but though we should grant the progress of the light from the Earth to the Moon, and from the Moon back to the Earth again to be full two Minutes in performing, I know not any possible means to discover it; nay, there may be some instances perhaps of Horizontal Eclypses that may seem very much to favour this supposition of the slower progression of Light then most imagine. And the like may be said of the Eclypses of the Sun, &c. But of this only by the by. Fourthly, That the motion is propagated every way through an *Homogeneous*

geneous medium by *direct* or *straight* lines extended every way like Rays from the center of a Sphere. Fifthly, in an *Homogeneous medium* this motion is propagated every way with *equal velocity*, whence necessarily every *pulse* or *vitration* of the luminous body will generate a Sphere, which will continually increase, and grow bigger, just after the same manner (though indefinitely swifter) as the waves or rings on the surface of the water do swell into bigger and bigger circles about a point of it, where, by the sinking of a Stone the motion was begun, whence it necessarily follows, that all the parts of these Spheres undulated through an *Homogeneous medium* cut the Rays at right angles.

But because all transparent *mediums* are not *Homogeneous* to one another, therefore we will next examine how this pulse or motion will be propagated through differingly transparent *mediums*. And here, according to the most acute and excellent Philosopher *Des Cartes*, I suppose the sign of the angle of inclination in the first *medium* to be to the sign of refraction in the second, As the density of the first, to the density of the second. By density, I mean not the density in respect of gravity (with which the refractions or transparency of *mediums* hold no proportion) but in respect onely to the *trajection* of the Rays of light, in which respect they only differ in this; that the one propagates the pulse more easily and weakly, the other more slowly, but more strongly. But as for the pulses themselves, they will by the refraction acquire another propriety, which we shall now endeavour to explicate.

We will suppose therefore in the first Figure A C E D to be a physical Ray, or A B C and D E F to be two Mathematical Rays, *trajected* from a very remote point of a luminous body through an *Homogeneous* transparent *medium* L L L, and D A, E B, F C, to be small portions of the orbicular impulses which must therefore cut the Rays at right angles; these Rays meeting with the plain surface N O of a *medium* that yields an easier *transitus* to the propagation of light, and falling *obliquely* on it, they will in the *medium* M M M be refracted towards the perpendicular of the surface. And because this *medium* is more easily *trajected* then the former by a third, therefore the point C of the orbicular pulse F C will be mov'd to H four spaces in the same time that F the other end of it is mov'd to G three spaces, therefore the whole refracted pulse G H shall be *oblique* to the refracted Rays C H K and G I; and the angle G H C shall be an acute, and so much the more acute by how much the greater the refraction be, then which nothing is more evident, for the sign of the inclination is to be the sign of refraction as G F to T C the distance between the point C and the perpendicular from G on C K, which being as four to three, H C being longer then G F is longer also then T C, therefore the angle G H C is less than G T C. So that henceforth the parts of the pulses G H and I K are mov'd ascew, or cut the Rays at *oblique* angles.

It is not my business in this place to set down the reasons why this or that body should impede the Rays more, others less: as why Water should transmit the Rays more easily, though more weakly than air. Onely thus

 much

much in general I shall hint, that I suppose the *medium* M M M to have less of the transparent undulating subtile matter, and that matter to be less implicated by it, whereas L L L I suppose to contain a greater quantity of the fluid undulating substance, and this to be more implicated with the particles of that *medium*.

But to proceed, the same kind of *obliquity* of the Pulses and Rays will happen also when the refraction is made out of a more easie into a more difficult *mediũ*; as by the calculations of G Q & C S R which are refracted from the perpendicular. In both which calculations 'tis *obvious* to observe, that always that part of the Ray towards which the refraction is made has the end of the *orbicular pulse* precedent to that of the other side. And always, the oftner the refraction is made the same way, Or the greater the single refraction is, the more is this unequal progress. So that having found this odd propriety to be an inseparable concomitant of a refracted Ray, not streightned by a contrary refraction, we will next examine the refractions of the Sun-beams, as they are suffer'd onely to pass through a small passage, *obliquely* out of a more difficult, into a more easie *medium*.

Let us suppose therefore A B C in the second Figure to represent a large *Chimical Glass-body* about two foot long, filled with very fair Water as high as A B, and inclin'd in a convenient posture with B towards the Sun: Let us further suppose the top of it to be cover'd with an *opacous* body, all but the hole *a b*, through which the Sun-beams are suffer'd to pass into the Water, and are thereby refracted to *c d e f*, against which part, if a Paper be expanded on the outside, there will appear all the colours of the Rain-bow, that is, there will be generated the two principal colours, *Scarlet* and *Blue*, and all the *intermediate* ones which arise from the composition and dilutings of these two, that is, *c d* shall exhibit a *Scarlet*, which toward *d* is diluted into a *Yellow*; this is the refraction of the Ray, *i k*, which comes from the underside of the Sun; and the Ray *e f* shall appear of a deep *Blue*, which is gradually towards *e* diluted into a pale *Watchet-blue*. Between *d* and *e* the two *diluted* colours, *Blue* and *Yellow* are mixt and compounded into a *Green*; and this I imagine to be the reason why *Green* is so acceptable a colour to the eye, and that either of the two extremes are, if intense, rather a little offensive, namely, the being plac'd in the middle between the two extremes, and compounded out of both those, *diluted* also, or somewhat qualifi'd, for the *composition*, arising from the mixture of the two extremes *undiluted*, makes a *Purple*, which though it be a lovely colour, and pretty acceptable to the eye, yet is it nothing comparable to the ravishing pleasure with which a curious and well tempered *Green* affects the eye. If removing the Paper, the eye be plac'd against *c d*, it will perceive the lower side of the Sun (or a Candle at night which is much better, because it offends not the eye, and is more easily manageable) to be of a deep *Red*, and if against *e f* it will perceive the upper part of the luminous body to be of a deep *Blue*; and these colours will appear deeper and deeper, according as the Rays from the luminous body fall more *obliquely* on the surface of the Water, and thereby suffer a greater refraction, and the

more

more distinct, the further *c d e f* is removed from the trajecting hole.

So that upon the whole, we shall find that the reason of the *Phænomena* seems to depend upon the *obliquity* of the *orbicular pulse*, to the Lines of Radiation, and in particular, that the Ray *c d* which constitutes the *Scarlet* has its inner parts, namely those which are next to the middle of the luminous body, precedent to the outermost which are contiguous to the dark and *unradiating* skie. And that the Ray *e f* which gives a *Blue*, has its outward part, namely, that which is contiguous to the dark skie precedent to the pulse from the innermost, which borders on the bright *area* of the luminous body.

We may observe further, that the cause of the *diluting* of the colours towards the middle, proceeds partly from the wideness of the hole through which the Rays pass, whereby the Rays from several parts of the luminous body, fall upon many of the same parts between *c* and *f* as is more manifest by the Figure: And partly also from the nature of the refraction it self, for the vividness or strength of the two terminating colours, arising chiefly as we have seen, from the very great difference that is betwixt the outsides of those *oblique undulations* & the dark Rays circumambient, and that disparity betwixt the *approximate* Rays, decaying gradually: the further inward toward the middle of the luminous body they are remov'd, the more must the colour approach to a white or an undisturbed light.

Upon the calculation of the refraction and reflection from a Ball of Water or Glass, we have much the same *Phænomena*, namely, an *obliquity* of the undulation in the same manner as we have found it here. Which, because it is very much to our present purpose, and affords such an *Instancia crucis*, as no one that I know has hitherto taken notice of, I shall further examine. For it does very plainly and positively distinguish, and shew, which of the two *Hypotheses*, either the *Cartesian* or this is to be followed, by affording a generation of all the colors in the Rainbow, where according to the *Cartesian Principles* there should be none at all generated. And secondly, by affording an instance that does more closely confine the cause of these *Phænomena* of colours to this present *Hypothesis*.

And first, for the *Cartesian*, we have this to object against it, That whereas he says (*Meteorum Cap.8.Sect.5.*) *Sed judicabam unicam (refractionē scilicet) ad minimū requiri, & quidem talem ut ejus effectus aliâ contrariâ (refractione) non destruatur: Nam experientia docet si superficies* NM & NP (*nempe refringentes*) *Parallelæ forent, radios tantundem per alteram iterum erectos quantum per unam frangerentur, nullos colores depicturos*; This Principle of his holds true indeed in a prisme where the refracting surfaces are plain, but is contradicted by the Ball or Cylinder, whether of Water or Glass, where the refracting surfaces are Orbicular or Cylindrical. For if we examine the passage of any *Globule* or Ray of the primary *Iris*, we shall find it to pass out of the Ball or Cylinder again, with the same inclination and refraction that it enter'd in withall, and that that last refraction by means of the *intermediate* reflection shall be the same as if without any reflection at all the Ray had been twice refracted by two Parallel surfaces.

And that this is true, not onely in one, but in every Ray that goes to the constitution of the Primary Iris; nay, in every Ray, that suffers only two refractions, and one reflection, by the surface of the round body, we shall presently see most evident, if we repeat the *Cartesian Scheme*, mentioned in the tenth *Section* of the eighth *Chapter* of his *Meteors*, where
Schem. 6. Fig. 3. E F K N P in the third Figure is one of the Rays of the Primary Iris, twice refracted at F and N, and once reflected at K by the surface of the Water-ball. For, first it is evident, that K F and K N are equal, because K N being the reflected part of K F they have both the same inclination on the surface K that is the angles F K T, and N K V made by the two Rays and the Tangent of K are equal, which is evident by the Laws of reflection; whence it will follow also, that K N has the same inclination on the surface N, or the Tangent of it X N that the Ray K F has to the surface F, or the Tangent of it F Y, whence it must necessarily follow, that the refractions at F and N are equal, that is, K F E and K N P are equal. Now, that the surface N is by the reflection at K made parallel to the surface at F, is evident from the principles of reflection; for reflection being nothing but an inverting of the Rays, if we re-invertthe Ray K N P, and make the same inclinations below the line T K V that it has above, it will be most evident, that K H the inverse of K N will be the continuation of the line F K, and that L H I the inverse of O X is parallel to F Y. And H M the inverse of N P is Parallel to E F for the angle K H I is equal to K N O which is equal to K F Y, and the angle K H M is equal to K N P which is equal to K F E which was to be prov'd.

So that according to the above mentioned *Cartesian* principles there should be generated no colour at all in a Ball of Water or Glass by two refractions and one reflection, which does hold most true indeed, if the surfaces be plain, as may be experimented with any kind of prisme where the two refracting surfaces are equally inclin'd to the reflecting; but in this the *Phænomena* are quite otherwise.

The cause therefore of the generation of colour must not be what *Des Cartes* assigns, namely, a certain *rotation* of the *Globuli ætherei*, which are the particles which he supposes to constitute the *Pellucid medium*, But somewhat else, perhaps what we have lately supposed, and shall by and by further prosecute and explain.

But, First I shall crave leave to propound some other difficulties of his, notwithstanding exceedingly ingenious *Hypothesis*, which I plainly confess to me seem such; and those are,

First, if that light be (as is affirmed, *Diopt.* cap. 1. §. 8.) not so properly a motion, as an action or propension to motion, I cannot conceive how the eye can come to be sensible of the *verticity* of a *Globule*, which is generated in a drop of Rain, perhaps a mile off from it. For that *Globule* is not carry'd to the eye according to his formerly recited Principle; and if not so, I cannot conceive how it can communicate its *rotation*, or circular motion to the line of the *Globules* between the drop and the eye. It cannot be by means of every ones turning the next before him; for if so, then onely all the *Globules* that are in the odd places must be turned the same

way

way with the first, namely, the 3. 5. 7. 9. 11, &c. but all the *Globules* interposited between them in the even places; namely, the 2. 4. 6. 8. 10. &c. must be the quite contrary; whence, according to the *Cartesian Hypothesis*, there must be no distinct colour generated, but a confusion. Next, since the *Cartesian Globuli* are suppos'd (*Principiorum Philosoph.* Part. 3. §. 86.) to be each of them continually in motion about their centers, I cannot conceive how the eye is able to distinguish this new generated motion from their former inherent one, if I may so call that other wherewith they are mov'd or *turbinated*, from some other cause than refraction. And thirdly, I cannot conceive how these motions should not happen sometimes to oppose each other, and then, in stead of a *rotation*, there would be nothing but a direct motion generated, and consequently no colour. And fourthly, I cannot conceive, how by the *Cartesian Hypothesis* it is possible to give any plausible reason of the nature of the Colours generated in the thin *laminæ* of these our *Microscopical Observations*; for in many of these, the refracting and reflecting surfaces are parallel to each other, and consequently no *rotation* can be generated, nor is there any necessity of a shadow or termination of the bright Rays, such as is suppos'd (*Chap.* 8. §. 5. *Et preterea observavi umbram quoque, aut limitationem luminis requiri:* and *Chap.* 8. §. 9.) to be necessary to the generation of any distinct colours; Besides that, here is oftentimes one colour generated without any of the other appendant ones, which cannot be by the *Cartesian Hypothesis*.

There must be therefore some other propriety of refraction that causes colour. And upon the examination of the thing, I cannot conceive any one more general, inseparable, and sufficient, than that which I have before assign'd. That we may therefore see how exactly our *Hypothesis* agrees also with the *Phænomena* of the refracting round body, whether *Globe* or *Cylinder*, we shall next subjoyn our *Calculation* or *Examen* of it.

And to this end, we will calculate any two Rays: as for instance; let *Schem. 8. Fig. 3.* E F be a Ray cutting the *Radius* C D (divided into 20. parts) in G 16. parts distant from C, and *e f* another Ray, which cuts the same *Radius* in *g* 17. parts distant, these will be refracted to K and *k*, and from thence reflected to N and *n*, and from thence refracted toward P and *p*; therefore the Arch F *f* will be 5.d 5′. The Arch F K 106.d 30′. the Arch *f k* 101.d 2′. The line F G 6000. and *f g* 5267. therefore *h f*. 733. therefore F *c* 980, almost. The line F K 16024. and *f k* 15436. therefore N *d* 196. and *n o* 147 almost, the line N n 1019 the Arch N *n* 5.d 51′. therefore the Angle N *n o* is 34.d 43′. therefore the Angle N *o n*. is 139.d 56′. which is almost 50.d more than a right Angle.

It is evident therefore by this *Hypothesis*, that at the same time that *e f* touches *f*. E F is arrived at *c*. And by that time *e f k n* is got to *n*, E F K N is got to *d*, and when it touches N, the pulse of the other Ray is got to *o*, and no farther, which is very short of the place it should have arriv'd to, to make the Ray *n p* to cut the *orbicular pulse*. N *o* at right Angles: therefore the Angle N *o p* is an acute Angle, but the quite contrary

trary of this will happen, if 17. and 18. be calculated in ſtead of 16. and 17. both which does moſt exactly agree with the *Phænomena*: For if the Sun, or a Candle (which is better) be placed about E *e*, and the eye about P *p*, the Rays E F *ef*. at 16. and 17. will paint the ſide of the luminous object toward *n p Blue*, and towards N P *Red*. But the quite contrary will happen when E F is 17. and *ef* 18. for then towards N P ſhall be a *Blue*, and towards *np* a *Red*, exactly according to the calculation. And there appears the *Blue* of the Rainbow, where the two *Blue* ſides of the two Images unite, and there the *Red* where the two *Red* ſides unite, that is, where the two Images are juſt diſappearing; which is, when the Rays E F and N P produc'd till they meet, make an Angle of about 41. and an half; the like union is there of the two Images in the Production of the *Secundary Iris*, and the ſame cauſes, as upon calculation may appear; onely with this difference, that it is ſomewhat more faint, by reaſon of the duplicate reflection, which does always weaken the impulſe the oftner it is repeated.

Now, though the ſecond refraction made at N *n* be convenient, that is, do make the Rays glance the more, yet is it not altogether requiſite; for it is plain from the calculation, that the pulſe *d n* is ſufficiently *oblique* to the Rays K N and *k n*, as wel as the pulſe *f c* is *oblique* to the Rays F K & *f k*. And therefore if a piece of very fine Paper be held cloſe againſt N *n* and the eye look on it either through the Ball as from D, or from the other ſide, as from B. there ſhall appear a Rainbow, or colour'd line painted on it with the part toward X appearing *Red*, towards O, *Blue*; the ſame alſo ſhall happen, if the Paper be placed about K *k*, for towards T ſhall appear a *Red*, and towards V a *Blue*, which does exactly agree with this my *Hypotheſis*, as upon the calculation of the progreſs of the pulſe will moſt eaſily appear.

Nor do theſe two obſervations of the colours appearing to the eye about *p* differing from what they appear on the Paper at N contradict each other; but rather confirm and exactly agree with one another, as will be evident to him that examines the reaſons ſet down by the ingenious *Des Cartes* in the 12. *Sect.* of the 8. *Chapter of his Meteors*, where he gives the true reaſon why the colours appear of a quite contrary order to the eye, to what they appear'd on the Paper if the eye be plac'd in ſteed of the Paper: And as in the Priſme, ſo alſo in the Water, Drop, or Globe the *Phænomena* and reaſon are much the ſame.

Having therefore ſhewn that there is ſuch a propriety in the *priſme* and water *Globule* whereby the pulſe is made *oblique* to the progreſſive, and that ſo much the more, by how much greater the refraction is, I ſhall in the next place conſider, how this conduces to the production of colours, and what kind of impreſſion it makes upon the bottom of the eye; and to this end it will be requiſite to examine this *Hypotheſis* a little more particularly.

Firſt therefore, if we conſider the manner of the progreſs of the pulſe, it will ſeem rational to conclude, that that part or end of the pulſe which precedes the other, muſt neceſſarily be ſomwhat more *obtunded*, or *impeded* by

by the resistance of the transparent *medium*, than the other part or end of it which is subsequent, whose way is, as it were, prepared by the other; especially if the adjacent *medium* be not in the same manner enlightned or agitated. And therefore (in the fourth *Figure* of the sixth *Iconism*) the Ray AAAHB will have its side HH more deadned by the resistance of the dark or quiet *medium* PPP, Whence there will be a kind of deadness superinduc'd on the side HHH, which will continually increase from B, and strike deeper and deeper into the Ray by the line BR; Whence all the parts of the triangle, RBHO will be of a dead *Blue* colour, and so much the deeper, by how much the nearer they lie to the line BHH, which is most deaded or impeded, and so much the more *dilute*, by how much the nearer it approaches the line BR. Next on the other side of the Ray AAN, the end A of the pulse AH will be promoted, or made stronger, having its passage already prepar'd as 'twere by the other parts preceding, and so its impression wil be stronger; And because of its *obliquity* to the Ray, there will be propagated a kind of faint motion into QQ the adjacent dark or quiet *medium*, which faint motion will spread further and further into QQ as the Ray is propagated further and further from A, namely, as far as the line MA, whence all the triangle MAN will be ting'd with a *Red*, and that *Red* will be the deeper the nearer it approaches the line MA, and the *paler* or *yellower* the nearer it is the line NA. And if the Ray be continued, so that the lines AN and BR (which are the bounds of the *Red* and *Blue diluted*) do meet and cross each other, there will be beyond that intersection generated all kinds of *Greens*.

Now, these being the proprieties of every single refracted Ray of light, it will be easie enough to consider what must be the result of very many such Rays collateral: As if we suppose infinite such Rays *interjacent* between AKSB and ANOB, which are the terminating: For in this case the Ray AKSB will have its *Red* triangle intire, as lying next to the dark or quiet *medium*, but the other side of it BS will have no *Blue*, because the *medium adjacent* to it SBO, is mov'd or enlightned, and consequently that light does destroy the colour. So likewise will the Ray ANOB lose its *Red*, because the *adjacent medium* is mov'd or enlightned, but the other side of the Ray that is *adjacent* to the dark, namely, AHO will preserve its *Blue* entire, and these Rays must be so far produc'd as till AN and BR cut each other, before there will be any *Green* produc'd. From these Proprieties well consider'd, may be deduc'd the reasons of all the *Phænomena* of the *prisme*, and of the *Globules* or drops of Water which conduce to the production of the Rainbow.

Next for the impression they make on the *Retina*, we will further examine this *Hypothesis*: Suppose therefore ABCDEF, in the fifth *Figure*, to represent the Ball of the eye: on the *Cornea* of which ABC two Rays GACH and KCAI (which are the terminating Rays of a luminous body) falling, are by the refraction thereof collected or *converg'd* into two points at the bottom of the eye. Now, because these terminating Rays, and all the *intermediate* ones which come from any part of the luminous body, are suppos'd by some sufficient refraction before they

enter

enter the eye, to have their pulses made *oblique* to their progression, and consequently each Ray to have potentially *superinduc'd* two proprieties, or colours, *viz.* a *Red* on the one side, and a *Blue* on the other, which notwithstanding are never actually manifest, but when this or that Ray has the one or the other side of it bordering on a dark or unmov'd *medium*, therefore as soon as these Rays are entred into the eye, and so have one side of each of them bordering on a dark part of the humours of the eye, they will each of them actually exhibit some colour; therefore A D G the production G A C H will exhibit a *Blue*, because the side C D is *adjacent* to the dark *medium* C Q D C, but nothing of a *Red*, because its side A D is *adjacent* to the enlightned *medium* A D F A: And all the Rays that from the points of the luminous body are collected on the parts of the *Retina* between D and F shall have their *Blue* so much the more *diluted* by how much the farther these points of collection are distant from D towards F; and the Ray A F C the production of K C A I, will exhibit a *Red*, because the side A F is adjacent to the dark or quiet *medium* of the eye A P F A, but nothing of a *Blue*, because its side C F is *adjacent* to the enlightned *medium* C F D C, and all the Rays from the intermediate parts of the luminous body that are collected between F and D shall have their *Red* so much the more diluted, by how much the farther they are distant from F towards D.

Now, because by the refraction in the *Cornea*, and some other parts of the eye, the sides of each Ray, which before were almost parallel, are made to *converge* and meet in a point at the bottom of the eye, therefore that side of the *pulse* which preceded before these refractions, shall first touch the *Retina*, and the other side last. And therefore according as this or that side, or end of the pulse shall be impeded, accordingly will the *impressions* on the *Retina* be varied; therefore by the Ray G A C H refracted by the *Cornea* to D there shall be on that point a stroke or impression confus'd, whose weakest end, namely, that by the line C D shall precede, and the stronger, namely, that by the line A D shall follow. And by the Ray K C A I refracted to F, there shall be on that part a confus'd stroke or impression, whose strongest part, namely, that by the line C F shal precede, and whose weakest or impeded, namely, that by the line A F shall follow, and all the intermediate points between F and D will receive impression from the *converg'd* Rays so much the more like the impressions on F and D by how much the nearer they approach that or this.

From the consideration of the proprieties of which impressions, we may collect these short definitions of Colours: That *Blue is an impression on the Retina of an oblique and confus'd pulse of light, whose weakest part precedes, and whose strongest follows.* And, that *Red is an impression on the Retina of an oblique and confus'd pulse of light, whose strongest part precedes, and whose weakest follows.*

Which proprieties, as they have been already manifested, in the Prisme and falling drops of Rain, to be the causes of the colours there generated, may be easily found to be the efficients also of the colours appearing in thin *laminated* transparent bodies; for the explication of which, all this has been premised.

And

And that this is so, a little closer examination of the *Phænomena* and the *Figure* of the body, by this *Hypothesis*, will make evident.

For first (as we have already observed) the *laminated* body must be of a determinate thickness, that is, it must not be thinner then such a determinate quantity; for I have always observ'd, that neer the edges of those which are exceeding thin, the colours disappear, and the part grows white; nor must it be thicker then another determinate quantity; for I have likewise observ'd, that beyond such a thickness, no colours appear'd, but the Plate looked white, between which two determinate thicknesses were all the colour'd Rings; of which in some substances I have found ten or twelve, in others not half so many, which I suppose depends much upon the transparency of the *laminated* body. Thus though the consecutions are the same in the scumm or the skin on the top of metals; yet in those consecutions the same colour is not so often repeated as in the consecutions in thin Glass, or in Sope-water, or any other more transparent and glutinous liquor; for in these I have observ'd, *Red*, *Yellow*, *Green*, *Blue*, *Purple*; *Red*, *Yellow*, *Green*, *Blue*, *Purple*; *Red*, *Yellow*, *Green*, *Blue*, *Purple*; *Red*, *Yellow*, &c. to succeed each other, ten or twelve times, but in the other more *opacous* bodies the consecutions will not be half so many.

And therefore secondly, the *laminated* body must be transparent, and this I argue from this, that I have not been able to produce any colour at all with an *opacous* body, though never so thin. And this I have often try'd, by pressing a small *Globule* of *Mercury* between two smooth Plates of Glass, whereby I have reduc'd that body to a much greater thinness then was requisite to exhibit the colours with a transparent body.

Thirdly, there must be a considerable reflecting body adjacent to the under or further side of the *lamina* or *plate*: for this I always found, that the greater that reflection was, the more vivid were the appearing colours.

From which Observations, it is most evident, that the reflection from the under or further side of the body is the principal cause of the production of these colours; which, that it is so, and how it conduces to that effect, I shall further explain in the following Figure, which is here described of a very great thickness, as if it had been view'd through the *Microscope*; and 'tis indeed much thicker than any *Microscope* (I have yet us'd) has been able to shew me those colour'd plates of Glass, or *Muscovie-glass*, which I have not without much trouble view'd with it; for though I have endeavoured to magnifie them as much as the Glasses were capable of, yet are they so exceeding thin, that I have not hitherto been able positively to determine their thickness. This Figure therefore I here represent, is wholy *Hypothetical*.

Let ABCDHFE in the sixth Figure be a *frustum* of *Muscovy-glass*, thinner toward the end AE, and thicker towards DF. Let us first suppose the Ray *a g h b* coming from the Sun, or some remote luminous object to fall *obliquely* on the thinner plate BAE, part therefore is reflected back, by *c g h d*, the first *Superficies*; whereby the perpendicular

pulse *a b* is after reflection propagated by *c d*, *c d*, equally remote from each other with *a b*, *a b*, so that *ag* + *gc*, or *bh* + *hd* are either of them equal to *aa*, as is also *cc*, but the body BAE being transparent, a part of the light of this Ray is refracted in the surface AB, and propagated by *gikh* to the surface EF, whence it is reflected and refracted again by the surface AB. So that after two refractions and one reflection, there is propagated a kind of fainter Ray *emnf*, whose pulse is not only weaker by reason of the two refractions in the surface AB, but by reason of the time spent in passing and repassing between the two surfaces AB and EF, *ef* which is this fainter or weaker pulse comes behind the pulse *cd*; so that hereby (the surfaces AB, and EF being so neer together, that the eye cannot *discriminate* them from one) this confus'd or *duplicated* pulse, whose strongest part precedes, and whose weakest follows, does produce on the *Retina* (or the *optick nerve* that covers the bottom of the eye) the sensation of a *Yellow*.

And secondly, this *Yellow* will appear so much the deeper, by how much the further back towards the middle between *cd* and *cd* the spurious pulse *ef* is remov'd, as in 2 where the surface BC being further remov'd from EF, the weaker pulse *ef* will be nearer to the middle, and will make an impression on the eye of a *Red*.

But thirdly, if the two reflecting surfaces be yet further remov'd asunder (as in 3 CD and EF are) then will the weaker pulse be so farr behind, that it will be more then half the distance between *cd* and *cd*. And in this case it will rather seem to precede the following stronger pulse, then to follow the preceding one, and consequently a *Blue* will be generated. And when the weaker pulse is just in the middle beween two strong ones, then is a deep and lovely *Purple* generated; but when the weaker pulse *ef* is very neer to *cd*, then is there generated a *Green*, which will be *bluer*, or *yellower*, according as the *approximate* weak pulse does precede or follow the stronger.

Now fourthly, if the thicker Plate chance to be cleft into two thinner Plates, as CDFE is divided into two Plates by the surface GH then from the composition arising from the three reflections in the surfaces CD, GH, and EF, there will be generated several compounded or mixt colours, which will be very differing, according as the proportion between the thicknesses of those two divided Plates CDHG, and GHFE are varied.

And fifthly, if these surfaces CD and FE are further remov'd asunder, the weaker pulse will yet lagg behind much further, and not onely be *coincident* with the second, *cd*, but lagg behind that also, and that so much the more, by how much the thicker the Plate be; so that by degrees it will be *coincident* with the third *cd* backward also, and by degrees, as the Plate grows thicker with a fourth, and so onward to a fifth, sixth, seventh, or eighth; so that if there be a thin transparent body, that from the greatest thinness requisite to produce colours, does, in the manner of a Wedge, by degrees grow to the greatest thickness that a Plate can be of, to exhibit a colour by the reflection of Light from such a body, there

shall

shall be generated several consecutions of colours, whose order from the thin end towards the thick, shall be *Yellow*, *Red*, *Purple*, *Blue*, *Green*; *Yellow*, *Red*, *Purple*, *Blue*, *Green*; *Yellow*, *Red*, *Purple*, *Blue*, *Green*; *Yellow*, &c. and these so often repeated, as the weaker pulse does lose paces with its *Primary*, or first pulse, and is *coincident* with a second, third, fourth, fifth, sixth, *&c.* pulse behind the first. And this, as it is *coincident*, or follows from the first *Hypothesis* I took of colours, so upon exeriment have I found it in multitudes of instances that seem to prove it. One thing which seems of the greatest concern in this *Hypothesis*, is to determine the greatest or least thickness requisite for these effects, which, though I have not been wanting in attempting, yet so exceeding thin are these coloured Plates, and so imperfect our *Microscope*, that I have not been hitherto successfull, though if my endeavours shall answer my expectations, I shall hope to gratifie the curious Reader with some things more remov'd beyond our reach hitherto.

Thus have I, with as much brevity as I was able, endeavoured to explicate (*Hypothetically* at least) the causes of the *Phænomena* I formerly recited, on the consideration of which I have been the more particular.

First, because I think these I have newly given are capable of explicating all the *Phænomena* of colours, not onely of those appearing in the *Prisme*, Water-drop, or Rainbow, and in *laminated* or plated bodies, but of all that are in the world, whether they be fluid or solid bodies, whether in thick or thin, whether transparent, or seemingly opacous, as I shall in the next Observation further endeavour to shew. And secondly, because this being one of the two ornaments of all bodies discoverable by the sight, whether looked on with, or without a *Microscope*, it seem'd to deserve (somewhere in this Tract, which contains a description of the Figure and Colour of some minute bodies) to be somewhat the more intimately enquir'd into.

Observ. X. *Of* Metalline, *and other real Colours.*

HAving in the former Discourse, from the Fundamental cause of Colour, made it probable, that there are but two Colours, and shewn, that the *Phantasm* of Colour is caus'd by the sensation of the *oblique* or uneven pulse of Light which is capable of no more varieties than two that arise from the two sides of the *oblique* pulse, though each of those be capable of infinite gradations or degrees (each of them beginning from *White*, and ending the one in the deepest *Scarlet* or *Yellow*, the other in the deepest *Blue*) I shall in this *Section* set down some Observations which I have made of other colours, such as *Metalline* powders tinging or colour'd bodies and several kinds of tinctures or ting'd liquors, all which, together with those I treated of in the former Observation, will, I suppose, comprise the several subjects in which colour is observ'd to be inherent, and the several manners by which it *inheres*, or is apparent

in them. And here I shall endeavour to shew by what composition all kind of compound colours are made, and how there is no colour in the world but may be made from the various degrees of these two colours, together with the intermixtures of *Black* and *White*.

And this being so, as I shall anon shew, it seems an evident argument to me, that all colours whatsoever, whether in fluid or solid, whether in very transparent or seemingly *opacous*, have the same efficient cause, to wit, some kind of *refraction* whereby the Rays that proceed from such bodies, have their pulse *obliquated* or confus'd in the manner I explicated in the former *Section*; that is, a *Red* is caus'd by a duplicated or confus'd pulse, whose strongest pulse precedes, and a weaker follows: and a *Blue* is caus'd by a confus'd pulse, where the weaker pulse precedes, and the stronger follows. And according as these are, more or less, or variously mixt and compounded, so are the *sensations*, and consequently the *phantasms* of colours *diversified*.

To proceed therefore; I suppose, that all transparent colour'd bodies, whether fluid or solid, do consist at least of two parts, or two kinds of substances, the one of a substance of a somewhat differing *refraction* from the other. That one of these substances which may be call'd the *tinging* substance, does consist of distinct parts, or particles of a determinate bigness which are *disseminated*, or dispers'd all over the other: That these particles, if the body be equally and uniformly colour'd, are evenly rang'd and dispers'd over the other contiguous body; That where the body is deepest ting'd, there these particles are rang'd thickest; and where 'tis but faintly ting'd, they are rang'd much thinner, but uniformly. That by the mixture of another body that unites with either of these, which has a differing refraction from either of the other, quite differing effects will be produc'd, that is, the *consecutions* of the confus'd pulses will be much of another kind, and consequently produce other *sensations* and *phantasms* of colours, and from a *Red* may turn to a *Blue*, or from a *Blue* to a *Red*, &c.

Now, that this may be the better understood, I shall endeavour to explain my meaning a little more sensible by a *Scheme*: Suppose we therefore in the seventh *Figure* of the sixth *Scheme*, that A B C D represents a Vessel holding a ting'd liquor, let I I I I I, &c. be the clear liquor, and let the tinging body that is mixt with it be E E, &c. F F, &c. G G, &c. H H, &c. whose particles (whether round, or some other determinate Figure is little to our purpose) are first of a determinate and equal bulk. Next, they are rang'd into the form of *Quincunx*, or *Equilaterotriangular* order, which that probably they are so, and why they are so, I shall elsewhere endeavour to shew. Thirdly, they are of such a nature, as does either more easily or more difficultly transmit the Rays of light then the liquor; if more easily, a *Blue* is generated, and if more difficultly, a *Red* or *Scarlet*.

And first, let us suppose the tinging particles to be of a substance that does more *impede* the Rays of light, we shall find that the pulse or wave of light mov'd from A D to B C, will proceed on, through the containing *medium* by the pulses or waves K K, L L, M M, N N, O O; but because

because several of these Rays that go to the constitution of these pulses will be slugged or stopped by the tinging particles E,F,G,H; therefore there shall be a *secundary* and weak pulse that shall follow the Ray, namely P P which will be the weaker: first, because it has suffer'd many refractions in the impeding body; next, for that the Rays will be a little dispers'd or confus'd by reason of the refraction in each of the particles, whether *round* or *angular*; and this will be more evident, if we a little more closely examine any one particular tinging *Globule*.

Suppose we therefore A B in the eighth *Figure* of the sixth *Scheme*, to represent a tinging *Globule* or particle which has a greater refraction than the liquor in which it is contain'd: Let C D be a part of the pulse of light which is *propagated* through the containing *medium*; this pulse will be a little stopt or impeded by the *Globule*, and so by that time the pulse is past to E F that part of it which has been impeded by passing through the *Globule*, will get but to L M, and so that pulse which has been *propagated* through the *Globule*, to wit, L M, N O, P Q, will always come behind the pulses E F, G H, I K, *&c.*

Next, by reason of the greater impediment in A B, and its *Globular* Figure, the Rays that pass through it will be dispers'd, and very much scatter'd. Whence C A and D B which before went *direct* and *parallel*, will after the refraction in A B, *diverge* and spread by A P, and B Q; so that as the Rays do meet with more and more of these tinging particles in their way, by so much the more will the pulse of light further lagg behind the clearer pulse, or that which has fewer refractions, and thence the deeper will the colour be, and the fainter the light that is trajected through it; for not onely many Rays are reflected from the surfaces of A B, but those Rays that get through it are very much disordered.

By this *Hypothesis* there is no one experiment of colour that I have yet met with, but may be, I conceive, very rationably solv'd, and perhaps, had I time to examine several particulars requisite to the demonstration of it, I might prove it more than probable, for all the experiments about the changes and mixings of colours related in the Treatise of Colours, published by the *Incomparable* Mr. *Boyle*, and multitudes of others which I have observ'd, do so easily and naturally flow from those principles, that I am very apt to think it probable, that they own their production to no other *secundary* cause: As to instance in two or three experiments. In the twentieth Experiment, this *Noble Authour* has shewn that the deep *bluish purple-colour* of *Violets*, may be turn'd into a *Green*, by *Alcalizate Salts*, and to a *Red* by *acid*; that is, a *Purple* consists of two colours, a deep *Red*, and a deep *Blue*; when the *Blue* is diluted, or altered, or destroy'd by *acid Salts*, the *Red* becomes predominant; but when the *Red* is diluted by *Alcalizate*, and the *Blue* heightned, there is generated a *Green*; for of a *Red* diluted, is made a *Yellow*, and *Yellow* and *Blue* make a *Green*.

Now, because the *spurious* pulses which cause a *Red* and a *Blue*, do the one follow the clear pulse, and the other precede it, it usually follows, that those *Saline* refracting bodies which do *dilute* the colour of the one, do deepen that of the other. And this will be made manifest by almost

most all kinds of *Purples*, and many sorts of *Greens*, both these colours consisting of mixt colours; for if we suppose A and A in the ninth Figure, to represent two pulses of clear light, which follow each other at a convenient distance, A A, each of which has a *spurious* pulse preceding it, as B B, which makes a *Blue*, and another following it, as C C, which makes a *Red*, the one caus'd by tinging particles that have a greater refraction, the other by others that have a less refracting quality then the liquor or *Menstruum* in which these are dissolv'd, whatsoever liquor does so alter the refraction of the one, without altering that of the other part of the ting'd liquor, must needs very much alter the colour of the liquor; for if the refraction of the *dissolvent* be increas'd, and the refraction of the tinging particles not altered, then will the preceding *spurious* pulse be shortned or stopt, and not out-run the clear pulse so much; so that B B will become E E, and the *Blue* be *diluted*, whereas the other *spurious* pulse which follows will be made to lagg much more, and be further behind A A than before, and C C will become *f f*, and so the *Yellow* or *Red* will be heightned.

A *Saline* liquor therefore, mixt with another ting'd liquor, may alter the colour of it several ways, either by altering the refraction of the liquor in which the colour swims: or secondly by varying the refraction of the coloured particles, by uniting more intimately either with some particular *corpuscles* of the tinging body, or with all of them, according as it has a *congruity* to some more especially, or to all alike: or thirdly, by uniting and interweaving it self with some other body that is already joyn'd with the tinging particles, with which substance it may have a *congruity*, though it have very little with the particles themselves: or fourthly, it may alter the colour of a ting'd liquor by dis-joyning certain particles which were before united with the tinging particles, which though they were somewhat *congruous* to these particles, have yet a greater *congruity* with the newly *infus'd Saline menstruum*. It may likewise alter the colour by further dissolving the tinging substance into smaller and smaller *particles*, and so *diluting* the colour; or by uniting several *particles* together as in precipitations, and so deepning it, and some such other ways, which many experiments and comparisons of differing trials together, might easily inform one of.

From these Principles applied, may be made out all the varieties of colours observable, either in liquors, or any other ting'd bodies, with great ease, and I hope intelligible enough, there being nothing in the *notion* of colour, or in the suppos'd production, but is very conceivable, and may be possible.

The greatest difficulty that I find against this *Hypothesis*, is, that there seem to be more distinct colours then two, that is, then Yellow and Blue. This Objection is grounded on this reason, that there are several Reds, which *diluted*, make not a Saffron or pale Yellow, and therefore Red, or Scarlet seems to be a third colour distinct from a deep degree of Yellow.

To which I answer, that Saffron affords us a deep Scarlet tincture, which may be *diluted* into as pale a Yellow as any, either by making a weak solution

lution of the Saffron, by infusing a small parcel of it into a great quantity of liquor, as in spirit of Wine, or else by looking through a very thin quantity of the tincture, and which may be heightn'd into the loveliest Scarlet, by looking through a very thick body of this tincture, or through a thinner parcel of it, which is highly *impregnated* with the tinging body, by having had a greater quantity of the Saffron dissolv'd in a smaller parcel of the liquor.

Now, though there may be some particles of other tinging bodies that give a lovely Scarlet also, which though *diluted* never so much with liquor, or looked on through never so thin a parcel of ting'd liquor, will not yet afford a pale Yellow, but onely a kind of faint Red; yet this is no argument but that those ting'd particles may have in them the faintest degree of Yellow, though we may be unable to make them exhibit it; For that power of being *diluted* depending upon the divisibility of the ting'd body, if I am unable to make the tinging particles so thin as to exhibit that colour, it does not therefore follow, that the thing is impossible to be done; now, the tinging particles of some bodies are of such a nature, that unless there be found some way of comminuting them into less bulks then the liquor does dissolve them into, all the Rays that pass through them must necessarily receive a tincture so deep, as their appropriate refractions and bulks compar'd with the proprieties of the dissolving liquor must necessarily dispose them to empress, which may perhaps be a pretty deep Yellow, or pale Red.

And that this is not *gratis dictum*, I shall add one instance of this kind, wherein the thing is most manifest.

If you take Blue *Smalt*, you shall find, that to afford the deepest Blue, which *cæteris paribus* has the greatest particles or sands; and if you further divide, or grind those particles on a Grindstone, or *porphyry* stone, you may by *comminuting* the sands of it, *dilute* the Blue into as pale a one as you please, which you cannot do by laying the colour thin; for wheresoever any single particle is, it exhibits as deep a Blue as the whole mass. Now, there are other Blues, which though never so much ground, will not be *diluted* by grinding, because consisting of very small particles, very deeply ting'd, they cannot by grinding be actually separated into smaller particles then the operation of the fire, or some other dissolving *menstruum*, has reduc'd them to already.

Thus all kind of *Metalline* colours, whether *precipitated*, *sublim'd*, *calcin'd*, or otherwise prepar'd, are hardly chang'd by grinding, as *ultra marine* is not more *diluted*; nor is *Vermilion* or *Red-lead* made of a more faint colour by grinding; for the smallest particles of these which I have view'd with my greatest Magnifying-Glass, if they be well enlightned, appear very deeply ting'd with their peculiar colours; nor, though I have magnified and enlightned the particles exceedingly, could I in many of them, perceive them to be transparent, or to be whole particles, but the smallest specks that I could find among well ground *Vermilion* and *Red-lead*, seem'd to be a Red mass, compounded of a multitude of less and less motes, which sticking together, compos'd a bulk, not one thousand thousandth part of the smallest visible sand or mote.

And

And this I find generally in most *Metalline* colours, that though they consist of parts so exceedingly small, yet are they very deeply ting'd, they being so ponderous, and having such a multitude of terrestrial particles throng'd into a little room; so that 'tis difficult to find any particle transparent or resembling a pretious stone, though not impossible; for I have observ'd divers such shining and resplendent colours intermixt with the particles of *Cinnaber*, both natural and artificial, before it hath been ground and broken or flaw'd into *Vermilion*: As I have also in *Orpiment*, *Red-lead*, and *Bise*, which makes me suppose, that those *metalline* colours are by grinding, not onely broken and separated actually into smaller pieces, but that they are also flaw'd and bruised, whence they, for the most part, become *opacous*, like flaw'd Crystal or Glass, *&c.* But for *Smalts* and *verditures*, I have been able with a *Microscope* to perceive their particles very many of them transparent.

Now, that the others also may be transparent, though they do not appear so to the *Microscope*, may be made probable by this Experiment: that if you take *ammel* that is almost *opacous*, and grind it very well on a *Porphyry*, or *Serpentine*, the small particles will by reason of their flaws, appear perfectly *opacous*; and that 'tis the flaws that produce this *opacousness*, may be argued from this, that particles of the same *Ammel* much thicker if unflaw'd will appear somewhat transparent even to the eye; and from this also, that the most transparent and clear Crystal, if heated in the fire, and then suddenly quenched, so that it be all over flaw'd, will appear *opacous* and white.

And that the particles of *Metalline* colours are transparent, may be argued yet further from this, that the Crystals, or *Vitriols* of all Metals, are transparent, which since they consist of *metalline* as well as *saline* particles, those *metalline* ones must be transparent, which is yet further confirm'd from this, that they have for the most part, *appropriate* colours; so the *vitriol* of Gold is Yellow; of Copper, Blue, and sometimes Green; of Iron, green; of Tinn and Lead, a pale White; of Silver, a pale Blue, *&c.*

And next, the *Solution* of all Metals into *menstruums* are much the same with the *Vitriols*, or Crystals. It seems therefore very probable, that those colours which are made by the *precipitation* of those particles out of the *menstruums* by transparent *precipitating* liquors should be transparent also. Thus Gold *precipitates* with *oyl of Tartar*, or *spirit of Urine* into a brown Yellow. Copper with spirit of *Urine* into a Mucous blue, which retains its transparency. A solution of sublimate (as the same Illustrious Authour I lately mention'd shews in his 40. Experiment) *precipitates* with oyl of *Tartar per deliquium*, into an Orange colour'd *precipitate*; nor is it less probable, that the *calcination* of those *Vitriols* by the fire, should have their particles transparent: Thus *Saccarum Saturni*, or the *Vitriol of Lead* by *calcination* becomes a deep Orange-colour'd *minium*, which is a kind of *precipitation* by some Salt which proceeds from the fire; common *Vitriol calcin'd*, yields a deep Brown Red, *&c.*

A third Argument, that the particles of Metals are transparent, is, that being *calcin'd*, and melted with Glass, they tinge the Glass with transparent

rent colours. Thus the *Calx* of Silver tinges the Glass on which it is anneal'd with a lovely Yellow, or Gold colour, *&c.*

And that the parts of Metals are transparent, may be farther argued from the transparency of Leaf-gold, which held against the light, both to the naked eye, and the *Microscope*, exhibits a deep Green. And though I have never seen the other Metals *laminated* so thin, that I was able to perceive them transparent, yet, for Copper and Brass, if we had the same conveniency for *laminating* them, as we have for Gold, we might, perhaps, through such plates or leaves, find very differing degrees of Blue, or Green; for it seems very probable, that those Rays that rebound from them ting'd, with a deep Yellow, or pale Red, as from Copper, or with a pale Yellow, as from Brass, have past through them; for I cannot conceive how by reflection alone those Rays can receive a tincture, taking any *Hypothesis* extant.

So that we see there may a sufficient reason be drawn from these instances, why those colours which we are unable to *dilute* to the palest Yellow, or Blue, or Green, are not therefore to be concluded not to be a deeper degree of them; for supposing we had a great company of small *Globular* essence Bottles, or round Glass bubbles, about the bigness of a Walnut, fill'd each of them with a very deep mixture of Saffron, and that every one of them did appear of a deep Scarlet colour, and all of them together did *exhibit* at a distance, a deep dy'd Scarlet body. It does not follow, because after we have come nearer to this *congeries*, or mass, and divided it into its parts, and examining each of its parts severally or apart, we find them to have much the same colour with the whole mass; it does not, I say, therefore follow, that if we could break those *Globules* smaller, or any other ways come to see a smaller or thinner parcel of the ting'd liquor that fill'd those bubbles, that that ting'd liquor must always appear Red, or of a Scarlet hue, since if Experiment be made, the quite contrary will ensue; for it is capable of being *diluted* into the palest Yellow.

Now, that I might avoid all the Objections of this kind, by exhibiting an Experiment that might by ocular proof convince those whom other reasons would not prevail with, I provided me a *Prismatical Glass*, made hollow, just in the form of a Wedge, such as is represented in the tenth *Figure* of the sixth *Scheme*. The two *parallelogram* sides ABCD, ABEF, which met at a point, were made of the clearest Looking-glass plates well ground and polish'd that I could get; these were joyn'd with hard cement to the *triangular* sides, BCE, ADF, which were of Wood; the *Parallelogram* base BCEF, likewise was of Wood joyn'd on to the rest with hard cement, and the whole *Prismatical* Box was exactly stopt every where, but onely a little hole near the base was left, whereby the Vessel could be fill'd with any liquor, or emptied again at pleasure.

One of these Boxes (for I had two of them) I fill'd with a pretty deep tincture of *Aloes*, drawn onely with fair Water, and then stopt the hole with a piece of Wax, then, by holding this Wedge against the Light, and looking through it, it was obvious enough to see the tincture of the liquor near the edge of the Wedge where it was but very thin, to be a pale but

well colour'd Yellow, and further and further from the edge, as the liquor grew thicker and thicker, this tincture appear'd deeper and deeper; so that near the blunt end, which was seven Inches from the edge and three Inches and an half thick; it was of a deep and well colour'd Red. Now, the clearer and purer this tincture be, the more lovely will the deep Scarlet be, and the fouler the tincture be, the more dirty will the Red appear; so that some dirty tinctures have afforded their deepest Red much of the colour of burnt Oker or *Spanish* brown; others as lovely a colour as *Vermilion*, and some much brighter; but several others, according as the tinctures were worse or more foul, exhibited various kinds of Reds, of very differing degrees.

The other of these Wedges, I fill'd with a most lovely tincture of Copper, drawn from the filings of it, with spirit of *Urine*, and this Wedge held as the former against the Light, afforded all manner of Blues, from the faintest to the deepest, so that I was in good hope by these two, to have produc'd all the varieties of colours imaginable; for I thought by this means to have been able by placing the two *Parallelogram* sides together, and the edges contrary ways, to have so mov'd them to and fro one by another, as by looking through them in several places, and through several thicknesses, I should have compounded, and consequently have seen all those colours, which by other like compositions of colours would have ensued.

But insteed of meeting with what I look'd for, I met with somewhat more admirable; and that was, that I found my self utterly unable to see through them when placed both together, though they were transparent enough when asunder; and though I could see through twice the thickness, when both of them were fill'd with the same colour'd liquors, whether both with the Yellow, or both with the Blue, yet when one was fill'd with the Yellow, the other with the Blue, and both looked through, they both appear'd dark, onely when the parts near the tops were look'd through, they exhibited Greens, and those of very great variety, as I expected, but the Purples and other colours, I could not by any means make, whether I endeavour'd to look through them both against the Sun, or whether I plac'd them against the hole of a darkned room.

But notwithstanding this mis-ghessing, I proceeded on with my trial in a dark room, and having two holes near one another, I was able, by placing my Wedges against them, to mix the ting'd Rays that past through them, and fell on a sheet of white Paper held at a convenient distance from them as I pleas'd; so that I could make the Paper appear of what colour I would, by varying the thicknesses of the Wedges, and consequently the tincture of the Rays that past through the two holes, and sometimes also by varying the Paper, that is, insteed of a white Paper, holding a gray, or a black piece of Paper.

Whence I experimentally found what I had before imagin'd, that all the varieties of colours imaginable are produc'd from several degrees of these two colours, namely, Yellow and Blue, or the mixture of them with light and darkness, that is, white and black. And all those almost infinite varieties which Limners and Painters are able to make by com-

pounding

pounding those several colours they lay on their Shels or *Palads*, are nothing else, but some *compositum*, made up of some one or more, or all of these four.

Now, whereas it may here again be objected, that neither can the Reds be made out of the Yellows, added together, or laid on in greater or less quantity, nor can the Yellows be made out of the Reds though laid never so thin; and as for the addition of White or Black, they do nothing but either whiten or darken the colours to which they are added, and not at all make them of any other kind of colour: as for instance, *Vermilion*, by being temper'd with White Lead, does not at all grow more Yellow, but onely there is made a whiter kind of Red. Nor does Yellow *Oker*, though laid never so thick, produce the colour of *Vermilion*, nor though it be temper'd with Black, does it at all make a Red; nay, though it be temper'd with White, it will not afford a fainter kind of Yellow, such as *masticut*, but onely a whiten'd Yellow; nor will the Blues be *diluted* or deepned after the manner I speak of, as *Indico* will never afford so fine a Blue as *Ultramarine* or *Bise*; nor will it, temper'd with *Vermilion*, ever afford a Green, though each of them be never so much temper'd with white.

To which I answer, that there is a great difference between *diluting* a colour and whitening of it; for *diluting* a colour, is to make the colour'd parts more thin, so that the ting'd light, which is made by trajecting those ting'd bodies, does not receive so deep a tincture; but whitening a colour is onely an intermixing of many clear reflections of light among the same ting'd parts; deepning also, and darkning or blacking a colour, are very different; for deepning a colour, is to make the light pass through a greater quantity of the same tinging body; and darkning or blacking a colour, is onely interposing a multitude of dark or black spots among the same ting'd parts, or placing the colour in a more faint light.

First therefore, as to the former of these operations, that is, diluting and deepning, most of the colours us'd by the Limners and Painters are incapable of, to wit, *Vermilion* and *Red-lead*, and *Oker*, because the ting'd parts are so exceeding small, that the most curious Grindstones we have, are not able to separate them into parts actually divided so small as the ting'd particles are; for looking on the most curiously ground *Vermilion*, and *Oker*, and *Red-lead*, I could perceive that even those small *corpuscles* of the bodies they left were compounded of many pieces, that is, they seem'd to be small pieces compounded of a multitude of lesser ting'd parts: each piece seeming almost like a piece of Red Glass, or ting'd Crystal all flaw'd; so that unless the Grindstone could actually divide them into smaller pieces then those flaw'd particles were, which compounded that ting'd mote I could see with my *Microscope*, it would be impossible to *dilute* the colour by grinding, which, because the finest we have will not reach to do in *Vermilion* or *Oker*, therefore they cannot at all, or very hardly be *diluted*.

Other colours indeed, whose ting'd particles are such as may be made smaller, by grinding their colour, may be *diluted*. Thus several of the

Blues may be *diluted*, as *Smalt* and *Bise*; and *Masticut*, which is Yellow, may be made more faint: And even *Vermilion* it self may, by too much grinding, be brought to the colour of *Red-lead*, which is but an Orange colour, which is confest by all to be very much upon the Yellow. Now, though perhaps somewhat of this *diluting* of *Vermilion* by overmuch grinding may be attributed to the Grindstone, or muller, for that some of their parts may be worn off and mixt with the colour, yet there seems not very much, for I have done it on a Serpentine-stone with a muller made of a Pebble, and yet observ'd the same effect follow.

And secondly, as to the other of these operations on colours, that is, the deepning of them, Limners and Painters colours are for the most part also uncapable. For they being for the most part *opacous*; and that *opacousness*, as I said before, proceeding from the particles, being very much flaw'd, unless we were able to joyn and re-unite those flaw'd particles again into one piece, we shall not be able to deepen the colour, which since we are unable to do with most of the colours which are by Painters accounted *opacous*, we are therefore unable to deepen them by adding more of the same kind.

But because all those *opacous* colours have two kinds of beams or Rays reflected from them, that is, Rays unting'd, which are onely reflected from the outward surface, without at all penetrating of the body, and ting'd Rays which are reflected from the inward surfaces or flaws after they have suffer'd a two-fold refraction; and because that transparent liquors mixt with such *corpuscles*, do, for the most part, take off the former kind of reflection; therefore these colours mixt with Water or Oyl, appear much deeper than when dry, for most part of that white reflection from the outward surface is remov'd. Nay, some of these colours are very much deepned by the mixture with some transparent liquor, and that because they may perhaps get between those two flaws, and so consequently joyn two or more of those flaw'd pieces together; but this happens but in a very few.

Now, to shew that all this is not *gratis dictum*, I shall set down some Experiments which do manifest these things to be probable and likely, which I have here deliver'd.

For, first, if you take any ting'd liquor whatsoever, especially if it be pretty deeply ting'd, and by any means work it into a froth, the *congeries* of that froth shall seem an *opacous* body, and appear of the same colour, but much whiter than that of the liquor out of which it is made. For the abundance of reflections of the Rays against those surfaces of the bubbles of which the froth consists, does so often rebound the Rays backwards, that little or no light can pass through, and consequently the froth appears *opacous*.

Again, if to any of these ting'd liquors that will endure the boiling there be added a small quantity of fine flower (the parts of which through the *Microscope* are plainly enough to be perceiv'd to consist of transparent *corpuscles*) and suffer'd to boyl till it thicken the liquor, the mass of the liquor will appear *opacous*, and ting'd with the same colour, but very much whiten'd.

Thus

Thus, if you take a piece of transparent Glass that is well colour'd, and by heating it, and then quenching it in Water, you flaw it all over, it will become *opacous*, and will exhibit the same colour with which the piece is ting'd, but fainter and whiter.

Or, if you take a Pipe of this transparent Glass, and in the flame of a Lamp melt it, and then blow it into very thin bubbles, then break those bubbles, and collect a good parcel of those *laminæ* together in a Paper, you shall find that a small thickness of those Plates will constitute an *opacous* body, and that you may see through the mass of Glass before it be thus *laminated*, above four times the thickness: And besides, they will now afford a colour by reflection as other *opacous* (as they are call'd) colours will, but much fainter and whiter than that of the Lump or Pipe out of which they were made.

Thus also, if you take *Putty*, and melt it with any transparent colour'd Glass, it will make it become an *opacous* colour'd lump, and to yield a paler and whiter colour than the lump by reflection.

The same thing may be done by a preparation of *Antimony*, as has been shewn by the Learned *Physician*, Dr. *C. M.* in his Excellent Observations and Notes on *Nery's Art of Glass*; and by this means all transparent colours become *opacous*, or *ammels*. And though by being ground they lose very much of their colour, growing much whiter by reason of the multitude of single reflections from their outward surface, as I shew'd afore, yet the fire that in the nealing or melting re-unites them, and so renews those *spurious* reflections, removes also those whitenings of the colour that proceed from them.

As for the other colours which Painters use, which are transparent, and us'd to varnish over all other paintintings, 'tis well enough known that the laying on of them thinner or thicker, does very much *dilute* or deepen their colour.

Painters Colours therefore consisting most of them of solid particles, so small that they cannot be either re-united into thicker particles by any Art yet known, and consequently cannot be deepned; or divided into particles so small as the flaw'd particles that exhibit that colour, much less into smaller, and consequently cannot be *diluted*; It is necessary that they which are to imitate all kinds of colours, should have as many degrees of each colour as can be procur'd.

And to this purpose, both Limners and Painters have a very great variety both of Yellows and Blues, besides several other colour'd bodies that exhibit very compounded colours, such as Greens and Purples; and others that are compounded of several degrees of Yellow, or several degrees of Blue, sometimes unmixt, and sometimes compounded with several other colour'd bodies.

The Yellows, from the palest to the deepest Red or Scarlet, which has no intermixture of Blue, are *pale and deep Masticut*, *Orpament*, *English Oker*, *brown Oker*, *Red Lead*, *and Vermilion*, *burnt English Oker*, *and burnt brown Oker*, which last have a mixture of dark or dirty parts with them, *&c.*

Their

Their Blues are several kinds of *Smalts*, and *Verditures*, and *Bise*, and *Ultramarine*, and *Indico*, which last has many dirty or dark parts intermixt with it.

Their compounded colour'd bodies, as *Pink*, and *Verdigrese*, which are Greens, the one a *Popingay*, the other a *Sea-green*; then *Lac*, which is a very lovely *Purple*.

To which may be added their Black and White, which they also usually call Colours, of each of which they have several kinds, such as *Bone Black*, made of *Ivory* burnt in a close Vessel, and *Blue Black*, made of the small coal of *Willow*, or some other Wood; and *Cullens earth*, which is a kind of brown Black, *&c.* Their usual Whites are either artificial or natural *White Lead*, the last of which is the best they yet have, and with the mixing and tempering these colours together, are they able to make an imitation of any colour whatsoever: Their Reds or deep Yellows, they can *dilute* by mixing pale Yellows with them, and deepen their pale by mixing deeper with them; for it is not with *Opacous* colours as it is with transparent, where by adding more Yellow to yellow, it is deepned, but in *opacous diluted*. They can whiten any colour by mixing White with it, and darken any colour by mixing Black, or some dark and dirty colour. And in a word, most of the colours, or colour'd bodies they use in Limning and Painting, are such, as though mixt with any other of their colours, they preserve their own hue, and by being in such very smal parts dispers'd through the other colour'd bodies, they both, or altogether represent to the eye a *compositum* of all; the eye being unable, by reason of their smalness, to distinguish the peculiarly colour'd particles, but receives them as one intire *compositum*: whereas in many of these, the *Microscope* very easily distinguishes each of the compounding colours distinct, and exhibiting its own colour.

Thus have I by gently mixing *Vermilion* and *Bise* dry, produc'd a very fine Purple, or mixt colour, but looking on it with the *Microscope*, I could easily distinguish both the Red and the Blue particles, which did not at all produce the *Phantasm* of Purple.

To summ up all therefore in a word, I have not yet found any solid colour'd body, that I have yet examin'd, perfectly *opacous*; but those that are least transparent are *Metalline* and *Mineral* bodies, whose particles generally, seeming either to be very small, or very much flaw'd, appear for the most part *opacous*, though there are very few of them that I have look'd on with a *Microscope*, that have not very plainly or circumstantially manifested themselves transparent.

And indeed, there seem to be so few bodies in the world that are *in minimis* opacous, that I think one may make it a rational *Query*, Whether there be any body absolutely thus *opacous*? For I doubt not at all (and I have taken notice of very many circumstances that make me of this mind) that could we very much improve the *Microscope*, we might be able to see all those bodies very plainly transparent, which we now are fain onely to ghess at by circumstances. Nay, the Object Glasses we yet make use of are such, that they make many transparent bodies to the

eye,

eye, seem *opacous* through them, which if we widen the Aperture a little, and cast more light on the objects, and not charge the Glasses so deep, will again disclose their transparency.

Now, as for all kinds of colours that are dissolvable in Water, or other liquors, there is nothing so manifest, as that all those ting'd liquors are transparent; and many of them are capable of being *diluted* and compounded or mixt with other colours, and divers of them are capable of being very much chang'd and heightned, and fixt with several kinds of *Saline menstruums*. Others of them upon compounding, destroy or vitiate each others colours, and *precipitate*, or otherwise very much alter each others tincture. In the true ordering and *diluting*, and deepning, and mixing, and fixing of each of which, consists one of the greatest mysteries of the Dyers; of which particulars, because our *Microscope* affords us very little information, I shall add nothing more at present; but onely that with a very few tinctures order'd and mixt after certain ways, too long to be here set down, I have been able to make an appearance of all the various colours imaginable, without at all using the help of *Salts*, or *Saline menstruums* to vary them.

As for the mutation of Colours by *Saline menstruums*, they have already been so fully and excellently handled by the lately mention'd Incomparable *Authour*, that I can add nothing, but that of a multitude of trials that I made, I have found them exactly to agree with his Rules and Theories; and though there may be infinite instances, yet may they be reduc'd under a few Heads, and compris'd within a very few Rules. And generally I find, that *Saline menstruums* are most operative upon those colours that are Purple, or have some degree of Purple in them, and upon the other colours much less. The *spurious* pulses that compose which, being (as I formerly noted) so very neer the middle between the true ones, that a small variation throws them both to one side, or both to the other, and so consequently must make a vast mutation in the formerly appearing Colour.

Observ. XI. *Of* Figures *observ'd in small Sand.*

SAnd generally seems to be nothing else but exceeding small Pebbles, or at least some very small parcels of a bigger stone; the whiter kind seems through the *Microscope* to consist of small transparent pieces of some *pellucid* body, each of them looking much like a piece of *Alum*, or *Salt Gem*; and this kind of Sand is angled for the most part irregularly, without any certain shape, and the *granules* of it are for the most part flaw'd, though amongst many of them it is not difficult to find some that are perfectly *pellucid*, like a piece of clear Crystal, and divers likewise most curiously shap'd, much after the manner of the bigger *Striæ* of Crystal, or like the small Diamants I observ'd in certain Flints, of which I shall by and by relate; which last particular seems to argue, that this kind of Sand is not made

made by the comminution of greater transparent Crystaline bodies, but by the *concretion* or *coagulation* of Water, or some other fluid body.

There are other kinds of courser Sands, which are browner, and have their particles much bigger; these, view'd with a *Microscope*, seem much courser and more *opacous* substances, and most of them are of some irregularly rounded Figures; and though they seem not so *opacous* as to the naked eye, yet they seem very foul and cloudy, but neither do these want curiously transparent, no more than they do regularly figur'd and well colour'd particles, as I have often found.

There are multitudes of other kinds of Sands, which in many particulars, plainly enough discoverable by the *Microscope*, differ both from these last mention'd kinds of Sands, and from one another: there seeming to be as great variety of Sands, as there is of Stones. And as amongst Stones some are call'd precious from their excellency, so also are there Sands which deserve the same Epithite for their beauty; for viewing a small parcel of *East-India* Sand (which was given me by my highly honoured friend, Mr. *Daniel Colwall*) and, since that, another parcel, much of the same kind, I found several of them, both very transparent like precious Stones, and regularly figur'd like Crystal, *Cornish* Diamants, some Rubies, *&c.* and also ting'd with very lively and deep colours, like *Rubys*, *Saphyrs*, *Emeralds*, &c. These kinds of granuls I have often found also in *English* Sand. And 'tis easie to make such a counterfeit Sand with deeply ting'd Glass, Enamels and Painters colours.

It were endless to describe the multitudes of Figures I have met with in these kind of minute bodies, such as *Spherical*, *Oval*, *Pyramidal*, *Conical*, *Prismatical*, of each of which kinds I have taken notice.

But amongst many others, I met with none more observable than this pretty Shell (described in the *Figure* X. of the fifth *Scheme*) which, though as it was light on by chance, deserv'd to have been omitted (I being unable to direct any one to find the like) yet for its rarity was it not inconsiderable, especially upon the account of the information it may afford us. For by it we have a very good instance of the curiosity of Nature in another kind of Animals which are remov'd, by reason of their minuteness, beyond the reach of our eyes; so that as there are several sorts of Insects, as Mites, and others, so small as not yet to have had any names; (some of which I shall afterwards describe) and small Fishes, as Leeches in Vineger; and smal vegetables, as Moss, and Rose-Leave-plants; and small Mushroms, as mould: so are there, it seems, small Shel-fish likewise, Nature shewing her curiosity in every Tribe of *Animals*, *Vegetables*, and *Minerals*.

I was trying several small and single Magnifying Glasses, and casually viewing a parcel of white Sand, when I perceiv'd one of the grains exactly shap'd and wreath'd like a Shell, but endeavouring to distinguish it with my naked eye, it was so very small, that I was fain again to make use of the Glass to find it; then, whilest I thus look'd on it, with a Pin I separated all the rest of the granules of Sand, and found it afterwards to appear to the naked eye an exceeding small white spot, no bigger than the point of a

Pin.

Pin. Afterwards I view'd it every way with a better *Microscope*, and found it on both sides, and edge-ways, to resemble the Shell of a small Water-Snail with a flat spiral Shell: it had twelve wreathings, *a*, *b*, *c*, *d*, *e*, &c. all very proportionably growing one less than another toward the middle or center of the Shell, where there was a very small round white spot. I could not certainly discover whether the Shell were hollow or not, but it seem'd fill'd with somewhat, and tis probable that it might be *petrify'd* as other larger Shels often are, such as are mention'd in the seventeenth *Observation*.

Observ. XII. *Of* Gravel *in Urine.*

I Have often observ'd the Sand or Gravel of Urine, which seems to be a *tartareous* substance, generated out of a *Saline* and a *terrestrial* substance *crystallizi'd* together, in the form of *Tartar*, sometimes sticking to the sides of the *Urinal*, but for the most part sinking to the bottom, and there lying in the form of coorse common Sand; these, through the *Microscope*, appear to be a company of small bodies, partly transparent, and partly *opacous*, some White, some Yellow, some Red, others of more brown and duskie colours.

The Figure of them is for the most part flat, in the manner of Slats, or such like plated Stones, that is, each of them seem to be made up of several other thinner Plates, much like *Muscovie Glass*, or *English Spar*, to the last of which, the white plated Gravel seems most likely; for they seem not onely plated like that, but their sides shap'd also into *Rhombs*, *Rhomboeids*, and sometimes into *Rectangles* and *squares*. Their bigness and Figure may be seen in the second *Figure* of the sixth *Plate*, which represents about a dozen of them lying upon a plate A B C D, some of which, as *a*, *b*, *c*, *d*, seem'd more regular than the rest, and *e*, which was a small one, sticking on the top of another, was a perfect *Rhomboeid* on the top, and had four *Rectangular* sides.

The line E which was the measure of the *Microscope*, is $\frac{1}{50}$ part of an *English* Inch, so that the greatest bredth of any of them, exceeded not $\frac{1}{1000}$ part of an Inch.

Putting these into several liquors, I found *Oyl of Vitriol*, *Spirit of Urine*, and several other *Saline menstruums* to dissolve them; and the first of these in less than a minute without *Ebullition*, Water, and several other liquors, had no sudden operation upon them. This I mention, because those liquors that dissolve them, first make them very white, not *vitiating*, but rather rectifying their Figure, and thereby make them afford a very pretty object for the *Microscope*.

How great an advantage it would be to such as are troubled with the Stone, to find some *menstruum* that might dissolve them without hurting the Bladder, is easily imagin'd, since some *injections* made of such bodies might likewise dissolve the stone, which seems much of the same nature.

It may therefore, perhaps, be worthy some Physicians enquiry, whether there may not be something mixt with the Urine in which the Gravel or Stone lies, which may again make it dissolve it, the first of which seems by it's regular Figures to have been sometimes *Crystalliz'd* out of it. For whether this *Crystallization* be made in the manner as *Alum*, *Peter*, &c. are *crystallized* out of a cooling liquor, in which, by boyling they have been dissolv'd; or whether it be made in the manner of *Tartarum Vitriolatum*, that is, by the *Coalition* of an *acid* and a *Sulphureous* substance, it seems not impossible, but that the liquor it lies in, may be again made a *dissolvent* of it. But leaving these inquiries to Physicians or Chymists, to whom it does more properly belong, I shall proceed.

Observ. XIII. *Of the small* Diamants, *or* Sparks *in* Flints.

CHancing to break a Flint stone in pieces, I found within it a certain cavity all crusted over with a very pretty candied substance, some of the parts of which, upon changing the posture of the Stone, in respect of the *Incident* light, exhibited a number of small, but very vivid reflections; and having made use of my *Microscope*, I could perceive the whole surface of that cavity to be all beset with a multitude of little *Crystaline* or *Adamantine* bodies, so curiously shap'd, that it afforded a not unpleasing object.

Having considered those vivid *repercussions* of light, I found them to be made partly from the plain external surface of these regularly figured bodies (which afforded the vivid reflections) and partly to be made from within the somewhat *pellucid* body, that is, from some surface of the body, opposite to that superficies of it which was next the eye.

And because these bodies were so small, that I could not well come to make Experiments and Examinations of them, I provided me several small *stiriæ* of Crystals or Diamants, found in great quantities in *Cornwall*, and are therefore commonly called *Cornish Diamants*: these being very *pellucid*, and growing in a hollow cavity of a Rock (as I have been several times informed by those that have observ'd them) much after the same manner as these do in the Flint; and having besides their outward surface very regularly shap'd, retaining very near the same Figures with some of those I observ'd in the other, became a convenient help to me for the Examination of the proprieties of those kinds of bodies.

And first for the Reflections; in these I found it very observable, That the brightest reflections of light proceeded from within the *pellucid* body; that is, that the Rays admitted through the *pellucid* substance in their getting out on the opposite side, were by the contiguous and strong reflecting surface of the Air very vividly reflected, so that more Rays were reflected to the eye by this surface, though the Ray in entring and getting out of the Crystal had suffer'd a double refraction, than there were from the outward surface of the Glass where the Ray had suffer'd no refraction at all.

And

Fig: 1





Fig: 2.





And that this was the surface of the Air that gave so vivid a *re-percussion* I try'd by this means. I sunk half of a *stiria* in Water, so that only Water was contiguous to the under surface, and then the internal reflection was so exceedingly faint, that it was scarce discernable. Again, I try'd to alter this vivid reflection by keeping off the Air, with a body not fluid, and that was by rubbing and holding my finger very hard against the under surface, so as in many places the pulp of my finger did touch the Glass, without any *interjacent* air between; then observing the reflection, I found, that wheresoever my finger or skin toucht the surface, from that part there was no reflection, but in the little furrows or creases of my skin, where there remain'd little small lines of air, from them was return'd a very vivid reflection as before. I try'd further, by making the surface of very pure Quicksilver to be contiguous to the under surface of this *pellucid* body, and then the reflection from that was so exceedingly more vivid than from the air, as the reflection from air was than the reflection from the Water; from all which trials I plainly saw, that the strong reflecting air was the cause of this *Phenomenon*.

And this agrees very well with the *Hypothesis* of light and *Pellucid* bodies which I have mention'd in the description of *Muscovy-glass*; for we there suppose Glass to be a *medium*, which does less resist the pulse of light, and consequently, that most of the Rays incident on it enter into it, and are refracted towards the *perpendicular*; whereas the air I suppose to be a body that does more resist it, and consequently more are *re-percuss'd* then do enter it: the same kind of trials have I made, with *Crystalline Glass*, with drops of fluid bodies, and several other ways, which do all seem to agree very exactly with this *Theory*. So that from this Principle well establish'd, we may deduce severall Corollaries not unworthy observation.

And the first is, that it plainly appears by this, that the production of the Rainbow is as much to be ascribed to the reflection of the concave surface of the air, as to the refraction of the *Globular* drops: this will be evidently manifest by these Experiments, if you *foliate* that part of a Glass-ball that is to reflect an *Iris*, as in the *Cartesian* Experiment, above mention'd, the reflections will be abundantly more strong, and the colours more vivid: and if that part of the surface be touch'd with Water, scarce affords any sensible colour at all.

Next we learn, that the great reason why *pellucid* bodies beaten small are white, is from the multitude of reflections, not from the particles of the body, but from the *contiguous* surface of the air. And this is evidently manifested, by filling the *Interstitia* of those powder'd bodies with Water, whereby their whiteness presently disappears. From the same reason proceeds the whiteness of many kinds of Sands, which in the *Microscope* appear to be made up of a multitude of little *pellucid* bodies, whose brightest reflections may by the *Microscope* be plainly perceiv'd to come from their internal surfaces; and much of the whiteness of it may be destroy'd by the affusion of fair Water to be contiguous to those surfaces.

The whiteness also of froth, is for the most part to be ascribed to the

reflection of the light from the ſurface of the air within the Bubbles, and very little to the reflection from the ſurface of the Water it ſelf: for this laſt reflection does not return a quarter ſo many Rays, as that which is made from the ſurface of the air, as I have certainly found by a multitude of Obſervations and Experiments.

The whiteneſs of *Linnen*, *Paper*, *Silk*, &c. proceeds much from the ſame reaſon, as the *Microſcope* will eaſily diſcover; for the Paper is made up of an abundance of *pellucid* bodies, which afford a very plentifull reflection from within, that is, from the concave ſurface of the air contiguous to its component particles; wherefore by the affuſion of Water, Oyl, Tallow, Turpentine, *&c.* all thoſe reflections are made more faint, and the beams of light are ſuffer'd to traject & run through the Paper more freely.

Hence further we may learn the reaſon of the whiteneſs of many bodies, and by what means they may be in part made *pellucid*: As white Marble for inſtance, for this body is compoſed of a *pellucid* body exceedingly flaw'd, that is, there are abundance of thin, and very fine cracks or chinks amongſt the multitude of particles of the body, that contain in them ſmall parcels of air, which do ſo *re-percuſs* and drive back the penetrating beams, that they cannot enter very deep within that body, which the *Microſcope* does plainly inform us to be made up of a *Congeries* of *pellucid* particles. And I further found it ſomewhat more evidently by ſome attempts I made towards the making tranſparent Marble, for by heating the Stone a little, and ſoaking it in Oyl, Turpentine, Oyl of Turpentine, *&c*, I found that I was able to ſee much deeper into the body of Marble then before; and one trial, which was not with an unctuous ſubſtance, ſucceeded better than the reſt, of which, when I have a better opportunity, I ſhall make further trial.

This alſo gives us a probable reaſon of the ſo much admired *Phænomena* of the *Oculus Mundi*, an *Oval* ſtone, which commonly looks like white Alabaſter, but being laid a certain time in Water, it grows *pellucid*, and tranſparent, and being ſuffer'd to lie again dry, it by degrees loſes that tranſparency, and becomes white as before. For the Stone being of a hollow ſpongie nature, has in the firſt and laſt of theſe appearances, all thoſe pores fill'd with the obtunding and reflecting air; whereas in the ſecond, all thoſe pores are fill'd with a *medium* that has much the ſame refraction with the particles of the Stone, and therefore thoſe two being *contiguous*, make, as twere, one *continued medium*, of which more is ſaid in the 15. *Obſervation*.

There are a multitude of other *Phænomena*, that are produc'd from this ſame Principle, which as it has not been taken notice of by any yet that I know, ſo I think, upon more diligent obſervation, will it not be found the leaſt conſiderable. But I have here onely time to hint *Hypotheſes*, and not to proſecute them ſo fully as I could wiſh; many of them having a vaſt extent in the production of a multitude of *Phænomena*, which have been by others, either not attempted to be explain'd, or elſe attributed to ſome other cauſe than what I have aſſign'd, and perhaps than the right; and therefore I ſhall leave this to the proſecution of ſuch as have more leiſure: onely

onely before I leave it, I must not pretermit to hint, that by this Principle, multitudes of the *Phænomena* of the air, as about *Mists*, *Clouds*, *Meteors*, *Haloes*, &c. are most plainly and (perhaps) truly explicable; multitudes also of the *Phænomena* in colour'd bodies, as liquors, *&c.* are deducible from it.

And from this I shall proceed to a second considerable *Phænomenon* which these Diamants exhibit, and that is the regularity of their *Figure*, which is a propriety not less general than the former; It comprising within its extent, all kinds of *Metals*, all kinds of *Minerals*, most *Precious stones*, all kinds of *Salts*, multitudes of *Earths*, and almost all kinds of *fluid bodies*. And this is another propiety, which, though a little superficially taken notice of by some, has not, that I know, been so much as attempted to be explicated by any.

This propriety of bodies, as I think it the most worthy, and next in order to be consider'd after the contemplation of the *Globular Figure*, so have I long had a desire as wel as a determination to have prosecuted it if I had had an opportunity, having long since propos'd to my self the method of my enquiry therein, it containing all the allurements that I think any enquiry is capable of: For, first I take it to proceed from the most simple principle that any kind of form can come from, next the *Globular*, which was therefore the first I set upon, and what I have therein perform'd, I leave the Judicious Reader to determine. For as that form proceeded from a propiety of fluid bodies, which I have call'd *Congruity*, or *Incongruity*; so I think, had I time and opportunity, I could make probable, that all these regular Figures that are so conspicuously *various* and *curious*, and do so adorn and beautifie such multitudes of bodies, as I have above hinted, arise onely from three or four several positions or postures of *Globular* particles, and those the most plain, obvious, and necessary conjunctions of such figur'd particles that are possible, so that supposing such and such plain and obvious causes concurring the *coagulating particles* must necessarily compose a body of such a determinate regular Figure, and no other; and this with as much necessity and obviousness as a fluid body encompast with a *Heterogeneous* fluid must be protruded into a *Spherule* or *Globe*. And this I have *ad oculum* demonstated with a company of bullets, and some few other very simple bodies; so that there was not any regular Figure, which I have hitherto met with all, of any of those bodies that I have above named, that I could not with the composition of bullets or globules, and one or two other bodies, imitate, even almost by shaking them together. And thus for instance may we find that the *Globular* bullets will of themselves, if put on an inclining plain, so that they may run together, naturally run into a *triangular* order, composing all the variety of figures that can be imagin'd to be made out of *æquilateral triangles*; and such will you find, upon trial, all the surfaces of *Alum* to be compos'd of: For three bullets lying on a plain, as close to one another as they can compose an *æquilatero-triangular* form, as in A in the 7. *Scheme*. If a fourth be joyn'd to them on either side as closely as it can, they four compose the most regular Rhombus consisting of two *æquilateral triangles*,

as

as B. If a fifth be joyn'd to them on either side in as close a position as it can, which is the propriety of the *Texture*, it makes a *Trapezium*, or four-sided Figure, two of whose angles are 120. and two 60. degrees, as C. If a sixth be added, as before, either it makes an *æquilateral triangle*, as D, or a Rhomboeid, as E, or an *Hex-angular Figure*, as F, which is compos'd of two *primary Rhombes*. If a seventh be added, it makes either an *æquilatero-hexagonal* Figure, as G, or some kind of six-sided *Figure*, as H, or I. And though there be never so many placed together, they may be rang'd into some of these lately mentioned Figures, all the angles of which will be either 60. degrees, or 120. as the figure K. which is an *æquiangular hexagonal* Figure is compounded of 12. *Globules*, or may be of 25, or 27, or 36, or 42, *&c.* and by these kinds of texture, or position of globular bodies, may you find out all the variety of regular shapes, into which the smooth surfaces of *Alum* are form'd, as upon examination any one may easily find; nor does it hold only in superficies, but in solidity also, for it's obvious that a fourth *Globule* laid upon the third in this texture, composes a regular *Tetrahedron*, which is a very usual Figure of the *Crystals* of *Alum*. And (to hasten) there is no one Figure into which *Alum* is observ'd to be crystallized, but may by this texture of *Globules* be imitated, and by no other.

I could instance also in the Figure of *Sea-salt*, and *Sal-gem*, that it is compos'd of a texture of *Globules*, placed in a *cubical* form, as L, and that all the Figures of those Salts may be imitated by this texture of *Globules*, and by no other whatsoever. And that the forms of *Vitriol* and of *Salt-Peter*, as also of *Crystal*, *Hore-frost*, &c. are compounded of these two textures, but modulated by certain proprieties: But I have not here time to insist upon, as I have not neither to shew by what means *Globules* come to be thus context, and what those *Globules* are, and many other particulars requisite to a full and intelligible explication of this propriety of bodies. Nor have I hitherto found indeed an opportunity of prosecuting the inquiry so farr as I design'd; nor do I know when I may, it requiring abundance of time, and a great deal of assistance to go through with what I design'd; the model of which was this:

First, to get as exact and full a collection as I could, of all the differing kinds of Geometrical figur'd bodies, some three or four several bodies of each kind.

Secondly, with them to get as exact a History as possibly I could learn of their places of Generation or finding, and to enquire after as many circumstances that tended to the Illustrating of this Enquiry, as possibly I could observe.

Thirdly, to make as many trials as upon experience I could find requisite, in Dissolutions and Coagulations of several crystallizing Salts; for the needfull instruction and information in this Enquiry.

Fourthly, to make several trials on divers other bodies, as Metals, Minerals, and Stones, by dissolving them in several *Menstruums*, and crystalizing them, to see what Figures would arise from those several *Compositums*.

Fifthly,

Fifthly, to make Compositions and Coagulations of several Salts together into the same mass, to observe of what Figure the product of them would be; and in all, to note as many circumstances as I should judge conducive to my Enquiry.

Sixthly, to enquire the closeness or rarity of the texture of these bodies, by examining their gravity, and their refraction, *&c.*

Seventhly, to enquire particularly what operations the fire has upon several kinds of Salts, what changes it causes in their Figures, Textures, or Energies.

Eighthly, to examine their manner of dissolution, or acting upon those bodies dissoluble in them; The texture of those bodies before and after the process. And this for the History.

Next for the Solution, To have examin'd by what, and how many means, such and such Figures, actions and effects could be produc'd possibly.

And lastly, from all circumstances well weigh'd, I should have endeavoured to have shewn which of them was most likely, and (if the informations by these Enquiries would have born it) to have demonstrated which of them it must be, and was.

But to proceed, As I believe it next to the Globular the most simple; so do I, in the second place, judge it not less pleasant; for that which makes an Enquiry pleasant, are, first a noble *Inventum* that promises to crown the successfull endeavour; and such must certainly the knowledge of the efficient and concurrent causes of all these curious Geometrical Figures be, which has made the Philosophers hitherto to conclude nature in these things to play the Geometrician, according to that saying of *Plato*, ὁ Θεὸς γεωμετρεῖ. Or next, a great variety of matter in the Enquiry; and here we meet with nothing less than the *Mathematicks* of nature, having every day a new Figure to contemplate, or a variation of the same in another body,

Which do afford us a third thing, which will yet more sweeten the Enquiry, and that is, a multitude of information; we are not so much to grope in the dark, as in most other Enquiries, where the *Inventum* is great; for having such a multitude of instances to compare, and such easie ways of generating, or compounding and of destroying the form, as in the *Solution* and *Crystallization* of Salts, we cannot but learn plentifull information to proceed by. And this will further appear from the universality of the Principle which Nature has made use of almost in all inanimate bodies. And therefore, as the contemplation of them all conduces to the knowledg of any one; so from a Scientifical knowledge of any one does follow the same of all, and every one.

And fourthly, for the usefulness of this knowledge, when acquir'd, certainly none can doubt, that considers that it caries us a step forward into the Labirinth of Nature, in the right way towards the end we propose our selves in all Philosophical Enquiries. So that knowing what is the form of Inanimate or Mineral bodies, we shall be the better able to proceed in our next Enquiry after the forms of Vegeta-

tive

tive bodies; and last of all, of Animate ones, that seeming to be the highest step of natural knowledge that the mind of man is capable of.

Observ. XIV. *Of several kindes of frozen* Figures.

I Have very often in a Morning, when there has been a great *hoar-frost*, with an indifferently magnifying *Microscope*, observ'd the small *Striæ*, or Crystalline beard, which then usually covers the face of most bodies that lie open to the cold air, and found them to be generally *Hexangular prismatical* bodies, much like the long Crystals of *Salt-peter*, save onely that the ends of them were differing: for whereas those of *Nitre* are for the most part *pyramidal*, being terminated either in a point or edge; these of Frost were hollow, and the cavity in some seem'd pretty deep, and this cavity was the more plainly to be seen, because usually one or other of the six *parallelogram* sides was wanting, or at least much shorter then the rest.

But this was onely the Figure of the *Bearded hoar-frost*; and as for the particles of other kinds of *hoar-frosts*, they seem'd for the most part irregular, or of no certain Figure. Nay, the parts of those curious branchings, or *vortices*, that usually in cold weather tarnish the surface of Glass, appear through the *Microscope* very rude, and unshapen, as do most other kinds of frozen *Figures*, which to the naked eye seem exceeding neat and curious, such as the Figures of *Snow*, frozen *Urine*, *Hail*, several *Figures* frozen in common Water, *&c.* Some Observations of each of which I shall hereunto annex, because if well consider'd and examin'd, they may, perhaps, prove very instructive for the finding out of what I have endeavoured in the preceding Observation to shew, to be (next the *Globular Figure* which is caus'd by *congruity*, as I hope I have made probable in the sixth *Observation*) the most simple and plain operation of Nature, of which, notwithstanding we are yet ignorant.

I.

Several Observables in the six-branched *Figures form'd on the surface of Urine by freezing.*

Schem. 8. Fig. 1. 1 The Figures were all frozen almost even with the surface of the *Urine* in the Vessel, but the bigger *stems* were a little *prominent* above that surface, and the parts of those stems which were nearest the center (*a*) were biggest above the surface.

2 I have observ'd several kinds of these Figures, some smaller, no bigger then a Two-pence, others so bigg, that I have by measure found one of its stems or branches above four foot long; and of these, some were pretty round, having all their branches pretty neer alike; other of them were more extended towards one side, as usually those very large ones

were

Fig: 2



Fig 4

Fig: 5

Fig: 3





Fig: 1

Fig: 6



were, which I have observ'd in Ditches which have been full of foul water.

3 None of all these Figures I have yet taken notice of, had any regular position in respect of one another, or of the sides of the Vessel; nor did I find any of them equally to exactness extended every way from the center *a*.

4 Where ever there was a center, the branchings from it, *ab*, *ac*, *ad*, *ae*, *af*, *ag*, were never fewer, or more then six, which usually concurr'd, or met one another very neer in the same point or center, *a*; though oftentimes not exactly; and were enclin'd to each other by an angle, of very neer sixty degrees, I say, very neer, because, though having endeavoured to measure them the most acurately I was able, with the largest Compasses I had, I could not find any sensible variation from that measure, yet the whole six-branched Figure seeming to compose a solid angle, they must necessarily be somewhat less.

5 The middle lines or stems of these branches, *ab*, *ac*, *ad*, *ae*, *af*, *ag*, seem'd somewhat whiter, and a little higher then any of the *intermediate* branchings of these Figures; and the center *a*, was the most *prominent* part of the whole Figure, seeming the *apex* of a solid angle or *pyramid*, each of the six plains beinga little enclin'd below the surface of the *Urin*.

6 The lateral branchings issuing out of the great ones, such as *op*, *nq*, &c. were each of them inclin'd to the great ones, by the same angle of about sixty degrees, as the great ones were one to another, and always the bigger branchings were *prominent* above the less, and the less above the least, by proportionate *gradations*.

7 The *lateral* branches shooting out of the great ones, went all of them from the center, and each of them was parallel to that great branch, next to which it lay; so that as all the branches on one side were parallel to one another, so were they all of them to the *approximate* great branch, as *po*, *qr*, as they were parallel to each other, and shot from the center, so were they parallel also to the great branch *ab*.

8 Some of the stems of the six branches proceeded straight, and of a thickness that gradually grew sharper towards the end, as *ag*.

9 Others of the stems of those branches grew bigger and knotty towards the middle, and the branches also as well as stems, from Cylinders grew into Plates, in a most admirable and curious order, so exceeding regular and delicate, as nothing could be more, as is visible in *ab*, *ac*, *ad*, *ae*, *af*, but towards the end of some of these stems, they began again to grow smaller and to recover their former branchings, as about *k* and *n*.

10 Many of the *lateral* branches had *collateral* branches (if I may so call them) as *qm* had many such as *ft*, and most of those again *subcollateral*, as *vw*, and these again had others less, which one may call *laterosubcollateral*, and these again others, and they others, *&c.* in greater Figures.

11 The branchings of the main Stems joyn'd not together by any regular line, nor did one side of the one lie over the other side of the other, but the small *collateral* and *subcollateral* branches did lie at top of one

another according to a certain order or method, which I always obſerv'd to be this.

12 That ſide of a *collateral* or *ſubcollateral*, &c. branch, lay over the ſide of the *approximate* (as the feathers in the wing of a Bird) whoſe branchings proceeded parallel to the laſt biggeſt ſtem from which it ſprung, and not to the biggeſt ſtem of all, unleſs that were a ſecond ſtem backwards.

13 This rule that held in the branchings of the *Sexangular Figure* held alſo in the branchings of any other great or ſmall ſtem, though it did not proceed from a center.

14 The exactneſs and curioſity of the figuration of theſe branches, was in every particular ſo tranſcendent, that I judge it almoſt impoſſible for humane art to imitate.

15 Taſting ſeveral cleer pieces of this *Ice*, I could not find any *Urinous* taſte in them, but thoſe few I taſted, ſeem'd as *inſipid* as water.

16 A figuration ſomewhat like this, though indeed in ſome particulars much more curious, I have ſeveral times obſerv'd in *regulus martis ſtellatus*, but with this difference, that all the ſtems and branchings are bended in a moſt excellent and regular order, whereas in *Ice* the ſtems and branchings are ſtreight, but in all other particulars it agrees with this, and ſeems indeed nothing but one of theſe ſtars, or branched Figures frozen on *Urine*, diſtorted, or wreathed a little, with a certain proportion: *Lead* alſo that has *Arſenick* and ſome other things mixt with it, I have found to have its ſurface, when ſuffer'd to cool, figured ſomewhat like the branchings of *Urine*, but much ſmaller.

17 But there is a *Vegetable* which does exceedingly imitate theſe branches, and that is, *Fearn*, where the main ſtem may be obſerv'd to ſhoot out branches, and the ſtems of each of theſe *lateral* branches, to ſend forth *collateral*, and thoſe *ſubcollateral*, and thoſe *latero ſubcollateral*, &c. and all thoſe much after the ſame order with the branchings, diviſions, and ſubdiviſions in the branchings of theſe Figures in frozen *Urine*; ſo that if the Figures of both be well conſider'd, one would gheſs that there were not much greater need of a *ſeminal principle* for the production of *Fearn*, then for the production of the branches of *Urine*, or the *Stella martis*, there ſeeming to be as much form and beauty in the one as in the other.

And indeed, this Plant of *Fearn*, if all particulars be well conſider'd, will ſeem of as ſimple, and uncompounded a form as any *Vegetable*, next to *Mould* or *Muſhromes*, and would next after the invention of the forms of thoſe, deſerve to be enquir'd into; for notwithſtanding ſeveral have affirm'd it to have ſeed, and to be propagated thereby; yet, though I have made very diligent enquiry after that particular, I cannot find that there is any part of it that can be imagin'd to be more ſeminal then another: But this onely here by the by:

For the freezing Figures in *Urine*, I found it requiſite,

Firſt, that the Superficies be not diſturbed with any wind, or other commotion of the air, or the like.

Secondly,

Secondly, that it be not too long exposed, so as that the whole bulk be frozen, for oftentimes, in such cases, by reason of the swelling the of *Ice*, or from some other cause, the curious branched Figures disappear.

Thirdly, an artificial freezing with *Snow* and *Salt*, apply'd to the outside of the containing Vessel, succeeds not well, unless there be a very little quantity in the Vessel.

Fourthly, If you take any cleer and smooth Glass, and wetting all the inside of it with *Urine*, you expose it to a very sharp freezing, you will find it cover'd with a very regular and curious Figure.

II.

Observables in figur'd Snow.

Exposing a piece of black Cloth, or a black Hatt to the falling *Snow*, I have often with great pleasure, observ'd such an infinite variety of curiously figur'd *Snow*, that it would be as impossible to draw the Figure and shape of every one of them, as to imitate exactly the curious and Geometrical *Mechanisme* of Nature in any one. Some coorse draughts, such as the coldness of the weather, and the ill provisions, I had by me for such a purpose, would permit me to make, I have here added in the Second *Figure* of the Eighth *Scheme*. *Schem.* 8. *Fig.* 2.

In all which I observ'd, that if they were of any regular Figures, they were always branched out with six principal branches, all of equal length, shape and make, from the center, being each of them inclin'd to either of the next branches on either side of it, by an angle of sixty degrees.

Now, as all these stems were for the most part in one flake exactly of the same make, so were they in differing Figures of very differing ones; so that in a very little time I have observ'd above an hundred several cizes and shapes of these starry flakes.

The branches also out of each stem of any one of these flakes, were exactly alike in the same flake; so that of whatever Figure one of the branches were, the other five were sure to be of the same, very exactly, that is, if the branchings of the one were small *Perallelipipeds* or Plates, the branchings of the other five were of the same; and generally, the branchings were very conformable to the rules and method observ'd before, in the Figures on *Urine*, that is, the branchings from each side of the stems were parallel to the next stem on that side, and if the stems were plated, the branches also were the same; if the stems were very long, the branches also were so, *&c.*

Observing some of these figur'd flakes with a *Microscope*, I found them not to appear so curious and exactly figur'd as one would have imagin'd, but like Artificial Figures, the bigger they were magnify'd, the more irregularites appear'd in them; but this irregularity seem'd ascribable to the thawing and breaking of the flake by the fall, and not at all to the defect of the *plastick* virtue of Nature, whose curiosity in the formation of most of these kind of regular Figures, such as those of *Salt*, *Minerals*, &c.

 appears

appears by the help of the *Microscope*, to be very many degrees smaller then the most acute eye is able to perceive without it. And though one of these six-branched Stars appear'd here below much of the shape described in the Third *Figure* of the Eighth *Scheme*; yet I am very apt to think, that could we have a sight of one of them through a *Microscope* as they are generated in the Clouds before their Figures are vitiated by external accidents, they would exhibit abundance of curiosity and neatness there also, though never so much magnify'd: For since I have observ'd the Figures of *Salts* and *Minerals* to be some of them so exceeding small, that I have scarcely been able to perceive them with the *Microscope*, and yet have they been regular, and since (as far as I have yet examin'd it) there seems to be but one and the same cause that produces both these effects, I think it not irrational to suppose that these pretty figur'd Stars of *Snow*, when at first generated might be also very regular and exact.

III.

Several kinds of Figures in Water *frozen.*

Putting fair Water into a large capacious Vessel of *Glass*, and exposing it to the cold, I observ'd after a little time, several broad, flat, and thin *laminæ*, or plates of *Ice*, crossing the bulk of the water and one another very irregularly, onely most of them seem'd to turn one of their edges towards that side of the Glass which was next it, and seem'd to grow, as 'twere from the inside of the Vessel inwards towards the middle, almost like so many blades of *Fern*. Having taken several of these plates out of water on the blade of a Knife, I observ'd them figur'd much after the manner of *Herring bones*, or *Fern blades*, that is, there was one bigger stem in the middle like the back-bone, and out of it, on either side, were a multitude of small *stiriæ*, or *icicles*, like the smaller bones, or the smaller branches in *Fern*, each of these branches on the one side, were parallel to all the rest on the same side, and all of them seem'd to make an angle with the stem, towards the top, of sixty degrees, and towards the bottom or root of this stem, of 120. See the fourth *Figure* of the 8. *Plate*.

I observ'd likewise several very pretty varieties of Figures in Water, frozen on the top of a broad flat Marble-stone, expos'd to the cold with a little Water on it, some like feathers, some of other shapes, many of them were very much of the shape exprest in the fifth Figure of the 8. *Scheme*, which is extremely differing from any of the other Figures.

I observ'd likewise, that the shootings of *Ice* on the top of Water, beginning to freez, were in streight *prismatical* bodies much like those of *roch-peter*, that they croft each other usually without any kind of order or rule, that they were always a little higher then the surface of the Water that lay between them; that by degrees those *interjacent* spaces would be fill'd with *Ice* also, which usually would be as high as the surface of the rest.

In flakes of *Ice* that had been frozen on the top of Water to any considerable

Figur: 1



Figur: 2.

Fig: 3.



siderable thickness, I observ'd that both the upper and the under sides of it were curiously quill'd, furrow'd, or grain'd, as it were, which when the Sun shone on the Plate, was exceeding easily to be perceiv'd to be much after the shape of the lines in the 6. *Figure* of the 8. *Scheme*, that is, they consisted of several streight ends of parallel Plates, which were of divers lengths and angles to one another without any certain order.

The cause of all which regular Figures (and of hundreds of others, namely of *Salts*, *Minerals*, *Metals*, &c. which I could have here inserted, would it not have been too long) seems to be deducible from the same Principles, which I have (in the 13. *Observation*) hinted only, having not yet had time to compleat a *Theory* of them. But indeed (which I there also hinted) I judge it the second step by which the *Pyramid* of natural knowledge (which is the knowledge of the form of bodies) is to be ascended: And whosoever will climb it, must be well furnish'd with that which the Noble *Verulam* calls *Scalam Intellectus*; he must have scaling Ladders, otherwise the steps are so large and high, there will be no getting up them, and consequently little hopes of attaining any higher station, such as to the knowledge of the most simple principle of Vegetation manifested in Mould and Mushromes, which, as I elsewhere endeavoured to shew, seems to be the third step; for it seems to me, that the Intellect of man is like his body, destitute of wings, and cannot move from a lower to a higher and more sublime station of knowledg, otherwise then step by step, nay even there where the way is prepar'd and already made passible; as in the *Elements of Geometry*, or the like, where it is fain to climb a whole *series* of Propositions by degrees, before it attains the knowledge of one *Probleme*. But if the ascent be high, difficult and above its reach, it must have recourse to a *novum organum*, some new engine and contrivance, some new kind of *Algebra*, or *Analytick Art* before it can surmount it.

Observ. XV. *Of* Kettering-stone, *and of the pores of* Inanimate *bodies.*

THis Stone which is brought from *Kettering* in *Northampton-shire*, and digg'd out of a Quarry, as I am inform'd, has a grain altogether admirable, nor have I ever seen or heard of any other stone that has the like. It is made up of an innumerable company of small bodies, not all of the same cize or shape, but for the most part, not much differing from a Globular form, nor exceed they one another in Diameter above three or four times; they appear to the eye, like the Cobb or Ovary of a *Herring*, or some smaller fishes, but for the most part, the particles seem somewhat less, and not so uniform; but their variation from a perfect globular ball, seems to be only by the pressure of the *contiguous* bals which have a little depreſt and protruded those toucht sides inward, and forc'd the *Schem. 9. Fig. 1.*

the other ſides as much outwards beyond the limits of a Globe; juſt as it would happen, if a heap of exactly round Balls of ſoft Clay were heap'd upon one another; or, as I have often ſeen a heap of ſmall Globules of *Quickſilver*, reduc'd to that form by rubbing it much in a glaz'd Veſſel, with ſome ſlimy or ſluggiſh liquor, ſuch as Spittle, when though the top of the upper Globules be very neer ſpherical, yet thoſe that are preſt upon by others, exactly imitate the forms of theſe lately mention'd grains.

Where theſe grains touch each other, they are ſo firmly united or ſettled together, that they ſeldom part without breaking a hole in one or th'other of them, ſuch as *a*, *a*, *a*, *b*, *c*, *c*, &c. Some of which fractions, as *a*, *a*, *a*, *a*, where the touch has been but light, break no more then the outward cruſt, or firſt ſhell of the ſtone, which is of a white colour, a little daſh'd with a browniſh Yellow, and is very thin, like the ſhell of an Egg: and I have ſeen ſome of thoſe grains perfectly reſemble ſome kind of Eggs, both in colour and ſhape: But where the union of the *contiguous granules* has been more firm, there the divulſion has made a greater Chaſm, as at *b*, *b*, *b*, in ſo much that I have obſerv'd ſome of them quite broken in two, as at *c*, *c*, *c*, which has diſcovered to me a further reſemblance they have to Eggs, they having an appearance of a white and yelk, by two differing ſubſtances that envelope and encompaſs each other.

That which we may call the white was pretty whitiſh neer the yelk, but more duſkie towards the ſhell; ſome of them I could plainly perceive to be ſhot or radiated like a *Pyrites* or *fire-ſtone*; the yelk in ſome I ſaw hollow, in others fill'd with a duſkie brown and porous ſubſtance like a kind of pith.

The ſmall pores, or *interſtitia e e e e* betwixt the Globules, I plainly ſaw, and found by other trials to be every way pervious to air and water, for I could blow through a piece of this ſtone of a conſiderable thickneſs, as eaſily as I have blown through a Cane, which minded me of the pores which *Des Cartes* allow his *materia ſubtilis* between the *æthereal* globules.

The object, through the *Microſcope*, appears like a *Congeries* or heap of Pibbles, ſuch as I have often ſeen caſt up on the ſhore, by the working of the Sea after a great ſtorm, or like (in ſhape, though not colour) a company of ſmall Globules of Quickſilver, look'd on with a *Microſcope*, when reduc'd into that form by the way lately mentioned. And perhaps, this laſt may give ſome hint at the manner of the formation of the former: For ſuppoſing ſome *Lapideſcent* ſubſtance to be generated, or ſome way brought (either by ſome commixture of bodies in the Sea it ſelf, or protruded in, perhaps, out of ſome *ſubterraneous* caverns) to the bottom of the Sea, and there remaining in the form of a liquor like Quickſilver, *heterogeneous* to the ambient *Saline* fluid, it may by the working and tumblings of the Sea to and fro be jumbled and comminuted into ſuch Globules as may afterwards be hardned into Flints, the lying of which one upon another, when in the Sea, being not very hard, by reaſon of the weight of the incompaſſing fluid, may cauſe the undermoſt to be a little, though not much, varied from a globular Figure. But this only by the by.

After

After what manner this *Kettering-stone* should be generated I cannot learn, having never been there to view the place, and observe the circumstances; but it seems to me from the structure of it to be generated from some substance once more fluid, and afterwards by degrees growing harder, almost after the same manner as I supposed the generation of Flints to be made.

But whatever were the cause of its curious texture, we may learn this information from it; that even in those things which we account vile, rude, and coorse, Nature has not been wanting to shew abundance of curiosity and excellent Mechanisme.

We may here find a Stone by help of a *Microscope*, to be made up of abundance of small Balls, which do but just touch each other, and yet there being so many contacts, they make a firm hard mass, or a Stone much harder then Free-stone.

Next, though we can by a *Microscope* discern so curious a shape in the particles, yet to the naked eye there scarce appears any such thing; which may afford us a good argument to think, that even in those bodies also, whose *texture* we are not able to discern, though help'd with *Microscopes*, there may be yet *latent* so curious a *Schematisme*, that it may abundantly satisfie the curious searcher, who shall be so happy as to find some way to discover it.

Next, we here find a Stone, though to the naked eye a very close one, yet every way perforated with innumerable pores, which are nothing else but the *interstitia*, between those multitudes of minute globular particles, that compose the bulk it self; and these pores are not only discover'd by the *Microscope*, but by this contrivance.

I took a pretty large piece of this stone, and covering it all over with cement, save only at two opposite parts, I found my self able, by blowing in at one end that was left open, to blow my spittle, with which I had wet the other end, into abundance of bubbles, which argued these pores to be open and pervious through the whole stone, which affords us a very pretty instance of the porousness of some seemingly close bodies, of which kind I shall anon have occasion to subjoyn many more, tending to prove the same thing.

I must not here omit to take notice, that in this body there is not a *vegetative* faculty that should so contrive this structure for any peculiar use of *Vegetation* or growth, whereas in the other instances of vegetable porous bodies, there is an *anima*, or *forma informans*, that does contrive all the Structures and *Mechanismes* of the constituting body, to make them subservient and usefull to the great Work or Function they are to perform. And so I ghess the pores in Wood, and other vegetables, in bones, and other Animal substances, to be as so many channels, provided by the Great and Alwise Creator, for the conveyance of appropriated juyces to particular parts. And therefore, that this may tend, or be pervious all towards one part, and may have impediments, as valves or the like, to any other; but in this body we have very little reason to suspect there should be any such design, for it is equally pervious every way, not onely forward,

ward, but backwards, and side-ways, and seems indeed much rather to be *Homogeneous* or similar to those pores, which we may with great probability believe to be the channels of *pellucid* bodies, not directed, or more open any one way, then any other, being equally pervious every way. And, according as these pores are more or greater in respect of the *interstitial* bodies, the more transparent are the so constituted concretes; and the smaller those pores are, the weaker is the *Impulse* of light communicated through them, though the more quick be the progress.

Upon this Occasion, I hope it will not be altogether unseasonable, if I propound my conjectures and *Hypothesis* about the *medium* and conveyance of light.

I suppose then, that the greatest part of the *Interstitia* of the world, that lies between the bodies of the Sun and Starrs, and the Planets, and the Earth, to be an exceeding fluid body, very apt and ready to be mov'd, and to communicate the motion of any one part to any other part, though never so far distant: Nor do I much concern my self, to determine what the Figure of the particles of this exceedingly subtile fluid *medium* must be; nor whether it have any interstitiated pores or vacuities, it being sufficient to solve all the *Phænomena* to suppose it an exceedingly fluid, or the most fluid body in the world, and as yet impossible to determine the other difficulties.

That being so exceeding fluid a body, it easily gives passage to all other bodies to move to and fro in it.

That it neither receives from any of its parts, or from other bodies; nor communicates to any of its parts, or to any other body, any impulse, or motion in a direct line, that is not of a determinate quickness. And that when the motion is of such determinate swiftness, it both receives, and communicates, or propagates an impulse or motion to any imaginable distance in streight lines, with an unimaginable celerity and vigour.

That all kind of solid bodies consist of pretty massie particles in respect of the particles of this fluid *medium*, which in many places do so touch each other, that none of this fluid *medium* interposes much after the same mannner (to use a gross similitude) as a heap of great stones compass one great *congeries* or mass in the midst of the water.

That all fluid bodies which we may call *tangible*, are nothing but some more subtile parts of those particles, that serve to constiture all *tangible* bodies.

That the water, and such other fluid bodies, are nothing but a *congeries* of particles agitated or made fluid by it in the same manner as the particles of *Salt* are agitated or made fluid by a parcel of water, in which they are dissolv'd, and subsiding to the bottom of it, constitute a fluid body, much more massie and dense, and less fluid then the pure water it self.

That the air on the other side is a certain company of particles of quite another kind, that is, such as are very much smaller, and more easiely moveable by the motion of this fluid *medium*; much like those very subtile parts of *Cochenel*, and other very deep tinging bodies, where by a very small

ſmall parcel of matter is able to tinge and diffuſe it ſelf over a very great quantity of the fluid diſſolvent; or ſomewhat after that manner, as ſmoak, and ſuch like minute bodies, or ſteams, are obſerv'd to tinge a very great quantity of air; onely this laſt ſimilitude is deficient in one propriety, and that is a perpetuity or continuance in that ſtate of commixture with the air, but the former does more neerly approach to the nature and manner of the air's being diſſolv'd by this fluid or *Æther*. And this Similitude will further hold in theſe proprieties; that as thoſe tinctures may be increaſed by certain bodies, ſo may they be precipitated by others; as I ſhall afterwards ſhew it to be very probable, that the like accidents happen even to the Air it ſelf.

Further, as theſe ſolutions and tinctures do alter the nature of theſe fluid bodies, as to their aptneſs to propagate a motion or impulſe through them, even ſo does the particles of the Air, Water, and other fluid bodies, and of Glaſs, Cryſtal, *&c.* which are commixt with this bulk of the *Æther*, alter the motion of the propagated pulſe of light; that is, where theſe more bulkie particles are more plentifull, and conſequently a leſſer quantity of the *Æther* between them to be mov'd, there the motion muſt neceſſarily be the ſwifter, though not ſo robuſt, which will produce thoſe effects, which I have (I hope) with ſome probability, aſcribed to it in the digreſſion about Colours, at the end of the *Obſervations* on *Muſcovy-glaſs*.

Now, that other Stones, and thoſe which have the cloſeſt and hardeſt textures, and ſeem (as far as we are able to diſcover with our eyes, though help'd with the beſt *Microſcopes*) freeſt from pores, are yet notwithſtanding repleniſh'd with them; an Inſtance or two will, I ſuppoſe, make more probable.

A very ſolid and unflaw'd piece of cleer white *Marble*, if it be well poliſh'd and glaz'd, has ſo curiouſly ſmooth a ſurface, that the beſt and moſt poliſh'd ſurface of any wrought-glaſs, ſeems not to the naked eye, nor through a *Microſcope*, to be more ſmooth, and leſs porous. And yet, that this hard cloſe body is repleniſh'd with abundance of pores, I think theſe following Experiments will ſufficiently prove.

The firſt is, That if you take ſuch a piece, and for a pretty while boyl it in Turpentine and Oyl of Turpentine, you ſhall find that the ſtone will be all imbu'd with it; and whereas before it look'd more white, but more opacous, now it will look more greaſie, but be much more tranſparent; and if you let it lie but a little while, and then break off a part of it, you ſhall find the unctuous body to have penetrated it to ſuch a determinate depth every way within the ſurface. This may be yet eaſier try'd with a piece of the ſame *Marble*, a little warm'd in the fire, and then a little Pitch or Tarr melted on the top of it; for theſe black bodies, by their inſinuating themſelves into the inviſible pores of the ſtone, ting it with ſo black a hue, that there can be no further doubt of the truth of this aſſertion, that it abounds with ſmall imperceptible pores.

Now, that other bodies will alſo ſink into the pores of *Marble*, beſides *unctuous*, I have try'd, and found, that a very Blue tincture made in

Spirit of Urine would very readily and easily sink into it, as would also several tinctures drawn with *Spirit of Wine*.

Nor is *Marble* the only seemingly close stone, which by other kinds of Experiments may be found porous; for I have by this kind of Experiment on divers other stones found much the same effect, and in some, indeed much more notable. Other stones I have found so porous, that with the *Microscope* I could perceive several small winding holes, much like Worm-holes, as I have noted in some kind of *Purbeck-stone*, by looking on the surface of a piece newly flaw'd off; for if otherwise, the surface has been long expos'd to the Air, or has been scraped with any tool, those small caverns are fill'd with dust, and disappear.

And to confirm this *Conjecture*, yet further, I shall here insert an excellent account, given into the *Royal Society* by that Eminently Learned Physician, Doctor *Goddard*, of an Experiment, not less instructive, then curious and accurate, made by himself on a very hard and seemingly close stone call'd *Oculus Mundi*, as I find it preserv'd in the Records of that Honourable Society.

A small stone of the kind, call'd by some Authours, *Oculus Mundi*, being dry and cloudy, weigh'd $5\frac{209}{256}$ *Grains*.

The same put under water for a night, and somewhat more, became transparent, and the superficies being wiped dry, weighed $6\frac{3}{256}$ *Grains*.

The difference between these two weights, $0\frac{50}{256}$ of a *Grain*.

The same Stone kept out of water one Day and becoming cloudy again weighed, $5\frac{225}{256}$ *Graines*.

Which was more then the first weight, $0\frac{16}{256}$ of a *Grain*.

The same being kept two Days longer weighed, $5\frac{202}{256}$ *Graines*.

Which was less then at first, $0\frac{7}{256}$ of a *Grain*.

Being kept dry something longer it did not grow sensibly lighter.

Being put under water for a night and becoming again transparent and wiped dry, the weight was, $6\frac{3}{256}$ *Grains*, the same with the first after putting in water, and more then the last weight after keeping of it dry, $0\frac{57}{256}$ of a *Grain*.

Another Stone of the same kind being variegated with milky *white* and *gray* like some sorts of *Agates*, while it lay under water, was alwaies invironed with little Bubbles, such as appear in water

water a little before boyling, next the sides of the Vessel.

There were also some the like Bubbles on the Surface of the water just over it, as if either some exhalations came out of it, or that it did excite some fermentation in the parts of the water contiguous to it.

There was little sensible difference in the transparency of this Stone, before the putting under water, and after: To be sure the milky-*white* parts continued as before, but more difference in weight then in the former. For whereas before the putting into the water the weight was $18\frac{27}{128}$ *Graines*. After it had lyen in about four and twenty hours the weight was $20\frac{37}{128}$ *Graines*, so the difference was, $1\frac{8}{128}$ *Graines*.

The same Stone was infused in the water sealding hot, and so continued for a while after it was cold, but got no more weight then upon infusing in the cold, neither was there any sensible Difference in the weight both times.

In which Experiment, there are three Observables, that seem very manifestly to prove the porousness of these seemingly close bodies: the first is their acquiring a transparency, and losing their whiteness after steeping in water, which will seem the more strongly to argue it, if what I have already said about the making transparent, or clarifying of some bodies, as the white powder of beaten Glass, and the froth of some glutinous transparent liquor be well consider'd; for thereby it will seem rational to think that this transparency arises from the insinuation of the Water (which has much the same refraction with such stony particles, as may be discoverd by Sand view'd with a *Microscope*) into those pores which were formerly repleat with air (that has a very differing refraction, and consequently is very reflective) which seems to be confirm'd by the second Observable, namely, the increase of weight after steeping, and decrease upon drying. And thirdly, seem'd yet more sensibly confirm'd by the multitude of bubbles in the last Experiment.

We find also most Acid Salts very readily to dissolve and separate the parts of this body one from another; which is yet a further Argument to confirm the porousness of bodies, and will serve as such, to shew that even Glass also has an abundance of pores in it, since there are several liquors, that with long staying in a Glass, will so *Corrode* and eat into it, as at last, to make it pervious to the liquor it contain'd, of which I have seen very many Instances.

Since therefore we find by other proofs, that many of those bodies

which we think the most solid ones, and appear so to our sight, have notwithstanding abundance of those grosser kind of pores, which will admit several kinds of liquors into them, why should we not believe that Glass, and all other transparent bodies abound with them, since we have many other arguments, besides the propagation of light, which seem to argue for it?

And whereas it may be objected, that the propagation of light is no argument that there are those atomical pores in glass, since there are *Hypotheses* plausible enough to solve those *Phænomena*, by supposing the pulse onely to be communicated through the transparent body.

To this I answer, that that *Hypothesis* which the industrious *Moreanus* has publish'd about the slower motion of the end of a Ray in a denser *medium*, then in a more rare and thin, seems altogether unsufficient to solve abundance of *Phænomena*, of which this is not the least considerable, that it is impossible from that supposition, that any colours should be generated from the refraction of the Rays; for since by that *Hypothesis* the *undulating pulse* is always carried perpendicular, or at right angles with the Ray or Line of direction, it follows, that the stroke of the pulse of light, after it has been once or twice refracted (through a Prisme, for example) must affect the eye with the same kind of stroke as if it had not been refracted at all. Nor will it be enough for a Defendant of that *Hypothesis*, to say, that perhaps it is because the refractions have made the Rays more weak, for if so, then two refractions in the two parallel sides of a *Quadrangular Prisme* would produce colours, but we have no such *Phænomena* produc'd.

There are several Arguments that I could bring to evince that there are in all transparent bodies such atomical pores. And that there is such a fluid body as I am arguing for, which is the *medium*, or Instrument, by which the pulse of Light is convey'd from the *lucid body* to the enlightn'd. But that it being a digression from the Observations I was recording, about the Pores of *Kettering Stone*, it would be too much such, if I should protract it too long; and therefore I shall proceed to the next *Observation*.

Observ. XVI. *Of* Charcoal, *or burnt* Vegetables.

CHarcoal, or a Vegetable burnt black, affords an object no less pleasant than instructive; for if you take a small round Charcoal, and break it short with your fingers, you may perceive it to break with a very smooth and sleek surface, almost like the surface of black sealing Wax; this surface, if it be look'd on with an ordinary *Micnoscope*, does manifest abundance of those pores which are also visible to the eye in many kinds of *Wood*, rang'd round the pith, both a in kind of circular order, and a radiant one. Of these there are a multitude in the substance of the Coal, every where almost perforating and drilling it from end to end; by means

means of which, be the Coal never so long, you may easily blow through it; and this you may presently find, by wetting one end of it with Spittle, and blowing at the other.

But this is not all, for besides those many great and conspicuous irregular spots or pores, if a better *Microscope* be made use of, there will appear an infinite company of exceedingly small, and very regular pores, so thick and so orderly set, and so close to one another, that they leave very little room or space between them to be fill'd with a solid body, for the apparent *interstitia*, or separating sides of these pores seem so thin in some places, that the texture of a Honey-comb cannot be more porous. Though this be not every where so, the intercurrent partitions in some places being very much thicker in proportion to the holes.

Most of these small pores seem'd to be pretty round, and were rang'd in rows that radiated from the pith to the bark; they all of them seem'd to be continued open pores, running the whole length of the Stick; and that they were all perforated, I try'd by breaking off a very thin sliver of the Coal cross-ways, and then with my *Microscope*, diligently surveying them against the light, for by that means I was able to see quite through them.

These pores were so exceeding small and thick, that in a line of them, $\frac{1}{18}$ part of an Inch long, I found by numbring them no less then 150. small pores; and therefore in a line of them an Inch long, must be no less then 2700. pores, and in a circular *area* of an Inch diameter, must be about 5725350. of the like pores; so that a Stick of an Inch Diameter, may containe no less then seven hundred and twenty five thousand, besides 5 Millions of pores, which would, I doubt not, seem even incredible, were not every one left to believe his own eyes. Nay, having since examin'd *Cocus, black and green Ebony, Lignum Vitæ*, &c. I found, that all these Woods have their pores, abundantly smaller then those of soft light Wood; in so much, that those of *Guajacum* seem'd not above an eighth part of the bigness of the pores of Beech, but then the *Interstitia* were thicker; so prodigiously curious are the contrivances, pipes, or sluces by which the *Succus nutritius*, or Juyce of a Vegetable is convey'd from place to place.

This *Observation* seems to afford us the true reason of several *Phænomena* of Coals; as

First, why they look black; and for this we need go no further then the *scheme*, for certainly, a body that has so many pores in it as this is discover'd to have, from each of which no light is reflected, must necessarily look black, especially, when the pores are somewhat bigger in proportion to the intervals then they are cut in the *Scheme*, black being nothing else but a privation of Light, or a want of reflection; and wheresover this reflecting quality is deficient, there does that part look black, whether it be from a porousness of the body, as in this Instance, or in a deadning and dulling quality, such as I have observ'd in the *Scoria* of Lead, Tin, Silver, Copper, *&c.*

Next, we may also as plainly see the reason of its shining quality, and that

that is from the even breaking off of the ſtick, the ſolid *interſtitia* having a regular termination or ſurface, and having a pretty ſtrong reflecting quality, the many ſmall reflections become united to the naked eye, and make a very pretty ſhining ſurface.

Thirdly, the reaſon of its hardneſs and brittleneſs ſeems evident, for ſince all the watery or liquid ſubſtance that moiſtn'd and toughn'd thoſe *Interſtitia* of the more ſolid parts, are evaporated and remov'd, that which is left hehind becomes of the nature almoſt of a ſtone, which will not at all, or very little, bend without a *divulſion* or *ſolution* of its *continuity*.

It is not my deſign at preſent, to examine the uſe and *Mechaniſme* of theſe parts of Wood, that being more proper to another Enquiry; but rather to hint, that from this Experiment we may learn,

Firſt, what is the cauſe of the blackneſs of many burnt bodies, which we may find to be nothing elſe but this; that the heat of the fire agitating and rarifying the wateriſh, tranſparent, and volatile water that is contain'd in them, by the continuation of that action, does ſo totally expel and drive away all that which before fill'd the pores, and was diſpers'd alſo through the ſolid maſs of it, and thereby caus'd an univerſal kind of tranſparency, that it not onely leaves all the pores empty, but all the *Interſtitia* alſo ſo dry and *opacous*, and perhaps alſo yet further perforated, that that light onely is reflected back which falls upon the very outward edges of the pores, all they that enter into the pores of the body, never returning, but being loſt in it.

Now, that the Charring or coaling of a body is nothing elſe, may be eaſily believ'd by one that ſhall conſider the means of its production, which may be done after this, or any ſuch manner. The body to be charr'd or coal'd, may be put into a *Crucible*, Pot, or any other Veſſel that will endure to be made red-hot in the Fire without breaking, and then cover'd over with Sand, ſo as no part of it be ſuffer'd to be open to the Air, then ſet into a good Fire, and there kept till the Sand has continu'd red hot for a quarter, half, an hour or two, or more, according to the nature and bigneſs of the body to be coal'd or charr'd, then taking it out of the Fire, and letting it ſtand till it be quite cold, the body may be taken out of the Sand well charr'd and cleans'd of its wateriſh parts; but in the taking of it out, care muſt be had that the Sand be very neer cold, for elſe, when it comes into the free air, it will take fire, and readily burn away.

This may be done alſo in any cloſe Veſſel of Glaſs, as a *Retort*, or the like, and the ſeveral fluid ſubſtances that come over may be receiv'd in a fit *Recipient*, which will yet further countenance this *Hypotheſis*: And their manner of charring Wood in great quantity comes much to the ſame thing, namely, an application of a great heat to the body, and preſerving it from the free acceſs of the devouring air; this may be eaſily learn'd from the Hiſtory of Charring of Coal, moſt excellently deſcrib'd and publiſh'd by that moſt accompliſh'd Gentleman, Mr. *John Evelin*, in the 100, 101, 103, pages of his *Sylva*, to which I ſhall therefore refer the curious Reader that deſires a full information of it,

Next

Next, we may learn what part of the Wood it is that is the *combustible* matter; for since we shall find that none, or very little of those fluid substances that are driven over into the Receiver are *combustible*, and that most of that which is left behind is so, it follows, that the solid *interstitia* of the Wood are the *combustible* matter. Further, the reason why uncharr'd Wood burns with a greater flame then that which is charr'd, is as evident, because those waterish or volatil parts issuing out of the fired Wood, every way, not onely shatter and open the body, the better for the fire to enter, but issuing out in vapours or wind, they become like so many little *æolipiles*, or Bellows, whereby they blow and agitate the fir'd part, and conduce to the more speedy and violent consumption or dissolution of the body.

Thirdly, from the Experiment of charring of Coals (whereby we see that notwithstanding the great heat, and the duration of it, the solid parts of the Wood remain, whilest they are preserv'd from the free access of the air undissipated) we may learn, that which has not, that I know of, been publish'd or hinted, nay, not so much as thought of, by any; and that in short is this.

First, *that the Air* in which we live, move, and breath, and which encompasses very many, and cherishes most bodies it encompasses, that this Air is the *menstruum*, or universal dissolvent of all *Sulphureous* bodies.

Secondly, *that this action* it performs not, till the body be first sufficiently heated, as we find requisite also to the dissolution of many other bodies by several other *menstruums*.

Thirdly, *that this action* of dissolution, produces or generates a very great heat, and that which we call Fire; and this is common also to many dissolutions of other bodies, made by *menstruums*, of which I could give multitudes of Instances.

Fourthly, *that this action* is perform'd with so great a violence, and does so minutely act, and rapidly agitate the smallest parts of the *combustible* matter, that it produces in the *diaphanous medium* of the Air, the action or pulse of light, which what it is, I have else-where already shewn.

Fifthly, *that the dissolution* of sulphureous bodies is made by a substance inherent, and mixt with the Air, that is like, if not the very same, with that which is fixt in *Salt-peter*, which by multitudes of Experiments that may be made with *Saltpeter*, will, I think, most evidently be demonstrated.

Sixthly, *that in this dissolution* of bodies by the Air, a certain part is united and mixt, or dissolv'd and turn'd into the Air, and made to fly up and down with it in the same manner as a *metalline* or other body dissolv'd into any *menstruums*, does follow the motions and progresses of that *menstruum* till it be precipitated.

Seventhly, That as there is one part that is dissoluble by the Air, so are there other parts with which the parts of the Air mixing and uniting, do make a *Coagulum*, or *precipitation*, as one may call it, which causes it to be separated from the Air, but this *precipitate* is so light, and in so small and rarify'd or porous clusters, that it is very volatil, and is easily carry'd up by the motion of the Air, though afterwards, when the heat and agitation

agitation that kept it rarify'd ceases, it easily condenses, and commixt with other indissoluble parts, it sticks and adheres to the next bodies it meets withall; and this is a certain *Salt* that may be extracted out of *Soot*.

Eighthly, that many indissoluble parts being very apt and prompt to be rarify'd, and so, whilest they continue in that heat and agitation, are lighter then the Ambient Air, are thereby thrust and carry'd upwards with great violence, and by that means carry along with them, not onely that *Saline concrete* I mention'd before, but many terrestrial, or indissoluble and irrarefiable parts, nay, many parts also which are dissoluble, but are not suffer'd to stay long enough in a sufficient heat to make them prompt and apt for that action. And therefore we find in *Soot*, not onely a part, that being continued longer in a competent heat, will be dissolv'd by the Air, or take fire and burn; but a part also which is fixt, terrestrial, and irrarefiable.

Ninthly, that as there are these several parts that will rarifie and fly, or be driven up by the heat, so are there many others, that as they are indissoluble by the *aerial menstruum*, so are they of such sluggish and gross parts, that they are not easily rarify'd by heat, and therefore cannot be rais'd by it; the volatility or fixtness of a body seeming to consist only in this, that the one is of a texture, or has component parts that will be easily rarify'd into the form of Air, and the other, that it has such as will not, without much ado, be brought to such a constitution; and this is that part which remains behind in a white body call'd Ashes, which contains a substance, or *Salt*, which Chymists call *Alkali*: what the particular natures of each of these bodies are, I shall not here examine, intending it in another place, but shall rather add that this *Hypothesis* does so exactly agree with all *Phænomena* of Fire, and so genuinely explicate each particular circumstance that I have hitherto observ'd, that it is more then probable, that this cause which I have assign'd is the true adequate, real, and onely cause of those *Phænomena*; And therefore I shall proceed a little further, to shew the nature and use of the Air.

Tenthly, therefore the dissolving parts of the Air are but few, that is, it seems of the nature of those *Saline menstruums*, or spirits, that have very much flegme mixt with the spirits, and therefore a small parcel of it is quickly glutted, and will dissolve no more; and therefore unless some fresh part of this *menstruum* be apply'd to the body to be dissolv'd, the action ceases, and the body leaves to be dissolv'd and to shine, which is the Indication of it, though plac'd or kept in the greatest heat; whereas *Salt-peter* is a *menstruum*, when melted and red-hot, that abounds more with those Dissolvent particles, and therefore as a small quantity of it will dissolve a great sulphureous body, so will the dissolution be very quick and violent.

Therefore in the *Eleventh* place, it is observable, that, as in other solutions, if a copious and quick supply of fresh *menstruum*, though but weak, be poured on, or applied to the dissoluble body, it quickly consumes it: So this *menstruum* of the Air, if by Bellows, or any other such contrivance, it be copiously apply'd to the shining body, is found to

dissolve

diſſolve it as ſoon, and as violently as the more ſtrong *menſtruum* of melted *Nitre*.

Therefore twelfthly, it ſeems reaſonable to think that there is no ſuch thing as an Element of Fire that ſhould attract or draw up the flame, or towards which the flame ſhould endeavour to aſcend out of a deſire or appetite of uniting with that as its *Homogeneal* primitive and generating Element; but that that ſhining tranſient body which we call *Flame*, is nothing elſe but a mixture of Air, and volatil ſulphureous parts of diſſoluble or combuſtible bodies, which are acting upon each other whil'ſt they aſcend, that is, flame ſeems to be a mixture of Air, and the combuſtible volatil parts of any body, which parts the encompaſſing Air does diſſolve or work upon, which action, as it does intend the heat of the *aerial* parts of the diſſolvent, ſo does it thereby further rarifie thoſe parts that are acting, or that are very neer them, whereby they growing much lighter then the heavie parts of that *Menſtruum* that are more remote, are thereby protruded and driven upward; and this may be eaſily obſerv'd alſo in diſſolutions made by any other *menſtruum*, eſpecially ſuch as either create heat or bubbles. Now, this action of the *Menſtuum*, or *Air*, on the diſſoluble parts, is made with ſuch violence, or is ſuch, that it imparts ſuch a motion or pulſe to the *diaphanous* parts of the Air, as I have elſewhere ſhewn is requiſite to produce light.

This *Hypotheſis* I have endeavoured to raiſe from an Infinite of Obſervations and Experiments, the proceſs of which would be much too long to be here inſerted, and will perhaps another time afford matter copious enough for a much larger Diſcourſe, the Air being a Subject which (though all the world has hitherto liv'd and breath'd in, and been unconverſant about) has yet been ſo little truly examin'd or explain'd, that a diligent enquirer will be able to find but very little information from what has been (till of late) written of it: But being once well underſtood, it will, I doubt not, inable a man to render an intelligible, nay probable, if not the true reaſon of all the *Phænomena* of Fire, which, as it has been found by Writers and Philoſophers of all Ages a matter of no ſmall difficulty, as may be ſufficiently underſtood by their ſtrange *Hypotheſes*, and unintelligible Solutions of ſome few *Phænomena* of it; ſo will it prove a matter of no ſmall concern and uſe in humane affairs, as I ſhall elſewhere endeavour to manifeſt when I come to ſhew the uſe of the Air in reſpiration, and for the preſervation of the life, nay, for the conſervation and reſtauration of the health and natural conſtitution of mankind as well as all other aereal *animals*, as alſo the uſes of this principle or propriety of the Air in chymical, mechanical, and other operations. In this place I have onely time to hint an *Hypotheſis*, which, if God permit me life and opportunity, I may elſewhere proſecute, improve and publiſh. In the mean time, before I finiſh this Diſcourſe, I muſt not forget to acquaint the Reader, that having had the liberty granted me of making ſome trials on a piece of *Lignum foſſile* ſhewn to the Royal Society, by the eminently Ingenious and Learned Phyſician, Doctor *Ent*, who receiv'd it for a Preſent from the famous *Ingenioſo Cavalliero de Pozzi*, it being one of th[illegible] [illegible]ireſt

and best pieces of *Lignum fossile* he had seen; Having (I say) taken a small piece of this Wood, and examin'd it, I found it to burn in the open Air almost like other Wood, and insteed of a resinous smoak or fume, it yielded a very bituminous one, smelling much of that kind of sent: But that which I chiefly took notice of, was, that cutting off a small piece of it, about the bigness of my Thumb, and charring it in a *Cruoible* with Sand, after the manner I above prescrib'd, I found it infinitely to abound with the smaller sort of pores, so extreme thick, and so regularly perforating the substance of it long-ways, that breaking it off a-cross, I found it to look very like an Honey-comb; but as for any of the second, or bigger kind of pores, I could not find that it had any; so that it seems, whatever were the cause of its production, it was not without those small kind of pores which we have onely hitherto found in Vegetable bodies: and comparing them with the pores which I have found in the Charcoals that I by this means made of several other kinds of Wood, I find it resemble none so much as those of Firr, to which it is not much unlike in grain also, and several other proprieties.

And therefore, what ever is by some, who have written of it, and particularly by *Francisco Stelluto*, who wrote a Treatise in *Italian* of that Subject, which was Printed at *Rome*, 1637. affirm'd that it is a certain kind of Clay or Earth, which in tract of time is turn'd into Wood, I rather suspect the quite contrary, that it was at first certain great Trees of Fir or Pine, which by some Earthquake, or other casualty, came to be buried under the Earth, and was there, after a long time's residence (according to the several natures of the encompassing adjacent parts) either rotted and turn'd into a kind of Clay, or *petrify'd* and turn'd into a kind of Stone, or else had its pores fill'd with certain Mineral juices, which being stayd in them, and in tract of time coagulated, appear'd, upon cleaving out, like small Metaline Wires, or else from some flames or scorching forms that are the occasion oftentimes, and usually accompany Earthquakes, might be blasted and turn'd into Coal, or else from certain *subterraneous* fires which are affirm'd by that Authour to abound much about those parts (namely, in a Province of *Italy*, call'd *Umbria*, now the *Dutchie* of *Spoletto*, in the Territory of *Todi*, anciently call'd *Tudor*; and between the two Villages of *Collesecco* and *Rosaro* not far distant from the high-way leading to *Rome*, where it is found in greater quantity then elsewhere) are by reason of their being encompassed with Earth, and so kept close from the dissolving Air, charr'd and converted into Coal. It would be too long a work to describe the several kinds of pores which I met withall, and by this means discovered in several other Vegetable bodies; nor is it my present design to expatiate upon Instances of the same kind, but rather to give a Specimen of as many kinds as I have had opportunity as yet of observing, reserving the prosecution and enlarging on particulars till a more fit opportunity; and in prosecution of this design, I shall here add:

Observ.

Sch

Fig: 1



Fig: 2:



Obſerv. XVII. *Of* Petrify'd wood, *and other* Petrify'd bodies.

OF this ſort of ſubſtance, I obſerv'd ſeveral pieces of very differing kinds, both for their outward ſhape, colour, grain, *texture*, hardneſs, *&c.* ſome being brown and rediſh; others gray, like a Hone; others black, and Flint-like: ſome ſoft, like a Slate or Whetſtone, others as hard as a Flint, and as brittle. That which I more particular examin'd, was a piece about the bigneſs of a mans hand, which ſeem'd to have been a part of ſome large tree, that by rottenneſs had been broken off from it before it began to be *petrify'd.*

And indeed, all that I have yet ſeen, ſeem to have been rotten Wood before the petrifaction was begun; and not long ſince, examining and viewing a huge great *Oak*, that ſeem'd with meer age to be rotten as it ſtood, I was very much confirm'd in this opinion; for I found, that the grain, colour, and ſhape of the Wood, was exactly like this *petrify'd* ſubſtance; and with a *Microſcope*, I found, that all thoſe *Microſcopical* pores, which in ſappy or firm and ſound Wood are fill'd with the natural or innate juices of thoſe Vegetables, in this they were all empty, like thoſe of *Vegetables charr'd*; but with this difference, that they ſeem'd much larger then I have ſeen any in *Char-coals*; nay, even then thoſe of Coals made of great blocks of Timber, which are commonly call'd *Old-coals.*

The reaſon of which difference may probably be, that the charring of Vegetables, being an operation quickly perform'd, and whileſt the Wood is ſappy, the more ſolid parts may more eaſily ſhrink together, and contract the pores or *interſtitia* between them, then in the rotten Wood, where that natural juice ſeems onely to be waſh'd away by *adventitious* or unnatural moiſture; and ſo though the natural juice be waſted from between the firm parts, yet thoſe parts are kept aſunder by the *adventitious* moyſtures, and ſo by degrees ſettled in thoſe poſtures.

And this I likewiſe found in the *petrify'd* Wood, that the pores were ſomewat bigger then thoſe of *Charcoal*, each pore being neer upon half as bigg again, but they did not bear that diſproportion which is expreſt in the tenth *Scheme*, between the ſmall ſpecks or pores in the firſt Figure (which repreſenteth the pores of Coal or Wood charr'd) and the black ſpots of the ſecond Figure (which repreſent the like *Microſcopical pores* in the *petrify'd* Wood) for theſe laſt were drawn by a *Microſcope* that magnify'd the object above ſix times more in Diameter then the *Microſcope* by which thoſe pores of Coal were obſerv'd.

Now, though they were a little bigger, yet did they keep the exact figure and order of the pores of Coals and of rotten Wood, which laſt alſo were much of the ſame cize.

The other Obſervations on this *petrify'd* ſubſtance, that a while ſince, by the appointment of the *Royal Society*, I made, and preſented to them an account of, were theſe that follow, which had the honour done them

by the most accomplish'd Mr. *Evelin*, my highly honour'd friend, to be inserted and published among those excellent Observations wherewith his *Sylva* is replenish'd, and would therefore have been here omitted, had not the Figure of them, as they appear'd through the *Microscope* been before that engraven.

This *Petrify'd* substance resembled Wood, in that

First, all the parts of it seem'd not at all *dislocated*, or alter'd from their natural Position, whil'st they were Wood, but the whole piece retain'd the exact shape of Wood, having many of the conspicuous pores of wood still remaining pores, and shewing a manifest difference visible enough between the grain of the Wood and that of the bark, especially when any side of it was cut smooth and polite; for then it appear'd to have a very lovely grain, like that of some curious close Wood.

Next (it resembled Wood) in that all the smaller and (if I may so call those which are onely visible with a good magnifying Glass) *Microscopical* pores of it appear (both when the substance is cut and polish'd *transversly* and *parallel* to the pores of it) perfectly like the *Microscopical* pores of several kinds of Wood, especially like and equal to those of several sorts of rotten Wood which I have since observ'd, retaining both the shape, position and magnitude of such pores. It was differing from Wood:

First, in *weight*, being to common water as $3\frac{1}{4}$ to 1. whereas there are few of our *English* Woods, that when very dry are found to be full as heavie as water.

Secondly, in *hardness*, being very neer as hard as a Flint; and in some places of it also resembling the grain of a Flint: and, like it, it would very readily cut Glass, and would not without difficulty, especially in some parts of it, be scratch'd by a black hard Flint: It would also as readily strike fire against a Steel, or against a Flint, as any common Flint.

Thirdly, in the *closeness* of it, for though all the *Microscopical* pores of this *petrify'd* substance were very conspicuous in one position, yet by altering that position of the polish'd surface to the light, it was also manifest, that those pores appear'd darker then the rest of the body, onely because they were fill'd up with a more duskie substance, and not because they were hollow.

Fourthly, in its *incombustibleness*, in that it would not burn in the fire; nay, though I kept it a good while red-hot in the flame of a Lamp, made very *intense* by the blast of a small Pipe, and a large Charcoal, yet it seem'd not at all to have diminish'd its extension; but only I found it to have chang'd its colour, and to appear of a more dark and duskie brown colour; nor could I perceive that those parts which seem'd to have been Wood at first, were any thing wasted, but the parts appear'd as solid and close as before. It was further observable also, that as it did not consume like Wood, so neither did it crack and flie like a Flint, or such like hard Stone, nor was it long before it appear'd red-hot.

Fifthly, in its *dissolubleness*; for putting some drops of distill'd *Vinegar* upon the Stone, I found it presently to yield very many Bubbles, just like those which may be observ'd in spirit of *Vinegar* when it corrodes *corals*, though

though perhaps many of those small Bubbles might proceed from some small parcels of Air which were driven out of the pores of this *petrify'd* substance by the insinuating liquid *menstruum*.

Sixthly, in its *rigidness* and *friability*, being not at all flexible but brittle like a Flint, insomuch that I could with one knock of a Hammer break off a piece of it, and with a few more, reduce that into a pretty fine powder.

Seventhly, it seem'd also very differing from Wood to the *touch*, *feeling* more cold then Wood usually does, and much like other close stones and Minerals.

The Reasons of all which *Phænomena* seem to be,

That this *petrify'd* Wood having lain in some place where it was well soak'd with *petrifying* water (that is, such a water as is well *impregnated* with stony and earthy particles) did by degrees separate, either by straining and *filtration*, or perhaps, by *precipitation*, *cohesion* or *coagulation*, abundance of stony particles from the permeating water, which stony particles, being by means of the fluid *vehicle* convey'd, not onely into the *Microscopical* pores, and so perfectly stoping them up, but also into the pores or *interstitia*, which may, perhaps, be even in the texture or *Schematisme* of that part of the Wood, which, through the *Microscope*, appears most solid, do thereby so augment the weight of the Wood, as to make it above three times heavier then water, and perhaps, six times as heavie as it was when Wood.

Next, they thereby so lock up and fetter the parts of the Wood, that the fire cannot easily make them flie away, but the action of the fire upon them is onely able to *Char* those parts, as it were, like a piece of Wood, if it be clos'd very fast up in Clay, and kept a good while red-hot in the fire, will by the heat of the fire be charr'd and not consum'd, which may, perhaps, also be somewhat of the cause, why the *petrify'd* substance appear'd of a dark brown colour after it had been burnt.

By this *intrusion* of the *petrifying* particles, this substance also becomes hard and *friable*; for the smaller pores of the Wood being perfectly wedg'd, and stuft up with those stony particles, the small parts of the Wood have no places or pores into which they may slide upon bending, and consequently little or no flexion or yielding at all can be caus'd in such a substance.

The remaining particles likewise of the Wood among the stony particles, may keep them from cracking and flying when put into the fire, as they are very apt to do in a Flint.

Nor is Wood the onely substance that may by this kind of *transmutation* be chang'd into stone; for I my self have seen and examin'd very many kinds of substances, and among very credible Authours, we may meet with Histories of such *Metamorphoses* wrought almost on all kind of substances, both *Vegetable* and *Animal*, which Histories, it is not my business at present, either to relate, or *epitomise*, but only to set down some Observation I lately made on several kind of *petrify'd* Shels, found about *Keinsham*, which lies within four or five miles of *Bristol*, which are commonly call'd *Serpentine-stones*.

Exami-

Examining ſeveral of theſe very curiouſly figur'd bodies (which are commonly thought to be Stones form'd by ſome extraordinary *Plaſtick virtue latent* in the Earth itſelf) I took notice of theſe particulars:

Firſt, that theſe figured bodies, or ſtones, were of very differing ſubſtances, as to hardneſs: ſome of Clay, ſome Marle, ſome ſoft Stone, almoſt of the hardneſs of thoſe ſoft ſtones which Maſons call Fire-ſtone, others as hard as Portland ſtone, others as hard as Marble, and ſome as hard a a Flint or Cryſtal.

Next, they were of very differing ſubſtances as to tranſparency and colour; ſome white, ſome almoſt black, ſome brown, ſome Metalline, or like Marchaſites; ſome tranſparent like white Marble, others like flaw'd Cryſtal, ſome gray, ſome of divers colours; ſome radiated like theſe long *petrify'd drops*, which are commonly found at the *Peak*, and in other *ſubterraneous caverns*, which have a kind of pith in the middle.

Thirdly, that they were very different as to the manner of their outward figuration; for ſome of them ſeem'd to have been the ſubſtance that had fill'd the Shell of ſome kind of Shel-fiſh; others, to have been the ſubſtance that had contain'd or enwrapp'd one of thoſe Shels, on both which, the perfect impreſſion either of the inſide or outſide of ſuch Shells ſeem'd to be left, but for the moſt part, thoſe impreſſions ſeem'd to be made by an imperfect or broken Shell, the great end or mouth of the Shell being always wanting, and oftentimes the little end, and ſometimes half, and in ſome there were impreſſions, juſt as if there had been holes broken in the figurating, imprinting or moulding Shell; ſome of them ſeem'd to be made by ſuch a Shell very much bruſed or flaw'd, inſomuch that one would verily have thought that very figur'd ſtone had been broken or bruſed whilſt a gelly, as 'twere, and ſo hardned, but within in the grain of the ſtone, there appear'd not the leaſt ſign of any ſuch bruſe or breaking, but onely on the very uttermoſt ſuperficies.

Fourthly, they were very different, as to their outward covering, ſome having the perfect Shell, both in figure, colour, and ſubſtance, ſticking on upon its ſurface, and adhering to it, but might very eaſily be ſeparated from it, and like other common *Cockle* or *Scolop-ſhels*, which ſome of them moſt accurately reſembled, were very diſſoluble in common *Vinegar*, others of them, eſpecially thoſe *Serpentine*, or *Helical ſtones* were cover'd or retained the ſhining or Pearl-colour'd ſubſtance of the inſide of a Shel, which ſubſtance, on ſome parts of them, was exceeding thin, and might very eaſily be rubbed off; on other parts it was pretty thick, and retained a white coat, or flaky ſubſtance on the top, juſt like the outſides of ſuch Shells; ſome of them had very large pieces of the Shell very plainly ſticking on to them, which were eaſily to be broken or flaked off by degrees: they likewiſe, ſome of them retain'd all along the ſurface of them very pretty kind of *ſutures*, ſuch as are obſerv'd in the ſkulls of ſeveral kinds of living creatures, which *ſutures* were moſt curiouſly ſhap'd in the manner of leaves, and every one of them in the ſame Shell, exactly one like another, which I was able to diſcover plainly enough with my naked eye, but more perfectly and diſtinctly with my *Microſcope*; all

theſe

these *sutures*, by breaking some of these stones, I found to be the *termini*, or boundings of certain *diaphragms*, or partitions, which seem'd to divide the cavity of the Shell into a multitude of very proportionate and regular *cells* or *caverns*, these *Diaphragms*, in many of them, I found very perfect and compleat, of a very distinct substance from that which fill'd the cavities, and exactly of the same kind with that which covered the outside, being for the most part whitish, or *mother-of-pearl* colour'd.

As for the cavities between those *Diaphragms*, I found some of them fill'd with Marle, and others with several kinds of stones, others, for the most part hollow, onely the whole cavity was usually covered over with a kind of *tartareous petrify'd* substance, which stuck about the sides, and was there shot into very curious regular Figures, just as *Tartar*, or other dissolv'd Salts are observ'd to stick and *crystallize* about the sides of the containing Vessels; or like those little *Diamants* which I before observed to have covered the vaulted cavity of a Flint; others had these cavities all lin'd with a kind of *metalline* or *marchasite-like* substance, which with a *Microscope* I could as plainly see most curiously and regularly figured, as I had done those in a Flint.

From all which, and several other particulars which I observ'd, I cannot but think, that all these, and most other kinds of stony bodies which are found thus strangely figured, do owe their formation and figuration, not to any kind of *Plastick virtue* inherent in the earth, but to the Shells of certain Shel-fishes, which, either by some Deluge, Inundation, Earthquake, or some such other means, came to be thrown to that place, and there to be fill'd with some kind of Mudd or Clay, or *petrifying* Water, or some other substance, which in tract of time has been settled together and hardned in those shelly moulds into those shaped substances we now find them; that the great and thin end of these Shells by that Earthquake, or what ever other extraordinay cause it was that brought them thither, was broken off; and that many others were otherwise broken, bruised and disfigured; that these Shells which are thus *spirallied* and separated with *Diaphragmes*, were some kind of *Nautili* or *Porcelane shells*; and that others were shells of *Cockles*, *Muscles*, *Periwincles*, *Scolops*, &c. of various sorts; that these Shells in many, from the particular nature of the containing or enclos'd Earth, or some other cause, have in tract of time rotted and mouldred away, and onely left their impressions, both on the containing and contained substances; and so left them pretty loose one within another, so that they may be easily separated by a knock or two of a Hammer. That others of these Shells, according to the nature of the substances adjacent to them, have, by a long continuance in that posture, been *petrify'd* and turn'd into the nature of stone, just as I even now observ'd several sorts of Wood to be. That oftentimes the Shell may be found with one kind of substance within, and quite another without, having, perhaps, been fill'd in one place, and afterwards translated to another, which I have very frequently observ'd in *Cockle*, *Muscle*, *Periwincle*, and other shells, which I have found by the Sea side. Nay, further, that some parts of the same Shell may be fill'd in one place, and

some

ſome other caverns in another, and others in a third, or a fourth, or a fifth place, for ſo many differing ſubſtances have I found in one of theſe *petrify'd* Shells, and perhaps all theſe differing from the encompaſſing earth or ſtone; the means how all which varieties may be caus'd, I think, will not be difficult to conceive, to any one that has taken notice of thoſe Shells, which are commonly found on the Sea ſhore: And he that ſhall throughly examine ſeveral kinds of ſuch curiouſly form'd ſtones, will (I am very apt to think) find reaſon to ſuppoſe their generation or formation to be aſcribable to ſome ſuch accidents as I have mention'd, and not to any *Plaſtick virtue*: For it ſeems to me quite contrary to the infinite prudence of Nature, which is obſervable in all its works and productions, to deſign every thing to a determinate end, and for the attaining of that end, makes uſe of ſuch ways as are (as farr as the knowledge of man has yet been able to reach) altogether conſonant, and moſt agreeable to man's reaſon, and of no way or means that does contradict, or is contrary to humane Ratiocination; whence it has a long time been a general obſervation and *maxime*, that *Nature does nothing in vain*; It ſeems, I ſay, contrary to that great Wiſdom of Nature, that theſe prettily ſhap'd bodies ſhould have all thoſe curious Figures and contrivances (which many of them are adorn'd and contriv'd with) generated or wrought by a *Plaſtick virtue*, for no higher end then onely to exhibite ſuch a form; which he that ſhall throughly conſider all the circumſtances of ſuch kind of Figur'd bodies, will, I think, have great reaſon to believe, though, I confeſs, one cannot preſently be able to find out what Nature's deſigns are. It were therefore very deſirable, that a good collection of ſuch kind of figur'd ſtones were collected; and as many particulars, circumſtances, and informations collected with them as could be obtained, that from ſuch a Hiſtory of Obſervations well rang'd, examin'd and digeſted, the true original or production of all thoſe kinds of ſtones might be perfectly and ſurely known; ſuch as are *Thunder-ſtones*, *Lapides Stellares*, *Lapides Judaici*, and multitudes of other, whereof mention is made in *Aldrovandus Wormius*, and other Writers of Minerals.

Obſerv. XVIII. *Of the* Schematiſme *or* Texture *of* Cork, *and of the Cells and Pores of ſome other ſuch frothy Bodies.*

I Took a good clear piece of Cork, and with a Pen-knife ſharpen'd as keen as a Razor, I cut a piece of it off, and thereby left the ſurface of it exceeding ſmooth, then examining it very diligently with a *Microſcope*, me thought I could perceive it to appear a little porous; but I could not ſo plainly diſtinguiſh them, as to be ſure that they were pores, much leſs what Figure they were of: But judging from the lightneſs and yielding quality of the Cork, that certainly the texture could not be ſo curious,

Fig: 1.



Fig: 2.



curious, but that possibly, if I could use some further diligence, I might find it to be discernable with a *Microscope*, I with the same sharp Pen-knife, cut off from the former smooth surface an exceeding thin piece of it, and placing it on a black object Plate, because it was it self a white body, and casting the light on it with a deep *plano-convex Glass*, I could exceeding plainly perceive it to be all perforated and porous, much like a Honey-comb, but that the pores of it were not regular; yet it was not unlike a Honey-comb in these particulars.

First, in that it had a very little solid substance, in comparison of the empty cavity that was contain'd between, as does more manifestly appear by the Figure A and B of the XI. *Scheme*, for the *Interstitia*, or walls (as I may so call them) or partitions of those pores were neer as thin in proportion to their pores, as those thin films of Wax in a Honey-comb (which enclose and constitute the *sexangular cells*) are to theirs.

Next, in that these pores, or cells, were not very deep, but consisted of a great many little Boxes, separated out of one continued long pore, by certain *Diaphragms*, as is visible by the Figure B, which represents a sight of those pores split the long-ways.

I no sooner discern'd these (which were indeed the first *microscopical* pores I ever saw, and perhaps, that were ever seen, for I had not met with any Writer or Person, that had made any mention of them before this) but me thought I had with the discovery of them, presently hinted to me the true and intelligible reason of all the *Phænomena* of Cork; As,

First, if I enquir'd why it was so exceeding light a body? my *Microscope* could presently inform me that here was the same reason evident that there is found for the lightness of froth, an empty Honey-comb, Wool, a Spunge, a Pumice-stone, or the like; namely, a very small quantity of a solid body, extended into exceeding large dimensions.

Next, it seem'd nothing more difficult to give an intelligible reason, why Cork is a body so very unapt to suck and drink in Water, and consequently preserves it self, floating on the top of Water, though left on it never so long: and why it is able to stop and hold air in a Bottle, though it be there very much condens'd and consequently presses very strongly to get a passage out, without suffering the least bubble to pass through its substance. For, as to the first, since our *Microscope* informs us that the substance of Cork is altogether fill'd with Air, and that that Air is perfectly enclosed in little Boxes or Cells distinct from one another. It seems very plain, why neither the Water, nor any other Air can easily insinuate it self into them, since there is already within them an *intus existens*; and consequently, why the pieces of Cork become so good floats for Nets, and stopples for Viols, or other close Vessels.

And thirdly, if we enquire why Cork has such a springiness and swelling nature whem compress'd? and how it comes to suffer so great a compression, or seeming penetration of dimensions, so as to be made a substance as heavie again and more, bulk for bulk, as it was before compression, and yet suffer'd to return, is found to extend it self again into the same space? Our *Microscope* will easily inform us, that the whole mass

consists of an infinite company of small Boxes or Bladders of Air, which is a substance of a springy nature, and that will suffer a considerable condensation (as I have several times found by divers trials, by which I have most evidently condens'd it into less then a twentieth part of its usual dimensions neer the Earth, and that with no other strength then that of my hands without any kind of forcing Engine, such as Racks, Leavers, Wheels, Pullies, or the like, but this onely by and by) and besides, it seems very probable that those very films or sides of the pores, have in them a springing quality, as almost all other kind of Vegetable substances have, so as to help to restore themselves to their former position.

And could we so easily and certainly discover the *Schematisme* and *Texture* even of these films, and of several other bodies, as we can these of Cork; there seems no probable reason to the contrary, but that we might as readily render the true reason of all their *Phænomena*; as namely, what were the cause of the springiness, and toughness of some, both as to their flexibility and restitution. What, of the friability or brittleness of some others, and the like; but till such time as our *Microscope*, or some other means, enable us to discover the true *Schematism* and *Texture* of all kinds of bodies, we must grope, as it were, in the dark, and onely gheſs at the true reasons of things by similitudes and comparisons.

But, to return to our Observation. I told several lines of these pores, and found that there were usually about threescore of these small Cells placed end-ways in the eighteenth part of an Inch in length, whence I concluded there must be neer eleven hundred of them, or somewhat more then a thousand in the length of an Inch, and therefore in a square Inch above a Million, or 1166400. and in a Cubick Inch, above twelve hundred Millions, or 1259712000. a thing almost incredible, did not our *Microscope* assure us of it by ocular demonstration; nay, did it not discover to us the pores of a body, which were they *diaphragm'd*, like those of Cork, would afford us in one Cubick Inch, more then ten times as many little Cells, as is evident in several charr'd Vegetables; so prodigiously curious are the works of Nature, that even these conspicuous pores of bodies, which seem to be the channels or pipes through which the *Succus nutritius*, or natural juices of Vegetables are convey'd, and seem to correspond to the veins, arteries and other Vessels in sensible creatures, that these pores I say, which seem to be the Vessels of nutrition to the vastest body in the World, are yet so exceeding small, that the *Atoms* which *Epicurus* fancy'd would go neer to prove too bigg to enter them, much more to constitute a fluid body in them. And how infinitely smaller then must be the Vessels of a Mite, or the pores of one of those little Vegetables I have discovered to grow on the back-side of a Rose-leaf, and shall anon more fully describe, whose bulk is many millions of times less then the bulk of the small shrub it grows on; and even that shrub, many millions of times less in bulk then several trees (that have heretofore grown in *England*, and are this day flourishing in other hotter Climates, as we are very credibly inform'd) if at least the pores of this small Vegetable should keep any such proportion to the body of it, as we have found these pores

of

of other Vegetables to do to their bulk. But of these pores I have said more elsewhere.

To proceed then, Cork seems to be by the transverse constitution of the pores, a kind of *Fungus* or Mushrome, for the pores lie like so many Rays tending from the center, or pith of the tree, outwards; so that if you cut off a piece from a board of Cork transversly, to the flat of it, you will, as it were, split the pores, and they will appear just as they are express'd in the Figure B of the XI. *Scheme*. But if you shave off a very thin piece from this board, parallel to the plain of it, you will cut all the pores transversly, and they will appear almost as they are express'd in the Figure A, save onely the solid *Interstitia* will not appear so thick as they are there represented.

So that Cork seems to suck its nourishment from the subjacent bark of the Tree immediately, and to be a kind of excrescence, or a substance distinct from the substances of the entire Tree, something *analogus* to the Mushrome, or Moss on other Trees, or to the hairs on Animals. And having enquir'd into the History of Cork, I find it reckoned as an excrescency of the bark of a certain Tree, which is distinct from the two barks that lie within it, which are common also to other trees; That 'tis some time before the Cork that covers the young and tender sprouts comes to be discernable; That it cracks, flaws, and cleaves into many great chaps, the bark underneath remaining entire; That it may be separated and remov'd from the Tree, and yet the two under-barks (such as are also common to that with other Trees) not at all injur'd, but rather helped and freed from an external injury. Thus *Jonstonus* in *Dendrologia*, speaking *de Subere*, says, *Arbor est procera, Lignum est robustum, dempto cortice in aquis non fluitat, Cortice in orbem detracto juvatur, crascescens enim præstringit & strangulat, intra triennium iterum repletur: Caudex ubi adolescit crassus, cortex superior densus carnosus, duos digitos crassus, scaber, rimosus, & qui nisi detrahatur dehiscit, alioque subnascente expellitur, interior qui subest novellus ita rubet ut arbor minio picta videatur.* Which Histories, if well consider'd, and the tree, substance, and manner of growing, if well examin'd, would, I am very apt to believe, much confirm this my conjecture about the origination of Cork.

Nor is this kind of Texture peculiar to Cork onely; for upon examination with my *Microscope*, I have found that the pith of an Elder, or almost any other Tree, the inner pulp or pith of the Cany hollow stalks of several other Vegetables: as of Fennel, Carrets, Daucus, Bur-docks, Teasels, Fearn, some kinds of Reeds, *&c.* have much such a kind of *Schematisme*, as I have lately shewn that of Cork, save onely that here the pores are rang'd the long-ways, or the same ways with the length of the Cane, whereas in Cork they are transverse.

The pith also that fills that part of the stalk of a Feather that is above the Quil, has much such a kind of texture, save onely that which way soever I set this light substance, the pores seem'd to be cut transversly; so that I ghess this pith which fills the Feather, not to consist of abundance of long pores separated with Diaphragms, as Cork does, but to be a kind

of ſolid or hardned froth, or a *congeries* of very ſmall bubbles conſolidated in that form, into a pretty ſtiff as well as tough concrete, and that each Cavern, Bubble, or Cell, is diſtinctly ſeparate from any of the reſt, without any kind of hole in the encompaſſing films, ſo that I could no more blow through a piece of this kinde of ſubſtance, then I could through a piece of Cork, or the ſound pith of an Elder.

But though I could not with my *Microſcope*, nor with my breath, nor any other way I have yet try'd, diſcover a paſſage out of one of thoſe cavities into another, yet I cannot thence conclude, that therefore there are none ſuch, by which the *Succus nutritius*, or appropriate juices of Vegetables, may paſs through them; for, in ſeveral of thoſe Vegetables, whil'ſt green, I have with my *Microſcope*, plainly enough diſcover'd theſe Cells or Poles fill'd with juices, and by degrees ſweating them out: as I have alſo obſerved in green Wood all thoſe long *Microſcopical* pores which appear in Charcoal perfectly empty of any thing but Air.

Now, though I have with great diligence endeavoured to find whether there be any ſuch thing in thoſe *Microſcopical* pores of Wood or Piths, as the *Valves* in the heart, veins, and other paſſages of Animals, that open and give paſſage to the contain'd fluid juices one way, and ſhut themſelves, and impede the paſſage of ſuch liquors back again, yet have I not hitherto been able to ſay any thing poſitive in it; though, me thinks, it ſeems very probable, that Nature has in theſe paſſages, as well as in thoſe of Animal bodies, very many appropriated Inſtruments and contrivances, whereby to bring her deſigns and end to paſs, which 'tis not improbable, but that ſome diligent Obſerver, if help'd with better *Microſcopes*, may in time detect.

And that this may be ſo, ſeems with great probability to be argued from the ſtrange *Phænomena* of ſenſitive Plants, wherein Nature ſeems to perform ſeveral Animal actions with the ſame *Schematiſm* or *Orginization* that is common to all Vegetables, as may appear by ſome no leſs inſtructive then curious Obſervations that were made by divers Eminent Members of the *Royal Society* on ſome of theſe kind of Plants, whereof an account was delivered in to them by the moſt Ingenious and Excellent *Phyſician*, Doctor *Clark*, which, having that liberty granted me by that moſt Illuſtrious Society, I have hereunto adjoyn'd.

Obſervations on the Humble *and* Senſible Plants *in* Mr. Chiffin's *Garden in Saint* James's *Park, made* Auguſt *the* 9th, 1661. *Preſent, the* Lord *Brouncker*, Sr. *Robert Moray*, Dr. *Wilkins*, Mr. *Evelin*, Dr. *Henſhaw, and* Dr. *Clark*.

There are four Plants, two of which are little ſhrub Plants, with a little ſhort ſtock, about an Inch above the ground, from whence are ſpread ſeveral ſticky branches, round, ſtreight, and ſmooth,

ſmooth in the diſtances between the Sprouts, but juſt under the Sprouts there are two ſharp thorny prickles, broad in the letting on, as in the Bramble, one juſt under the Sprout, the other on the oppoſite ſide of the branch.

The diſtances betwixt the Sprouts are uſually ſomething more then an Inch, and many upon a Branch, according to its length, and they grew ſo, that if the lower Sprout be on the left ſide of the Branch, the next above is on the right, and ſo to the end, not ſprouting by pairs. See Schem. II. Fig. 2.

At the end of each Sprout are generally four ſprigs, two at the Extremity, and one on each ſide, juſt under it. At the firſt ſprouting of theſe from the Branch to the Sprig where the leaves grow, they are full of little ſhort white hairs, which wear off as the leaves grow, and then they are ſmooth as the Branch.

Upon each of theſe ſprigs, are, for the moſt part, eleven pair of leaves, neatly ſet into the uppermoſt part of the little ſprig, exactly one againſt another, as it were in little *articulations*, ſuch as Anatomiſts call *Enarthroſis*, where the round head of a Bone is received into another fitted for its motion; and ſtanding very fitly to ſhut themſelves and touch, the pairs juſt above them cloſing ſomewhat upon them, as in the ſhut ſprig; ſo is the little round *Pedunculus* of this leaf fitted into a little cavity of the ſprig, viſible to the eye in a ſprig new pluck'd, or in a ſprig withered on the Branch, from which the leaves eaſily fall by touching.

The leaf being almoſt an oblong ſquare, and ſet into the *Pedunculus*, at one of the lower corners, receiveth from that not onely a *Spine*, as I may call it, which, paſſing through the leaf, divides it ſo length-ways that the outer-ſide is broader then the inner next the ſprig, but little *fibres* paſſing obliquely towards the oppoſite broader ſide, ſeem to make it here a little muſcular, and fitted to move the whole leaf, which, together with the whole ſprig, are ſet full with little ſhort whitiſh hairs.

One

One of these Plants, whose branch seem'd to be older and more grown then the other, onely the tender Sprouts of it, after the leaves are shut, fall and hang down; of the other, the whole branches fall to the ground, if the Sun shine very warm, upon the first taking off the Glass, which I therefore call the *humble Plant*.

The other two, which do never fall, nor do any of their branches flagg and hang down, shut not their leaves, but upon somewhat a hard stroke; the stalks seem to grow up from a root, and appear more *herbaceous*, they are round and smooth, without any prickle, the Sprouts from them have several pairs of sprigs, with much less leaves then the other on them, and have on each sprig generally seventeen pair.

Upon touching any of the sprigs with leaves on, all the leaves on that sprig contracting themselves by pairs, joyned their upper superficies close together.

Upon the dropping a drop of *Aqua fortis* on the sprig betwixt the leaves, *f f* all the leaves above shut presently, those below by pairs successively after, and by the lower leaves of the other branches, *l l*, *k k*, &c. and so every pair successively, with some little distance of time betwixt, to the top of each sprig, and so they continu'd shut all the time we were there. But I returning the next day, and several days since, found all the leaves dilated again on two of the sprigs; but from *f f*, where the *Aqua fortis* had dropped upwards, dead and withered; but those below on the same sprig, green, and closing upon the touch, and are so at this day, *August* 14.

With a pair of Scissers, as suddenly as it could be done, one of the leaves *b b* was clipped off in the middle, upon which that pair, and the pair above, closed presently, after a little interval, *d d*, then *e e*, and so the rest of the pairs, to the bottom of the sprig, and then the motion began in the lower pairs, *l l*, on the other sprigs, and so shut them by pairs upwards, though not with such distinct distances.

Under

Under a pretty large branch with its ſprigs on, there lying a large Shell betwixt two and three Inches below it, there was rubbed on a ſtrong ſented oyl, after a little time all the leaves on that ſprig were ſhut, and ſo they continued all the time of our ſtay there, but at my returne the next day, I found the poſition of the Shell alter'd, and the leaves expanded as before, and cloſing upon the touch.

Upon the application of the Sun-beams by a Burning-glaſs, the more *humble Plant* fell, the other ſhut their leaves.

We could not ſo apply the ſmoak of *Sulpher*, as to have any viſible effect from that, at two or three times trial; but on another trial, the ſmoak touching the leaves, it ſucceeded.

The *humble Plant* fell upon taking off the Glaſs wherewith it was covered.

Cutting off one of the little Sprouts, two or three drops of liquor were thruſt out of the part from whence that was cut, very cleer, and pellucid, of a bright greeniſh colour, taſting at firſt a little bitteriſh, but after leaving a licoriſh-like taſte in my mouth.

Since, going two or three times when it was cold, I took the Glaſſes from the more *humble Plant*, and it did not fall as formerly, but ſhut its leaves onely. But coming afterwards, when the Sun ſhone very warm, as ſoon as it was taken off, it fell as before.

Since I pluck'd off another ſprig, whoſe leaves were all ſhut, and had been ſo ſome time, thinking to obſerve the liquor ſhould come from that I had broken off, but finding none, though with preſſing, to come, I, as dexterouſly as I could, pull'd off one whoſe leaves were expanded, and then had upon the ſhutting of the leaves, a little of the mention'd liquor, from the end of the ſprig I had broken from the Plant. And this twice ſucceſſively, as often almoſt as I durſt rob the Plant.

But my curioſity carrying me yet further, I cut off one of the harder branches of the ſtronger Plant, and there came of the

liquor,

liquor, both from that I had cut, and that I had cut it from, without preſſure.

Which made me think, that the motion of this Plant upon touching, might be from this, that there being a conſtant *intercourſe* betwixt every part of this Plant and its root, either by a *circulation* of this liquor, or a conſtant preſſing of the ſubtiler parts of it to every extremity of the Plant. Upon every preſſure, from whatſoever it proceeds, greater then that which keeps it up, the ſubtile parts of this liquor are thruſt downwards, towards its *articulations* of the leaves, where, not having room preſently to get into the ſprig, the little round *pedunculus*, from whence the *Spine* and thoſe oblique *Fibres* I mention'd riſe, being dilated, the *Spine* and *Fibres* (being continued from it) muſt be contracted and ſhortned, and ſo draw the leaf upwards to joyn with its fellow in the ſame condition with it ſelf, where, being cloſed, they are held together by the implications of the little whitiſh hair, as well as by the ſtill retreating liquor, which diſtending the *Fibres* that are continued lower to the branch and root, ſhorten them above; and when the liquor is ſo much forced from the Sprout, whoſe *Fibres* are yet tender, and not able to ſupport themſelves, but by that tenſneſs which the liquor filling their *interſtices* gives them, the Sprout hangs and flags.

But, perhaps, he that had the ability and leiſure to give you the exact *Anatomy* of this pretty Plant, to ſhew you its *Fibres*, and viſible *Canales*, through which this fine liquor circulateth, or is moved, and had the faculty of better and more copiouſly expreſſing his Obſervations and conceptions, ſuch a one would eaſily from the motion of this liquor, ſolve all the *Phænomena*, and would not fear to affirm, that it is no obſcure ſenſation this Plant hath. But I have ſaid too much, I humbly ſubmit, and am ready to ſtand corrected.

I have not yet made ſo full and ſatisfactory Obſervations as I deſire on this Plant, which ſeems to be a Subject that will afford abundance of information.

information. But as farr as I have had opportunity to examine it, I have discovered with my *Microscope* very curious structures and contrivances; but designing much more accurate examinations and trials, both with my *Microscope*, and otherwise, as soon as the season will permit, I shall not till then add any thing of what I have already taken notice of; but as farr as I have yet observ'd, I judge the motion of it to proceed from causes very differing from those by which Gut-strings, or Lute-strings, the beard of a wilde *Oat*, or the beard of the Seeds of *Geranium*, *Moscatum*, or *Musk-grass* and other of kinds of *Cranes-bill*, move themselves. Of which I shall add more in the subsequent Observations on those bodies.

Observ. XIX. *Of a* Plant *growing in the blighted or yellow specks of* Damask-rose-leaves, Bramble-leaves, *and some other kind of leaves.*

I Have for several years together, in the Moneths of *June*, *July*, *August*, and *September* (when any of the green leaves of *Roses* begin to dry and grow yellow) observ'd many of them, especially the leaves of the old shrubs of *Damask-Roses*, all bespecked with yellow stains, and the under-sides just against them, to have little yellow hillocks of a gummous substance, and several of them to have small black spots in the midst of those yellow ones, which, to the naked eye, appear'd no bigger then the point of a Pin, or the smallest black spot or tittle of Ink one is able to make with a very sharp pointed Pen.

Examining these with a *Microscope*, I was able plainly to distinguish, up and down the surface, several small yellow knobs, of a kind of yellowish red gummy substance, out of which I perceiv'd there sprung multitudes of little cases or black bodies like Seed-cods, and those of them that were quite without the hillock of Gumm, disclos'd themselves to grow out of it with a small Straw-colour'd and transparent stem, the which seed and stem appear'd very like those of common Moss (which I elsewhere describe) but that they were abundantly less, many hundreds of them being not able to equalize one single seed Cod of Moss.

I have often doubted whether they were the seed Cods of some little Plant, or some kind of small Buds, or the Eggs of some very small Insect; they appear'd of a dark brownish red; some almost quite black, and of a Figure much resembling the seed-cod of Moss, but their stalks on which they grew were of a very fine transparent substance, almost like the stalk of mould, but that they seem'd somewhat more yellow.

That which makes me to suppose them to be Vegetables, is for that I perceiv'd many of those hillocks bare or destitute, as if those bodies lay yet conceal'd, as G. In others of them, they were just springing out of their gummy hillocks, which all seem'd to shoot directly outwards, as at A. In others, as at B, I found them just gotten out, with very little or no stalk,

and the Cods of an indifferent cize;but in others,as C, I found them begin to have little ſhort ſtalks, or ſtems; in others, as D, thoſe ſtems were grown bigger, and larger; and in others, as at E, F, H, I, K, L, *&c.* thoſe ſtems and Cods were grown a great deal bigger, and the ſtalks were more bulky about the root, and very much taper'd towards the top, as at F and L is moſt viſible.

I did not find that any of them had any ſeed in them, or that any of them were hollow, but as they grew bigger and bigger, I found thoſe heads or Cods begin to turn their tops towards their roots, in the ſame manner as I had obſerv'd that of Moſs to do; ſo that in all likelihood, Nature did intend in that poſture, what ſhe does in the like ſeed-cods of greater bulk, that is, that the ſeed, when ripe, ſhould be ſhaken out and diſperſed at the end of it, as we find in Columbine Cods, and the like.

The whole Oval OOOO in the ſecond *Figure* of the 12. *Scheme* repreſents a ſmall part of a Roſe leaf, about the bigneſs of the little Oval in the hillock, C, marked with the Figure X. in which I have not particularly obſerv'd all the other forms of the ſurface of the Roſe-leaf, as being little to my preſent purpoſe.

Now, if theſe Cods have a ſeed in them ſo proportion'd to the Cod, as thoſe of *Pinks*, and *Carnations*, and *Columbines*, and the like, how unimaginably ſmall muſt each of thoſe ſeeds neceſſarily be, for the whole length of one of the largeſt of thoſe Cods was not $\frac{1}{500}$ part of an Inch; ſome not above $\frac{1}{1000}$, and therefore certainly, very many thouſand of them would be unable to make a bulk that ſhould be viſible to the naked eye; and if each of theſe contain the Rudiments of a young Plant of the ſame kind, what muſt we ſay of the pores and conſtituent parts of that?

The generation of this Plant ſeems in part,aſcribable to a kind of *Mildew* or *Blight*,whereby the parts of the leaves grow ſcabby, or putrify'd, as it were, ſo as that the moiſture breaks out in little ſcabs or ſpots, which, as I ſaid before, look like little knobs of a red gummous ſubſtance.

From this putrify'd ſcabb breaks out this little Vegetable; which may be ſomewhat like a *Mould* or *Moſs*; and may have its *equivocal* generation much after the ſame manner as I have ſuppoſed *Moſs* or *Mould* to have, and to be a more ſimple and uncompounded kind of vegetation, which is ſet a moving by the *putrifactive* and *fermentative* heat, joyn'd with that of the ambient aerial, when (by the putrifaction and decay of ſome other parts of the vegetable, that for a while ſtaid its progreſs) it is unſetter'd and left at liberty to move in its former courſe, but by reaſon of its *regulators*, moves and acts after quite another manner then it did when a *coagent* in the more compounded *machine* of the more perfect Vegetable.

And from this very ſame Principle, I imagine the *Miſleto* of Oaks, Thorns, Appletrees, and other Trees, to have its original: It ſeldom or never growing on any of thoſe Trees,till they begin to wax decrepid,and decay with age, and are peſter'd with many other infirmities.

Hither alſo may be referr'd thoſe multitudes and varieties of *Muſhrooms*, ſuch as that,call'd *Jews-ears*, all ſorts of *gray* and *green* Moſſes, &c. which

infest all kind of Trees, shrubs, and the like, especially when they come to any bigness. And this we see to be very much the method of Nature throughout its operations, *putrifactive Vegetables* very often producing a Vegetable of a much less compounded nature, and of a much inferiour tribe; and *putrefactive* animal substances degenerating into some kind of animal production of a much inferiour rank, and of a more simple nature.

Thus we find the humours and substances of the body, upon *putrifaction*, to produce strange kinds of moving Vermine: the *putrifaction* of the slimes and juices of the Stomack and Guts, produce Worms almost like Earth-worms, the Wheals in childrens hands produce a little Worm, call'd a *Wheal-worm*: The bloud and milk, and other humours, produce other kinds of Worms, at least, if we may believe what is deliver'd to us by very famous Authors; though, I confess, I have not yet been able to discover such my self.

And whereas it may seem strange that *Vinegar*, *Meal*, musty *Casks*, &c. are observ'd to breed their differing kinds of Insects, or living creatures, whereas they being Vegetable substances, seem to be of an inferiour kind, and so unable to produce a creature more noble, or of a more compounded nature then they themselves are of, and so without some concurrent seminal principle, may be thought utterly unfit for such an operation; I must add, that we cannot presently positively say, there are no animal substances, either mediately, as by the soil or fatning of the Plant from whence they sprung, or more immediately, by thereal mixture or composition of such substances, join'd with them; or perchance some kind of Insect, in such places where such kind of *putrifying* or *fermenting* bodies are, may, by a certain instinct of nature, eject some sort of seminal principle, which cooperating with various kinds of *putrifying* substances, may produce various kinds of Insects, or Animate bodies: For we find in most sorts of those lower degrees of Animate bodies, that the *putrifying* substances on which these Eggs, Seeds, or seminal principles are cast by the Insect, become, as it were, the *Matrices* or Wombs, that conduce very much to their generation, and may perchance also to their variation and alteration, much after the same manner, as, by strange and unnatural copulations, several new kinds of Animals are produc'd, as *Mules*, and the like, which are usually call'd Monstrous, because a little unusual, though many of them have all their principal parts as perfectly shap'd and adapted for their peculiar uses, as any of the most perfect Animals. If therefore the *putrifying* body, on which any kind of seminal or vital principle chances to be cast, become somewhat more then meerly a nursing and fostering helper in the generation and production of any kind of Animate body, the more neer it approaches the true nature of a Womb, the more power will it have on the by-blow it incloses. But of this somewhat more in the description of the *Water-gnat*. Perhaps some more accurate Enquiries and Observations about these matters might bring the Question to some certainty, which would be of no small concern in Natural Philosophy.

But that *putrifying* animal substances may produce animals of an inferior

kind, I ſee not any ſo very great a difficulty, but that one may, without much abſurdity, admit: For as there may be multitudes of contrivances that go to the making up of one compleat Animate body; ſo, That ſome of thoſe *coadjutors*, in the perfect exiſtence and life of it, may be vitiated, and the life of the whole deſtroyed, and yet ſeveral of the conſtituting contrivances remain intire, I cannot think it beyond imagination or poſſibility; no more then that a like accidental proceſs, as I have elſwhere hinted, may alſo be ſuppoſed to explicate the method of Nature in the *Metamorphoſis* of Plants. And though the difference between a Plant and an Animal be very great, yet I have not hitherto met with any ſo *cogent* an Argument, as to make me poſitive in affirming theſe two to be altogether *Heterogeneous*, and of quite differing kinds of Nature: And beſides, as there are many *Zoophyts*, and ſenſitive Plants (divers of which I have ſeen, which are of a middle nature, and ſeem to be Natures tranſition from one degree to another, which may be obſerv'd in all her other paſſages, wherein ſhe is very ſeldom obſerv'd to leap from one ſtep to another) ſo have we, in ſome Authors, Inſtances of Plants turning into Animals, and Animals into Plants, and the like; and ſome other very ſtrange (becauſe unheeded) proceedings of Nature; ſomething of which kind may be met with, in the deſcription of the *Water-Gnat*, though it be not altogether ſo direct to the preſent purpoſe.

But to refer this Diſcourſe of Animals to their proper places, I ſhall add, that though one ſhould ſuppoſe, or it ſhould be prov'd by Obſervations, that ſeveral of theſe kinds of Plants are accidentally produc'd by a caſual *putrifaction*, I ſee not any great reaſon to queſtion, but that, notwithſtanding its own production was as 'twere caſual, yet it may germinate and produce ſeed, and by it propagate its own, that is, a new Species. For we do not know, but that the Omnipotent and All-wiſe Creator might as directly deſign the ſtructure of ſuch a Vegetable, or ſuch an Animal to be produc'd out of ſuch or ſuch a *putrifaction* or change of this or that body, towards the conſtitution or ſtructure of which, he knew it neceſſary, or thought it fit to make it an ingredient; as that the digeſtion or moderate heating of an Egg, either by the Female, or the Sun, or the heat of the Fire, or the like, ſhould produce this or that Bird; or that *Putrifactive* and warm ſteams ſhould, out of the blowings, as they call them, that is, the Eggs of a Flie, produce a living Magot, and that, by degrees, be turn'd into an *Aurelia*, and that, by a longer and a proportion'd heat, be *tranſmuted* into a Fly. Nor need we therefore to ſuppoſe it the more imperfect in its kind, then the more compounded Vegetable or Animal of which it is a part; for he might as compleatly furniſh it with all kinds of contrivances neceſſary for its own exiſtence, and the propagation of its own Species, and yet make it a part of a more compounded body: as a Clock-maker might make a Set of Chimes to be a part of a Clock, and yet, when the watch part or ſtriking part are taken away, and the hindrances of its motion remov'd, this chiming part may go as accurately, and ſtrike its tune as exactly, as if it were ſtill a part of the compounded *Automaton*. So, though the original cauſe, or

ſeminal

Fig: 1



Fig: 2.



ſeminal principle from which this minute Plant on Roſe leaves did ſpring, were, before the corruption caus'd by the Mill-dew, a component part of the leaf on which it grew, and did ſerve as a *coagent* in the production and conſtitution of it, yet might it be ſo conſummate, as to produce a ſeed which might have a power of propagating the ſame ſpecies: the works of the Creator ſeeming of ſuch an excellency, that though they are unable to help to the perfecting of the more compounded exiſtence of the greater Plant or Animal, they may have notwithſtanding an ability of acting ſingly upon their own internal principle, ſo as to produce a Vegetable body, though of a leſs compounded nature, and to proceed ſo farr in the method of other Vegetables, as to bear flowers and ſeeds, which may be capabale of propagating the like. So that the little caſes which appear to grow on the top of the ſlender ſtalks, may, for ought I know, though I ſhould ſuppoſe them to ſpring from the perverting of the uſual courſe of the parent Vegetable, contain a ſeed, which, being ſcatter'd on other leaves of the ſame Plant, may produce a Plant of much the ſame kind.

Nor are Damaſk-Roſe leaves the onely leaves that produce theſe kinds of Vegetable ſproutings; for I have obſerv'd them alſo in ſeveral other kinds of Roſe leaves, and on the leaves of ſeveral ſorts of Briers, and on Bramble leaves they are oftentimes to be found in very great cluſters; ſo that I have found in one cluſter, three, four, or five hundred of them, making a very conſpicuous black ſpot or ſcab on the back ſide of the leaf.

Obſerv. XX. *Of* blue Mould, *and of the firſt Principles of Vegetation ariſing from* Putrefaction.

THe Blue and White and ſeveral kinds of hairy mouldy ſpots, which are obſervable upon divers kinds of *putrify'd* bodies, whether Animal ſubſtances, or Vegetable, ſuch as the ſkin, raw or dreſs'd, fleſh, bloud, humours, milk, green Cheeſe, *&c.* or rotten ſappy Wood, or Herbs, Leaves, Barks, Roots, *&c.* of Plants, are all of them nothing elſe but ſeveral kinds of ſmall and variouſly figur'd Muſhroms, which, from convenient materials in thoſe *putrifying* bodies, are, by the concurrent heat of the Air, excited to a certain kind of vegetation, which will not be unworthy our more ſerious ſpeculation and examination, as I ſhall by and by ſhew. But, firſt, I muſt premiſe a ſhort deſcription of this *Specimen*, which I have added of this Tribe, in the firſt Figure of the XII. *Scheme*, which is nothing elſe but the appearance of a ſmall white ſpot of hairy mould, multitudes of which I found to beſpeck & whiten over the red covers of a ſmall book, which, it ſeems, were of Sheeps-ſkin, that being more apt to gather mould, even in a dry and clean room, then other leathers. Theſe ſpots appear'd, through a good *Microſcope*, to be a very pretty ſhap'd Vegetative body, which, from almoſt the ſame part of the Leather, ſhot

out

out multitudes of ſmall long cylindrical and tranſparent ſtalks,not exactly ſtreight,but a little bended with the weight of a round and white knob that grew on the top of each of them; many of theſe knobs I obſerv'd to be very round, and of a ſmooth ſurface, ſuch as A A, *&c.* others ſmooth likewiſe,but a little oblong,as B; ſeveral of them a little broken, or cloven with chops at the top, as C; others flitter'd as 'twere, or flown all to pieces, as D D. The whole ſubſtance of theſe pretty bodies was of a very tender conſtitution, much like the ſubſtance of the ſofter kind of common white Muſhroms, for by touching them with a Pin, I found them to be bruſed and torn; they ſeem'd each of them to have a diſtinct root of their own; for though they grew neer together in a cluſter, yet I could perceive each ſtem to riſe out of a diſtinct part or pore of the Leather; ſome of theſe were ſmall and ſhort, as ſeeming to have been but newly ſprung up, of theſe the balls were for the moſt part round, others were bigger,and taller,as being perhaps of a longer growth,and of theſe, for the moſt part, the heads were broken, and ſome much waſted, as E; what theſe heads contain'd I could not perceive; whether they were knobs and flowers, or ſeed caſes, I am not able to ſay, but they ſeem'd moſt likely to be of the ſame nature with thoſe that grow on Muſhroms, which they did,ſome of them, not a little reſemble.

Both their ſmell and taſte, which are active enough to make a ſenſible impreſſion upon thoſe organs, are unpleaſant and noiſome.

I could not find that they would ſo quickly be deſtroy'd by the actual flame of a Candle, as at firſt ſight of them I conceived they would be,but they remain'd intire after I had paſt that part of the Leather on which they ſtuck three or four times through the flame of a Candle; ſo that, it ſeems they are not very apt to take fire, no more then the common white Muſhroms are when they are ſappy.

There are a multitude of other ſhapes, of which theſe *Microſcopical* Muſhroms are figur'd, which would have been a long Work to have deſcribed,and would not have ſuited ſo well with my deſign in this Treatiſe, onely,amongſt the reſt, I muſt not forget to take notice of one that was a little like to, or reſembled, a Spunge, conſiſting of a multitude of little Ramifications almoſt as that body does, which indeed ſeems to be a kind of Water-Muſhrom, of a very pretty texture, as I elſe-where manifeſt. And a ſecond, which I muſt not omit, becauſe often mingled, and neer adjoining to theſe I have deſcrib'd,and this appear'd much like a Thicket of buſhes, or brambles, very much branch'd,and extended,ſome of them, to a great length,in proportion to their Diameter,like creeping brambles.

The manner of the growth and formation of this kind of Vegetable, is the third head of Enquiry,which, had I time,I ſhould follow: the figure and method of Generation in this concrete ſeeming to me, next after the Enquiry into the formation, figuration, or chryſtalization of Salts, to be the moſt ſimple, plain, and eaſie; and it ſeems to be a *medium* through which he muſt neceſſarily paſs, that would with any likelihood inveſtigate the *forma informans* of Vegetables: for as I think that he ſhall find it a very difficult taſk, who undertakes to diſcover the form of Saline

line cryſtallizations, without the conſideration and preſcience of the nature and reaſon of a Globular form, and as difficult to explicate this configuration of Muſhroms, without the previous conſideration of the form of Salts; ſo will the enquiry into the forms of Vegetables be no leſs, if not much more difficult, without the fore-knowledge of the forms of Muſhroms, theſe ſeveral Enquiries having no leſs dependance one upon another then any ſelect number of Propoſitions in Mathematical Elements may be made to have.

Nor do I imagine that the ſkips from the one to another will be found very great, if beginning from fluidity, or body without any form, we deſcend gradually, till we arrive at the higheſt form of a bruite Animal's Soul, making the ſteps or foundations of our Enquiry, *Fluidity*, *Orbiculation*, *Fixation*, *Angulization*, or *Cryſtallization Germination* or *Ebullition*, *Vegetation*, *Plantanimation*, *Animation*, *Senſation*, *Imagination*.

Now, that we may the better proceed in our Enquiry, It will be requiſite to conſider:

Firſt, that Mould and Muſhroms require no ſeminal property, but the former may be produc'd at any time from any kind of *putrifying* Animal, or Vegetable Subſtance, as Fleſh, *&c.* kept moiſt and warm, and the latter, if what *Mathiolus* relates be true, of making them by Art, are as much within our command, of which Matter take the *Epitomie* which Mr. *Parkinſon* has deliver'd in his *Herbal*, in his Chapter of *Muſhroms*, becauſe I have not *Mathiolus* now by me: *Unto theſe Muſhroms* (ſaith he) *may alſo be adjoyn'd thoſe which are made of Art* (*whereof* Mathiolus *makes mention*) *that grow naturally among certain ſtones in* Naples, *and that the ſtones being digg'd up, and carried to* Rome, *and other places, where they ſet them in their Wine Cellars, covering them with a little Earth, and ſprinkling a little warm water thereon, would within four days produce Muſhroms fit to be eaten, at what time one will: As alſo that Muſhroms may be made to grow at the foot of a wilde* Poplar Tree, *within four days after, warm water wherein ſome leaves have been diſſolv'd ſhall be pour'd into the Root* (*which muſt be ſlit*) *and the ſtock above ground.*

Next, that as Muſhroms may be generated without ſeed, ſo does it not appear that they have any ſuch thing as ſeed in any part of them; for having conſidered ſeveral kinds of them, I could never find any thing in them that I could with any probability gheſs to be the ſeed of it, ſo that it does not as yet appear (that I know of) that Muſhroms may be generated from a ſeed, but they rather ſeem to depend merely upon a convenient conſtitution of the matter out of which they are made, and a concurrence of either natural or artificial heat.

Thirdly, that by ſeveral bodies (as Salts and Metals both in Water and in the air, and by ſeveral kinds of ſublimations in the Air) actuated and guided with a congruous heat, there may be produc'd ſeveral kinds of bodies as curiouſly, if not of a more compos'd Figure; ſeveral kinds of riſing or Ebulliating Figures ſeem to manifeſt; as witneſs the ſhooting in the Rectification of ſpirits of *Urine*, *Hart-horn*, *Bloud*, &c. witneſs alſo the curious branches of evaporated diſſolutions, ſome of them againſt the

the ſides of the containing Jar: others ſtanding up, or growing an end, out of the bottom, of which I have taken notice of a very great variety. But above all the reſt, it is a very pretty kind of Germination which is afforded us in the Silver Tree, the manner of making which with Mercury and Silver, is well known to the Chymiſts, in which there is an Ebullition or Germination, very much like this of Muſhroms, if I have been rightly inform'd of it.

Fourthly, I have very often taken notice of, and alſo obſerv'd with a *Microſcope*, certain excreſcencies or Ebullitions in the ſnuff of a Candle, which, partly from the ſticking of the ſmoaky particles as they are carryed upwards by the current of the rarify'd Air and flame, and partly alſo from a kind of Germination or Ebullition of ſome actuated unctuous parts which creep along and filter through ſome ſmall ſtring of the Week, are formed into pretty round and uniform heads, very much reſembling the form of hooded Muſhroms, which, being by any means expos'd to the freſh Air, or that air which encompaſſes the flame, they are preſently lick'd up and devour'd by it, and vaniſh.

The reaſon of which *Phænomenon* ſeems to me, to be no other then this: That when a convenient thread of the Week is ſo bent out by the ſides of the ſnuff that are about half an Inch or more, remov'd above the bottom, or loweſt part of the flame, and that this part be wholly included in the flame; the Oyl (for the reaſon of filtration, which I have elſewhere rendred) being continualy driven up the ſnuff, is driven likewiſe into this ragged bended-end, and this being remov'd a good diſtance, as half an Inch or more, above the bottom of the flame, the parts of the air that paſſes by it, are already, almoſt ſatiated with the diſſolution of the boiling unctuous ſteams that iſſued out below, and therefore are not onely glutted, that is, can diſſolve no more then what they are already acting upon, but they carry up with them abundance of unctuous and ſooty particles, which meeting with that rag of the Week, that is plentifully fill'd with Oyl, and onely ſpends it as faſt as it evaporates, and not at all by diſſolution or burning, by means of theſe ſteamy parts of the filterated Oyl iſſuing out at the ſides of this ragg, and being inclos'd with an air that is already ſatiated and cannot prey upon them nor burn them, the aſcending ſooty particles are ſtay'd about it and fix'd, ſo as that about the end of that ragg or filament of the ſnuff, whence the greateſt part of the ſteams iſſue, there is conglobated or fix'd a round and pretty uniform cap, much reſembling the head of a Muſhrom, which, if it be of any great bigneſs, you may obſerve that its underſide will be bigger then that which is above the ragg or ſtem of it; for the Oyl that is brought into it by filtration, being by the bulk of the cap a little ſhelter'd from the heat of the flame, does by that means iſſue as much out from beneath from the ſtalk or downwards, as it does upwards, and by reaſon of the great acceſs of the adventitious ſmoak from beneath, it increaſes moſt that way. That this may be the true reaſon of this *Phænomenon*, I could produce many Arguments and Experiments to make it probable: As,

Firſt, that the *Filtration* carries the Oyl to the top of the Week, at leaſt

as

as high as these raggs, is visible to one that will observe the snuff of a burning Candle with a *Microscope*, where he may see an Ebullition or bubbling of the Oyl, as high as the snuff looks black.

Next, that it does steam away more then burn; I could tell you of the dim burning of a Candle, the longer the snuff be which arises from the abundance of vapours out of the higher parts of it.

And, thirdly, that in the middle of the flame of the Candle, neer the top of the snuff, the fire or dissolving principle is nothing neer so strong, as neer the bottom and out edges of the flame, which may be observ'd by the burning asunder of a thread, that will first break in those parts that the edges of the flame touch, and not in the middle.

And I could add several Observables that I have taken notice of in the flame of a Lamp actuated with Bellows, and very many others that confirm me in my opinion, but that it is not so much to my present purpose, which is onely to consider this concreet in the snuff of a Candle, so farr as it has any resemblance of a Mushrom, to the consideration of which, that I may return, I say, we may also observe:

In the first place, that the droppings or trillings of Lapidescent waters in Vaults under ground, seem to constitute a kind of *petrify'd* body, form'd almost like some kind of Mushroms inverted, in so much that I have seen some knobb'd a little at the lower end, though for the most part, indeed they are otherwise shap'd, and taper'd towards the end; the generation of which seems to be from no other reason but this, that the water by soaking through the earth and Lime (for I ghess that substance to add much to it *petrifying* quality) does so impregnate it self with stony particles, that hanging in drops in the roof of the Vault, by reason that the soaking of the water is but slow, it becomes expos'd to the Air, and thereby the outward part of the drop by degrees grows hard, by reason that the water gradually evaporating the stony particles neer the outsides of the drop begin to touch, and by degrees, to dry and grow closer together, and at length constitute a crust or shell about the drop; and this soaking by degrees, being more and more supply'd, the drop grows longer and longer, and the sides harden thicker and thicker into a Quill or Cane, and at length, that hollow or pith becomes almost stop'd up, and solid: afterwards the soaking of the *petrifying* water, finding no longer a passage through the middle, bursts out, and trickles down the outside, and as the water evaporates, leaves new superinduc'd shells, which more and more swell the bulk of those Iceicles; and because of the great supply from the Vault, of *petrifying* water, those bodies grow bigger and bigger next to the Vault, and taper or sharpen towards the point; for the access from the arch of the Vault being but very slow, and consequently the water being spread very thinly over the surface of the Iceicle, the water begins to settle before it can reach to the bottom, or corner end of it; whence, if you break one of these, you would almost imagine it a stick of Wood *petrify'd*, it having so pretty a resemblance of pith and grain, and if you look on the outside of a piece, or of one whole, you would think no less, both from its vegetable roundness and

tapering form; but whereas all Vegetables are observ'd to shoot and grow perpendicularly upwards, this does shoot or propend directly downwards.

By which last Observables, we see that there may be a very pretty body shap'd and concreeted by Mechanical principles, without the least shew or probability of any other seminal *formatrix*.

And since we find that the great reason of the *Phænomena* of this pretty *petrifaction*, are to be reduc'd from the gravity of a fluid and pretty volatil body impregnated with stony particles, why may not the *Phænomena* of Ebullition or Germination be in part possibly enough deduc'd from the levity of an impregnated liquor, which therefore perpendicularly ascending by degrees, evaporates and leaves the more solid and fix'd parts behind in the form of a Mushrom, which is yet further diversify'd and specificated by the forms of the parts that impregnated the liquor, and compose or help to constitute the Mushrom.

That the forementioned Figures of growing Salts, and the Silver Tree, are from this principle, I could very easily manifest; but that I have not now a convenient opportunity of following it, nor have I made a sufficient number of Experiments and Observations to propound, explicate, and prove so usefull a *Theory* as this of Mushroms: for, though the contrary principle to that of *petrify'd* Iceicles may be in part a cause; yet I cannot but think, that there is somewhat a more complicated cause, though yet Mechanical, and possible to be explain'd.

We therefore have further to enquire of it, what makes it to be such a liquor, and to ascend, whether the heat of the Sun and Air, or whether that of *firmentiation* and *putrifaction*, or both together; as also whether there be not a third or fourth; whether a Saline principle be not a considerable agent in this business also as well as heat; whether also a fixation, precipitation or settling of certain parts out of the aerial Mushrom may not be also a considerable coadjutor in the business. Since we find that many pretty beards or *stiriæ* of the particles of Silver may be precipitated upon a piece of Brass put into a *solution* of Silver very much diluted with fair water, which look not unlike a kind of mould or hoar upon that piece of metal; and the hoar frost looks like a kind of mould; and whether there may not be several others that do concurr to the production of a Mushrom, having not yet had sufficient time to prosecute according to my desires, I must referr this to a better opportunity of my own, or leave and recommend it to the more diligent enquiry and examination of such as can be masters both of leisure and conveniencies for such an Enquiry.

And in the mean time, I must conclude, that as far as I have been able to look into the nature of this Primary kind of life and vegetation, I cannot find the least probable argument to perswade me there is any other concurrent cause then such as is purely Mechanical, and that the effects or productions are as necessary upon the concurrence of those causes as that a Ship, when the Sails are hoist up, and the Rudder is set to such a position, should, when the Wind blows, be mov'd in such a way or course

to


B
A
C
F

to that or t'other place; Or, as that the bruſed Watch, which I mention in the deſcription of Moſs, ſhould, when thoſe parts which hindred its motion were fallen away, begin to move, but after quite another manner then it did before.

Obſerv. XXI. *Of* Moſs, *and ſeveral other ſmall vegetative Subſtances.*

MOſs is a Plant, that the wiſeſt of Kings thought neither unworthy his ſpeculation, nor his Pen, and though amongſt Plants it be in bulk one of the ſmalleſt, yet it is not the leaſt conſiderable: For, as to its ſhape, it may compare for the beauty of it with any Plant that grows, and bears a much bigger breadth; it has a root almoſt like a ſeedy Parſnep, furniſh'd with ſmall ſtrings and ſuckers, which are all of them finely branch'd, like thoſe of the roots of much bigger Vegetables; out of this ſprings the ſtem or body of the Plant, which is ſomewhat *Quadrangular*, rather then *Cylindrical*, moſt curiouſly *fluted* or ſtrung with ſmall creaſes, which run, for the moſt part, *parallel* the whole ſtem; on the ſides of this are cloſe and thick ſet, a multitude of fair, large, well-ſhap'd leaves, ſome of them of a rounder, others of a longer ſhape, according as they are younger or older when pluck'd; as I gheſs by this, that thoſe Plants that had the ſtalks growing from the top of them, had their leaves of a much longer ſhape, all the ſurface of each ſide of which, is curiouſly cover'd with a multitude of little oblong tranſparent bodies, in the manner as you ſee it expreſs'd in the leaf B, in the XIII. *Scheme.*

This Plant, when young and ſpringing up, does much reſemble a Houſleek, having thick leaves, almoſt like that, and ſeems to be ſomwhat of kin to it in other particulars; alſo from the top of the leaves, there ſhoots out a ſmall white and tranſparent hair, or thorn: This ſtem, in time, come to ſhoot out into a long, round and even ſtalk, which by cutting tranſverſly, when dry, I manifeſtly found to be a ſtiff, hard, and hollow Cane, or Reed, without any kind of knot, or ſtop, from its bottom, where the leaves encompaſs'd it, to the top, on which there grows a large ſeed caſe, A, cover'd with a thin, and more whitiſh ſkin, B, terminated in a long thorny top, which at firſt covers all the Caſe, and by degrees, as that ſwells, the ſkin cleaves, and at length falls off, with its thorny top and all (which is a part of it) and leaves the ſeed Caſe to ripen, and by degrees, to ſhatter out its ſeed at a place underneath this cap, B, which before the ſeed is ripe, appears like a flat barr'd button, without any hole in the middle; but as it ripens, the button grows bigger, and a hole appears in the middle of it, E, out of which, in all probability, the ſeed falls: For as it ripens by a proviſion of Nature, that end of this Caſe turns downward after the ſame manner as the ears of Wheat and Barley uſually do; and opening ſeveral of theſe dry red Caſes, F, I found them to be

quite hollow, without any thing at all in them; whereas when I cut them asunder with a sharp Pen-knife when green, I found in the middle of this great Case, another smaller round Case, between which two, the *interstices* were fill'd with multitudes of stringie *fibres*, which seem'd to suspend the lesser Case in the middle of the other, which (as farr as I was able to discern) seem'd full of exceeding small white seeds, much like the seed-bagg in the knop of a Carnation, after the flowers have been two or three days, or a week, fallen off; but this I could not so perfectly discern, and therefore cannot positively affirm it.

After the seed was fallen away, I found both the Case, Stalk, and Plant, all grow red and wither, and from other parts of the root continually to spring new branches or slips, which by degrees increased, and grew as bigg as the former, seeded, ripen'd, shatter'd, and wither'd.

I could not find that it observ'd any particular seasons for these several kinds of growth, but rather found it to be springing, mature, ripe, seedy, and wither'd at all times of the year; But I found it most to flourish and increase in warm and moist weather.

It gathers its nourishments, for the most part, out of some *Lapidescent*, or other substance corrupted or chang'd from its former texture, or substantial form; for I have found it to grow on the rotten parts of Stone, of Bricks, of Wood, of Bones, of Leather, *&c.*

It oft grows on the barks of several Trees, spreading it self, sometimes from the ground upwards, and sometimes from some chink or cleft of the bark of the Tree, which has some *putrify'd* substance in it; but this seems of a distinct kind from that which I observ'd to grow on *putrify'd* inanimate bodies, and rotten earth.

There are also great varieties of other kinds of Mosses, which grow on Trees, and several other Plants, of which I shall here make no mention, nor of the Moss growing on the skull of a dead man, which much resembles that of Trees.

Whether this Plant does sometimes originally spring or rise out of corruption, without any disseminated seed, I have not yet made trials enough to be very much, either positive or negative; for as it seems very hard to conceive how the seed should be generally dispers'd into all parts where there is a corruption begun, unless we may rationally suppose, that this seed being so exceeding small, and consequently exceeding light, is thereby taken up, and carried to and fro in the Air into every place, and by the falling drops of rain is wash'd down out of it, and so dispers'd into all places, and there onely takes root and propagates, where it finds a convenient soil or matrix for it to thrive in; so if we will have it to proceed from corruption, it is not less difficult to conceive,

First, how the corruption of any Vegetable, much less of any Stone or Brick, should be the Parent of so curiously figur'd, and so perfect a Plant as this is. But here indeed, I cannot but add, that it seems rather to be a product of the Rain in those bodies where it is stay'd, then of the very bodies themselves, since I have found it growing on Marble, and Flint; but always the *Microscope*, if not the naked eye, would discover some little hole of Dirt in which it was rooted.

Next,

Next, how the corruption of each of those exceedingly differing bodies should all conspire to the production of the same Plant, that is, that Stones, Bricks, Wood, or vegetable substances, and Bones, Leather, Horns, or animate substances, unless we may with some plausiblenes say, that Air and Water are the coadjutors, or *menstruums*, in all kinds of *putrifactions*, and that thereby the bodies (though whil'st they retain'd their substantial forms, were of exceeding differing natures, yet) since they are dissolv'd and mixt into another, they may be very *Homogeneous*, they being almost resolv'd again into Air, Water, and Earth; retaining, perhaps, one part of their vegetative faculty yet entire, which meeting with congruous assistants, such as the heat of the Air, and the fluidity of the Water, and such like coadjutors and conveniences, acquires a certain vegetation for a time, wholly differing perhaps from that kind of vegetation it had before.

To explain my meaning a little better by a gross Similitude:

Suppose a curious piece of Clock-work, that had had several motions and contrivances in it, which, when in order, would all have mov'd in their design'd methods and Periods. We will further suppose, by some means, that this Clock comes to be broken, bruised, or otherwise disordered, so that several parts of it being dislocated, are impeded, and so stand still, and not onely hinder its own progressive motion, and produce not the effect which they were design'd for, but because the other parts also have a dependence upon them, put a stop to their motion likewise; and so the whole Instrument becomes unserviceable, and not fit for any use. This Instrument afterwards, by some shaking and tumbling, and throwing up and down, comes to have several of its parts shaken out, and several of its curious motions, and contrivances, and particles all fallen asunder; here a Pin falls out, and there a Pillar, and here a Wheel, and there a Hammer, and a Spring, and the like, and among the rest, away falls those parts also which were bruised and disorder'd, and had all this while impeded the motion of all the rest; hereupon several of those other motions that yet remain, whose springs were not quite run down, being now at liberty, begin each of them to move, thus or thus, but quite after another method then before, there being many regulating parts and the like, fallen away and lost. Upon this, the Owner, who chances to hear and observe some of these effects, being ignorant of the Watch-makers Art, wonders what is betid his Clock, and presently imagines that some Artist has been at work, and has set his Clock in order, and made a new kind of Instrument of it, but upon examining circumstances, he finds there was no such matter, but that the casual slipping out of a Pin had made several parts of his Clock fall to pieces, and that thereby the obstacle that all this while hindred his Clock, together with other usefull parts were fallen out, and so his Clock was set at liberty. And upon winding up those springs again when run down, he finds his Clock to go, but quite after another manner then it was wont heretofore.

And thus may it be perhaps in the business of Moss and Mould, and Mushroms, and several other spontaneous kinds of vegetations, which

may

may be caus'd by a vegetative principle, which was a coadjutor to the life and growth of the greater Vegetable, and was by the destroying of the life of it stopt and impeded in performing its office; but afterwards, upon a further corruption of several parts that had all the while impeded it, the heat of the Sun winding up, as it were, the spring, sets it again into a vegetative motion, and this being single, and not at all regulated as it was before (when a part of that greater *machine* the pristine vegetable) is mov'd after quite a differing manner, and produces effects very differing from those it did before.

But this I propound onely as a conjecture, not that I am more enclin'd to this *Hypothesis* then the seminal, which upon good reason I ghess to be Mechanical also, as I may elsewhere more fully shew: But because I may, by this, hint a possible way how this appearance may be solv'd; supposing we should be driven to confess from certain Experiments and Observations made, that such or such Vegetables were produc'd out of the corruption of another, without any concurrent seminal principle (as I have given some reason to suppose, in the description of a *Microscopical* Mushrome) without derogating at all from the infinite wisdom of the Creator. For this accidental production, as I may call it, does manifest as much, if not very much more, of the excellency of his contrivance as any thing in the more perfect vegetative bodies of the world, even as the accidental motion of the *Automaton* does make the owner see, that there was much more contrivance in it then at first he imagin'd. But of this I have added more in the description of Mould, and the Vegetables on Rose leaves, *&c.* those being much more likely to have their original from such a cause then this which I have here described, in the 13. *Scheme*, which indeed I cannot conceive otherwise of, then as of a most perfect Vegetable, wanting nothing of the perfections of the most conspicuous and vastest Vegetables of the world, and to be of a rank so high, as that it may very properly be reckon'd with the tall Cedar of *Lebanon*, as that Kingly Botanist has done.

We know there may be as much curiosity of contrivance, and excellency of form in a very small Pocket-clock, that takes not up an Inch square of room, as there may be in a Church-clock that fills a whole room; And I know not whether all the contrivances and *Mechanisms* requisite to a perfect Vegetable, may not be crowded into an exceedingly less room then this of Moss, as I have heard of a striking Watch so small, that it serv'd for a Pendant in a Ladies ear; and I have already given you the description of a Plant growing on Rose leaves, that is abundantly smaller then Moss; insomuch, that neer 1000. of them would hardly make the bigness of one single Plant of Moss. And by comparing the bulk of Moss, with the bulk of the biggest kind of Vegetable we meet with in Story (of which kind we find in some hotter climates, as *Guine*, and *Brasile*, the stock or body of some Trees to be twenty foot in Diameter, whereas the body or stem of Moss, for the most part, is not above one sixtieth part of an Inch) we shall find that the bulk of the one will exceed the bulk of the other, no less then 2985984 Millions,

or

or 298598400000000, and supposing the production on a Rose leaf to be a Plant, we shall have of those *Indian* Plants to exceed a production of the same Vegetable kingdom no less then 1000 times the former number; so prodigiously various are the works of the Creator, and so All-sufficient is he to perform what to man would seem unpossible, they being both alike easie to him, even as one day, and a thousand years are to him as one and the same time.

I have taken notice of such an infinite variety of those smaller kinds of vegetations, that should I have described every one of them, they would almost have fill'd a Volume, and prov'd bigg enough to have made a new Herbal, such multitudes are there to be found in moist hot weather, especially in the Summer time, on all kind of putrifying substances, which, whether they do more properly belong to the *Classis* of *Mushrooms*, or *Moulds*, or *Mosses*, I shall not now dispute, there being some that seem more properly of one kind, others of another, their colours and magnitudes being as much differing as their Figures and substances.

Nay, I have observ'd, that putting fair Water (whether Rain-water or Pump-water, or *May-dew*, or Snow-water, it was almost all one) I have often observ'd, I say, that this Water would, with a little standing, tarnish and cover all about the sides of the Glass that lay under water, with a lovely green; but though I have often endeavour'd to discover with my *Microscope* whether this green were like Moss, or long striped Sea-weed, or any other peculiar form, yet so ill and imperfect are our *Microscopes*, that I could not certainly discriminate any.

Growing Trees also, and any kinds of Woods, Stones, Bones, *&c.* that have been long expos'd to the Air and Rain, will be all over cover'd with a greenish scurff, which will very much foul and green any kind of cloaths that are rubb'd against it; viewing this, I could not certainly perceive in many parts of it any determinate form, though in many I could perceive a Bed as 'twere of young Moss, but in other parts it look'd almost like green bushes, and very confus'd, but always of what ever irregular Figures the parts appear'd of, they were always green, and seem'd to be either some Vegetable, or to have some vegetating principle.

Observ. XXII. *Of common* Sponges, *and several other* Spongie *fibrous bodies.*

A Sponge is commonly reckon'd among the *Zoophyts*, or Plant Animals; and the *texture* of it, which the *Microscope* discovers, seems to confirm it; for it is of a form whereof I never observ'd any other Vegetable, and indeed, it seems impossible that any should be of it, for it consists of an infinite number of small short *fibres*, or nervous parts, much of the same bigness, curiously jointed or contex'd together in the form of a Net, as is more plainly manifest by the little Draught which I have added

added, in the third *Figure* of the IX. *Scheme*, of a piece of it, which you may perceive represents a confus'd heap of the fibrous parts curiously jointed and implicated. The joints are, for the most part, where three *fibres* onely meet, for I have very seldom met with any that had four.

At these joints there is no one of the three that seems to be the stock whereon the other grow, but each of the *fibres* are, for the most part, of an equal bigness, and seem each of them to have an equal share in the joint; the *fibres* are all of them much about the same bigness, not smaller towards the top of the Sponge, and bigger neerer the bottom or root, as is usuall in Plants, the length of each between the joints, is very irregular and different; the distance between some two joints, being ten or twelve times more then between some others.

Nor are the joints regular, and of an *equitriagonal Figure*, but, for the most part, the three *fibres* so meet, that they compose three angles very differing all of them from one another.

The meshes likewise, and holes of this reticulated body, are not less various and irregular: some *bilateral*, others *trilateral*, and *quadrilateral* Figures; nay, I have observ'd some meshes to have 5, 6, 7, 8, or 9. sides, and some to have onely one, so exceeding various is the *Lusus Naturæ* in this body.

As to the outward appearance of this Vegetative body, they are so usuall every where, that I need not describe them, consisting of a soft and porous substance, representing a Lock, sometimes a fleece of Wooll; but it has besides these small *microscopical* pores which lie between the *fibres*, a multitude of round pores or holes, which, from the top of it, pierce into the body, and sometimes go quite through to the bottom.

I have observ'd many of these Sponges, to have included likewise in the midst of their fibrous contextures, pretty large friable stones, which must either have been inclos'd whil'st this Vegetable was in formation, or generated in those places after it was perfectly shap'd. The later of which seems the more improbable, because I did not find that any of these stony substances were perforated with the *fibres* of the Sponge.

I have never seen nor been enform'd of the true manner of the growing of Sponges on the Rock; whether they are found to increase from little to great, like Vegetables, that is, part after part, or like Animals, all parts equally growing together; or whether they be *matrices* or seed-baggs of any kind of Fishes, or some kind of watry Insect; or whether they are at any times more soft and tender, or of another nature and texture, which things, if I knew, I should much desire to be informed of: but from a cursory view that I at first made with my *Microscope*, and some other trials, I supposed it to be some Animal substance cast out, and fastned upon the Rocks in the form of a froth, or *congeries* of bubbles, like that which I have often observ'd on Rosemary, and other Plants (wherein is included a little Insect) that all the little films which divide these bubbles one from another, did presently, almost after the substance began to grow a little harder, break, and leave onely the thread behind, which might be, as 'twere, the angle or thread between the bubbles, that the

great

great holes or pores obſervable in theſe Sponges were made by the eruption of the included *Heterogeneous* ſubſtance (whether air, or ſome other body, for many other fluid bodies will do the ſame thing) which breaking out of the leſſer, were collected into very large bubbles, and ſo might make their way out of the Sponge, and in their paſſage might leave a round cavity; and if it were large, might carry up with it the adjacent bubbles, which may be perceiv'd at the outſide of the Sponge, if it be firſt throughly wetted, and ſuffer'd to plump it ſelf into its natural form, or be then wrung dry, and ſuffer'd to expand it ſelf again, which it will freely do whil'ſt moiſt: for when it has thus plump'd it ſelf into its natural ſhape and dimenſions, 'tis obvious enough that the mouths of the larger holes have a kind of lip or riſing round about them, but the other ſmaller pores have little or none. It may further be found, that each of theſe great pores has many other ſmall pores below, that are united unto it, and help to conſtitute it, almoſt like ſo many rivulets or ſmall ſtreams that contribute to the maintenance of a large River. Nor from this *Hypotheſis* would it have been difficult to explicate, how thoſe little branches of *Coral*, ſmal *Stones*, *Shells*, and the like, come to be included by theſe frothy bodies: But this inded was but a conjecture; and upon a more accurate enquiry into the form of it with the *Microſcope*, it ſeems not to be the true origine of them; for whereas Sponges have onely three arms which join together at each knot, if they had been generated from bubbles they muſt have had four.

But that they are Animal Subſtances, the *Chymical* examination of them ſeems to manifeſt, they affording a volatil Salt and ſpirit, like *Harts-Horn*, as does alſo their great ſtrength and toughneſs, and their ſmell when burn'd in the Fire of a Candle, which has a kind of fleſhy ſent, not much unlike to hair. And having ſince examin'd ſeveral Authors concerning them, among others, I find this account given by *Bellonius*, in the XI. *Chap.* of his 2[d] Book, *De Aquatilibus*. *Spongiæ recentes*, ſays he, *à ſiccis longe diverſæ, ſcopulis aquæ marinæ ad duos vel tres cubitos, nonnunquam quatuor tantum digitos immerſis, ut fungi arboribus adhærent, ſordido quodam ſucco aut mucoſa potius ſanie refertæ, uſque adeò fœtida, ut vel eminus naſeum excitet, continetur autem iis cavernis, quas inanes in ſiccis & lotis ſpongiis cernimus: Putris pulmonis modo nigræ conſpiciuntur, verùm quæ in ſublimi aquæ naſcuntur multo magis opaca nigredine ſuffuſæ ſunt. Vivere quidem Spongias adhærendo* Ariſtoteles *cenſet: abſolute vero minime: ſenſumque aliquem habere, vel eo argumento (inquit) credantur, quod difficillime abſtrahantur, niſi clanculum agatur: Atq; ad avulſoris acceſſum ita contrahantur, ut eas evellere difficile ſit, quod idem etiam faciunt quoties flatus tempeſtatéſque urgent. Puto autem illis ſuccum ſordidum quem ſupra diximus carnis loco à natura attributum fuiſſe: atque meatibus latioribus tanquam inteſtinis aut interaneis uti. Cæterum pars ea quæ Spongiæ cautibus adhærent eſt tanquam folii petiolus, à quo veluti collum quoddam gracile incipit: quod deinde in latitudinem diffuſum capitis globum facit. Recentibus nihil eſt fiſtuloſum, hæſitantque tanquam radicibus. Superne omnes propemodum meatus concreti latent: inferne verò quaterni aut quini patent, per quos*

eas ſugere exiſtimamus. From which Deſcription, they ſeem to be a kind of Plant-Animal that adheres to a Rock, and theſe ſmall *fibres* or threads which we have deſcribed, ſeem to have been the Veſſels which ('tis very probable) were very much bigger whil'ſt the *Interſtitia* were fill'd (as he affirms) with a mucous, pulpy or fleſhy ſubſtance; but upon the drying were ſhrunk into the bigneſs they now appear.

The texture of it is ſuch, that I have not yet met with any other body in the world that has the like, but onely one of a larger ſort of Sponge (which is preſerv'd in the *Muſeum Harveanum* belonging to the moſt Illuſtrious and moſt learned Society of the *Phyſicians* of *London*) which is of a horney, or rather of a *petrify'd* ſubſtance. And of this indeed, the texture and make is exactly the ſame with common Sponges, but onely that both the holes and the *fibres*, or texture of it is exceedingly much bigger, for ſome of the holes were above an Inch and half over, and the *fibres* and *texture* of it was bigg enough to be diſtinguiſhed eaſily with ones eye, but conſpicuouſly with an ordinary ſingle *Microſcope*. And theſe indeed, ſeem'd to have been the habitation of ſome Animal; and examining *Ariſtotle*, I find a very conſonant account hereunto, namely, that he had known a certain little Animal, call'd *Pinnothera*, like a Spider, to be bred in thoſe caverns of a Sponge, from within which, by opening and cloſing thoſe holes, he inſnares and catches the little Fiſhes; and in another place he ſays, That 'tis very confidently reported, that there are certain Moths or Worms that reſide in the cavities of a Sponge, and are there nouriſhed: Notwithſtanding all which Hiſtories, I think it well worth the enquiring into the Hiſtory and nature of a Sponge, it ſeeming to promiſe ſome information of the Veſſels in Animal ſubſtances, which (by reaſon of the ſolidity of the interſerted fleſh that is not eaſily remov'd, without deſtroying alſo thoſe interſpers'd Veſſels) are hitherto undiſcover'd; whereas here in a Sponge, the *Parenchyma*, it ſeems, is but a kind of mucous gelly, which is very eaſily and cleerly waſh'd away.

The reaſon that makes me imagine, that there may probably be ſome ſuch texture in Animal ſubſtances, is, that examining the texture of the filaments of tann'd Leather, I find it to be much of the ſame nature and ſtrength of a Sponge; and with my *Microſcope*, I have obſerv'd many ſuch joints and knobs, as I have deſcribed in Sponges, the *fibres* alſo in the hollow of ſeveral ſorts of Bones, after the Marrow has been remov'd, I have found ſomewhat to reſemble this texture, though, I confeſs, I never yet found any texture exactly the ſame, nor any for curioſity comparable to it.

The filaments of it are much ſmaller then thoſe of Silk, and through the *Microſcope* appear very neer as tranſparent, nay, ſome parts of them I have obſerv'd much more.

Having examin'd alſo ſeveral kinds of Muſhroms, I finde their texture to be ſomewhat of this kind, that is, to conſiſt of an infinite company of ſmall filaments, every way contex'd and woven together, ſo as to make a kind of cloth, and more particularly, examining a piece of Touch-wood (which is a kind of *Jews-ear*, or Muſhrom, growing here in *England* alſo,

on

on several sorts of Trees, such as Elders, Maples, Willows, &c. and is commonly call'd by the name of *spunk*; but that we meet with to be sold in Shops, is brought from beyond Seas) I found it to be made of an exceeding delicate texture: For the substance of it feels, and looks to the naked eye, and may be stretch'd any way, exactly like a very fine piece of *Chamois* Leather, or wash'd Leather, but it is of somewhat a browner hew, and nothing neer so strong; but examining it with my *Microscope*, I found it of somewhat another make then any kind of Leather; for whereas both *Chamois*, and all other kinds of Leather I have yet view'd, consist of an infinite company of filaments, somewhat like bushes interwoven one within another, that is, of bigger parts or stems, as it were, and smaller branchings that grow out of them; or like a heap of Ropes ends, where each of the larger Ropes by degrees seem to split or untwist, into many smaller Cords, and each of those Cords into smaller Lines, and those Lines into Threads, &c. and these strangely intangled, or interwoven one within another: The texture of this Touch-wood seem more like that of a Lock or a Fleece of Wool, for it consists of an infinite number of small filaments, all of them, as farr as I could perceive, of the same bigness like those of a Sponge, but that the *filaments* of this were not a twentieth part of the bigness of those of a Sponge; and I could not so plainly perceive their joints, or their manner of interweaving, though, as farr as I was able to discern with that *Microscope* I had, I suppose it to have some kind of resemblance, but the joints are nothing neer so thick, nor without much trouble visible.

The filaments I could plainly enough perceive to be even, round, cylindrical, transparent bodies, and to cross each other every way, that is, there were not more seem'd to lie *horizontally* then *perpendicularly* and thwartway, so that it is somewhat difficult to conceive how they should grow in that manner. By tearing off a small piece of it, and looking on the ragged edge, I could among several of those *fibres* perceive small joints, that is, one of those hairs split into two, each of the same bigness with the other out of which they seem'd to grow, but having not lately had an opportunity of examining their manner of growth, I cannot positively affirm any thing of them.

But to proceed, The swelling of Sponges upon wetting, and the rising of the Water in it above the surface of the Water that it touches, are both from the same cause, of which an account is already given in the sixth Observation.

The substance of them indeed, has so many excellent properties, scarce to be met with in any other body in the world, that I have often wondered that so little use is made of it, and those onely vile and sordid; certainly, if it were well consider'd, it would afford much greater conveniencies.

That use which the Divers are said to make of it, seems, if true, very strange, but having made trial of it my self, by dipping a small piece of it in very good Sallet-oyl, and putting it in my mouth, and then keeping my mouth and nose under water, I could not find any such thing; for I

was as soon out of breath, as if I had had no Sponge, nor could I fetch my breath without taking in water at my mouth; but I am very apt to think, that were there a contrivance whereby the expir'd air might be forc'd to pass through a wet or oyly Sponge before it were again inspir'd, it might much cleanse, and strain away from the Air divers fuliginous and other noisome steams, and the dipping of it in certain liquors might, perhaps, so renew that property in the Air which it loses in the Lungs, by being breath'd, that one square foot of Air might last a man for respiration much longer, perhaps, then ten will now serve him of common Air.

Observ. XXIII. *Of the curious texture of* Sea-weeds.

FOr curiosity and beauty, I have not among all the Plants or Vegetables I have yet observ'd, seen any one comparable to this Sea-weed I have here describ'd, of which I am able to say very little more then what is represented by the second *Figure* of the ninth *Scheme*: Namely, that it is a Plant which grows upon the Rocks under the water, and increases and spreads it self into a great tuft, which is not onely handsomely branch'd into several leaves, but the whole surface of the Plant is cover'd over with a most curious kind of carv'd work, which consists of a texture much resembling a Honey-comb; for the whole surface on both sides is cover'd over with a multitude of very small holes, being no bigger then so many holes made with the point of a small Pinn, and rang'd in the neatest and most delicate order imaginable, they being plac'd in the manner of a *Quincunx*, or very much like the rows of the eyes of a Fly, the rows or orders being very regular, which way soever they are observ'd: what the texture was, as it appear'd through a pretty bigg Magnifying *Microscope*, I have here adjoin'd in the first *Figure* of the 14. *Scheme*, which round Area ABCD represents a part of the surface about one eighth part of an Inch in Diameter: Those little holes, which to the eye look'd round, like so many little spots, here appear'd very regularly shap'd holes, representing almost the shape of the sole of a round toed shoe, the hinder part of which, is, as it were, trod on or cover'd by the toe of that next below it; these holes seem'd wall'd about with a very thin and transparent substance, looking of a pale straw-colour; from the edge of which, against the middle of each hole, were sprouted out four small transparent straw-colour'd Thorns, which seem'd to protect and cover those cavities, from either side two; neer the root of this Plant, were sprouted out several small branches of a kind of bastard *Coralline*, curiously branch'd, though small.

And to confirm this, having lately the opportunity of viewing the large Plant (if I may so call it) of a Sponge *petrify'd*, of which I made mention in the last Observation, I found, that each of the Branches or Figures of it, did, by the range of its pores, exhibit just such a texture, the

Fig: I.



Fig. 2.



Fig: 3.



the rows of pores crossing one another, much after the manner as the rows of eyes do which are describ'd in the 26. *Scheme*: *Coralline* also, and several sorts of white *Coral*, I have with a *Microscope* observ'd very curiously shap'd. And I doubt not, but that he that shall observe these several kinds of Plants that grow upon Rocks, which the Sea sometimes overflows, and those heaps of others which are vomited out of it upon the shore, may find multitudes of little Plants, and other bodies, which like this will afford very beautifull objects for the *Microscope*; and this *Specimen* here is adjoin'd onely to excite their curiosities who have opportunity of observing to examine and collect what they find worthy their notice; for the Sea, among terrestrial bodies, is also a *prolifick* mother, and affords as many Instances of *spontaneous* generations as either the Air or Earth.

Observ. XXIV. *Of the surfaces of* Rosemary, *and other leaves.*

THis which is delineated within the circle of the second *Figure* of the 14. *Scheme*, is a small part of the back or under side of a leaf of Rosemary, which I did not therefore make choice of, because it had any thing peculiar which was not observable with a *Microscope* in several other Plants, but because it exhibits at one view,

First, a smooth and shining surface, namely, A B, which is a part of the upper side of the leaf, that by a kind of hem or doubling of the leaf appears on this side. There are multitudes of leaves, whose surfaces are like this smooth, and as it were quilted, which look like a curious quilted bagg of green Silk, or like a Bladder, or some such pliable transparent substance, full stuffed out with a green juice or liquor; the surface of Rue, or Herbgrass, is polish'd, and all over indented, or pitted, like the Silk-worm's Egg, which I shall anon describe; the smooth surfaces of other Plants are otherwise quilted, Nature in this, as it were, expressing her Needle-work, or imbroidery.

Next a downy or bushy surface, such as is all the under side almost, appearing through the *Microscope* much like a thicket of bushes, and with this kind of Down or Hair the leaves and stalks of multitudes of Vegetables are covered; and there seems to be as great a variety in the shape, bulk, and manner of the growing of these secundary Plants, as I may call them (they being, as it were, a Plant growing out of a Plant, or somewhat like the hairs of Animals) as there is to be found amongst small shrubs that compose bushes; but for the most part, they consist of small transparent parts, some of which grow in the shape of small Needles or Bodkins, as on the Thistle, Cowag-cod and Nettle; others in the form of Cat's claws, as in Cliders, the beards of Barley, the edges of several sorts of Grass and Reeds, *&c.* in other, as Coltsfoot, Rose-campion, Aps, Poplar, Willow, and almost all other downy Plants, they grow in the form of bushes very much diversify'd in each particular Plant. That which I have before

before in the 19. Obſervation noted on Roſe-leaves, is of a quite differing kind, and ſeems indeed a real Vegetable, diſtinct from the leaf.

Thirdly, among theſe ſmall buſhes are obſervable an infinite company of ſmall round Balls, exactly Globular, and very much reſembling Pearls, namely, CCCC, of theſe there may be multitudes obſerv'd in Sage, and ſeveral other Plants, which I ſuppoſe was the reaſon why *Athanaſius Kircher* ſuppoſed them to be all cover'd with Spiders Eggs, or young Spiders, which indeed is nothing elſe but ſome kind of gummous exſudation, which is always much of the ſame bigneſs. At firſt ſight of theſe, I confeſs, I imagin'd that they might have been ſome kind of *matrices*, or nouriſhing receptacles for ſome ſmall Inſect, juſt as I have found Oak-apples, and multitudes of ſuch other large excreſcencies on the leaves and other parts of Trees and ſhrubs to be for Flyes, and divers other Inſects, but obſerving them to be there all the year, and ſcarce at all to change their magnitude, that conjecture ſeem'd not ſo probable. But what ever be the uſe of it, it affords a very pleaſant object through the *Microſcope*, and may, perhaps, upon further examination, prove very luciferous.

Obſerv. XXV. *Of the ſtinging points and juice of* Nettles, *and ſome other venomous Plants.*

A Nettle is a Plant ſo well known to every one, as to what the appearance of it is to the naked eye, that it needs no deſcription; and there are very few that have not felt as well as ſeen it; and therefore it will be no news to tell that a gentle and ſlight touch of the ſkin by a Nettle, does oftentime, not onely create very ſenſible and acute pain, much like that of a burn or ſcald, but often alſo very angry and hard ſwellings and inflamations of the parts, ſuch as will preſently riſe, and continue ſwoln divers hours. Theſe obſervations, I ſay, are common enough; but how the pain is ſo ſuddenly created, and by what means continued, augmented for a time, and afterwards diminiſh'd, and at length quite exſtinguiſh'd, has not, that I know, been explain'd by any.

And here we muſt have recourſe to our *Microſcope*, and that will, if almoſt any part of the Plant be looked on, ſhew us the whole ſurface of it very thick ſet with turn-Pikes, or ſharp Needles, of the ſhape of thoſe repreſented in the 15. *Scheme* and firſt *Figure* by A B, which are viſible alſo to the naked eye; each of which conſiſts of two parts very diſtinct for ſhape, and differing alſo in quality from one another. For the part A, is ſhaped very much like a round Bodkin, from B tapering till it end in a very ſharp point; it is of a ſubſtance very hard and ſtiff, exceedingly tranſparent and cleer, and, as I by many trials certainly found, is hollow from top to bottom.

This I found by this Experiment, I had a very convenient *Microſcope*

Fig: 1.

Schem. XV.



Fig: 2.

Fig: 4.



Fig: 3.



scope with a single Glass which drew about half an Inch, this I had fastned into a little frame, almost like a pair of Spectacles, which I placed before mine eyes, and so holding the leaf of a Nettle at a convenient distance from my eye, I did first, with the thrusting of several of these bristles into my skin, perceive that presently after I had thrust them in I felt the burning pain begin; next I observ'd in divers of them, that upon thrusting my finger against their tops, the Bodkin (if I may so call it) did not in the least bend, but I could perceive moving up and down within it a certain liquor, which upon thrusting the Bodkin against its basis, or bagg B, I could perceive to rise towards the top, and upon taking away my hand, I could see it again subside, and shrink into the bagg; this I did very often, and saw this *Phænomenon* as plain as I could ever see a parcel of water ascend and descend in a pipe of Glass. But the basis underneath these Bodkins on which they were fast, were made of a more pliable substance, and looked almost like a little bagg of green Leather, or rather resembled the shape and surface of a wilde Cucumber, or *cucumeris asinini*, and I could plainly perceive them to be certain little baggs, bladders, or receptacles full of water, or as I ghess, the liquor of the Plant, which was poisonous, and those small Bodkins were but the Syringe-pipes, or Glyster-pipes, which first made way into the skin, and then served to convey that poisonous juice, upon the pressing of those little baggs, into the interior and sensible parts of the skin, which being so discharg'd, does corrode, or, as it were, burn that part of the skin it touches; and this pain will sometimes last very long, according as the impression is made deeper or stronger.

The other parts of the leaf or surface of the Nettle, have very little considerable, but what is common to most of these kinds of Plants, as the ruggedness or indenting, and hairiness, and other roughnesses of the surface or out-side of the Plant, of which I may say more in another place. As I shall likewise of certain little pretty cleer Balls or Apples which I have observed to stick to the sides of these leaves, both on the upper and under side, very much like the small Apples which I have often observ'd to grow on the leaves of an Oak call'd *Oak-apples* which are nothing but the *Matrices* of an Insect, as I elsewhere shew.

The chief thing therefore is, how this Plant comes, by so slight a touch, to create so great a pain; and the reason of this seems to be nothing else, but the corrosive penetrant liquor contain'd in the small baggs or bladders, upon which grow out those sharp Syringe-pipes, as I before noted; and very consonant to this, is the reason of the pain created by the sting of a Bee, Wasp, *&c.* as I elsewhere shew: For by the Dart, which is likewise a pipe, is made a deep passage into the skin, and then by the anger of the Fly, is his gally poisonous liquor injected; which being admitted among the sensible parts, and so mix'd with the humours or *stagnating* juices of that part, does create an Ebullition perhaps, or *effervescens*, as is usually observ'd in the mingling of two differing *Chymical saline* liquors, by which means the parts become swell'd, hard, and very painfull; for thereby the nervous and sensible parts are not onely stretch'd and strain'd

beyond

beyond their natural *tone*, but are alſo prick'd, perhaps, or corroded by the pungent and incongruous pores of the intruded liquor.

And this ſeems to be the reaſon, why *Aqua fortis*, and other *ſaline* liquors, if they come to touch the ſenſitive parts, as in a cut of the ſkin, or the like, do ſo violently and intollerably *excruciate* and torment the Patient. And 'tis not unlikely, but the Inventors of that Diabolical practice of poiſoning the points of Arrows and Ponyards, might receive their firſt hint from ſome ſuch Inſtance in natural contrivances, as this of the Nettle: for the ground why ſuch poiſon'd weapons kill ſo infallibly as they do, ſeems no other then this of our Nettle's ſtinging; for the Ponyard or Dart makes a paſſage or entrance into the ſenſitive or vital parts of the body, whereby the contagious ſubſtance comes to be diſſolv'd by, and mix'd with the fluid parts or humours of the body, and by that means ſpreads it ſelf by degrees into the whole liquid part of the body, in the ſame manner, as a few grains of Salt, put into a great quantity of Water, will by degrees diffuſe it ſelf over the whole.

And this I take to be the reaſon of killing of Toads, Frogs, Effs, and ſeveral Fiſhes, by ſtrewing Salt on their backs (which Experiment was ſhewn to the *Royal Society* by a very ingenious Gentleman, and a worthy Member of it) for thoſe creatures having always a continual exſudation, as it were, of ſlimy and watry parts, ſweating out of the pores of their ſkin, the *ſaline* particles, by that means obtain a *vehicle*, which conveys them into the internal and vital parts of the body.

This ſeems alſo to be the reaſon why bathing in Mineral waters are ſuch ſoveraign remedies for multitudes of diſtempers, eſpecially chronical; for the liquid & warm *vehicles* of the Mineral particles, which are known to be in very conſiderable quantities in thoſe healing baths, by the body's long ſtay in them, do by degrees ſteep and inſinuate themſelves into the pores and parts of the ſkin, and thereby thoſe Mineral particles have their ways and paſſages open'd to penetrate into the inner parts, and mingle themſelves with the *ſtagnant* juices of the ſeveral parts; beſides, many of thoſe offenſive parts which were united with thoſe *ſtagnant* juices, and which were contrary to the natural conſtitution of the parts, and ſo become irkſome and painfull to the body, but could not be diſcharged, becauſe Nature had made no proviſion for ſuch accidental miſchiefs, are, by means of this ſoaking, and filling the pores of the ſkin with a liquor, afforded a paſſage through that liquor that fills the pores into the ambient fluid, and thereby the body comes to be diſcharged.

So that 'tis very evident, there may be a good as well as an evil application of this Principle. And the ingenious Invention of that Excellent perſon, Doctor *Wren*, of injecting liquors into the veins of an Animal, ſeems to be reducible to this head: I cannot ſtay, nor is this a fit place, to mention the ſeveral Experiments made of this kind by the moſt incomparable Mr. *Boyle*, the multitudes made by the lately mention'd *Phyſician* Doctor *Clark*, the Hiſtory whereof, as he has been pleas'd to communicate to the *Royal Society*, ſo he may perhaps be prevail'd with to make publique himſelf: But I ſhall rather hint, that certainly, if this Principle

were

were well consider'd, there might, besides the further improving of Bathing and Syringing into the veins, be thought on several ways, whereby several obstinate distempers of a humane body, such as the Gout, Dropsie, Stone, &c. might be master'd, and expell'd; and good men might make as good a use of it, as evil men have made a perverse and Diabolical.

And that the filling of the pores of the skin with some fluid *vehicle*, is of no small efficacy towards the preparing a passage for several kinds of penetrant juices, and other dissoluble bodies, to insinuate themselves within the skin, and into the sensitive parts of the body, may be, I think, prov'd by an Instance given us by *Bellonius*, in the 26. *Chapter* of the second Book of his *Observations*, which containing a very remarkable Story I have here transcrib'd: *Cum Chamæleonis nigri radices* (says he) *apud Pagum quendam Livadochorio nuncupatum erui curaremus, plurimi Græci & Turcæ spectatum venerunt quid eruerenus, eas vero frustulatim secabamus, & filo trajiciebamus ut facilius exsiccari possent. Turcæ in eo negotio occupatos nos videntes, similiter eas radices tractare & secare voluerunt: at cum summus esset æstus, & omnes sudore maderent, quicunque eam radicem manibus tractaverant sudoremque absterserant, aut faciem digitis scalpserant, tantam pruriginem iis locis quos attigerant postea senserunt, ut aduri viderentur. Chamæleonis enim nigri radix ea virtute pollet, ut cuti applicata ipsam adeo inflammet, ut nec squillæ, nec urticæ ullæ centesima parte ita adurent: At prurigo non adeo celeriter sese prodit. Post unam aut alteram porro horam, singuli variis faciei locis cutem adeo inflammatam habere cœpimus, ut tota sanguinea videretur, atque quo magis eam confricabamus, tanto magis excitabatur prurigo. Fonti assidebamus sub platano, atque initio pro ludicro habebamus & ridebamus: at tandem illi plurimum indignati sunt, & nisi asseveraßemus nunquam expertos tali virtute eam plantam pollere, haud dubie male nos multassent. Attamen nostra excusatio fuit ab illis facilius accepta, cum eodem incommodo nos affectos conspicerent. Mirum sane quod in tantillo radice tam ingentem efficaciam nostro malo experti sumus.*

By which observation of his, it seems manifest, that their being all cover'd with sweat who gather'd and cut this root of the black *Chameleon* Thistle, was the great reason why they suffer'd that inconvenience, for it seems the like circumstance had not been before that noted, nor do I find any mention of such a property belonging to this Vegetable in any of the Herbals I have at present by me.

I could give very many Observations which I have made of this kind, whereby I have found that the best way to get a body to be insinuated into the substance or insensible pores of another, is first, to find a fluid *vehicle* that has some congruity, both to the body to be insinuated, and to the body into whose pores you would have the other convey'd. And in this Principle lies the great mystery of staining several sorts of bodies, as Marble, Woods, Bones, &c. and of Dying Silks, Cloaths, Wools, Feathers, &c. But these being digressions, I shall proceed to:

Observ. XXVI. *Of* Cowage, *and the itching operation of some bodies.*

THere is a certain Down of a Plant, brought from the *East-Indies*, call'd commonly, though very improperly, *Cow-itch*, the reason of which

mistake is manifest enough from the description of it, which Mr. *Parkinson* sets down in his *Herbal*, Tribe XI. Chap. 2. *Phaseolus siliqua hirsuta*; *The hairy Kidney-bean, called in* Zurratte *where it grows, Couhage: We have had* (says he) *another of this kind brought us out of the* East-Indies, *which being planted, was in shew like the former, but came not to perfection, the unkindly season not suffering it to shew the flower; but of the Cods that were brought, some were smaller, shorter, and rounder then the Garden kind; others much longer, and many growing together, as it were in clusters, and cover'd all over with a brown short hairiness, so fine, that if any of it be rubb'd, or fall on the back of ones hand, or other tender parts of the skin, it will cause a kind of itching, but not strong, nor long induring, but passing quickly away, without either danger or harm; the Beans were smaller then ordinary, and of a black shining colour.*

Having one of these Cods given me by a Sea-Captain, who had frequented those parts, I found it to be a small Cod, about three Inches long, much like a short Cod of *French Beans*, which had six Beans in it, the whole surface of it was cover'd over with a very thick and shining brown Down or Hair, which was very fine, and for its bigness stiff; taking some of this Down, and rubbing it on the back of my hand, I found very little or no trouble, only I was sensible that several of these little downy parts with rubbing did penetrate, and were sunk, or stuck pretty deep into my skin. After I had thus rubb'd it for a pretty while, I felt very little or no pain, in so much that I doubted, whether it were the true Couhage; but whil'st I was considering, I found the Down begin to make my hand itch, and in some places to smart again, much like the stinging of a Flea or Gnat, and this continued a pretty while, so that by degrees I found my skin to be swell'd with little red pustules, and to look as if it had been itchie. But suffering it without rubbing or scratching, the itching tickling pain quickly grew languid, and within an hour I felt nothing at all, and the little *protuberancies* were vanish'd.

The cause of which odd *Phænomenon*, I suppose to be much the same with that of the stinging of a Nettle, for by the *Microscope*, I discover'd this Down to consist of a multitude of small and slender conical bodies, much resembling Needles or Bodkins, such as are represented by A B. C D. E F. of the first Figure of the XVI. *Scheme*; that their ends A A A, were very sharp, and the substance of them stiff and hard, much like the substance of several kinds of Thorns and crooks growing on Trees. And though they appear'd very cleer and transparent, yet I could not perceive whether they were hollow or not, but to me they appear'd like solid transparent bodies, without any cavity in them; whether, though they might not be a kind of Cane, fill'd with some transparent liquor which was hardned (because the Cod which I had was very dry) I was not able to examine.

Now, being such stiff, sharp bodies, it is easie to conceive, how with rubbing they might easily be thrust into the tender parts of the skin, and there, by reason of their exceeding fineness and drineſs, not create any considerable trouble or pain, till by remaining in those places moistned with the humours of the body, some caustick part sticking on them, or residing

residing within them might be dissolv'd and mix'd with the ambient juices of that place, and thereby those *fibres* and tender parts adjoyning become affected, and as it were corroded by it; whence, while that action lasts, the pains created are pretty sharp and pungent, though small, which is the essential property of an itching one.

That the pain also caused by the stinging of a Flea, a Gnat, a Flie, a Wasp, and the like, proceeds much from the very same cause, I elsewhere in their proper places endeavour to manifest. The stinging also of shred Horse-hair, which in meriment is often strew'd between the sheets of a Bed, seems to proceed from the same cause.

Observ. XXVII. *Of the* Beard *of a wilde* Oat, *and the use that may be made of it for exhibiting always to the Eye the temperature of the Air, as to drineß and moisture.*

THis Beard of a wild *Oat*, is a body of a very curious structure, though to the naked Eye it appears very slight, and inconsiderable, it being only a small black or brown Beard or Bristle, which grows out of the side of the inner Husk that covers the Grain of a wild *Oat*; the whole length of it, when put in Water, so that it may extend it self to its full length, is not above an Inch and a half, and for the most part somewhat shorter, but when the Grain is ripe, and very dry, which is usualy in the Moneths of *July*, and *August*, this Beard is bent somewhat below the middle, namely, about ⅔ from the bottom of it, almost to a right Angle, and the under part of it is wreath'd lik a With; the substance of it is very brittle when dry, and it will very easily be broken from the husk on which it grows.

If you take one of these Grains, and wet the Beard in Water, you will presently see the small bended top to turn and move round, as if it were sensible; and by degrees, if it be continued wet enough, the joint or knee will streighten it self; and if it be suffer'd to dry again, it will by degrees move round another way, and at length bend again into its former posture.

If it be view'd with an ordinary single *Microscope*, it will appear like a small wreath'd Sprig, with two clefts; and if wet as before, and then look'd on with this *Microscope*, it will appear to unwreath it self, and by degrees, to streighten its knee, and the two clefts will become streight, and almost on opposite sides of the small cylindrical body.

If it be continued to be look'd a little longer with a *Microscope*, it will within a little while begin to wreath it self again, and soon after return to its former posture, bending it self again neer the middle, into a kind of knee or angle.

Several of those bodies I examin'd with larger *Microscopes*, and there found them much of the make of those two long wreath'd cylinders delineated in the second Figure of the 15. *Scheme*, which two cylinders re-

present the wreathed part broken into two pieces, whereof the end A B is to be suppos'd to have join'd to the end C D, so that E A C F does represent the whole wreath'd part of the Beard, and E G a small piece of the upper part of the Beard which is beyond the knee, which as I had not room to insert, so was it not very considerable, either for its form, or any known property; but the under or wreathed part is notable for both: As to its form, it appear'd, if it were look'd on side-ways, almost like a Willow, or a small tapering rod of *Hazel*, the lower or bigger half of which onely, is twisted round several times, in some three, in others more, in others less, according to the bigness and maturity of the Grain on which it grew, and according to the drineſs and moisture of the ambient Air, as I shall shew more at large by and by.

The whole outward Superficies of this Cylindrical body is curiously adorned or fluted with little channels, and interjacent ridges, or little *protuberances* between them, which run the whole length of the Beard, and are streight where the Beard is not twisted, and wreath'd where it is, just after the same manner: each of those sides is beset pretty thick with small Brisles or Thorns, somewhat in form resembling that of *Porcupines* Quills, such as *a a a a a* in the Figure; all whose points are directed like so many Turn-pikes towards the small end or top of the Beard, which is the reason, why, if you endeavour to draw the Beard between your fingers the contrary way, you will find it to stick, and grate, as it were, against the skin.

The proportion of these small conical bodies *a a a a a* to that whereon they grow, the Figure will sufficiently shew, as also their manner of growing, their thickness, and neerness to each other, as, that towards the root or bottom of the Beard, they are more thin, and much shorter, insomuch that there is usually left between the top of the one, and the bottom of that next above it, more then the length of one of them, and that towards the top of the Beard they grow more thick and close (though there be fewer ridges) so that the root, and almost half the upper are hid by the tops of those next below them.

I could not perceive any *transverse* pores, unless the whole wreath'd part were separated and cleft, in those little channels, by the wreathing into so many little strings as there were ridges, which was very difficult to determine; but there were in the wreathed part two very conspicuous channels or clefts, which were continued from the bottom F to the elbow E H, or all along the part which was wreath'd, which seem'd to divide the wreath'd Cylinder into two parts, a bigger and a less; the bigger was that which was at the *convex* side of the knee, namely, on the side A, and was wreath'd by O O O O O; this, as it seem'd the broader, so did it also the longer, the other P P P P P, which was usually purs'd or wrinckled in the bending of the knee, as about E, seem'd both the shorter and narrower, so that at first I thought the wreathing and unwreathing of the Beard might have been caus'd by the shrinking or swelling of that part; but upon further examination, I found that the clefts, K K, L L, were stuft up with a kind of Spongie substance, which, for the most part, was very

very conſpicuous neer the knee, as in the cleft K K, when the Beard was dry; upon the diſcovery of which, I began to think, that it was upon the ſwelling of this porous pith upon the acceſs of moiſture or water that the Beard, being made longer in the midſt, was ſtreightned, and by the ſhrinking or ſubſiding of the parts of that Spongie ſubſtance together, when the water or moiſture was exhal'd or dried, the pith or middle parts growing ſhorter, the whole became twiſted.

But this I cannot be poſitive in, for upon cutting the wreath'd part in many places tranſverſly, I was not ſo well ſatisfy'd with the ſhape and manner of the pores of the pith; for looking on theſe tranſverſe Sections with a very good *Microſcope*, I found that the ends of thoſe tranſverſe Sections appear'd much of the manner of the third Figure of the 15. *Scheme* A B C F E, and the middle or pith C C, ſeem'd very full of pores indeed, but all of them ſeem'd to run the long-ways.

This Figure plainly enough ſhews in what manner thoſe clefts, K and L divided the wreath'd Cylinder into two unequal parts, and alſo of what kind of ſubſtance the whole body conſiſts; for by cutting the ſame Beard in many places, with tranſverſe Sections, I found much the ſame appearance with this expreſs'd; ſo that thoſe pores ſeem to run, as in moſt other ſuch Cany bodies, the whole length of it.

The clefts of this body K K, and L L, ſeem'd (as is alſo expreſs'd in the Figure) to wind very oddly in the inner part of the wreath; and in ſome parts of them, they ſeem'd ſtuffed, as it were, with that Spongie ſubſtance, which I juſt now deſcribed.

This ſo oddly conſtituted Vegetable ſubſtance, is firſt (that I have met with) taken notice of by *Baptiſta Porta*, in his *Natural Magick*, as a thing known to children and Juglers, and it has been call'd by ſome of thoſe laſt named perſons, the better to cover their cheat, the Legg of an *Arabian Spider*, or the Legg of an inchanted *Egyptian Fly*, and has been uſed by them to make a ſmall Index, Croſs, or the like, to move round upon the wetting of it with a drop of Water, and muttering certain words.

But the uſe that has been made of it, for the diſcovery of the various conſtitutions of the Air, as to drineſs and moiſtneſs, is incomparably beyond any other; for this it does to admiration: The manner of contriving it ſo, as to perform this great effect, is onely thus:

Provide a good large Box of Ivory, about four Inches over, and of what depth you ſhall judge convenient (according to your intention of making uſe of one, two, three, or more of theſe ſmall Beards, ordered in the manner which I ſhall by and by deſcribe) let all the ſides of this Box be turned of Baſket-work (which here in *London* is eaſily enough procur'd) full of holes, in the manner almoſt of a Lettice, the bigger, or more the holes are, the better, that ſo the Air may have the more free paſſage to the incloſed Beard, and may the more eaſily paſs through the Inſtrument; it will be better yet, though not altogether ſo handſom, if inſteed of the Baſket-work on the ſides of the Box, the bottom and top of the Box be join'd together onely with three or four ſmall Pillars, after the manner repre-

ſented

ſented in the 4.Figure of the 15. *Scheme.* Or,if you intend to make uſe of many of theſe ſmall Beards join'd together, you may have a ſmall long Caſe of Ivory, whoſe ſides are turn'd of Baſket-work, full of holes, which may be ſcrew'd on to the underſide of a broad Plate of Ivory,on the other ſide of which is to be made the divided Ring or Circle, to which diviſions the pointing of the Hand or Index, which is moved by the conjoin'd Beard, may ſhew all the *Minute* variations of the Air.

There may be multitudes of other ways for contriving this ſmall Inſtrument, ſo as to produce this effect, which any one may, according to his peculiar uſe, and the exigency of his preſent occaſion, eaſily enough contrive and take, on which I ſhall not therefore inſiſt. The whole manner of making any one of them is thus: Having your Box or frame A A B B, fitly adapted for the free paſſage of the Air through it,in the midſt of the bottom B B B, you muſt have a very ſmall hole C, into which the lower end of the Beard is to be fixd,the upper end of which Beard *a b*,is to paſs through a ſmall hole of a Plate, or top A A, if you make uſe onely of a ſingle one, and on the top of it *e*, is to be fix'd a ſmall and very light *Index f g*, made of a very thin ſliver of a Reed or Cane; but if you make uſe of two or more Beards, they muſt be fix'd and bound together, either with a very fine piece of Silk, or with a very ſmall touch of hard Wax, or Glew,which is better, and the *Index f g*, is to be fix'd on the top of the ſecond,third, or fourth in the ſame manner as on the ſingle one.

Now, becauſe that in every of theſe contrivances, the *Index f g*, will with ſome temperatures of Air, move two, three, or more times round, which without ſome other contrivance then this,will be difficult to diſtinguiſh,therefore I thought of this Expedient: The *Index* or *Hand f g*, being rais'd a pretty way above the ſurface of the Plate A A, fix in at a little diſtance from the middle of it a ſmall Pin *h*, ſo as almoſt to touch the ſurface of the Plate A A, and then in any convenient place of the ſurface of the Plate,fix a ſmall Pin, on which put on a ſmall piece of Paper, or thin Paſt-board, Vellom, or Parchment, made of a convenient cize, and ſhap'd in the manner of that in the Figure expreſs'd by *i k*, ſo that having a convenient number of teeth every turn or return of the Pin *h*, may move this ſmall indented Circle, a tooth forward or backwards, by which means the teeth of the Circle, being mark'd, it will be thereby very eaſie to know certainly, how much variation any change of weather will make upon the ſmall wreath'd body. In the making of this Secundary Circle of Vellom, or the like, great care is to be had, that it be made exceeding light, and to move very eaſily, for otherwiſe a ſmall variation will ſpoil the whole operation. The Box may be made of Braſs, Silver, Iron, or any other ſubſtance, if care be taken to make it open enough, to let the Air have a ſufficiently free acceſs to the Beard. The *Index* alſo may be various ways contrived, ſo as to ſhew both the number of the revolutions it makes, and the *Minute* diviſions of each revolution.

I have made ſeveral trials and Inſtruments for diſcovering the drineſs and moiſture of the Air with this little wreath'd body,and find it to vary exceeding ſenſibly with the leaſt change in the conſtitution of the Air, as

to

to drineſs and moiſture, ſo that with one breathing upon it, I have made it untwiſt a whole bout, and the *Index* or *Hand* has ſhew'd or pointed to various diviſions on the upper Face or Ring of the Inſtrument, according as it was carried neerer and neerer to the fire, or as the heat of the Sun increaſed upon it.

Other trials I have made with Gut-ſtrings, but find them nothing neer ſo ſenſible, though they alſo may be ſo contriv'd as to exhibit the changes of the Air, as to drineſs and moiſture, both by their ſtretching and ſhrinking in length, and alſo by their wreathing and unwreathing themſelves; but theſe are nothing neer ſo exact or ſo tender, for their varying property will in a little time change very much. But there are ſeveral other Vegetable ſubſtances that are much more ſenſible then even this Beard of a wilde *Oat*; ſuch I have found the Beard of the ſeed of Muſk-graſs, or *Geranium moſchatum*, and thoſe of other kinds of *Cranesbil* ſeeds, and the like. But always the ſmaller the wreathing ſubſtance be, the more ſenſible is it of the mutations of the Air, a conjecture at the reaſon of which I ſhall by and by add.

The lower end of this wreath'd Cylinder being ſtuck upright in a little ſoft Wax, ſo that the bended part or *Index* of it lay *horizontal*, I have obſerv'd it always with moiſture to unwreath it ſelf from the Eaſt (For inſtance) by the South to the Weſt, and ſo by the North to the Eaſt again, moving with the Sun (as we commonly ſay) and with heat and drouth to re-twiſt, and wreath it ſelf the contrary way, namely, from the Eaſt, (for inſtance) by the North to the Weſt, and ſo onwards.

The cauſe of all which *Phænomena*, ſeems to be the differing texture of the parts of theſe bodies, each of them (eſpecially the Beard of a wilde *Oat*, and of *Mosk-graſs* ſeed) ſeeming to have two kind of ſubſtances, one that is very porous, looſe, and ſpongie, into which the watry ſteams of the Air may be very eaſily forced, which will be thereby ſwell'd and extended in its dimenſions, juſt as we may obſerve all kind of Vegetable ſubſtance upon ſteeping in water to ſwell and grow bigger and longer. And a ſecond that is more hard and cloſe, into which the water can very little, or not at all penetrate, this therefore retaining always very neer the ſame dimenſions, and the other ſtretching and ſhrinking, according as there is more or leſs moiſture or water in its pores, by reaſon of the make and ſhape of the parts, the whole body muſt neceſſarily unwreath and wreath it ſelf.

And upon this Principle, it is very eaſie to make ſeveral ſorts of contrivances that ſhould thus wreath and unwreath themſelves, either by heat and cold, or by drineſs and moiſture, or by any greater or leſs force, from whatever cauſe it proceed, whether from gravity or weight, or from wind which is motion of the Air, or from ſome ſpringing body, or the like.

This, had I time, I ſhould enlarge much more upon; for it ſeems to me to be the very firſt footſtep of *Senſation*, and Animate motion, the moſt plain, ſimple, and obvious contrivance that Nature has made uſe of to produce a motion, next to that of Rarefaction and Condenſation by heat

and

and cold. And were this Principle very well examin'd, I am very apt to think, it would afford us a very great help to find out the *Mechanism* of the Muscles, which indeed, as farr as I have hitherto been able to examine, seems to me not so very perplex as one might imagine, especially upon the examination which I made of the Muscles of *Crabs*, *Lobsters*, and several sorts of large Shell-fish, and comparing my Observations on them, with the circumstances I observ'd in the muscles of terrestrial Animals.

Now, as in this Instance of the Beard of a wilde *Oat*, we see there is nothing else requisite to make it wreath and unwreath it self, and to streighten and bend its knee, then onely a little breath of moist or dry Air, or a small *atome* almost of water or liquor, and a little heat to make it again evaporate; for, by holding this Beard, plac'd and fix'd as I before directed, neer a Fire, and dipping the tip of a small shred of Paper in well rectify'd spirit of Wine, and then touching the wreath'd *Cylindrical* part, you may perceive it to untwist it self; and presently again, upon the *avolation* of the spirit, by the great heat, it will re-twist it self, and thus will it move forward and backwards as oft as you repeat the touching it with the spirit of Wine; so may, perhaps, the shrinking and relaxing of the muscles be by the influx and evaporation of some kind of liquor or juice. But of this Enquiry I shall add more elsewhere.

Observ. XXVIII. *Of the Seeds of* Venus *looking-glass, or* Corn *Violet.*

FRom the Leaves, and Downs, and Beards of Plants, we come at last to the Seeds; and here indeed seems to be the Cabinet of Nature, wherein are laid up its Jewels. The providence of Nature about Vegetables, is in no part manifested more, then in the various contrivances about the seed, nor indeed is there in any part of the Vegetable so curious carvings, and beautifull adornments, as about the seed; this in the larger sorts of seeds is most evident to the eye; nor is it less manifest through the *Microscope*, in those seeds whose shape and structure, by reason of their smalness, the eye is hardly able to distinguish.

Of these there are multitudes, many of which I have observ'd through a *Microscope*, and find, that they do, for the most part, every one afford exceeding pleasant and beautifull objects. For besides those that have various kinds of carv'd surfaces, there are other that have smooth and perfectly polish'd surfaces, others a downy hairy surface; some are cover'd onely with a skin, others with a kind of shell, others with both, as is observable also in greater seeds.

Of these seeds I have onely described four sorts which may serve as a *specimen* of what the inquisitive observers are likely to find among the rest. The first of these seeds which are described in the 17. *Scheme*, are those of Corn-Violets, the seed is very small, black, and shining, and, to the naked eye, looks almost like a very small Flea; But through the

Microscope

Schema XVII

A
B
C
D
E
F
G
H
I

Microscope, it appears a large body, cover'd with a tough thick and bright reflecting skin very irregularly shrunk and pitted, insomuch that it is almost an impossibility to find two of them wrinkled alike, so great a variety may there be even in this little seed.

This, though it appear'd one of the most promising seeds for beauty to the naked eye, yet through the *Microscope* it appear'd but a rude mishapen seed, which I therefore drew, that I might thereby manifest how unable we are by the naked eye to judge of beauteous or less curious *microscopical* Objects; cutting some of them in sunder, I observ'd them to be fill'd with a greenish yellow pulp, and to have a very thick husk, in proportion to the pulp.

Observ. XXIX. *Of the Seeds of* Tyme.

THese pretty fruits here represented, in the 18. *Scheme*, are nothing else, but nine several seeds of Tyme; they are all of them in differing posture, both as to the eye and the light; nor are they all of them exactly of the same shape, there being a great variety both in the bulk and figure of each seed; but they all agreed in this, that being look'd on with a *Microscope*, they each of them exactly resembled a Lemmon or Orange dry'd; and this both in shape and colour. Some of them are a little rounder, of the shape of an Orange, as A and B, they have each of them a very conspicuous part by which they were join'd to their little stalk, and one of them had a little piece of stalk remaining on; the opposite side of the seed, you may perceive very plainly by the Figure, is very copped and prominent, as is very usual in Lemmons, which prominencies are express'd in D, E and F.

They seem'd each of them a little creas'd or wrinckled, but E was very conspicuously furrow'd, as if the inward make of this seed had been somewhat like that of a Lemmon also, but upon dividing several seeds with a very sharp Pen-knife, and examining them afterward, I found their make to be in nothing but bulk differing from that of Peas, that is, to have a pretty thick coat, and all the rest an indifferent white pulp, which seem'd very close; so that it seems Nature does not very much alter her method in the manner of inclosing and preserving the vital Principle in the seed, in these very small grains, from that of Beans, Peas, *&c.*

The Grain affords a very pretty Object for the *Microscope*, namely, a Dish of Lemmons plac'd in a very little room; should a Lemmon or Nut be proportionably magnify'd to what this seed of Tyme is, it would make it appear as bigg as a large Hay-reek, and it would be no great wonder to see *Homers Iliads*, and *Homer* and all, cramm'd into such a Nut-shell. We may perceive even in these small Grains, as well as in greater, how curious and carefull Nature is in preserving the seminal principle of Vegetable bodies, in what delicate, strong and most convenient Cabinets she

lays them and closes them in a pulp for their safer protection from outward dangers, and for the supply of convenient alimental juice, when the heat of the Sun begins to animate and move these little *automatons* or Engines; as if she would, from the ornaments wherewith she has deckt these Cabinets, hint to us, that in them she has laid up her Jewels and Master-pieces. And this, if we are but diligent in observing, we shall find her method throughout. There is no curiosity in the Elemental kingdom, if I may so call the bodies of Air, Water, Earth, that are comparable in form to those of Minerals; Air and Water having no form at all, unless a potentiality to be form'd into Globules; and the clods and parcels of Earth are all irregular, whereas in Minerals she does begin to *Geometrize*, and practise, as 'twere, the first principles of *Mechanicks*, shaping them of plain regular figures, as triangles, squares, *&c.* and *tetraedrons*, cubes, *&c.* But none of their forms are comparable to the more compounded ones of Vegetables; For here she goes a step further, forming them both of more complicated shapes, and adding also multitudes of curious Mechanick contrivances in their structure; for whereas in Vegetables there was no determinate number of the leaves or branches, nor no exactly certain figure of leaves, or flowers, or seeds, in Animals all those things are exactly defin'd and determin'd; and where-ever there is either an excess or defect of those determinate parts or limbs, there has been some impediment that has spoil'd the principle which was most regular: Here we shall find, not onely most curiously compounded shapes, but most stupendious Mechanisms and contrivances, here the ornaments are in the highest perfection, nothing in all the Vegetable kingdom that is comparable to the deckings of a Peacock; nay, to the curiosity of any feather, as I elsewhere shew; nor to that of the smallest and most despicable Fly. But I must not stay on these speculations, though perhaps it were very well worth while for one that had leisure, to see what Information may be learn'd of the nature, or use, or virtues of bodies, by their several forms and various excellencies and properties. Who knows but *Adam* might from some such contemplation, give names to all creatures? If at least his names had any significancy in them of the creature's nature on which he impos'd it; as many (upon what grounds I know not) have suppos'd: And who knows, but the Creator may, in those characters, have written and engraven many of his most mysterious designs and counsels, and given man a capacity, which, assisted with diligence and industry, may be able to read and understand them. But not to multiply my digression more then I can the time, I will proceed to the next, which is,

---

Observ. XXX. *Of the Seeds of* Poppy.

THe small seeds of Poppy, which are described in the 19. *Scheme*, both for their smalness, multiplicity and prettiness, as also for their admirable soporifick quality, deserve to be taken notice of among the other

Schem: XIX.











other *microscopical* seeds of Vegetables: For first, though they grow in a Case or Hive oftentimes bigger then one of these Pictures of the *microscopical* appearance, yet are they for the most part so very little, that they exceed not the bulk of a small Nitt, being not above $\frac{1}{32}$ part of an Inch in Diameter, whereas the Diameter of the Hive of them oftentimes exceeds two Inches, so that it is capable of containing neer two hundred thousand, and so in all likelihood does contain a vast quantity, though perhaps not that number. Next, for their prettiness, they may be compar'd to any *microscopical* seed I have yet seen; for they are of a dark brownish red colour, curiously Honey-comb'd all over with a very pretty variety of Net-work, or a small kind of imbosment of very orderly rais'd ridges, the surface of them looking not unlike the inside of a Beev's stomack. But that which makes it most considerable of all, is, the medicinal virtues of it, which are such as are not afforded us by any Mineral preparation; and that is for the procuring of sleep, a thing as necessary to the well-being of a creature as his meat, and that which refreshes both the voluntary and rational faculties, which, whil'st this affection has seis'd the body, are for the most part unmov'd, and at rest. And, methinks, Nature does seem to hint some very notable virtue or excellency in this Plant from the curiosity it has bestow'd upon it. First, in its flower, it is of the highest scarlet-Dye, which is indeed the prime and chiefest colour, and has been in all Ages of the world most highly esteem'd: Next, it has as much curiosity shew'd also in the husk or case of the seed, as any one Plant I have yet met withall; and thirdly, the very seeds themselves, the *Microscope* discovers to be very curiously shap'd bodies; and lastly, Nature has taken such abundant care for the propagation of it, that one single seed grown into a Plant, is capable of bringing some hundred thousands of seeds.

It were very worthy some able man's enquiry whether the intention of Nature, as to the secundary end of Animal and Vegetable substances might not be found out by some such characters and notable impressions as these, or from divers other circumstances, as the figure, colour, place, time of flourishing, springing and fading, duration, taste, smell, *&c.* For if such there are (as an able *Physician* upon good grounds has given me cause to believe) we might then, insteed of studying Herbals (where so little is deliver'd of the virtues of a Plant, and less of truth) have recourse to the Book of Nature it self, and there find the most natural, usefull, and most effectual and specifick Medicines, of which we have amongst Vegetables, two very noble Instances to incourage such a hope, the one of the *Jesuite powder* for the cure of *intermitting Feavers*, and the other of the juice of *Poppy* for the curing the defect of sleeping.

Obſerv. XXXI. *Of* Purſlane-ſeed.

THe Seeds of *Purſlane* ſeem of very notable ſhapes, appearing through the *Microſcope* ſhap'd ſomewhat like a *nautilus* or *Porcelane* ſhell, as may be ſeen in the XX. *Scheme*, it being a ſmall body, coyl'd round in the manner of a Spiral; at the greater end whereof, which repreſents the mouth or orifice of the Shell, there is left a little white tranſparent ſubſtance, like a ſkin, repreſented by B B B B, which ſeems to have been the place whereunto the ſtem was join'd. The whole ſurface of this *Coclea* or Shell, is cover'd over with abundance of little *prominencies* or buttons very orderly rang'd into Spiral rows, the ſhape of each of which ſeem'd much to reſemble a Wart upon a mans hand. The order, variety, and curioſity in the ſhape of this little ſeed, makes it a very pleaſant object for the *Microſcope*, one of them being cut aſunder with a very ſharp Penknife, diſcover'd this carved Caſket to be of a browniſh red, and ſomewhat tranſparent ſubſtance, and manifeſted the inſide to be fill'd with a whitiſh green ſubſtance or pulp, the Bed wherein the ſeminal principle lies *invelop'd*.

There are multitudes of other ſeeds which in ſhape repreſent or imitate the forms of divers other ſorts of Shells: as the ſeed of *Scurvy-graſs*, very much reſembles the make of a *Concha Venerea*, a kind of Purcelane Shell; others repreſent ſeveral ſorts of larger fruits, ſweat Marjerome and Pot-marjerome repreſent Olives. Carret ſeeds are like a cleft of a Coco-Nut Huſk; others are like Artificial things, as Succory ſeeds are like a Quiver full of Arrows, the ſeeds of *Amaranthus* are of an exceeding lovely ſhape, ſomewhat like an Eye: The ſkin of the black and ſhrivled ſeeds of Onyons and Leeks, are all over knobbed like a Seals ſkin. Sorrel has a pretty black ſhining three-ſquare ſeed, which is picked at both ends with three ridges, that are bent the whole length of it. It were almoſt endleſs to reckon up the ſeveral ſhapes, they are ſo many and ſo various; Leaving them therefore to the curious obſerver, I ſhall proceed to the Obſervations on the parts of Animals.

Obſerv. XXXII. *Of the Figure of ſeveral ſorts of* Hair, *and of the texture of the* ſkin.

VIewing ſome of the Hairs of my Head with a very good *Microſcope*, I took notice of theſe particulars:

1. That they were, for the moſt part, *Cylindrical*, ſome of them were ſomewhat *Priſmatical*, but generally they were veryneer round, ſuch as are repreſented in the ſecond Figure of the 5. *Scheme*, by the *Cylinders* E E E. nor could I find any that had ſharp angules.

2. That


B

B

B


B


B

2. That that part which was next the top, was bigger then that which was neerer the root.

3. That they were all along from end to end transparent, though not very cleer, the end next the root appearing like a black transparent piece of Horn, the end next the top more brown, somewhat like transparent Horn.

4. That the root of the Hairs were pretty smooth, tapering inwards, almost like a Parsneb; nor could I find that it had any filaments, or any other vessels, such as the *fibres* of Plants.

5. That the top when split (which is common in long Hair) appear'd like the end of a stick, beaten till it be all flitter'd, there being not onely two splinters, but sometimes half a score and more.

6. That they were all, as farr as I was able to find, solid *Cylindrical* bodies, not pervious, like a Cane or Bulrush; nor could I find that they had any Pith, or distinction of Rind, or the like, such as I had observ'd in Horse-hairs, the Bristles of a Cat, the *Indian* Deer's Hair, *&c.*

Observations on several other sorts of Hair.

For the Brisles of a Hogg, I found them to be first a hard transparent horny substance, without the least appearance of pores or holes in it; and this I try'd with the greatest care I was able, cutting many of them with a very sharp Razor, so that they appear'd, even in the Glass, to have a pretty smooth surface, but somewhat waved by the sawing to and fro of the Razor, as is visible in the end of the *Prismatical* body A of the same Figure; and then making trials with causing the light to be cast on them all the various ways I could think of, that was likely to make the pores appear, if there had been any, I was not able to discover any.

Next, the Figure of the Brisles was very various, neither perfectly round, nor sharp edg'd, but *Prismatical*, with divers sides, and round angles, as appears in the Figure A. The bending of them in any part where they before appear'd cleer, would all flaw them, and make them look white.

The Mustacheos of a Cat (part of one of which is represented by the short *Cylinder* B of the same Figure) seem'd to have, all of them that I observ'd, a large pith in the middle, like the pith of an Elder, whose texture was so close, that I was not able to discover the least sign of pores; and those parts which seem to be pores, as they appear'd in one position to the light, in another I could find a manifest reflection to be cast from them.

This I instance in, to hint that it is not safe to conclude any thing to be positively this or that, though it appear never so plain and likely when look'd on with a *Microscope* in one posture, before the same be examin'd by placing it in several other positions.

And this I take to be the reason why many have believed and asserted the Hairs of a man's head to be hollow, and like so many small pipes perforated from end to end.

Now, though I grant that by an *Analogie* one may suppose them so, and

and from the *Polonian* diſeaſe one may believe them ſuch, yet I think we have not the leaſt encouragement to either from the *Microſcope*, much leſs poſitively to aſſert them ſuch. And perhaps the very eſſence of the *Plica Polonica* may be the hairs growing hollow, and of an unnatural conſtitution.

And as for the *Analogie*, though I am apt enough to think that the hairs of ſeveral Animals may be perforated ſomewhat like a Cane, or at leaſt have a kind of pith in them, firſt, becauſe they ſeem as 'twere a kind of Vegetable growing on an Animal, which growing, they ſay, remains a long while after the Animal is dead, and therefore ſhould like other Vegetables have a pith; and ſecondly, becauſe Horns and Feathers, and Porcupine's Quils, and Cats Briſles, and the long hairs of Horſes, which come very neer the nature of a mans hair, ſeem all of them to have a kind of pith, and ſome of them to be porous, yet I think it not (in theſe caſes, where we have ſuch helps for the ſenſe as the *Microſcope* affords) ſafe concluding or building on more then we ſenſibly know, ſince we may, with examining, find that Nature does in the make of the ſame kind of ſubſtance, often vary her method in framing of it: Inſtances enough to confirm this we may find in the Horns of ſeveral creatures: as what a vaſt difference is there between the Horns of an Oxe, and thoſe of ſome ſorts of Staggs as to their ſhape? and even in the hairs of ſeveral creatures, we find a vaſt difference; as the hair of a man's head ſeems, as I ſaid before, long, *Cylindrical* and ſometime a little *Priſmatical*, ſolid or impervious, and very ſmall; the hair of an *Indian* Deer (a part of the middle of which is deſcribed in the third Figure of the fifth *Scheme*, marked with F) is bigger in compaſs through all the middle of it, then the Briſle of an Hogg, but the end of it is ſmaller then the hair of any kind of Animal (as may be ſeen by the Figure G) the whole belly of it, which is about two or three Inches long, looks to the eye like a thread of courſe Canvaſs, that has been newly unwreath'd, it being all wav'd or bended to and fro, much after that manner, but through the *Microſcope*, it appears all perforated from ſide to ſide, and Spongie, like a ſmall kind of ſpongy Coral, which is often found upon the *Engliſh* ſhores; but though I cut it tranſverſly, I could not perceive that it had any pores that ran the long-way of the hair: the long hairs of Horſes C C and D, ſeem *Cylindrical* and ſomewhat pithy; the Briſles of a Cat B, are conical and pithy: the Quils of Porcupines and Hedghoggs, being cut tranſverſly, have a whitiſh pith, in the manner of a Starr, or Spur-rowel: Piggs-hair (A) is ſomewhat *triagonal*, and ſeems to have neither pith nor pore: And other kinds of hair have quite a differing ſtructure and form. And therefore I think it no way agreeable to a true natural Hiſtorian, to pretend to be ſo ſharp-ſighted, as to ſee what a pre-conceiv'd *Hypotheſis* tells them ſhould be there, where another man, though perhaps as ſeeing, but not foreſtall'd, can diſcover no ſuch matter.

But to proceed; I obſerv'd ſeveral kind of hairs that had been Dyed, and found them to be a kind of horny *Cylinder*, being of much about the tranſparency of a pretty cleer piece of Oxe horn; theſe appear'd quite through-

throughout ting'd with the colours they exhibited. And 'tis likely, that those hairs being boyl'd or steep'd in those very hot ting'd liquors in the Dye-fat, And the substance of the hair being much like that of an Oxes Horn, the penetrant liquor does so far mollifie and soften the substance, that it sinks into the very center of it, and so the ting'd parts come to be mix'd and united with the very body of the hair, and do not (as some have thought) only stick on upon the outward surface. And this, the boiling of Horn will make more probable; for we shall find by that action, that the water will insinuate it self to a pretty depth within the surface of it, especially if this penetrancy of the water be much helped by the Salts that are usually mix'd with the Dying liquors. Now, whereas Silk may be dyed or ting'd into all kind of colours without boiling or dipping into hot liquors, I ghess the reason to be two-fold: First, because the filaments, or small cylinders of Silk, are abundantly smaller and finer, and so have a much less depth to be penetrated then most kind of hairs; and next, because the substance or matter of Silk, is much more like a Glew then the substance of Hair is. And that I have reason to suppose; First, because when it is spun or drawn out of the Worm, it is a perfect glutinous substance, and very easily sticks and cleaves to any adjacent body, as I have several times observed, both in Silk-worms and Spiders. Next, because that I find that water does easily dissolve and mollifie the substance again, which is evident from their manner of ordering those bottoms or pods of the Silk-worm before they are able to unwind them. It is no great wonder therefore, if those Dyes or ting'd liquors do very quickly mollifie and tinge the surfaces of so small and so glutinous a body. And we need not wonder that the colours appear so lovely in the one, and so dull in the other, if we view but the ting'd cylinders of both kinds with a good *Microscope*; for whereas the substance of Hair, at best, is but a dirty duskish white somewhat transparent, the filaments of Silk have a most lovely transparency and cleerness, the difference between those two being not much less then that between a piece of Horn, and a piece of Crystal; the one yielding a bright and vivid reflection from the concave side of the cylinder, that is, from the concave surface of the Air that incompasses the back-part of the cylinder; the other yielding a dull and perturb'd reflection from the several *Heterogeneous* parts that compose it. And this difference will be manifest enough to the eye, if you get a couple of small Cylinders, the smaller of Crystal Glass, the other of Horn, and then varnishing them over very thinly with some transparent colour, which will represent to the naked eye much the same kind of object which is represented to it from the filaments of Silk and Hair by the help of the *Microscope*. Now, since the threads of Silk and Serge are made up of a great number of these filaments, we may henceforth cease to wonder at the difference. From much the same reason proceeds the vivid and lovely colours of Feathers, wherein they very farr exceed the natural as well as Artificial colours of hair, of which I shall say more in its proper place.

The Teguments indeed of creatures are all of them adapted to the peculiar use and convenience of that Animal which they inwrap; and very

much

much also for the ornament and beauty of it, as will be most evident to any one that shall attentively consider the various kinds of cloathings wherewith most creatures are by Nature invested and cover'd. Thus I have observed, that the hair or furr of those Northern white Bears that inhabite the colder Regions, is exeeeding thick and warm: the like have I observ'd of the hair of a *Greenland* Deer, which being brought alive to *London*, I had the opportunity of viewing; its hair was so exceeding thick, long and soft, that I could hardly with my hand, grasp or take hold of his skin, and it seem'd so exceeding warm, as I had never met with any before. And as for the ornamentative use of them, it is most evident in a multitude of creatures, not onely for colour, as the Leopards, Cats, Rhein Deer, *&c.* but for the shape, as in Horses manes, Cats beards, and several other of the greater sort of terrestrial Animals, but is much more conspicuous, in the Vestments of Fishes, Birds, Insects, of which I shall by and by give some Instances.

As for the skin, the *Microscope* discovers as great a difference between the texture of those several kinds of Animals, as it does between their hairs; but all that I have yet taken notice of, when tann'd or dress'd, are of a Spongie nature, and seem to be constituted of an infinite company of small long *fibres* or hairs, which look not unlike a heap of Tow or Okum; every of which *fibres* seem to have been some part of a Muscle, and probably, whil'st the Animal was alive, might have its distinct function, and serve for the contraction and relaxation of the skin, and for the stretching and shrinking of it this or that way.

And indeed, without such a kind of texture as this, which is very like that of *Spunk*, it would seem very strange, how any body so strong as the skin of an Animal usually is, and so close as it seems, whil'st the Animal is living, should be able to suffer so great an extension any ways, without at all hurting or dilacerating any part of it. But, since we are inform'd by the *Microscope*, that it consists of a great many small filaments, which are implicated, or intangled one within another, almost no otherwise then the hairs in a lock of Wool, or the flakes in a heap of Tow, though not altogether so loose; but the filaments are here and there twisted, as twere, or interwoven, and here and there they join and unite with one another, so as indeed the whole skin seems to be but one piece, we need not much wonder: And though these *fibres* appear not through a *Microscope*, exactly jointed and contex'd, as in Sponge; yet, as I formerly hinted, I am apt to think, that could we find some way of discovering the texture of it, whil'st it invests the living Animal, or had some very easie way of separating the pulp or intercurrent juices, such as in all probability fill those *Interstitia*, without dilacerating, brusing, or otherwise spoiling the texture of it (as it seems to be very much by the ways of tanning and dressing now us'd) we might discover a much more curious texture then I have hitherto been able to find; perhaps, somewhat like that of Sponges.

That of *Chamoise* Leather is indeed very much like that of *Spunk*, save onely that the *filaments* seem nothing neer so even and round, nor altogether so small, nor has it so curious joints as *Spunk* has, some of which I have

have lately discover'd like those of a Sponge, and perhaps all these three bodies may be of the same kind of substance, though two of them indeed are commonly accounted Vegetable (which, whether they be so or no, I shall not now dispute) But this seems common to all three, that they undergo a tanning or dressing, whereby the interspers'd juices are wasted and wash'd away before the texture of them can be discover'd.

What their way is of dressing, or curing Sponges, I confess, I cannot learn; but the way of dressing *Spunk*, is, by boiling it a good while in a strong *Lixivium*, and then beating it very well; and the manner of dressing Leather is sufficiently known.

It were indeed extremely desirable, if such a way could be found whereby the *Parenchyma* or flesh of the Muscles, and several other parts of the bod,y might be wash'd, or wasted clean away, without vitiating the form of the *fibrous* parts or vessells of it, for hereby the texture of those parts, by the help of a good *Microscope*, might be most accurately found.

But to digress no further, we may, from this discovery of the *Microscope*, plainly enough understand how the skin, though it looks so close as it does, comes to give a passage to so vast a quantity of *excrementitious* substances, as the diligent *Sanctorius* has excellently observed it to do, in his *medicina statica*; for it seems very probable, from the texture after dressing, that there are an infinit of pores that every way pierce it, and that those pores are onely fill'd with some kind of juice, or some very pulpy soft substance, and thereby the steams may almost as easily find a passage through such a fluid *vehicle* as the vaporous bubbles which are generated at the bottom of a Kettle of hot water do find a passage through that fluid *medium* into the ambient Air.

Nor is the skin of animals only thus pervious, but even those of vegetables also seem to be the same; for otherwise I cannot conceive why, if two sprigs of Rosemary (for Instance) be taken as exactly alike in all particulars as can be, and the one be set with the bottom in a Glass of water, and the other be set just without the Glass, but in the Air onely, though you stop the lower end of that in the Air very carefully with Wax, yet shall it presently almost wither, whereas the other that seems to have a supply from the subjacent water by its small pipes, or *microscopical* pores, preserves its greenness for many days, and sometimes weeks.

Now, this to me, seems not likely to proceed from any other cause then the *avolation* of the juice through the skin; for by the Wax, all those other pores of the stem are very firmly and closely stop'd up. And from the more or less porousness of the skins or rinds of Vegetables may, perhaps, be somewhat of the reason given, why they keep longer green, or sooner wither; for we may observe by the bladdering and craking of the leaves of Bays, Holly, Laurel, *&c.* that their skins are very close, and do not suffer so free a passage through them of the included juices.

But of this, and of the Experiment of the Rosemary, I shall elsewhere more fully consider, it seeming to me an extreme luciferous Experiment, such as seems indeed very plainly to prove the *Schematism* or structure

of Vegetables altogether *mechanical*, and as neceſſary, that (water and warmth being apply'd to the bottom of the ſprig of a Plant) ſome of it ſhould be carried upwards into the ſtem, and thence diſtributed into the leaves, as that the water of the *Thames* covering the bottom of the Mills at the Bridge foot of *London*, and by the ebbing aud flowing of it, paſſing ſtrongly by them, ſhould have ſome part of it convey'd to the Ceſterns above, and thence into ſeveral houſes and Ceſterns up and down the City.

Obſerv. XXXIII. *Of the* Scales *of a* Soal, *and other Fiſhes.*

HAving hinted ſomewhat of the ſkin and covering of terreſtrial Animals, I ſhall next add an Obſervation I made on the ſkin and Scales of a *Soal*, a ſmall Fiſh, commonly enough known; and here in Fiſhes, as well as other Animals, Nature follows its uſual method, framing all parts ſo, as that they are both uſefull and ornamental in all its compoſures, mingling *utile* and *dulce* together; and both theſe deſigns it ſeems to follow, though our unaſſiſted ſenſes are not able to peceive them: This is not onely manifeſt in the covering of this Fiſh only, but in multitudes of others, which it would be too long to enumerate, witneſs particularly that ſmall Sand Shell, which I mention'd in the XI. Obſervation, and infinite other ſmall Shells and Scales, divers of which I have view'd. This ſkin I view'd, was flead from a prettylarge *Soal*, and then expanded and dry'd, the inſide of it, when dry, to the naked eye, look'd very like a piece of Canvaſs, but the *Microſcope* diſcover'd that texture to be nothing elſe, but the inner ends of thoſe curious Scolop'd Scales I, I, I, in the ſecond *Figure* of the XXI. *Scheme*, namely, the part of GGGG (of the larger repreſentation of a ſingle Scale, in the firſt *Figure* of the ſame *Scheme*) which on the back ſide, through an ordinary ſingle Magnifying Glaſs, look'd not unlike the Tyles on an houſe.

The outſide of it, to the naked eye, exhibited nothing more of ornament, ſave the uſual order of ranging the Scales into a *triagonal* form, onely the edges ſeem'd a little to ſhine, the finger being rubb'd from the tail-wards towards the head, the Scales ſeem'd to ſtay and raze it; But through an ordinary Magnifying glaſs, it exhibited a moſt curiouſly carved and adorned ſurface, ſuch as is viſible in the ſecond *Figure*, each of thoſe (formerly almoſt imperceptible) Scales appearing much of the ſhape I, I, I, that is, they were round, and protuberant, and ſomewhat ſhap'd like a Scolop, the whole Scale being creas'd with curiouſly wav'd and indented ridges, with proportionable furrows between; each of which was terminated with a very ſharp tranſparent bony ſubſtance, which, like ſo many ſmall Turnpikes, ſeem'd to arm the edges.

The back part KKK was the ſkin into which each of theſe Scales were very deeply fix'd, in the curious regular order, viſible in the ſecond

Figure.

Schem. XXI



Fig. 1

Fig. 2




Fig: 1
Fig: 2
A
B
C
D
E
F

Figure. The length and ſhape of the part of the Scale which was buried by the ſkin, is evidenced by the firſt *Figure*; which is the repreſentation of one of them pluck'd out and view'd through a good *Microſcope*, namely, the part L F G G F L, wherein is alſo more plainly to be ſeen, the manner of carving of the ſcolopt part of every particular Scale, how each ridge or barr E E E is alternately hollowed or engraven, and how every gutter between them is terminated with very tranſparent and hard pointed ſpikes, and how every other of theſe, as A A A A, are much longer then the interjacent ones, D D D.

The texture or form alſo of the hidden part appears, namely, the middle part, G G G, ſeems to conſiſt of a great number of ſmall quills or pipes, by which, perhaps, the whole may be nouriſhed; and the ſide parts F F conſiſt of a more fibrous texture, though indeed the whole Scale ſeem'd to be of a very tough griſly ſubſtance, like the larger Scales of other Fiſhes.

The Scales of the ſkin of a Dog-fiſh (which is us'd by ſuch as work in Wood, for the ſmoothing of their work, and conſiſts plainly enough to the naked eye, of a great number of ſmall horny points) through the *Microſcope* appear'd each of them curiouſly ridg'd, and very neatly carved; and indeed, you can hardly look on the ſcales of any Fiſh, but you may diſcover abundance of curioſity and beautifying; and not only in theſe Fiſhes, but in the ſhells and cruſts or armour of moſt ſorts of *Marine* Animals ſo inveſted.

Obſerv. XXXIV. *Of the Sting of a* Bee.

THe Sting of a *Bee*, delineated in the ſecond Figure of the XVI. *Scheme*, ſeems to be a weapon of offence, and is as great an Inſtance, that Nature did realy intend revenge as any, and that firſt, becauſe there ſeems to be no other uſe of it. Secondly, by reaſon of its admirable ſhape, ſeeming to be purpoſely ſhap'd for that very end. Thirdly, from the virulency of the liquor it ejects, and the ſad effects and ſymptoms that follow it.

But whatever be the uſe of it, certain it is, that the ſtructure of it is very admirable; what it appears to the naked eye, I need not deſcribe, the thing being known almoſt to every one, but it appears through the *Microſcope*, to conſiſt of two parts, the one a ſheath, without a chape or top, ſhap'd almoſt like the Holſter of a Piſtol, beginning at *d*, and ending at *b*, this ſheath I could moſt plainly perceive to be hollow, and to contain in it, both a Sword or Dart, and the poiſonous liquor that cauſes the pain. The ſheath or caſe ſeem'd to have ſeveral joints or ſettings together, marked by *f g h i k l m n o*, it was arm'd moreover neer the top, with ſeveral crooks or forks (*p q r ſ t*) on one ſide, and (*p q r ſ t u*) on the other, each of which ſeem'd like ſo many Thorns growing on a briar, or rather like ſo many Cat's Claws; for the crooks themſelves ſeem'd to be little ſharp tranſparent points or claws, growing out of little *protuberancies* on

the ſide of the ſheath, which, by obſerving the Figure diligently, is eaſie enough to be perceiv'd; and from ſeveral particulars, I ſuppoſe the Animal has a power of diſplaying them, and ſhutting them in again as it pleaſes, as a Cat does its claws, or as an Adder or Viper can its teeth or fangs.

The other part of the Sting was the Sword, as I may ſo call it, which is ſheath'd, as it were, in it, the top of which *a b* appears quite through at the ſmaller end, juſt as if the chape of the ſheath of a Sword were loſt, and the end of it appear'd beyond the Scabbard; the end of this Dart(*a*) was very ſharp, and it was arm'd likewiſe with the like Tenterhooks or claws with thoſe of the ſheath, ſuch as (*v x y*, *x y z z*) theſe crooks, I am very apt to think, can be clos'd up alſo, or laid flat to the ſides of the Sword when it is drawn into the Scabbard, as I have ſeveral times obſerv'd it to be, and can be ſpred again or extended when ever the Animal pleaſes.

The conſideration of which very pretty ſtructure, has hinted to me, that certainly the uſe of theſe claws ſeems to be very conſiderable, as to the main end of this Inſtrument, for the drawing in, and holding the ſting in the fleſh; for the point being very ſharp, the top of the Sting or Dagger (*a b*) is very eaſily thruſt into an Animal's body, which being once entred, the Bee, by endeavouring to pull it into the ſheath, draws (by reaſon of the crooks (*v x y*) and (*x y z z*) which lay hold of the ſkin on either ſide) the top of the ſheath (*t ſ r v*) into the ſkin after it, and the crooks *t*, *ſ*, and *r*, *v*, being entred, when the Bee endeavours to thruſt out the top of the ſting out of the ſheath again, they lay hold of the ſkin on either ſide, and ſo not onely keep the ſheath from ſliding back, but helps the top inwards, and thus, by an alternate and ſucceſſive retracting and emitting of the Sting in and out of the ſheath, the little enraged creature by degrees makes his revengfull weapon pierce the toughest and thickeſt Hides of his enemies, in ſo much that ſome few of theſe ſtout and reſolute ſoldiers with theſe little engines, do often put to flight a huge maſty Bear, one of their deadly enemies, and thereby ſhew the world how much more conſiderable in Warr a few ſkilfull Engineers and reſolute ſoldiers politickly order'd, that know how to manage ſuch engines, are, then a vaſt unweildy rude force, that confides in, and acts onely by, its ſtrength. But (to proceed) that he thus gets in his Sting into the ſkin, I conjecture, becauſe, when I have obſerv'd this creature living, I have found it to move the Sting thus, to and fro, and thereby alſo, perhaps, does, as 'twere, pump or force out the poiſonous liquor, and make it hang at the end of the ſheath about *b* in a drop. The crooks, I ſuppoſe alſo to be the cauſe why theſe angry creatures, haſtily removing themſelves from their revenge, do often leave theſe weapons behind them, ſheath'd, as 'twere, in the fleſh, and, by that means, cauſe the painfull ſymptoms to be greater, and more laſting, which are very probably caus'd, partly by the piercing and tearing of the ſkin by the Sting, but chiefly by the corroſive and poiſonous liquor that is by this Syringe-pipe convey'd among the ſenſitive parts thereof and thereby more eaſily gnaws

and

and corrodes those tender *fibres*: As I have shewed in the description of a Nettle and of Cowhage.

Observ. XXXV. *Of the contexture and shape of the particles of* Feathers.

EXamining several sorts of *Feathers*, I took notice of these particulars in all sorts of wing-Feathers, especially in those which serv'd for the beating of the air in the action of flying.

That the outward surface of the Quill and Stem was of a very hard, stiff, and horny substance, which is obvious enough, and that the part above the Quill was fill'd with a very white and light pith, and, with the *Microscope*, I found this pith to be nothing else, but a kind of natural *congeries* of small bubbles, the films of which seem to be of the same substance with that of the Quill, that is, of a stiff transparent horny substance.

Which particular seems to me, very worthy a more serious consideration; For here we may observe Nature, as 'twere, put to its shifts, to make a substance, which shall be both light enough, and very stiff and strong, without varying from its own establish'd principles, which we may observe to be such, that very strong bodies are for the most part very heavie also, a strength of the parts usually requiring a density, and a density a gravity; and therefore should Nature have made a body so broad and so strong as a Feather, almost, any other way then what it has taken, the gravity of it must necessarily have many times exceeded this; for this pith seems to be like so many stops or cross pieces in a long optical tube, which do very much contribute to the strength of the whole, the pores of which were such, as that they seem'd not to have any communication with one another, as I have elsewhere hinted.

But the Mechanism of Nature is usually so excellent, that one and the same substance is adapted to serve for many ends. For the chief use of this, indeed, seems to be for the supply of nourishment to the downy or feathery part of the stem; for 'tis obvious enough in all sorts of Feathers, that 'tis plac'd just under the roots of the branches that grow out of either side of the quill or stalk, and is exactly shap'd according to the ranking of those branches, coming no lower into the quill, then just the beginning of the downy branches, and growing onely on the under side of of the quill where those branches do so. Now, in a ripe Feather (as one may call it) it seems difficult to conceive how the *Succus nutritius* should be convey'd to this pith; for it cannot, I think, be well imagin'd to pass through the substance of the quill, since, having examin'd it with the greatest diligence I was able, I could not find the least appearance of pores; but he that shall well examine an unripe or pinn'd Feather, will plainly enough perceive the Vessel for the conveyance of it to be the thin filmy pith (as tis call'd) which passes through the middle of the quill.

As for the make and contexture of the Down it self, it is indeed very

rare

rare and admirable, and such as I can hardly believe, that the like is to be discover'd in any other body in the world; for there is hardly a large Feather in the wing of a Bird, but contains neer a million of distinct parts, and every one of them shap'd in a most regular & admirable form, adapted to a particular Design: For examining a middle ciz'd Goose-quill, I easily enough found with my naked eye, that the main stem of it contain'd about 300. longer and more Downy branchings upon one side, and as many on the other of more stiff but somewhat shorter branchings. Many of these long and downy branchings, examining with an ordinary *Microscope*, I found divers of them to contain neer 1200. small leaves (as I may call them, such as E F of the first Figure of the 23. *Scheme*) and as many stalks; on the other side, such as I K of the same Figure, each of the leaves or branchings, E F, seem'd to be divided into about sixteen or eighteen small joints, as may be seen plainly enough in the Figure, out of most of which there seem to grow small long *fibres*, such as are express'd in the Figure, each of them very proportionably shap'd according to its position, or plac'd on the stalk E F; those on the under side of it, namely, 1, 2, 3, 4, 5, 6, 7, 8, 9, *&c.* being much longer then those directly opposite to them on the upper; and divers of them, such as 2, 3, 4, 5, 6, 7, 8, 9, *&c.* were terminated with small crooks, much resembling those small crooks, which are visible enough to the naked eye, in the seed-buttons of Bur-docks. The stalks likewise, I K on the other side, seem'd divided into neer as many small knotted joints, but without any appearance of strings or crooks, each of them about the middle K, seem'd divided into two parts by a kind of fork, one side of which, namely, K L, was extended neer the length of K I, the other, M, was very short.

The transverse Sections of the stems of these branchings, manifested the shape or figure of it to be much like I N O E, which consisted of a horny skin or covering, and a white seemingly frothy pith, much like the make of the main stem of a Feather.

The use of this strange kind of form, is indeed more admirable then all the rest, and such as deserves to be much more seriously examin'd and consider'd, then I have hitherto found time or ability to do; for certainly, it may very much instruct us in the nature of the Air, especially as to some properties of it.

The stems of the Downy branches I N O E, being rang'd in the order visible enough to the naked eye, at the distance of I F, or somewhat more, the *collateral* stalks and leaves (if I may so call those bodies I newly described) are so rang'd, that the leaves or hairy stalks of the one side lie at top, or are incumbent on the stalks of the other, and cross each other, much after the manner express'd in the second Figure of the 23. *Scheme*, by which means every of those little hooked *fibres* of the leaved stalk get between the naked stalks, and the stalks being full of knots, and a prety way dis-join'd, so as that the *fibres* can easily get between them, the two parts are so closely and admirably woven together, that it is able to impede, for the greatest part, the transcursion of the Air; and though they are so exceeding small, as that the thickness of one of

these


Fig: 1.
L
M
K
T
E
N
O
F
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
Fig: 2.
Fig: 3.
Fig: 4.
Fig: 5.
1/12 of an inch

these stalks amounts not to a 500. part of an Inch, yet do they compose so strong a texture, as, notwithstanding the exceeding quick and violent beating of them against the Air, by the strength of the Birds wing, they firmly hold together. And it argues an admirable providence of Nature in the contrivance and fabrick of them; for their texture is such, that though by any external injury the parts of them are violently dis-joyn'd, so as that the leaves and stalks touch not one another, and consequently several of these rents would impede the Bird's flying; yet, for the most part, of themselves they readily re-join and re-contex themselves, and are easily by the Birds stroking the Feather, or drawing it through its Bill, all of them settled and woven into their former and natural posture; for there are such an infinite company of those small *fibres* in the under side of the leaves, and most of them have such little crooks at their ends, that they readily catch and hold the stalks they touch.

From which strange contexture, it seems rational to suppose that there is a certain kind of mesh or hole so small, that the Air will not very easily pass through it, as I hinted also in the sixth Observation about small Glass Canes, for otherwise it seems probable, that Nature would have drawn over some kind of thin film which should have covered all those almost square meshes or holes, there seeming through the *Microscope* to be more then half of the surface of the Feather which is open and visibly pervious; which conjecture will yet seem more probable from the texture of the brushie wings of the *Tinea argentea*, or white Feather wing'd moth, which I shall anone describe. But Nature, that knows best its own laws, and the several properties of bodies, knows also best how to adapt and fit them to her designed ends, and whoso would know those properties, must endeavour to trace Nature in its working, and to see what course she observes. And this I suppose will be no inconsiderable advantage which the *Schematisms* and Structures of Animate bodies will afford the diligent enquirer, namely, most sure and excellent instructions, both as to the practical part of *Mechanicks* and to the *Theory* and knowledge of the nature of the bodies and motions.

Observ. XXXVI. *Of* Peacoks, Ducks, *and other* Feathers *of changeable colours.*

THe parts of the Feathers of this glorious Bird appear, through the *Microscope*, no less gaudy then do the whole Feathers; for, as to the naked eye 'tis evident that the stem or quill of each Feather in the tail sends out multitudes of *Lateral* branches, such as A B in the third Figure of the 23. *Scheme* represents a small part of about $\frac{1}{32}$ part of an Inch long, and each of the *lateral* branches emit multitudes of little sprigs, threads or hairs on either side of them, such as C D, C D, C D, so each of those threads in the *Microscope* appears a large long body, consisting of a multitude

tude of bright reflecting parts, whose Figure 'tis no easie matter to determine, as he that examines it shall find; for every new position of it to the light makes it perfectly seem of another form and shape, and nothing what it appear'd a little before; nay, it appear'd very differing oftimes from so seemingly inconsiderable a circumstance, that the interposing of ones hand between the light and it, makes a very great change, and the opening or shutting a Casement and the like, very much diversifies the appearance. And though, by examining the form of it very many ways, which would be tedious here to enumerate, I suppose I have discover'd the true Figure of it, yet oftentimes, upon looking on it in another posture, I have almost thought my former observations deficient, though indeed, upon further examination, I have found even those also to confirm them.

These threads therefore I find to be a *congeries* of small *Laminæ* or plates, as *e e e e e*, &c. each of them shap'd much like this of *a b c d*, in the fourth *Figure*, the part *a c* being a ridge, prominency, or stem, and *b* and *d* the corners of two small thin Plates that grow unto the small stalk in the middle, so that they make a kind of little feather; each of these Plates lie one close to another, almost like a company of sloping ridge or gutter Tyles; they grow on each side of the stalk opposite to one another, by two and two, from top to bottom, in the manner expres'd in the fifth Figure, the tops of the lower covering the roots of the next above them; the under side of each of these laminated bodies, is of a very dark and opacous substance, and suffers very few Rays to be trajected, but reflects them all toward that side from whence they come, much like the foil of a Looking-glass; but their upper sides seem to me to consist of a multitude of thin plated bodies, which are exceeding thin, and lie very close together, and thereby, like mother of Pearl shells, do not onely reflect a very brisk light, but tinge that light in a most curious manner; and by means of various positions, in respect of the light, they reflect back now one colour, and then another, and those most vividly.

Now, that these colours are onely *fantastical* ones, that is, such as arise immediately from the refractions of the light, I found by this, that water wetting these colour'd parts, destroy'd their colours, which seem'd to proceed from the alteration of the reflection and refraction. Now, though I was not able to see those hairs at all transparent by a common light, yet by looking on them against the Sun, I found them to be ting'd with a darkish red colour, nothing a-kin to the curious and lovely greens and blues they exhibited.

What the reason of colour seems to be in such thin plated bodies, I have elsewhere shewn. But how water cast upon those threads destroys their colours, I suppose to be perform'd thus; The water falling upon these plated bodies from its having a greater congruity to Feathers then the Air, insinuates it self between those Plates, and so extrudes the strong reflecting Air, whence both these parts grow more transparent, as the *Microscope* informs, and colourless also, at best retaining a very faint and dull

Schem. XI

Fig. 1



Fig. 3

Fig. 2



Fig. 4



dull colour. But this wet being wasted away by the continual evaporations and steams that pass through them from the Peacock, whil'st that Bird is yet alive, the colours again appear in their former luster, the *interstitia* of these Plates being fill'd with the strongly reflecting Air.

The beauteous and vivid colours of the Feathers of this Bird, being found to proceed from the curious and exceeding smalness and fineness of the reflecting parts, we have here the reason given us of all those gauderies in the apparel of other Birds also, and how they come to exceed the colours of all other kinds of Animals, besides Insects; for since (as we here and elsewhere also shew) the vividness of a colour, depends upon the fineness and transparency of the reflecting and refracting parts; and since our *Microscope* discovers to us, that the component parts of feathers are such, and that the hairs of Animals are otherwise; and since we find also by the Experiment of that Noble and most Excellent Person I formerly named; that the difference between Silk and Flax, as to its colour, is nothing else (for Flax reduc'd to a very great fineness of parts, both white and colour'd, appears as white and as vivid as any Silk, but loses that brightness and its Silken aspect as soon as it is twisted into thread, by reason that the component parts, though very small and fine, are yet pliable flakes, and not cylinders, and thence, by twisting, become united into one opacous body, whereas the threads of Silk and Feathers retain their lustre, by preserving their cylindrical form intire without mixing; so that each reflected and refracted beam that composes the gloss of Silk, preserves its own property of modulating the light intire); And since we find the same confirm'd by many other Experiments elsewhere mentioned, I think we may safely conclude this for an Axiome, that wheresoever we meet with transparent bodies, spun out into very fine parts, either cleer, or any ways ting'd, the colours resulting from such a *composition* must necessarily be very glorious, vivid, and cleer, like those of Silk and Feathers. This may perhaps hint some usefull way of making other bodies, besides Silk, be susceptible of bright tinctures, but of this onely by the by.

The changeable colour'd Feathers also of Ducks, and several other Birds, I have found by examination with my *Microscope*, to proceed from much the same causes and textures.

Observ. XXXVII. *Of the Feet of* Flies, *and several other* Insects.

THe foot of a Fly (delineated in the first *Figure* of the 23. *Scheme*, which represents three joints, the two Tallons, and the two Pattens in a flat posture; and in the second *Figure* of the same *scheme*, which represents onely one joint, the Tallons and Pattens in another posture) is of a most admirable and curious contrivance, for by this the Flies are inabled to walk against the sides of Glass, perpendicularly upwards, and to

 contain

contain themſelves in that poſture as long as they pleaſe; nay, to walk and ſuſpend themſelves againſt the under ſurface of many bodies, as the ceiling of a room, or the like, and this with as great a ſeeming facility and firmneſs, as if they were a kind of *Antipodes*, and had a *tendency* upwards, as we are ſure they have the contrary, which they alſo evidently diſcover, in that they cannot make themſelves ſo light, as to ſtick or ſuſpend themſelves on the under ſurface of a Glaſs well poliſh'd and cleans'd; their ſuſpenſion therefore is wholly to be aſcrib'd to ſome Mechanical contrivance in their feet; which, what it is, we ſhall in brief explain, by ſhewing, that its Mechaniſm conſiſts principally in two parts, that is, firſt its two Claws, or Tallons, and ſecondly, two Palms, Pattens, or Soles.

The two Tallons are very large, in proportion to the foot, and handſomly ſhap'd in the manner deſcrib'd in the *Figures*, by A B, and A C, the bigger part of them from A to *d d*, is all hairy, or briſled, but toward the top, at C and B ſmooth, the tops or points, which ſeem very ſharp turning downwards and inwards, are each of them mov'd on a joint at A, by which the Fly is able to open or ſhut them at pleaſure, ſo that the points B and C being entered in any pores, and the Fly endeavouring to ſhut them, the Claws not onely draw one againſt another, and ſo faſten each other, but they draw the whole foot, G G A D D forward, ſo that on a ſoft footing, the tenters or points G G G G, (whereof a Fly has about ten in each foot, to wit, two in every joint) run into the pores, if they find any, or at leaſt make their way; and this is ſenſible to the naked eye, in the feet of a *Chafer*, which, if he be ſuffer'd to creep over the hand, or any other part of the ſkin of ones body, does make his ſteps as ſenſible to the touch as the ſight.

But this contrivance, as it often fails the *Chafer*, when he walks on hard and cloſe bodies, ſo would it alſo our Fly, though he be a much leſſer, and nimbler creature, and therefore Nature has furniſh'd his foot with another *additament* much more curious and admirable, and that is, with a couple of Palms, Pattens or Soles D D, the ſtructure of which is this:

From the bottom or under part of the laſt joint of his foot, K, ariſe two ſmall thin plated horny ſubſtances, each conſiſting of two flat pieces, D D, which ſeem to be flexible, like the covers of a Book, about F F, by which means, the plains of the two ſides E E, do not always lie in the ſame plain, but may be ſometimes ſhut cloſer, and ſo each of them may take a little hold themſelves on a body; but that is not all, for the under ſides of theſe Soles are all beſet with ſmall briſles, or tenters, like the Wire teeth of a Card uſed for working Wool, the points of all which tend forwards, hence the two Tallons drawing the feet forwards, as I before hinted, and theſe being applied to the ſurface of the body with all the points looking the contrary way, that is, forwards and outwards, if there be any irregularity or yielding in the ſurface of the body, the Fly ſuſpends it ſelf very firmly and eaſily, without the acceſs or need of any ſuch Sponges fill'd with an imaginary *gluten*, as many have, for want of good Glaſſes, perhaps, or a troubleſome and diligent examination, ſuppos'd.

Now, that the Fly is able to walk on Glaſs, proceeds partly from ſome ruggedneſs

ruggedness of the surface; and chiefly from a kind of tarnish, or dirty smoaky substance, which adheres to the surface of that very hard body; and though the pointed parts cannot penetrate the substance of Glass, yet may they find pores enough in the tarnish, or at least make them.

This Structure I somewhat the more diligently survey'd, because I could not well comprehend, how, if there were such a glutinous matter in those supposed Sponges, as most (that have observ'd that Object in a *Microscope*) have hitherto believ'd, how, I say, the Fly could so readily unglew and loosen its feet: and, because I have not found any other creature to have a contrivance any ways like it; and chiefly, that we might not be cast upon unintelligible explications of the *Phenomena* of Nature, at least others then the true ones, where our senses were able to furnish us with an intelligible, rationall and true one.

Somewhat a like contrivance to this of Flies shall we find in most other Animals, such as all kinds of Flies and case-wing'd creatures; *nay, in a* Flea, an Animal abundantly smaller then this Fly. Other creatures, as Mites, the Land-Crab, *&c.* have onely one small very sharp Tallon at the end of each of their legs, which all drawing towards the center or middle of their body, inable these exceeding light bodies to suspend and fasten themselves to almost any surface.

Which how they are able to do, will not seem strange, if we consider, first, how little body there is in one of these creatures compar'd to their superficies, or outside, their thickness, perhaps, oftentimes, not amounting to the hundredth part of an Inch: Next, the strength and agility of these creatures compar'd to their bulk, being, proportionable to their bulk, perhaps, an hundred times stronger then an Horse or Man. And thirdly, if we consider that Nature does always appropriate the instruments, so as they are the most fit and convenient to perform their offices, and the most simple and plain that possibly can be; this we may see further verify'd also in the foot of a Louse which is very much differing from those I have been describing, but more convenient and necessary for the place of its habitation, each of his leggs being footed with a couple of small claws which he can open or shut at pleasure, shap'd almost like the claws of a Lobster or Crab, but with appropriated contrivances for his peculiar use, which being to move its body to and fro upon the hairs of the creature it inhabits, Nature has furnish'd one of its claws with joints, almost like the joints of a man's fingers, so as thereby it is able to encompass or grasp a hair as firmly as a man can a stick or rope.

Nor, is there a less admirable and wonderfull *Mechanism* in the foot of a Spider, whereby he is able to spin, weave, and climb, or run on his curious transparent clew, of which I shall say more in the description of that Animal.

And to conclude, we shall in all things find, that Nature does not onely work Mechanically, but by such excellent and most compendious, as well as stupendious contrivances, that it were impossible for all the reason in the world to find out any contrivance to do the same thing that should have more convenient properties. And can any be so sottish,

as to think all those things the productions of chance? Certainly, either their Ratiocination must be extremely depraved, or they did never attentively consider and contemplate the Works of the Al-mighty.

Observ. XXXVIII. *Of the Structure and motion of the Wings of* Flies.

THe Wings of all kinds of Insects, are, for the most part, very beautifull Objects, and afford no less pleasing an Object to the mind to speculate upon, then to the eye to behold. This of the blue Fly, among the rest, wants not its peculiar ornaments and contrivances; it grows out of the *Thorax*, or middle part of the body of a Fly, and is seated a little beyond the center of gravity in the body towards the head, but that *Excentricly* is curiously balanc'd; first, by the expanded *Area* of the wings which lies all more backwards then the root, by the motion of them, whereby the center of their vibration is much more backwards towards the tail of the Fly then the root of the wing is. What the vibrative motion of the wings is, and after what manner they are moved, I have endeavoured by many trials to find out: And for the first manner of their motion, I endeavoured to observe several of those kind of small spinning Flies, which will naturally suspend themselves, as it were, pois'd and steady in one place of the air, without rising or falling, or moving forwards or backwards; for by looking down on those, I could by a kind of faint shadow, perceive the utmost extremes of the vibrative motion of their wings, which shadow, whil'st they so endeavoured to suspend themselves, was not very long, but when they endeavour'd to flie forwards, it was somewhat longer; next, I tried it, by fixing the leggs of a Fly upon the top of the stalk of a feather, with Glew, Wax, *&c.* and then making it endeavour to flie away; for being thereby able to view it in any posture, I collected that the motion of the wing was after this manner. The extreme limits of the vibrations were usually somewhat about the length of the body distant from one another, oftentimes shorter, and sometimes also longer; that the formost limit was usually a little above the back, and the hinder somwhat beneath the belly; between which two limits, if one may ghess by the sound, the wing seem'd to be mov'd forwards and backwards with an equal velocity: And if one may (from the shadow or faint representation the wings afforded, and from the consideration of the nature of the thing) ghess at the posture or manner of the wings moving betweeen them, it seem'd to be this: The wing being suppos'd placed in the upmost limit, seems to be put so that the plain of it lies almost *horizontal*, but onely the forepart does dip a little, or is somewhat more depreſt; in this position is the wing vibrated or mov'd to the lower limit, being almost arrived at the lower limit, the hinder part of the wing moving somewhat faster then the former,

former, the *Area* of the wing begins to dip behind, and in that posture seems it to be mov'd to the upper limit back again, and thence back again in the first posture, the former part of the *Area* dipping again, as it is moved downwards by means of the quicker motion of the main stem which terminates or edges the forepart of the wing. And these vibrations or motions to and fro between the two limits seem so swift, that 'tis very probable (from the sound it affords, if it be compar'd with the vibration of a musical string, tun'd unison to it) it makes many hundreds, if not some thousands of vibrations in a second minute of time. And, if we may be allow'd to ghess by the sound, the wing of a Bee is yet more swift, for the tone is much more acute, and that, in all likelihood, proceeds from the exceeding swift beating of the air by the small wing. And it seems the more likely too, because the wing of a Bee is less in proportion to its body, then the other wing to the body of a Fly; so that for ought I know, it may be one of the quickest vibrating *spontaneous* motions of any in the world; and though perhaps there may be many Flies in other places that afford a yet more shrill noise with their wings, yet 'tis most probable that the quickest vibrating *spontaneous* motion is to be found in the wing of some creature. Now, if we consider the exceeding quickness of these Animal spirits that must cause these motions, we cannot chuse but admire the exceeding vividness of the governing faculty or *Anima* of the Insect, which is able to dispose and regulate so the the motive faculties, as to cause every peculiar organ, not onely to move or act so quick, but to do it also so regularly.

Whilst I was examining and considering the curious *Mechanism* of the wings, I observ'd that under the wings of most kind of Flies, Bees, *&c.* there were plac'd certain *pendulums* or extended drops (as I may so call them from their resembling motion and figure) for they much resembled a long hanging drop of some transparent viscous liquor; and I observed them constantly to move just before the wings of the Fly began to move, so that at the first sight I could not but ghess, that there was some excellent use, as to the regulation of the motion of the wing, and did phancy, that it might be something like the handle of a Cock, which by vibrating to and fro, might, as 'twere, open and shut the Cock, and thereby give a passage to the determinate influences into the Muscles; afterwards, upon some other trials, I suppos'd that they might be for some use in respiration, which for many reasons I suppose those Animals to use, and, me thought, it was not very improbable, but that they might have convenient passages under the wings for the emitting, at least, of the air, if not admitting, as in the gills of Fishes is most evident; or, perhaps, this *Pendulum* might be somewhat like the staff to a Pump, whereby these creatures might exercise their *Analogus* lungs, and not only draw in, but force out, the air they live by: but these were but conjectures, and upon further examination seem'd less probable.

The fabrick of the wing, as it appears through a moderately magnifying *Microscope*, seems to be a body consisting of two parts, as is visible in the 4. *Figure* of the 23. *Scheme*; and by the 2. *Figure* of the 26. *Scheme*; the one is a quilly

a quilly or finny substance, consisting of several long, slender and variously bended quills or wires, something resembling the veins of leaves; these are, as 'twere, the finns or quills which stiffen the whole *Area*, and keep the other part distended, which is a very thin transparent skin or membrane variously folded, and platted, but not very regularly, and is besides exceeding thickly bestuck with innumerable small brisles, which are onely perceptible by the bigger magnifying *Microscope*, and not with that neither, but with a very convenient augmentation of sky-light projected on the Object with a burning Glass, as I have elsewhere shew'd, or by looking through it against the light.

In steed of these small hairs, in several other Flies, there are infinite of small Feathers, which cover both the under and upper sides of this thin film as in almost all the sorts of Butterflies and Moths: and those small parts are not onely shap'd very much like the feathers of Birds, but like those variegated with all the variety of curious bright and vivid colours imaginable; and those feathers are likewise so admirably and delicately rang'd, as to compose very fine flourishings and ornamental paintings, like *Turkie* and *Persian* Carpets, but of far more surpassing beauty, as is evident enough to the naked eye, in the painted wings of Butterflies, but much more through an ordinary *Microscope*.

Intermingled likewise with these hairs, may be perceived multitudes of little pits, or black spots, in the exended membrane, which seem to be the root of the hairs that grow on the other side; these two bodies seem dispers'd over the whole surface of the wing.

The hairs are best perceiv'd, by looking through it against the light, or, by laying the wing upon a very white piece of Paper, in a convenient light, for thereby every little hair most manifestly appears; a *Specimen*; of which you may observe drawn in the fourth *Figure* of the 23. *Scheme*, A B, C D, E F whereof represent some parts of the bones or quills of the wing, each of which you may perceive to be cover'd over with a multitude of scales, or brisles, the former A B, is the biggest stem of all the wing, and may be properly enough call'd the cut-air, it being that which terminates and stiffens the formost edge of the wing; the fore-edge of this is arm'd with a multitude of little brisles, or Tenter-hooks, in some standing regular and in order, in others not; all the points of which are directed from the body towards the tip of the wing, nor is this edge onely thus fring'd, but even all the whole edge of the wing is cover'd with a small fringe, consisting of short and more slender brisles.

This Subject, had I time, would afford excellent matter for the contemplation of the nature of wings and of flying; but, because I may, perhaps, get a more convenient time to prosecute that speculation, and recollect several Observations that I have made of that particular. I shall at present proceed to

Observ-

Obſerv. XXXIX. *Of the Eyes and Head of a* Grey drone-Fly, *and of ſeveral other creatures.*

I took a large grey *Drone-Fly*, that had a large head, but a ſmall and ſlender body in proportion to it, and cutting off its head, I fix'd it with the forepart or face upwards upon my Object Plate (this I made choice of rather then the head of a great blue Fly, becauſe my enquiry being now about the eyes, I found this Fly to have, firſt the biggeſt cluſters of eyes in proportion to his head, of any ſmall kind of Fly that I have yet ſeen, it being ſomewhat inclining towards the make of the large *Dragon-Flies*. Next, becauſe there is a greater variety in the knobs or balls of each cluſter, then is of any ſmall Fly) Then examining it according to my uſual manner, by varying the degrees of light, and altering its poſition to each kinde of light, I drew that repreſentation of it which is delineated in the 24. *Scheme*, and found theſe things to be as plain and evident, as notable and pleaſant.

Firſt, that the greateſt part of the face, nay, of the head, was nothing elſe but two large and *protuberant* bunches, or *prominent* parts, A B C D E A, the ſurface of each of which was all cover'd over, or ſhap'd into a multitude of ſmall *Hemiſpheres*, plac'd in a *triagonal* order, that being the cloſeſt and moſt compacted, and in that order, rang'd over the whole ſurface of the eye in very lovely rows, between each of which, as is neceſſary, were left long and regular trenches, the bottoms of every of which, were perfectly intire and not at all perforated or drill'd through, which I moſt certainly was aſſured of, by the regularly reflected Image of certain Objects which I mov'd to and fro between the head and the light. And by examining the *Cornea* or outward ſkin, after I had ſtript it off from the ſeveral ſubſtances that lay within it, and by looking both upon the inſide and againſt the light.

Next, that of thoſe multitudes of *Hemiſpheres*, there were obſervable two degrees of bigneſs, the half of them that were lowermoſt, and look'd toward the ground or their own leggs, namely, C D E, C D E being a pretty deal ſmaller then the other, namely, A B C E, A B C E, that look'd upward, and ſide-ways, or foreright, and backward, which variety I have not found in any other ſmall Fly.

Thirdly, that every one of theſe *Hemiſpheres*, as they ſeem'd to be pretty neer the true ſhape of a *Hemiſphere*, ſo was the ſurface exceeding ſmooth and regular, reflecting as exact, regular, and perfect an Image of any Object from the ſurface of them, as a ſmall Ball of Quick-ſilver of that bigneſs would do, but nothing neer ſo vivid, the reflection from theſe being very languid, much like the reflection from the outſide of Water, Glaſs, Cryſtal, *&c.* In ſo much that in each of theſe *Hemiſpheres*, I have been able to diſcover a Land-ſcape of thoſe things which lay before my window,

window, one thing of which was a large Tree, whose trunk and top I could plainly discover, as I could also the parts of my window, and my hand and fingers, if I held it between the Window and the Object; a small draught of nineteen of which, as they appear'd in the bigger Magnifying-glass to reflect the Image of the two windows of my Chamber, are delineated in the third *Figure* of the 23. *Scheme.*

Fourthly, that these rows were so dispos'd, that there was no quarter visible from his head that there was not some of these *Hemispheres* directed against; so that a Fly may be truly said to have *an eye every way*, and to be really *circumspect*. And it was further observable, that that way where the trunk of his body did hinder his prospect backward, these *protuberances* were elevated, as it were, above the plain of his shoulders and back, so that he was able to see backwards also over his back.

Fifthly, in living Flies, I have observ'd, that when any small mote or dust, which flies up and down the air, chances to light upon any part of these knobs, as it is sure to stick firmly to it and not fall, though through the *Microscope* it appears like a large stone or stick (which one would admire, especially since it is no ways probable that there is any wet or glutinous matter upon these *Hemispheres*, but I hope I shall render the reason in another place) so the Fly presently makes use of his two fore-feet in stead of eye-lids, with which, as with two Brooms or Brushes, they being all bestuck with Brisles, he often sweeps or brushes off what ever hinders the prospect of any of his *Hemispheres*, and then, to free his leggs from that dirt, he rubs them one against another, the pointed Brisles or Tenters of which looking both one way, the rubbing of them to and fro one against another, does cleanse them in the same manner as I have observ'd those that Card Wool, to cleanse their Cards, by placing their Cards, so as the teeth of both look the same way, and then rubbing them one against another. In the very same manner do they brush and cleanse their bodies and wings, as I shall by and by shew; other creatures have other contrivances for the cleansing and cleering their eyes.

Sixthly, that the number of the *Pearls* or *Hemispheres* in the clusters of this Fly, was neer 14000. which I judged by numbering certain rows of them several ways, and casting up the whole content, accounting each cluster to contain about seven thousand Pearls, three thousand of which were of a size, and consequently the rows not so thick, and the foure thousand I accounted to be the number of the smaller Pearls next the feet and *proboscis*. Other Animals I observ'd to have yet a greater number, as the *Dragon-Fly* or *Adderbolt*: And others to have a much less company, as an *Ant*, &c. and several other small Flies and Insects.

Seventhly, that the order of these eies or *Hemispheres* was altogether curious and admirable, they being plac'd in all kind of Flies, and *aerial* animals, in a most curious and regular ordination of triangular rows, in which order they are rang'd the neerest together that possibly they can, and consequently leave the least pits or trenches between them. But in *Shrimps*, *Crawfishes*, *Lobsters*, and such kinds of *Crustaceous* water Animals, I have

yet

yet obſerv'd them rang'd in a quadrangular order, the rows cutting each other at right angles, which as it admits of a leſs number of Pearls in equal ſurfaces; ſo have thoſe creatures a recompence made them, by having their eyes a little movable in their heads, which the other altogether want. So infinitely wiſe and provident do we find all the Diſpenſations in Nature, that certainly *Epicurus*, and his followers, muſt very little have conſider'd them, who aſcrib'd thoſe things to the production of chance, that wil, to a more attentive conſiderer, appear the products of the higheſt Wiſdom and Providence.

Upon the Anatomy or Diſſection of the Head, I obſerv'd theſe particulars:

Firſt, that this outward ſkin, like the *Cornea* of the eyes of the greater Animals, was both flexible and tranſparent, and ſeem'd, through the *Microſcope*, perfectly to reſemble the very ſubſtance of the *Cornea* of a man's eye; for having cut out the cluſter, and remov'd the dark and *mucous* ſtuff that is ſubjacent to it, I could ſee it tranſparent like a thin piece of ſkin, having as many cavities in the inſide of it, and rang'd in the ſame order as it had *protuberances* on the outſide, and this propriety, I found the ſame in all the Animals that had it, whether Flies or Shell-Fiſh.

Secondly, I found that all Animals that I have obſerv'd with thoſe kind of eyes, have within this *Cornea*, a certain cleer liquor or juice, though in a very little quantity, and,

I obſerv'd thirdly, that within that cleer liquor, they had a kind of dark *mucous* lining, which was all ſpread round within the cavity of the cluſter, and ſeem'd very neer adjoining to it, the colour of which, in ſome Flies, was grey; in others, black; in others red; in others, of a mix'd colour; in others, ſpotted; and that the whole cluſters, when look'd on whil'ſt the Animal was living, or but newly kill'd, appear'd of the ſame colour that this coat (as I may ſo call it) appear'd of, when that outward ſkin, or *Cornea*, was remov'd.

Fourthly, that the reſt of the capacity of the cluſters was in ſome, as in Dragon Flies, *&c.* hollow, or empty; in others fill'd with ſome kind of ſubſtance; in blue Flies, with a reddiſh muſculous ſubſtance, with *fibres* tending from the center or bottom outwards; and divers other, with various and differing kinds of ſubſtances.

That this curious contrivance is the organ of ſight to all thoſe various *Cruſtaceous* Animals, which are furniſh'd with it, I think we need not doubt, if we conſider but the ſeveral congruities it has with the eyes of greater creatures.

As firſt, that it is furniſh'd with a *Cornea*, with a *tranſparent humour*, and with a *uvea* or *retina*, that the Figure of each of the ſmall *Hemiſpheres* are very *Spherical*, exactly poliſh'd, and moſt vivid, lively and plump, when the Animal is living, as in greater Animals, and in like manner dull, flaccid, and irregular, or ſhrunk, when the Animal is dead.

Next, that thoſe creatures that are furniſh'd with it, have no other organs that have any reſemblance to the known eyes of other creatures.

Thirdly, that those which they call the eyes of Crabs, Lobsters, Shrimps, and the like, and are really so, are *Hemispher'd*, almost in the same manner as these of Flies are. And that they really are so, I have very often try'd, by cutting off these little movable knobs, and putting the creature again into the water, that it would swim to and fro, and move up and down as well as before, but would often hit it self against the rocks or stones; and though I put my hand just before its head, it would not at all start or fly back till I touch'd it, whereas whil'st those were remaining, it would start back, and avoid my hand or a stick at a good distance before it touch'd it. And if in *crustaceous* Sea-animals, then it seems very probable also, that these knobs are the eyes in *crustaceous* Insects, which are also of the same kind, onely in a higher and more active Element; this the conformity or congruity of many other parts common to either of them, will strongly argue, their *crustaceous* armour, their number of leggs, which are six, beside the two great claws, which answer to the wings in Insects; and in all kind of Spiders, as also in many other Insects that want wings, we shall find the compleat number of them, and not onely the number, but the very shape, figure, joints, and claws of Lobsters and Crabs, as is evident in Scorpions and Spiders, as is visible in the second *Figure* of the 31. *Scheme*, and in the little Mite-worm, which I call a Land-crab, describ'd in the second Figure of the 33. *Scheme*, but in their manner of generation being oviparous, *&c.* And it were very worthy observation, whether there be not some kinds of transformation and metamorphosis in the several states of *crustaceous* water-animals, as there is in several sorts of Insects; for if such could be met with, the progress of the variations would be much more conspicuous in those larger Animals, then they can be in any kind of Insects our colder Climate affords.

These being their eyes, it affords us a very pretty Speculation to contemplate their manner of vision, which, as it is very differing from that of *biocular* Animals, so is it not less admirable.

That each of these Pearls or *Hemispheres* is a perfect eye, I think we need not doubt, if we consider onely the outside or figure of any one of them, for they being each of them cover'd with a transparent protuberant *Cornea*, and containing a liquor within them, resembling the watry or glassie humours of the eye, must necessarily refract all the parallel Rays that fall on them out of the air, into a point not farr distant within them, where (in all probability) the *Retina* of the eye is placed, and that opacous, dark, and mucous inward coat that (I formerly shew'd) I found to subtend the concave part of the cluster is very likely to be that *tunicle* or coat, it appearing through the *Microscope* to be plac'd a little more than a Diameter of those Pearls below or within the *tunica cornea.* And if so, then is there in all probability, a little Picture or Image of the objects without, painted or made at the bottom of the *Retina* against every one of those Pearls, so that there are as many impressions on the *Retina* or opacous skin, as there are Pearls or *Hemispheres* on the cluster. But because it is impossible for any protuberant surface whatsoever, whether *sphærial* or other, so to refract the Rays that come from farr remote

lateral

lateral points of any Object as to collect them again, and unite them each in a distinct point, and that onely those Rays which come from some point that lies in the *Axis* of the Figure produc'd, are so accuratelly refracted to one and the same point again, and that the *lateral* Rays, the further they are remov'd, the more imperfect is their refracted confluence; It follows therefore, that onely the Picture of those parts of the external objects that lie in, or neer, the *Axis* of each *Hemisphere*, are discernably painted or made on the *Retina* of each *Hemisphere*, and that therefore each of them can distinctly sensate or see onely those parts which are very neer perpendiculaly oppos'd to it, or lie in or neer its optick *Axis*. Now, though there may be by each of these eye-pearls, a representation to the Animal of a whole *Hemisphere* in the same manner as in a man's eye there is a picture or sensation in the *Retina* of all the objects lying almost in an *Hemisphere*; yet, as in a man's eye also, there are but some very few points which lying in, or neer, the optick *Axis* are distinctly discern'd; So there may be multitudes of Pictures made of an Object in the several Pearls, and yet but one, or some very few that are distinct; The representation of any object that is made in any other Pearl, but that which is directly, or very neer directly, oppos'd, being altogether confus'd and unable to produce a distinct vision.

So that we see, that though it has pleas'd the All-wise Creator, to indue this creature with such multitudes of eyes, yet has he not indued it with the faculty of seeing more then another creature; for whereas this cannot move his head, at least can move it very little, without moving his whole body, *biocular* creatures can in an instant (or *the twinkling of an eye*, which, being very quick, is vulgarly used in the same signification) move their eyes so as to direct the optick *Axis* to any point; nor is it probable, that they are able to see attentively at one time more then one Physical point; for though there be a distinct Image made in every eye, yet 'tis very likely, that the observing faculty is only imploy'd about some one object for which they have most concern.

Now, as we accurately distinguish the site or position of an Object by the motion of the Muscles of the eye requisite to put the optick Line in a direct position, and confusedly by the position of the imperfect Picture of the object at the bottom of the eye; so are these *crustaceous* creatures able to judge confusedly of the position of objects by the Picture or impression made at the bottom of the opposite Pearl, and distinctly by the removal of the attentive or observing faculty, from one Pearl to another; but what this faculty is, as it requires another place, so a much deeper speculation. Now, because it were impossible, even with this multitude of eyeballs, to see any object distinct (for as I hinted before, onely those parts that lay in, or very neer, the optick Lines could be so) the Infinitely wise Creator has not left the creature without a power of moving the head a little in *Aerial crustaceous* animals, and the very eyes also in *crustaceous* Sea-animals; so that by these means they are inabled to direct some optick line or other against any object, and by that means they have the visive faculty as compleat as any Animal that can move its eyes.

Distances of Objects also, 'tis very likely they distinguish, partly by the consonant impressions made in some two convenient Pearls, one in each cluster; for, according as those congruous impressions affect, two Pearls neerer approach'd to each other, the neerer is the Object, and the farther they are distant, the more distant is the Object: partly also by the alteration of each Pearl, requisite to make the Sensation or Picture perfect; for 'tis impossible that the Pictures of two Objects, variously distant, can be perfectly painted, or made on the same *Retina* or bottom of the eye not altered, as will be very evident to any one that shall attentively consider the nature of refraction. Now, whether this alteration may be in the Figure of the *Cornea*, in the motion of access or recess of the *Retina* towards the *Cornea*, or in the alteration of a crustaline humour, if such there be, I pretend not to determine; though I think we need not doubt, but that there may be as much curiosity of contrivance and structure in every one of these Pearls, as in the eye of a Whale or Elephant, and the almighty's *Fiat* could as easily cause the existence of the one as the other; and as one day and a thousand years are the same with him, so may one eye and ten thousand.

This we may be sure of, that the filaments or sensative parts of the *Retina* must be most exceedingly curious and minute, since the whole Picture it self is such; what must needs the component parts be of that *Retina* which distinguishes the part of an object's Picture that must be many millions of millions less then that in a man's eye? And how exceeding curious and subtile must the component parts of the *medium* that conveys light be, when we find the instrument made for its reception or refraction to be so exceedingly small? we may, I think, from this speculation be sufficiently discouraged from hoping to discover by any optick or other instrument the determinate bulk of the parts of the *medium* that conveys the pulse of light, since we find that there is not less accuratenes shewn in the Figure, and polish of those exceedingly minute lenticular surfaces, then in those more large and conspicuous surfaces of our own eyes. And yet can I not doubt, but that there is a determinate bulk of those parts, since I find them unable to enter between the parts of Mercury, which being in motion, must necessarily have pores, as I shall elsewhere shew, and here pass by, as being a digression.

As concerning the horns F F, the feelers or smellers, G G, the *Probascis* H H, and I, the hairs and brisles, K K, I shall indeavour to describe in the 42. *Observation.*

Observ. XL. *Of the Teeth of a* Snail.

I Have little more to add of the Teeth of a Snail, besides the Picture of it, which is represented in the first *Figure* of the 25. *Scheme*, save that his bended body, A B C D E F, which seem'd fashioned very much like a row of small teeth, orderly plac'd in the Gums, and looks as if it were



Fig: I.



Fig: 2.

Fig: 3.

were divided into ſeveral ſmaller and greater black teeth, was nothing but one ſmall bended hard bone, which was plac'd in the upper jaw of the mouth of a Houſe-Snail, with which I obſerv'd this very Snail to feed on the leaves of a Roſe-tree, and to bite out pretty large and half round bits, not unlike the Figure of a (C) nor very much differing from it in bigneſs, the upper part A B C D of this bone, I found to be much whiter, and to grow out of the upper chap of the Snail G G G, and not to be any thing neer ſo much creas'd as the lower and blacker part of it H I I H K K H which was exactly ſhap'd like teeth, the bone growing thinner, or tapering to an edge towards K K K. It ſeem'd to have nine teeth, or prominent parts I K, I K, I F, *&c.* which were join'd together by the thinner interpos'd parts of the bone. The Animal to which theſe teeth belong, is a very *anomalous* creature, and ſeems of a kind quite diſtinct from any other terreſtrial Animal or Inſect, the Anatomy whereof exceedingly differing from what has been hitherto given of it I ſhould have inſerted, but that it will be more proper in another place. I have never met with any kind of Animal whoſe teeth are all join'd in one, ſave onely that I lately obſerv'd, that all the teeth of a Rhinocerot, which grow on either ſide of its mouth, are join'd into one large bone, the weight of one of which I found to be neer eleven pound *Haverdupois*. So that it ſeems one of the biggeſt ſort of terreſtrial Animals, as well as one of the ſmalleſt, has his teeth thus ſhap'd.

Obſerv. XLI. *Of the Eggs of* Silk-worms, *and other Inſects.*

THe Eggs of Silk-worms (one of which I have deſcrib'd in the ſecond *Figure* of 25. *Scheme*) afford a pretty Object for a *Microſcope* that magnifies very much, eſpecially if it be bright weather, and the light of a window be caſt or collected on it by a deep *Convex-glaſs*, or Water-ball. For then the whole ſurface of the Shell may be perceiv'd all cover'd over with exceeding ſmall pits or cavities with interpoſed edges, almoſt in the manner of the ſurface of a Poppy-ſeed, but that theſe holes are not an hundredth part ſcarce of their bigneſs; the Shell, when the young ones were hatch'd (which I found an eaſie thing to do, if the Eggs were kept in a warm place) appear'd no thicker in proportion to its bulk, then that of an Hen's or Goos's Egg is to its bulk, and all the Shell appear'd very white (which ſeem'd to proceed from its tranſparency) whence all thoſe pittings did almoſt vaniſh, ſo that they could not, without much difficulty, be diſcern'd, the inſide of the Shell ſeem'd to be lin'd alſo with a kind of thin film, not unlike (keeping the proportion to its Shell) that with which the ſhell of an Hen-egg is lin'd; and the ſhell it ſelf ſeem'd like common Egg-ſhells, very brittle, and crack'd. In divers other of theſe Eggs I could plainly enough, through the ſhell, perceive the ſmall Inſect lie coyled round the edges of the ſhell. The ſhape of the Egg it ſelf, the Figure pretty well repreſents (though by default of the Graver it does not

not appear so rounded, and lying above the Paper, as it were, as it ought to do) that is, it was for the most part pretty oval end-ways, somewhat like an Egg, but the other way it was a little flatted on two opposite sides. Divers of these Eggs, as is common to most others, I found to be barren, or addle, for they never afforded any young ones. And those I usually found much whiter then the other that were prolifick. The Eggs of other kinds of Oviparous Insects I have found to be perfectly round every way, like so many Globules, of this sort I have observ'd some sorts of Spiders Eggs; and chancing the last Summer to inclose a very large and curiously painted Butterfly in a Box, intending to examine its gaudery with my *Microscope*, I found within a day or two after I inclos'd her, almost all the inner surface of the Box cover'd over with an infinite of exactly round Eggs, which were stuck very fast to the sides of it, and in so exactly regular and close an order, that made me call to mind my *Hypothesis*, which I had formerly thought on for the making out of all the regular Figures of Salt, which I have elsewhere hinted; for here I found all of them rang'd into a most exact *triagonal* order, much after the manner as the *Hemispheres* are place on the eye of a Fly; all which Eggs I found after a little time to be hatch'd, and out of them to come a multitude of small Worms, very much resembling young Silk-worms, leaving all their thin hollow shells behind them, sticking on the Box in their *triagonal* posture; these I found with the *Microscope* to have much such a substance as the Silk-worms Eggs, but could not perceive them pitted. And indeed, there is as great a variety in the shape of the Eggs of Oviparous Insects as among those of Birds.

Of these Eggs, a large and lusty Fly will at one time lay neer four or five hundred, so that the increase of these kind of Insects must needs be very prodigious, were they not prey'd on by multitudes of Birds, and destroy'd by Frosts and Rains; and hence 'tis those hotter Climates between the *Tropicks* are infested with such multitudes of Locusts, and such other Vermine.

Observ. XLII. *Of a blue* Fly.

THis kind of Fly, whereof a *Microscopical* Picture is delineated in the first *Figure* of the 26. *Scheme*, is a very beautifull creature, and has many things about it very notable; divers of which I have already partly describ'd, namely, the feet, wings, eyes, and head, in the preceding Observations.

And though the head before describ'd be that of a grey *Drone-Fly*, yet for the main it is very agreeable to this. The things wherein they differ most, will be easily enough found by the following particulars:

First, the clusters of eyes of this Fly, are very much smaller then those of the *Dron-Fly*, in proportion to the head.

And


A
D
K
K
D
K
K
G
H
H
I

Schem: XXVI.



And next, all the eyes of each cluster seem'd much of the same bigness one with another, not differing as the other, but rang'd in the same *triagonal* order.

Thirdly, between these two clusters, there was a scaly prominent *front* B, which was arm'd and adorn'd with large tapering sharp black brisles, which growing out in rows on either side, were so bent toward each other neer the top, as to make a kind of arched arbour of Brisles, which almost cover'd the former *front*.

Fourthly, at the end of this Arch, about the middle of the face, on a prominent part C, grew two small oblong bodies, D D, which through a *Microscope* look'd not unlike the Pendants in Lillies, these seem'd to be jointed on to two small parts at C, each of which seem'd again jointed into the front.

Fifthly, out of the upper part and outsides of these horns (as I may call them, from the Figure they are of, in the 24. *Scheme*, where they are marked with F F) there grows a single feather, or brushy Brisle, E E, somewhat of the same kind with the tufts of a Gnat, which I have before described.

What the use of these kind of horned and tufted bodies should be, I cannot well imagine, unless they serve for smelling or hearing, though how they are adapted for either, it seems very difficult to describe they are in almost every several kind of Flies of so various a shape; though certainly they are some very essential part of the head, and have some very notable office assign'd them by Nature, since in all Insects they are to be found in one or other form.

Sixthly, at the under part of the face F F, were several of the former sort of bended Brisles; and below all, the mouth, out of the middle of which, grew the *proboscis* G H I, which, by means of several joints, whereof it seem'd to consist, the Fly was able to move to and fro, and thrust it in and out as it pleas'd; the end of this hollow body (which was all over cover'd with small short hairs or brisles) was, as 'twere, bent at H, and the outer or formost side of the bended part H I, slit, as it were, into two chaps, H I, H I, all the outside of which where cover'd with hairs, and pretty large brisles; these he could, like two chaps, very readily open and shut, and when he seem'd to suck any thing from the surface of a body, he would spread abroad those chaps, and apply the hollow part of them very close to it.

From either side of the *Proboscis*, within the mouth, grew two other small horns, or fingers, K K, which were hairy, but small in this Figure; but of another shape, and bigger in proportion, in the 24. *Scheme*, where they are marked with G G, which two indeed seem'd a kind of smellers, but whether so or not, I cannot positively determine.

The *Thorax* or middle part of this Fly, was cas'd, both above and beneath, with a very firm crust of armour, the upper part more round, and covered over with long *conical* brisles, all whose ends pointed backwards; out of the hinder and under part of this grew out in a cluster six leggs, three of which are apparent in the Figure, the other three were hid by the body

body plac'd in that posture. The leggs were all much of the same make, being all of them cover'd with a strong hairy scale or shel, just like the legs of a Crabb or Lobster, and the contrivance of the joints seem'd much the same; each legg seem'd made up of eight parts, 1, 2, 3, 4, 5, 6, 7, 8, to the eighth or last of which, grew the soles and claws, described before in the 38. *Observation.*

Out of the upper part of this trunck grew the two wings, which I mention'd in the 38. *Observation*, consisting of a film, extended on certain small stiff wires or bones: these in a blue Fly, were much longer then the body, but in other kind of Flies they are of very differing proportions to the body. These films, in many Flies, were so thin, that, like several other plated bodies (mention'd in the ninth *Observation*) they afforded all varieties of fantastical or transient colours (the reason of which I have here endeavoured to explain) they seem'd to receive their nourishment from the stalks or wires, which seem'd to be hollow, and neer the upper part of the wing L L several of them seem'd jointed, the shape of which will sufficiently appear by the black lines in the second Figure of the 26. *Scheme*, which is a delineation of one of those wings expanded directly to the eyes.

All the hinder part of its body is cover'd with a most curious blue shining armour, looking exactly like a polish'd piece of steel brought to that blue colour by annealing, all which armour is very thick bestuck with abundance of tapering brisles, such as grow on its back, as is visible enough by the Figure.

Nor was the inside of this creature less beautifull then its outside, for cutting off a part of the belly, and then viewing it, to see if I could discover any Vessels, such as are to be found in a greater Animals, and even in Snails exceeding manifestly, I found, much beyond my expectation, that there were abundance of branchings of Milk-white vessels, no less curious then the branchings of veins and arteries in bigger terrestrial Animals, in one of which, I found two notable branches, joining their two main stocks, as it were, into one common *ductus*; now, to what veins or arteries these Vessells were *analogus*, whether to the *vena porta*, or the *meseraick vessells*, or the like, or indeed, whether they were veins and arteries, or *vasa lactea*, properly so called, I am not hitherto able to determine, having not yet made sufficient enquiry; but in all particulars, there seems not to be any thing less of curious contrivance in these Insects, then in those larger terrestrial Animals, for I had never seen any more curious branchings of Vessells, then those I observ'd in two or three of these Flies thus opened.

It is a creature active and nimble, so as there are very few creatures like it, whether bigger or smaller, in so much, that it will scape and avoid a small body, though coming on it exceeding swiftly, and if it sees any thing approaching it, which it fears, it presently squats down, as it were, that it may be the more ready for its rise.

Nor is it less hardy in the Winter, then active in the Summer, induring all the Frosts, and surviving till the next Summer, notwithstanding the bitter


Fig: 3
Fig: 4.
Fig: 1.
Fig: 2.
V
M
T
H
G
F
E
D
C
B
A
I
O
P
N
Q
S
R

bitter cold of our Climate; nay, this creature will indure to be frozen, and yet not be destroy'd, for I have taken one of them out of the Snow whereon it has been frozen almost white, with the Ice about it, and yet by thawing it gently by the warmth of a fire, it has quickly reviv'd and flown about.

This kind of Fly seems by the steams or taste of fermenting and putrifying meat (which it often kisses, as'twere, with its *proboscis* as it trips over it) to be stimulated or excited to eject its Eggs or Seed on it, perhaps, from the same reason as Dogs, Cats, and many other brute creatures are excited to their particular lusts, by the smell of their females, when by Nature prepared for generation; the males seeming by those kind of smells, or other incitations, to be as much necessitated thereto, as *Aqua Regis* strongly impregnated with a solution of Gold, is forced to precipitate it by the affusion of spirit of *Urine*, or a solution of *Salt* of *Tartar*.

One of these put in spirit of *Wine*, was very quickly seemingly kill'd, and both its eys and mouth began to look very red, but upon the taking of it out, and suffering it to lie three or four hours, and heating it with the Sun beams cast through a Burning-glass, it again reviv'd, seeming, as it were, to have been all the intermediate time, but dead drunk, and after certain hours to grow fresh again and sober.

Observ. XLIII. *Of the* Water-Insect *or* Gnat.

THis little creature, described in the first *Figure* of the 27. *Scheme*, was a small scaled or crusted Animal, which I have often observ'd to be generated in Rain-water; I have also observ'd it both in Pond and River-water. It is suppos'd by some, to deduce its first original from the putrifaction of Rain-water, in which, if it have stood any time open to the air, you shall seldom miss, all the Summer long, of store of them frisking too and fro.

'Tis a creature, wholly differing in shape from any I ever observ'd; nor is its motion less strange: It has a very large head, in proportion to its body, all covered with a shell, like other *testaceous* Animals, but it differs in this, that it has, up and down several parts of it, several tufts of hairs, or brisles, plac'd in the order express'd in the Figure; It has two horns, which seem'd almost like the horns of an Oxe, inverted, and, as neer as I could ghess, were hollow, with tufts of brisles, likewise at the top; these horns they could move easily this or that way, and might, perchance, be their nostrils. It has a pretty large mouth, which seem'd contriv'd much like those of Crabs and Lobsters, by which, I have often observ'd them to feed on water, or some imperceptible nutritive substance in it.

I could perceive, through the transparent shell, while the Animal surviv'd, several motions in the head, thorax, and belly, very distinctly,

of differing kinds which I may, perhaps, elſewhere endeavour more accurately to examine, and to ſhew of how great benefit the uſe of a *Microſcope* may be for the diſcovery of Nature's courſe in the operations perform'd in Animal bodies, by which we have the opportunity of obſerving her through theſe delicate and pellucid teguments of the bodies of Inſects acting according to her uſual courſe and way, undiſturbed, whereas, when we endeavour to pry into her ſecrets by breaking open the doors upon her, and diſſecting and mangling creatures whil'ſt there is life yet within them, we find her indeed at work, but put into ſuch diſorder by the violence offer'd, as it may eaſily be imagin'd, how differing a thing we ſhould find, if we could, as we can with a *Microſcope*, in theſe ſmaller creatures, quietly peep in at the windows, without frighting her out of her uſual byas.

The form of the whole creature, as it appear'd in the *Microſcope*, may, without troubling you with more deſcriptions, be plainly enough perceiv'd by the *Scheme*, the hinder part or belly conſiſting of eight ſeveral jointed parts, namely, A B C D E F G H, of the firſt *Figure*, from the midſt of each of which, on either ſide, iſſued out three or four ſmall briſles or hairs, I, I, I, I, I, the tail was divided into two parts of very differing make; one of them, namely, K, having many tufts of hair or briſles, which ſeem'd to ſerve both for the finns and tail, for the Oars and Ruder of this little creature, wherewith it was able, by friſking and bending its body nimbly to and fro, to move himſelf any whither, and to ſkull and ſteer himſelf as he pleas'd; the other part, L, ſeem'd to be, as 'twere, the ninth diviſion of his belly, and had many ſingle briſles on either ſide. From the end V, of which, through the whole belly, there was a kind of Gut of a darker colour, M M M, wherein, by certain *Periſtaltick* motions there was a kind of black ſubſtance mov'd upwards and downwards through it from the orbicular part of it, N, (which ſeem'd the *Ventricle*, or ſtomach) to the tail V, and ſo back again, which *periſtaltick* motion I have obſerv'd alſo in a Louſe, a Gnat, and ſeveral other kinds of tranſparent body'd Flies. The *Thorax* or cheſt of this creature O O O O, was thick and ſhort, and pretty tranſparent, for through it I could ſee the white heart (which is the colour alſo of the bloud in theſe, and moſt other Inſects) to beat, and ſeveral other kind of motions. It was beſtuck and adorn'd up and down with ſeveral tufts of briſles, ſuch as are pointed out by P, P, P, P, the head Q was likewiſe beſtuck with ſeveral of thoſe tufts, S S S; it was broad and ſhort, had two black eyes, T T, which I could not perceive at all pearl'd, as they afterwards appear'd, and two ſmall horns, R R, ſuch as I formerly deſcrib'd.

Both its motion and reſt is very ſtrange, and pleaſant, and differing from thoſe of moſt other creatures I have obſerv'd; for, where it ceaſes from moving its body, the tail of it ſeeming much lighter then the reſt of its body, and a little lighter then the water it ſwims in, preſently boys it up to the top of the water, where it hangs ſuſpended with the head always downward; and like our *Antipodes*, if they do by a friſk get below that ſuperficies, they preſently aſcend again unto it, if they ceaſe moving,

moving, until they tread, as it were, under that superficies with their tails; the hanging of these in this posture, put me in mind of a certain creature I have seen in *London*, that was brought out of *America*, which would very firmly suspend it self by the tail, with the head downwards, and was said to sleep in that posture, with her young ones in her false belly, which is a Purse, provided by Nature for the production, nutrition, and preservation of her young ones, which is described by *Piso* in the 24. Chapter of the fifth Book of his Natural History of *Brasil*.

The motion of it was with the tail forwards, drawing its self backwards, by the frisking to and fro of that tuft which grew out of one of the stumps of its tail. It had another motion, which was more sutable to that of other creatures, and that is, with the head forward; for by the moving of his chaps (if I may so call the parts of his mouth) it was able to move it self downwards very gently towards the bottom, and did, as 'twere, eat up its way through the water.

But that which was most observable in this creature, was, its Metamorphosis or change; for having kept several of these Animals in a Glass of Rain-water, in which they were produc'd, I found, after about a fortnight or three weeks keeping, that several of them flew away in Gnats, leaving their husks behind them in the water floating under the surface, the place where these Animals were wont to reside, whil'st they were inhabitants of the water: this made me more diligently to watch them, to see if I could find them at the time of their transformation; and not long after, I observ'd several of them to be changed into an unusual shape, wholly differing from that they were of before, their head and body being grown much bigger and deeper, but not broader, and their belly, or hinder part smaller, and coyl'd, about this great body much of the fashion represented by the prick'd line in the second *Figure* of the 27. *Scheme*, the head and horns now swam uppermost, and the whole bulk of the body seem'd to be grown much lighter; for when by my frighting of it, it would by frisking out of its tail (in the manner expres'd in the Figure by B C) sink it self below the surface towards the bottom; the body would more swiftly re-ascend, then when it was in its former shape.

I still marked its progress from time to time, and found its body still to grow bigger and bigger, Nature, as it were, fitting and accoutring it for the lighter Element, of which it was now going to be an inhabitant; for, by observing one of these with my *Microscope*, I found the eyes of it to be altogether differing from what they seem'd before, appearing now all over pearl'd or knobb'd, like the eyes of Gnats. as is visible in the secong *Figure* by A. At length, I saw part of this creature to swim above, and part beneath the surface of the water, below which though it would quickly plunge it self if I by any means frighted it, and presently re-ascend into its former posture; after a little longer expectation, I found that the head and body of a Gnat, began to appear and stand cleer above the surface, and by degrees it drew out its leggs, first the two formost, then the other, at length its whole body perfect and entire appear'd out of the husk (which it left in the water) standing on its leggs upon

the top of the water, and by degrees it began to move, and after flew about the Glass a perfect Gnat.

I have been the more particular, and large in the relation of the transformation of divers of these little Animals which I observ'd, because I have not found that any Authour has observ'd the like; and because the thing it self is so strange and heterogeneous from the usual progress of other Animals, that I judge it may not onely be pleasant, but very usefull and necessary towards the compleating of Natural History.

There is indeed in *Piso*, a very odd History, which this relation may make the more probable; and that is in the 2. Chapter of the 4. Book of his Natural History of *Brasil*, where he says, *Porro præter tot documenta fertilitatis circa vegetabilia & sensitiva marina telluris æmula, accidit & illud, quod paucis à Paranambucensi milliaribus, piscatoris uncum citra intentionem contingat infigi vadis petrosis, & loco piscis spongia, coralla, aliasque arbusculas marinas capi. Inter hæc inusitatæ formæ prodit spongiosa arbuscula, sesquipedis longitudinis, brevioribus radicibus, lapideis nitens vadis, & rupibus infixa, erigiturque in corpus spongiosum molle oblongum rotundum turbinatum: intus miris cancellis & alveis fabricatum, extus autem tenaci glutine instar Apum propolis undique vestitum, ostio satis patulo & profundo in summitate relicto, sicut ex altera iconum probe depicta videre licet* (see the third and fourth *Figures* of the 27. *Scheme.*) *Ita ut Apiarium marinum vere dixeris; primo enim intuitu è Mare ad Terram delatum, vermiculis scatebat cæruleis parvis, qui mox à calore solis in Muscas, vel Apes potius, easq; exiguas & nigras transformebantur, circumvolantesque evanescebant, ita ut de eorum mellificatione nihil certi conspici datum fuerit, cum tamen cærosa materia propolis Apumque cellæ manifeste apparerent, atque ipsa mellis qualiscunque substantia procul dubio urinatoribus patebit, ubi curiosius inquisiverint hæc apiaria, eaque in natali solo & salo diversis temporibus penitius lustrarint.*

Which History contains things sufficiently strange to be consider'd, as whether the husk were a Plant, growing at the bottom of the Sea before, of it self, out of whose putrifaction might be generated these strange kind of Magots; or whether the seed of certain Bees, sinking to the bottom, might there naturally form it self that vegetable hive, and take root; or, whether it might not be placed there by some diving Fly; or, whether it might not be some peculiar propriety of that Plant, whereby it might ripen or form its vegetable juice into an Animal substance; or, whether it may not be of the nature of a Sponge, or rather a Sponge of the nature of this, according to some of those relations and conjectures I formerly made of that body, is a matter very difficult to be determined. But indeed, in this description, the Excellent *Piso* has not been sufficiently particular in the setting down the whole process, as it were to be wish'd: There are indeed very odd progresses in the production of several kinds of Insects, which are not less instructive then pleasant, several of which, the diligent *Goedartius* has carefully observ'd and recorded, but among all his Observations, he has none like this, though that of the *Hemerobius* be somewhat of this kind, which is added as an Appendix by *Johannes Mey.*

I have

I have, for my own particular, besides several of those mention'd by him, observ'd divers other circumstances, perhaps, not much taken notice of, though very common, which do indeed afford us a very *coercive* argument to admire the goodness and providence of the infinitely wise Creator in his most excellent contrivances and dispensations. I have observ'd, at several times of the Summer, that many of the leaves of divers Plants have been spotted, or, as it were scabbed, and looking on the undersides of those of them that have been but a litte irregular, I have perceiv'd them to be sprinkled with divers sorts of little Eggs, which letting alone, I have found by degrees to grow bigger, and become little Worms with leggs, but still to keep their former places, and those places of the leaves, of their own accords, to be grown very protuberant upwards, and very hollow, and arched underneath, whereby those young creatures are, as it were, shelter'd and housed from external injury; divers leaves I have observ'd to grow and swell so farr, as at length perfectly to inclose the Animal, which, by other observations I have made, I ghess to contain it, and become, as it were a womb to it, so long, till it be fit and prepar'd to be translated into another state, at what time, like (what they say of) Vipers, they gnaw their way through the womb that bred them; divers of these kinds I have met with upon Goosberry leaves, Rose-tree leaves, Willow leaves, and many other kinds.

There are often to be found upon Rose-trees and Brier bushes, little red tufts, which are certain knobs or excrescencies, growing out from the Rind, or barks of those kinds of Plants, they are cover'd with strange kinds of threads or red hairs, which feel very soft, and look not unpleasantly. In most of these, if it has no hole in it, you shall find certain little Worms, which I suppose to be the causes of their production; for when that Worm has eat its way through, they, having performed what they were design'd by Nature to do, by degrees die and wither away.

Now, the manner of their production, I suppose to be thus; that the Al-wise Creator has as well implanted in every creature a faculty of knowing what place is convenient for the hatching, nutrition, and preservation of their Eggs and of-springs, whereby they are stimulated and directed to convenient places, which becom, as 'twere the wombs that perform those offices: As he has also suited and adapted a property to those places wherby they grow and inclose those seeds, and having inclosed them, provide a convenient nourishment for them, but as soon as they have done the office of a womb, they die and wither.

The progress of inclosure I have often observ'd in leaves, which in those places where those seeds have been cast, have by degrees swell'd and inclos'd them, so perfectly round, as not to leave any perceptible passage out.

From this same cause, I suppose that Galls, Oak-apples, and several other productions of that kind, upon the branches and leaves of Trees, have their original; for if you open any of them, when almost ripe, you shall find a little Worm in them. Thus, if you open never so many dry Galls, you shall find either a hole whereby the Worm has eat its passage out,

out, or if you find no passage, you may, by breaking or cutting the Gall, find in the middle of it a small cavity, and in it a small body, which does plainly enough yet retain a shape, to manifest it once to have been a Worm, though it dy'd by a too early separation from the Oak on which it grew, its navel-string, as 'twere, being broken off from the leaf or branch by which the Globular body that invelop'd it, received its nourishment from the Oak.

And indeed, if we consider the great care of the Creator in the dispensations of his providences for the propagation and increase of the race, not onely of all kind of Animals, but even of Vegetables, we cannot chuse but admire and adore him for his Excellencies, but we shall leave off to admire the creature, or to wonder at the strange kind of acting in several Animals, which seem to savour so much of reason; it seeming to me most manifest, that those are but actings according to their structures, and such operations as such bodies, so compos'd, must necessarily, when there are such and such circumstances concurring, perform: thus, whenwe find Flies swarming, about any piece of flesh that does begin a little to ferment; Butterflies about Colworts, and several other leaves, which will serve to hatch and nourish their young; Gnats, and several other Flies about the Waters, and marishy places, or any other creatures, seeking and placing their Seeds in convenient repositories, we may, if we attentively consider and examine it, find that there are circumstances sufficient, upon the supposals of the excellent contrivance of their machine, to excite and force them to act after such or such a manner; those steams that rise from these several places may, perhaps, set several parts of these little Animals at work, even as in the contrivance of killing a Fox or Wolf with a Gun, the moving of a string, is the death of the Animal; for the Beast, by moving the flesh that is laid to entrap him, pulls the string which moves the trigger, and that lets go the Cock which on the steel strikes certain sparks of fire which kindle the powder in the pann, and that presently flies into the barrel, where the powder catching fire rarifies and drives out the bullet which kills the Animal; in all which actions, there is nothing of intention or ratiocination to be ascrib'd either to the Animal or Engine, but all to the ingeniousness of the contriver.

But to return to the more immediate consideration of our Gnat: We have in it an Instance, not usual or common, of a very stange *amphibious* creature, that being a creature that inhabits the Air, does yet produce a creature, that for some time lives in the water as a Fish, though afterward (which is as strange) it becomes an inhabitant of the Air, like its Sire, in the form of a Fly. And this, me thinks, does prompt me to propose certain conjectures, as Queries, having not yet had sufficient opportunity and leisure to answer them my self from my own Experiments or Observations.

And the first is, Whether all those things that we suppose to be bred from corruption and putrifaction, may not be rationally suppos'd to have their origination as natural as these Gnats, who, 'tis very probable, were first dropt into this Water, in the form of Eggs. Those Seeds or

Eggs

Eggs must certainly be very small, which so small a creature as a Gnat yields, and therefore we need not wonder that we find not the Eggs themselves, some of the younger of them, which I have observ'd, having not exceeded a tenth part of the bulk they have afterwards come to; and next, I have observed some of those little ones which must have been generated after the Water was inclosed in the Bottle, and therefore most probably from Eggs, whereas those creatures have been suppos'd to be bred of the corruption of the Water, there being not formerly known any probable way how they should be generated.

A second is, whether these Eggs are immediately dropt into the Water by the Gnats themselves, or, mediately, are brought down by the falling rain; for it seems not very improbable, but that those small seeds of Gnats may (being, perhaps, of so light a nature, and having so great a proportion of surface to so small a bulk of body) be ejected into the Air, and so, perhaps, carried for a good while too and fro in it, till by the drops of Rain it be wash'd out of it.

A third is, whether multitudes of those other little creatures that are found to inhabit the Water for some time, do not, at certain times, take wing and fly into the Air, others dive and hide themselves in the Earth, and so contribute to the increase both of the one and the other Element.

Postscript.

A good while since the writing of this Description, I was presented by Doctor *Peter Ball*, an ingenious Member of the *Royal Society*, with a little Paper of Nuts, which he told me was sent him from a Brother of his out of the Countrey, from *Mamhead* in *Devonshire*, some of them were loose, having been, as I suppose, broken off, others were still growing fast on upon the sides of a stick, which seem'd by the bark, pliableness of it, and by certain strings that grew out of it, to be some piece of the root of a Tree; they were all of them dry'd, and a little shrivell'd, others more round, of a brown colour; their shape was much like a Figg, but very much smaller, some being about the bigness of a Bay-berry, others, and the biggest, of a Hazel-Nut. Some of these that had no hole in them, I carefully opened with my Knife, and found in them a good large round white Maggot, almost as bigg as a small Pea, which seem'd shap'd like other Maggots, but shorter. I could not find them to move, though I ghess'd them to be alive, because upon pricking them with a Pinn, there would issue out a great deal of white *mucous* matter, which seem'd to be from a voluntary contraction of their skin; their husk or matrix consisted of three Coats, like the barks of Trees, the outermost being more rough and spongie, and the thickest, the middlemost more close, hard, white, and thin, the innermost very thin, seeming almost like the skin within an Egg's shell. The two outermost had root in the branch or stick, but the innermost had no stem or process, but was onely a skin that cover'd the cavity of the Nut. All the Nuts that had no holes eaten in them, I found to contain these Maggots, but all that had holes, I found empty, the Maggots,

it

it seems, having eaten their way through, taken wings and flown away, as this following account (which I receiv'd in writing from the same person, as it was sent him by his Brother) manifests. *In a moorish black Peaty mould, with some small veins of whitish yellow Sands, upon occasion of digging a hole two or three foot deep, at the head of a Pond or Pool, to set a Tree in, at that depth, were found, about the end of* October 1663. *in those very veins of Sand, those Buttons or Nuts, sticking to a little loose stick, that is, not belonging to any live Tree, and some of them also free by themselves.*

Four or five of which being then open'd, some were found to contvin live Insects come to perfection, most like to flying Ants, *if not the same; in others, Insects, yet imperfect, having but the head and wings form'd, the rest remaining a soft white pulpy substance.*

Now, as this furnishes us with one odd History more, very agreeable to what I before hinted, so I doubt not, but were men diligent observers, they might meet with multitudes of the same kind, both in the Earth and in the Water, and in the Air, on Trees, Plants, and other Vegetables, all places and things being, as it were, *animarum plena.* And I have often, with wonder and pleasure, in the Spring and Summer-time, look'd close to, and diligently on, common Garden mould, and in a very small parcel of it, found such multitudes and diversities of little *reptiles*, some in husks, others onely creepers, many wing'd, and ready for the Air; divers husks or habitations left behind empty. Now, if the Earth of our cold Climate be so fertile of animate bodies, what may we think of the fat Earth of hotter Climates? Certainly, the Sun may there, by its activity, cause as great a parcel of Earth to fly on wings in the Air, as it does of Water in steams and vapours. And what swarms must we suppose to be sent out of those plentifull inundations of water which are poured down by the sluces of Rain in such vast quantities? So that we need not much wonder at those innumerable clouds of Locusts with which *Africa*, and other hot countries are so pestred, since in those places are found all the convenient causes of their production, namely, genitors, or Parents, concurrent receptacles or matrixes, and a sufficient degree of natural heat and moisture.

I was going to annex a little draught of the Figure of those Nuts sent out of *Devonshire*; but chancing to examine Mr. *Parkinson's* Herbal for something else, and particularly about Galls and Oak-apples, I found among no less then 24. several kinds of excrescencies of the Oak, which I doubt not, but upon examination, will be all found to be the *matrixes* of so many several kinds of Insects; I having observ'd many of them my self to be so, among 24. several kinds, I say, I found one described and Figur'd directly like that which I had by me, the *Scheme* is there to be seen, the description, because but short, I have here adjoin'd *Theatri Botanici trib.* 16. *Chap.* 2. *There groweth at the roots of old Oaks in the Spring-time, and sometimes also in the very heat of Summer, a peculiar kind of Mushrom or Excrescence, call'd* Uva Quercina, *swelling out of the Earth, many growing one close unto another, of the fashion of a Grape, and therefore took the name, the* Oak-Grape, *and is of a Purplish colour on the outside,*

and

Schem: XXVIII.





and white within like Milk, and in the end of Summer becometh hard and woody. Whether this be the very same kind, I cannot affirm, but both the Picture and Description come very neer to that I have, but that he seems not to take notice of the hollowness or Worm, for which 'tis most observable. And therefore 'tis very likely, if men did but take notice, they might find very many differing Species of these Nuts, *Ovaries*, or *Matrixes*, and all of them to have much the same designation and office. And I have very lately found several kinds of Excrescencies on Trees and Shrubs, which having endured the Winter, upon opening them, I found most of them to contain little Worms, but dead, those things that contain'd them being wither'd and dry.

Observ. XLIV. *Of the tufted or Brush-horn'd* Gnat.

THis little creature was one of those multitudes that fill our *English* air all the time that warm weather lasts, and is exactly of the shape of that I observ'd to be generated and hatch'd out of those little Insects that wriggle up and down in Rain-water. But, though many were of this form, yet I observ'd others to be of quite other kinds; nor were all of this or the other kind generated out of Water Insects; for whereas I observ'd that those that proceeded from those Insects were at their full growth, I have also found multitudes of the same shape, but much smaller and tenderer seeming to be very young ones, creep up and down upon the leaves of Trees, and flying up and down in small clusters, in places very remote from water; and this Spring, I observ'd one day, when the Wind was very calm, and the afternoon very fair, and pretty warm, though it had for a long time been very cold weather, and the wind continued still in the East, several small swarms of them playing to and fro in little clouds in the Sun, each of which were not a tenth part of the bigness of one of these I here have delineated, though very much of the same shape, which makes me ghess, that each of these swarms might be the of-spring of one onely Gnat, which had been hoorded up in some safe repository all this Winter by some provident Parent, and were now, by the warmth of the Spring-air, hatch'd into little Flies.

And indeed, so various, and seemingly irregular are the generations or productions of Insects, that he that shall carefully and diligently observe the several methods of Nature therein, will have infinitely cause further to admire the wisdom and providence of the Creator; for not onely the same kind of creature may be produc'd from several kinds of ways, but the very same creature may produce several kinds: For, as divers Watches may be made out of several materials, which may yet have all the same appearance, and move after the same manner, that is, shew the hour equally true, the one as the other, and out of the same kind of matter, like Watches, may be wrought differing ways; and, as one and the same Watch

 may,

may, by being diversly agitated, or mov'd, by this or that agent, or after this or that manner, produce a quite contrary effect: So may it be with these most curious Engines of Insect's bodies; the All-wise God of Nature, may have so ordered and disposed the little *Automatons*, that when nourished, acted, or enlivened by this cause, they produce one kind of effect, or animate shape, when by another they act quite another way, and another Animal is produc'd. So may he so order several materials, as to make them, by several kinds of methods, produce similar *Automatons*.

But to come to the Description of this Insect, as it appears through a *Microscope*, of which a representation is made in the 28. *Scheme*. Its head A, is exceeding small, in proportion to its body, consisting of two clusters of pearl'd eyes B B, on each side of its head, whose pearls or eye-balls are curiously rang'd like those of other Flies; between these, in the forehead of it, there are plac'd upon two small black balls, C C, two long jointed horns, tapering towards the top, much resembling the long horns of Lobsters, each of whose stems or quills, D D, were brisled or brushed with multitudes of small stiff hairs, issuing out every way from the several joints, like the strings or sproutings of the herb *Horse-tail*, which is oft observ'd to grow among Corn, and for the whole shape, it does very much resemble those *brushy Vegetables*; besides these, there are two other jointed and brisled horns, or feelers, E E, in the forepart of the head, and a *proboscis*, F, underneath, which in some Gnats are very long, streight hollow pipes, by which these creatures are able to drill and penetrate the skin, and thence, through those pipes suck so much bloud as to stuff their bellies so full till they be ready to burst.

This small head, with its appurtenances, is fastned on by a short neck, G, to the middle of the *thorax*, which is large, and seems cased with a strong black shel, H I K, out of the under part of which, issue six long and slender legs, L L L L L L, shap'd just like the legs of Flies, but spun or drawn out longer and slenderer, which could not be express'd in the Figure, because of their great length; and from the upper part, two oblong, but slender transparent wings, M M, shaped somewhat like those of a Fly, underneath each of which, as I have observ'd also in divers sorts of Flies, and other kinds of Gnats, was placed a small body, N, much resembling a drop of some transparent glutinous substance, hardned or cool'd, as it was almost ready to fall, for it has a round knob at the end, which by degrees grows slenderer into a small stem, and neer the insertion under the wing, this stem again grows bigger; these little *Pendulums*, as I may so call them, the litle creature vibrates to and fro very quick when it moves its wings, and I have sometimes observ'd it to move them also, whil'st the wing lay still, but always their motion seem'd to further the motion of the wing ready to follow; of what use they are, as to the moving of the wing, or otherwise, I have not now time to examine.

Its belly was large, as it is usually in all Insects, and extended into nine lengths or partitions, each of which was cover'd with round armed rings or shells; six of which, O P Q R S T were transparent, and divers kinds of *Peristaltick* motions might be very easily perceiv'd, whil'st the Animal

was

Was alive, but especially a small cleer white part V, seemed to beat like the heart of a larger Animal. The last three divisios, W X Y, were cover'd with black and opacous shells. To conclude, take this creature altogether, and for beauty and curious contrivances, it may be compared with the largest Animal upon the Earth. Nor doth the Alwise Creator seem to have shewn less care and providence in the fabrick of it, then in those which seem most considerable.

Observ. XLV. *Of the great Belly'd* Gnat *or female* Gnat.

THe second Gnat, delineated in the twenty ninth *Scheme*, is of a very differing shape from the former; but yet of this sort also, I found several of the Gnats, that were generated out of the Water Insect: the wings of this, were much larger then those of the other, and the belly much bigger, shorter and of an other shape; and, from several particulars, I ghest it to be the Female Gnat, and the former to be the Male.

The *thorax* of this was much like that of the other, having a very strong and ridged back-piece, which went also on either side of its leggs; about the wings there were several joynted pieces of Armor, which seem'd curiously and conveniently contriv'd, for the promoting and strengthning the motion of the wings: its head was much differing from the other, being much bigger and neater shap'd, and the horns that grew out between his eyes on two little balls, were of a very differing shape from the tufts of the other Gnat, these having but a few knots or joynts, and each of those but a few, and those short and strong, brisles. The formost horns or feelers, were like those of the former Gnat.

One of these Gnats I have suffer'd to pierce the skin of my hand, with its *proboscis*, and thence to draw out as much blood as to fill its belly as full as it could hold, making it appear very red and transparent; and this without any further pain, then whil st it was sinking in its *proboscis*, as it is also in the stinging of Fleas: a good argument, that these creatures do not wound the skin, and suck the blood out of enmity and revenge, but for meer necessity, and to satisfy their hunger. By what means this creature is able to suck, we shall shew in another place.

Observ. XLVI. *Of the white featherwing'd* Moth *or* Tinea Argentea.

THis white long wing'd Moth, which is delineated in the 30. *Scheme*; afforded a lovely object both to the naked Eye, and through a *Microscope*: to the Eye it appear'd a small Milk white Fly with four white

Wings, the two formoſt ſomewhat longer then the two hindermoſt, and the two ſhorter about half an Inch long, each of which four Wings ſeem'd to conſiſt of two ſmall long Feathers, very curiouſly tufted, or haired on each ſide, with purely white, and exceedingly fine and ſmall Haires, proportion'd to the ſtalks or ſtems, out of which they grew, much like the tufts of a long wing-feather of ſome Bird, and their ſtalks or ſtems were, like thoſe, bended backwards and downwards, as may be plainly ſeen by the draughts of them in the Figure.

Obſerving one of theſe in my *Microſcope*, I found, in the firſt place, that all the Body, Legs, Horns and the Stalks of the Wings, were covered over with various kinds of curious white Feathers, which did, with handling or touching, eaſily rubb off and fly about, in ſo much that looking on my Fingers, with which I had handled this Moth, and perceiving on them little white ſpecks, I found by my *Microſcope*, that they were ſeveral of the ſmall Feathers of this little creature, that ſtuck up and down in the *rugoſities* of my Skin.

Next, I found that underneath theſe Feathers, the pretty Inſect was covered all over with a cruſted Shell, like other of thoſe Animals, but with one much thinner and tenderer.

Thirdly, I found, as in Birds alſo is notable, it had differing and appropriate kinds of Feathers, that covered ſeveral parts of its body.

Fourthly, ſurveying the parts of its body, with a more accurate and better Magnifying *Microſcope*, I found that the tufts or haires of its Wings were nothing elſe but a congeries, or thick ſet cluſter of ſmall *vimina* or twiggs, reſembling a ſmall twigg of Birch, ſtript or whitned, with which Bruſhes are uſually made, to beat out or bruſh off the duſt from Cloth and Hangings. Every one of the twiggs or branches that compoſed the Bruſh of the Feathers, appeared in this bigger Magnifying Glaſs (of which E F which repreſents $\frac{1}{24}$ part of an Inch, is the ſcale, as G is of the leſſer, which is only $\frac{1}{3}$) like the figure D. The Feathers alſo that covered a part of his Body, and were interſperſed among the bruſh of his Wings, I found, in the bigger Magnifying Glaſs, of the ſhape A, conſiſting of a ſtalk or ſtem in the middle, and a ſeeming tuftedneſs or bruſhy part on each ſide. The Feathers that cover'd moſt part of his Body and the ſtalk of his wings, were, in the ſame *Microſcope*, much of the figure B, appearing of the ſhape of a ſmall Feather, and ſeemed tufted: thoſe which covered the Horns and ſmall parts of the Leggs, through the ſame *Microſcope*, appear'd of the ſhape C. Whether the tufts of any or all of theſe ſmall Feathers, conſiſted of ſuch component particles as the Feathers of Birds, I much doubt, becauſe I find that Nature does not alwaies keep, or operate after the ſame method, in ſmaller and bigger creatures. And of this, we have particular Inſtances in the Wings of ſeveral creatures. For whereas, in Birds of all kinds, it compoſes each of the Feathers of which its Wing conſiſts, of ſuch an exceeding curious and moſt admirable and ſtupendious texture, as I elſe where ſhew, in the Obſervations on a Feather; we find it to alter its method quite, in the fabrick of the Wings of theſe minute creatures, compoſing ſome of thin extended membranes

or


1/3
1/24

or skins, such as the Wings of Dragon-flys; in others, those skins are all over-grown, or pretty thick bestuck, with short brisles, as in Flesh-flies; in others, those filmes are covered, both on the upper and under side, with small Feathers, plac'd almost like the tyles on a House, and are curiously rang'd and adorn'd with most lively colours, as is observable in Butter-flies, and several kinds of Moths; In others, instead of their films, Nature has provided nothing, but a matter of half a score stalks (if I well remember the number; for I have not lately met with any of these flys, and did not, when I first observ'd them, take sufficient notice of divers particulars) and each of these stalks, with a few single branchings on each side, resembling much the branched back-bone of a Herring or the like Fish, or a thin hair'd Peacocks feather, the top or the eye being broken off. With a few of these on either side (which it was able to shut up or expand at pleasure, much like a Fan, or rather like the posture of the feathers in a wing, which ly all one under another, when shut, and by the side of each other, when expanded) this pretty little grey Moth (for such was the creature I observ'd, thus wing'd) could very nimbly, and as it seem'd very easily move its *corpuscle*, through the Air, from place to place. Other Insects have their wings cas'd, or cover'd over, with certain hollow shells, shap'd almost like those hollow Trayes, in which Butchers carry meat, whose hollow sides being turn'd downwards, do not only secure their folded wings from injury of the earth, in which most of those creatures reside, but whilst they fly, serves as a help to sustain and bear them up. And these are observable in *Scarabees* and a multitude of other terrestrial *crustaceous* Insects; in which we may yet further observe a particular providence of Nature.

Now in all these kinds of wings, we observe this particular, as a thing most worthy remark; that where ever a wing consists of discontinued parts, the Pores or *interstitia* between those parts are very seldom, either much bigger, or much smaller, then these which we here find between the particles of these brushes, so that it should seem to intimate, that the parts of the Air are such, that they will not easily or readily, if at all, pass through these Pores, so that they seem to be strainers fine enough to hinder the particles of the Air (whether hinder'd by their bulk, or by their *agitation*, *circulation*, *rotation* or *undulation*, I shall not here determine) from getting through them, and, by that means, serve the Animal as well, if not better, then if they were little films. I say, if not better, because I have observ'd that all those creatures, that have film'd wings, move them abundantly quicker and more strongly, such as all kind of Flies and *Scarabees* and Batts, then such as have their wings covered with feathers, as Butter-flies and Birds, or twiggs, as Moths, which have each of them a much slower motion of their wings; That little ruggedness perhaps of their wings helping them somewhat, by taking better hold of the parts of the Air, or not suffering them so easily to pass by, any other way then one.

But what ever be the reason of it, 'tis most evident, that the smooth wing'd Insects have the strongest Muscles or movent parts of their wings, and the other much weaker; and this very Insect, we are now describing, had

had a very small *thorax* or middle part of his body, if compar'd to the length and number of his wings; which therefore, as he mov'd them very slowly, so must he move them very weakly. And this last propriety do we find somewhat observ'd also in bigger kind of Flying creatures, Birds; so that we see that the Wisdom and Providence of the All-wise Creator, is not less shewn in these small despicable creatures, Flies and Moths, which we have branded with a name of ignominy, calling them Vermine, then in those greater and more remakable animate bodies, Birds.

I cannot here stand to add any thing about the nature of flying, though, perhaps, on another occasion, I may say something on that subject, it being such as may deserve a much more accurate examination and scrutiny then it has hitherto met with; For to me there seems nothing wanting to make a man able to fly, but what may be easily enough supply'd from the Mechanicks hitherto known, save onely the want of strength, which the Muscles of a man seem utterly uncapable of, by reason of their smalness and texture, but how even strength also may be mechanically made, an artificial Muscle so contriv'd, that thereby a man shall be able to exert what strength he pleases, and to regulate it also to his own mind, I may elsewhere endeavour to manifest.

Observ. XLVII. *Of the* Shepherd Spider, *or long legg'd* Spider.

THe Carter, Shepherd Spider, or long-legg'd Spider, has, for two particularities, very few similar creatures that I have met with; the first, which is discoverable onely by the *Microscope*, and is in the first and second *Figures* of the 31. *Scheme*, plainly describ'd, is the curious contrivance of his eyes, of which (differing from most other Spiders) he has onely two, and those plac'd upon the top of a small pillar or hillock, rising out of the middle of the top of its back, or rather the crown of its head, for they were fix'd on the very top of this pillar (which is about the heighth of one of the transverse Diameters of the eye, and look'd on in another posture, appear'd much of the shape, B C D) The two eyes, B B, were placed back to back, with the transparent parts, or the pupils, looking towards either side, but somewhat more forward then backwards. C was the column or neck on which they stood, and D the crown of the head out of which that neck sprung.

These eyes, to appearance, seem'd to be of the very same structure with that of larger *binocular* creatures, seeming to have a very smooth and very protuberant *Cornea*, and in the midst of it to have a very black pupil, incompassed about with a kind of grey *Iris*, as appears by the *Figure*; whether it were able to move these eyes to and fro, I have not observ'd, but 'tis not very likely he should, the pillar or neck C, seeming to be cover'd and stiffen'd with a crusty shell; but Nature, in probability, has supply'd

Fig: 1



Fig: 3



ply'd that defect, by making the *Cornea* so very protuberant, and setting it so cleer above the shadowing or obstructing of its prospect by the body, that 'tis likely each eye may perceive, though not see distinctly, almost a *Hemisphere*, whence having so small and round a body plac'd upon such long leggs, it is quickly able so to wind, and turn it, as to see any thing distinct. This creature, as do all other Spiders I have yet examin'd, does very much differ from most other Insects in the Figure of its eyes; for I cannot, with my best *Microscope*, discover its eyes to be any ways knobb'd or pearl'd like those of other Insects.

The second Peculiarity which is obvious to the eye, is also very remarkable, and that is the prodigious length of its leggs, in proportion to its small round body, each legg of this I drew, being above sixteen times the length of its whole body, and there are some which have them yet longer, and others that seem of the same kind, that have them a great deal shorter; the eight leggs are each of them jointed, just like those of a Crab, but every of the parts are spun out prodigiously longer in proportion; each of these leggs are terminated in a small case or shell, shap'd almost like that of a Mussle-shell, as is evident in the third *Figure* of the same *Scheme* (that represents the appearance of the under part or belly of the creature) by the shape of the protuberant *conical* body, I I I I, *&c.* These are as 'twere plac'd or fasten'd on to the protuberant body of the Insect, which is to be suppos'd very high at M, making a kind of blunt cone whereof M is to be suppos'd the *Apex*, about which greater cone of the body, the smaller cones of the leggs are plac'd, each of them almost reaching to the top in so admirable a manner, as does not a little manifest the wisdom of Nature in the contrivance; for these long Leavers (as I may so call them) of the legs, having not the advantage of a long end on the other side of the *hypomochlion* or centers on which the parts of the leggs move, must necessarily require a vast strength to move them, and keep the body ballanc'd and suspended, in so much, that if we should suppose a man's body suspended by such a contrivance, an hundred and fifty times the strength of a man would not keep the body from falling on the breast. To supply therefore each of these leggs with its proper strength, Nature has allow'd to each a large Chest or Cell, in which is included a very large and strong Muscle, and thereby this little Animal is not onely able to suspend its body upon less then these eight, but to move it very swiftly over the tops of grass and leaves.

Nor are these eight leggs so prodigiously long, but the ninth, and tenth, which are the two claws, K K, are as short, and serve in steed of a *proboscis*, for those seem'd very little longer then his mouth; each of them had three parts, but very short, the joints K K, which represented the third, being longer then both the other. This creature, seems (which I have several times with pleasure observ'd) to throw its body upon the prey, insteed of its hands, not unlike a hunting Spider, which leaps like a Cat at a Mouse. The whole Fabrick was a very pretty one, and could I have dissected it, I doubt not but I should have found as many singularities within it as without, perhaps, for the most part, not unlike

the

the parts of a Crab, which this little creature does in many things, very much resemble; the curiosity of whose contrivance, I have in another place examin'd. I omit the description of the horns, A A, of the mouth, L L, which seem'd like that of a Crab; the specklednes of his shell, which proceeded from a kind of feathers or hairs, and the hairines of his leggs, his large *thorax* and little belly, and the like, they being manifested by the Figure; and shall onely take notice that the three parts of the body, namely, the head, breast, and belly, are in this creature strangely confus'd, so that 'tis difficult to determine which is which, as they are also in a Crab; and indeed, this seems to be nothing else, but an Air-crab, being made more light and nimble, proportionable to the *medium* wherin it resides; and as Air seems to have but one thousandth part of the body of Water, so does this Spider seem not to be a thousandth part of the bulk of a Crab.

Observ. XLVIII. *Of the hunting* Spider, *and several other sorts of* Spiders.

THe hunting Spider is a small grey Spider, prettily bespeck'd with black spots all over its body, which the *Microscope* discovers to be a kind of feathers like those on Butterflies wings, or the body of the white Moth I lately describ'd. Its gate is very nimble by fits, sometimes running, and sometimes leaping, like a Grashopper almost, then standing still, and setting it self on its hinder leggs, it will very nimbly turn its body, and look round it self every way: It has six very conspicuous eyes, two looking directly forwards, plac'd just before; two other, on either side of those, looking forward and side-ways; and two other about the middle of the top of its back or head, which look backwards and side-wards; these seem'd to be the biggest. The surface of them all was very black, sphærical, purely polish'd, reflecting a very cleer and distinct Image of all the ambient objects, such as a window, a man's hand, a white Paper, or the like. Some other properties of this Spider, observ'd by the most accomplish'd Mr. *Evelyn*, in his travels in *Italy*, are most emphatically set forth in the History hereunto annexed, which he was pleas'd upon my desire to send me in writing.

Of all the sorts of Insects, there is none has afforded me more divertisements then the *Venatores*, which are a sort of *Lupi*, that have their Denns in the rugged walls, and crevices of our houses; a small brown and delicately spotted kind of Spiders, whose hinder leggs are longer then the rest.

Such I did frequently observe at *Rome*, which espying a Fly at three or four yards distance, upon the Balcony (where I stood) would

would not make directly to her, but craul under the Rail, till being arriv'd to the *Antipodes*, it would steal up, seldom missing its aim; but if it chanced to want any thing of being perfectly opposite, would at first peep, immediatly slide down again, till taking better notice, it would come the next time exactly upon the Fly's back: But, if this hapn'd not to be within a competent leap, then would this Insect move so softly, as the very shadow of the Gnomon seem'd not to be more imperceptible, unless the Fly mov'd; and then would the Spider move also in the same proportion, keeping that just time with her motion, as if the same Soul had animated both those little bodies; and whether it were forwards, backwards, or to either side, without at all turning her body, like a well mannag'd Horse: But, if the capricious Fly took wing, and pitch'd upon another place behind our Huntress, then would the Spider whirle its body so nimbly about, as nothing could be imagin'd more swift; by which means, she always kept the head towards her prey, though to appearance, as immovable, as if it had been a Nail driven into the Wood, till by that indiscernable progress (being arriv'd within the sphere of her reach) she made a fatal leap (swift as Lightning) upon the Fly, catching him in the pole, where she never quitted hold till her belly was full, and then carried the remainder home. I have beheld them instructing their young ones, how to hunt, which they would sometimes discipline for not well observing; but, when any of the old ones did (as sometimes) miss a leap, they would run out of the field, and hide them in their crannies, as asham'd, and haply not be seen abroad for four or five hours after; for so long have I watched the nature of this strange Insect, the contemplation of whose so wonderfull sagacity and address has amaz'd me; nor do I find in any chase whatsoever, more cunning and Stratagem observ'd: I have found some of these Spiders in my Garden, when the weather (towards the Spring)

is very hot, but they are nothing so eager of hunting as they are in *Italy*.

There are multitudes of other sorts of Spiders, whose eyes, and most other parts and properties, are so exceedingly different both from those I have describ'd, and from one another, that it would be almost endless, at least too long for my present Essay, to describe them, as some with six eyes, plac'd in quite another order; others with eight eyes; others with fewer, and some with more. They all seem to be creatures of prey, and to feed on other small Insects, but their ways of catching them seem very differing: the Shepherd Spider by running on his prey; the Hunting Spider by leaping on it, other sorts weave Nets, or Cobwebs, whereby they ensnare them, Nature having both fitted them with materials and tools, and taught them how to work and weave their Nets, and to lie perdue, and to watch diligently to run on any Fly, as soon as ever entangled.

Their thread or web seems to be spun out of some viscous kind of excrement, lying in their belly, which, though soft when drawn out, is, presently by reason of its smalness, hardned and dried by the ambient Air. Examining several of which with my *Microscope*, I found them to appear much like white Horse-hair, or some such transparent horny substance, and to be of very differing magnitudes; some appearing as bigg as a Pigg's brisle, others equal to a Horse-hair; other no bigger then a man's hair; others yet smaller and finer. I observ'd further, that the radiating chords of the web were much bigger, and smoother then those that were woven round, which seem'd smaller, and all over knotted or pearl'd, with small transparent Globules, not unlike small Crystal Beads or seed Pearls, thin strung on a Clew of Silk; which, whether they were so spun by the Spider, or by the adventitious moisture of a fogg (which I have observ'd to cover all these filaments with such Crystalline Beads) I will not now dispute.

These threads were some of them so small, that I could very plainly, with the *Microscope*, discover the same consecutions of colours as in a *Prisme*, and they seem'd to proceed from the same cause with those colours which I have already describ'd in thin plated bodies.

Much resembling a Cobweb, or a confus'd lock of these Cylinders, is a certain white substance which, after a fogg, may be observ'd to fly up and down the Air; catching several of these, and examining them with my *Microscope*, I found them to be much of the same form, looking most like to a flake of Worsted prepar'd to be spun, though by what means they should be generated, or produc'd, is not easily imagined: they were of the same weight, or very little heavier then the Air; and 'tis not unlikely, but that those great white clouds, that appear all the Summer time, may be of the same substance.

Observ.


C
D
D
A
B
C
A
I
I

Obſerv. XLIX. *Of an* Ant *or* Piſmire.

THis was a creature, more troubleſom to be drawn, then any of the reſt, for I could not, for a good while, think of a way to make it ſuffer its body to ly quiet in a natural poſture; but whil'ſt it was alive, if its feet were fetter'd in Wax or Glew, it would ſo twiſt and wind its body, that I could not any wayes get a good view of it; and if I killed it, its body was ſo little, that I did often ſpoile the ſhape of it, before I could throughly view it: for this is the nature of theſe minute Bodies, that as ſoon, almoſt, as ever their life is deſtroy'd, their parts immediately ſhrivel, and loſe their beauty; and ſo is it alſo with ſmall Plants, as I inſtanced before, in the deſcription of Moſs. And thence alſo is the reaſon of the variations in the beards of wild Oats, and in thoſe of Muſk-graſs ſeed, that their bodies, being exceeding ſmall, thoſe ſmall variations which are made in the ſurfaces of all bodies, almoſt upon every change of Air, eſpecially if the body be porous, do here become ſenſible, where the whole body is ſo ſmall, that it is almoſt nothing but ſurface; for as in vegetable ſubſtances, I ſee no great reaſon to think, that the moiſture of the Aire (that, ſticking to a wreath'd beard, does make it untwiſt) ſhould evaporate, or exhale away, any faſter then the moiſture of other bodies, but rather that the avolation from, or acceſs of moiſture to, the ſurfaces of bodies being much the ſame, thoſe bodies become moſt ſenſible of it, which have the leaſt proportion of body to their ſurface. So is it alſo with Animal ſubſtances; the dead body of an Ant, or ſuch little creature, does almoſt inſtantly ſhrivel and dry, and your object ſhall be quite another thing, before you can half delineate it, which proceeds not from the extraordinary exhalation, but from the ſmall proportion of body and juices, to the uſual drying of bodies in the Air, eſpecially if warm. For which inconvenience, where I could not otherwiſe remove it, I thought of this expedient.

I took the creature, I had deſign'd to delineate, and put it into a drop of very well rectified ſpirit of Wine, this I found would preſently diſpatch, as it were, the Animal, and being taken out of it, and lay'd on a paper, the ſpirit of Wine would immediately fly away, and leave the Animal dry, in its natural poſture, or at leaſt, in a conſtitution, that it might eaſily with a pin be plac'd, in what poſture you deſired to draw it, and the limbs would ſo remain, without either moving, or ſhriveling. And thus I dealt with this Ant, which I have here delineated, which was one of many, of a very large kind, that inhabited under the Roots of a Tree, from whence they would ſally out in great parties, and make moſt grievous havock of the Flowers and Fruits, in the ambient Garden, and return back again very expertly, by the ſame wayes and paths they went.

It was more then half the bigneſs of an Earwig, of a dark brown, or reddiſh colour, with long legs, on the hinder of which it would ſtand

up, and raise its head as high as it could above the ground, that it might stare the further about it, just after the same manner as I have also observ'd a hunting Spider to do: and putting my finger towards them, they have at first all run towards it, till almost at it; and then they would stand round about it, at a certain distance, and smell, as it were, and consider whether they should any of them venture any further, till one more bold then the rest venturing to climb it, all the rest, if I would have suffered them, would have immediately followed: many such other seemingly rational actions I have observ'd in this little Vermine with much pleasure, which would be too long to be here related; those that desire more of them may satisfie their curiosity in *Ligons* History of the *Barbadoes*.

Having insnar'd several of these into a small Box, I made choice of the tallest grown among them, and separating it from the rest, I gave it a Gill of Brandy, or Spirit of Wine, which after a while e'en knock'd him down dead drunk, so that he became moveless, though at first putting in he struggled for a pretty while very much, till at last, certain bubbles issuing out of its mouth, it ceased to move; this (because I had before found them quickly to recover again, if they were taken out presently) I suffered to lye above an hour in the Spirit; and after I had taken it out, and put its body and legs into a natural posture, remained moveless about an hour; but then, upon a sudden, as if it had been awaken out of a drunken sleep, it suddenly reviv'd and ran away; being caught, and serv'd as before, he for a while continued struggling and striving, till at last there issued several bubbles out of its mouth, and then, *tanquam animam expirasset*, he remained moveless for a good while; but at length again recovering, it was again redipt, and suffered to lye some hours in the Spirit; notwithstanding which, after it had layen dry some three or four hours, it again recovered life and motion: Which kind of Experiments, if prosecuted, which they highly deserve, seem to me of no inconsiderable use towards the invention of the *Latent Scheme*, (as the Noble *Verulam* calls it) or the hidden, unknown Texture of Bodies.

Of what Figure this Creature appear'd through the *Microscope*, the 32. *Scheme* (though not so carefully graven as it ought) will represent to the eye, namely, That it had a large head A A, at the upper end of which were two protuberant eyes, pearl'd like those of a Fly, but smaller B B; out of the Nose, or foremost part, issued two horns C C, of a shape sufficiently differing from those of a blew Fly, though indeed they seem to be both the same kind of Organ, and to serve for a kind of smelling; beyond these were two indented jaws D D, which he open'd side-wayes, and was able to gape them asunder very wide; and the ends of them being armed with teeth, which meeting went between each other, it was able to grasp and hold a heavy body, three or four times the bulk and weight of its own body: It had only six legs, shap'd like those of a Fly, which, as I shewed before, is an Argument that it is a winged Insect, and though I could not perceive any sign of them in the middle part of its body (which seem'd to consist of three joints or pieces

Schem: XXXIII.



Fig: 3.



Fig: 1.



Fig: 2.

ces EFG, out of which sprung two legs, yet 'tis known that there are of them that have long wings, and fly up and down in the air.

The third and last part of its body III was bigger and larger then the other two, unto which it was joyn'd by a very small middle, and had a kind of loose shell, or another distinct part of its body H, which seem'd to be interpos'd, and to keep the *thorax* and belly from touching.

The whole body was cas'd over with a very strong armour, and the belly III was covered likewise with multitudes of small white shining brisles; the legs, horns, head, and middle parts of its body were bestuck with hairs also, but smaller and darker.

Observ. L. *Of the wandring* Mite.

IN *September* and *October*, 1661. I observ'd in *Oxford* several of these little pretty Creatures to wander to and fro, and often to travel over the plains of my Window. And in *September* and *October*. 1663. I observ'd likewise several of these very same Creatures traversing a window at *London*, and looking without the window upon the subjacent wall, I found whole flocks of the same kind running to and fro among the small groves and thickets of green moss, and upon the curiously spreading vegetable blew or yellow moss, which is a kind of a Mushrome or Jews-ear.

These Creatures to the naked eye seemed to be a kind of black Mite, but much nimbler and stronger then the ordinary Cheese-Mites; but examining them in a *Microscope*, I found them to be a very fine crusted or shell'd Insect, much like that represented in the first Figure of the three and thirtieth *Scheme*, with a protuberant oval shell A, indented or pitted with an abundance of small pits, all covered over with little white brisles, whose points all directed backwards.

It had eight legs, each of them provided with a very sharp tallon, or claw at the end, which this little Animal, in its going, fastned into the pores of the body over which it went. Each of these legs were bestuck in every joynt of them with multitudes of small hairs, or (if we respect the proportion they bore to the bigness of the leg) turnpikes, all pointing towards the claws.

The *Thorax*, or middle parts of the body of this Creature, was exceeding small, in respect both of the head and belly, it being nothing but that part which was covered by the two shells BB, though it seem'd to grow thicker underneath: And indeed, if we consider the great variety Nature uses in proportioning the three parts of the body, the *Head*, *Thorax*, and *Belly*) we shall not wonder at the small proportion of this *Thorax*, nor at the vaster bulk of the belly, for could we exactly anatomise this little Creature, and observe the particular designs of each part, we should doubtless, as we do in all her more manageable

nageable and tractable fabricks, find much more reason to admire the excellency of her contrivance and workmanship, then to wonder, it was not made otherwise.

The head of this little Insect was shap'd somewhat like a Mite's, that is, it had a long snout, in the manner of a Hogs, with a knobbed ridge running along the middle of it, which was bestuck on either side with many small brisles, all pointing forward, and two very large pikes or horns, which rose from the top of the head, just over each eye, and pointed forward also. It had two pretty large black eyes on either side of the head E E, from one of which I could see a very bright reflection of the window, which made me gheſs, that the *Cornea* of it was smooth, like those of bigger Insects. Its motion was pretty quick and strong, it being able very easily to tumble a stone or clod four times as big as its whole body.

At the same time and place, and divers times since, I have observed with my *Microscope*, another little Insect, which, though I have not annexed the picture of, may be worth noting, for its exceeding nimbleness as well as smalness; it was as small as a Mite, with a body deep and ridged, almost like a Flea; it had eight blood-red legs, not very long, but slender; and two horns or feelers before. Its motion was so exceeding quick, that I have often lost sight of one I have observed with my naked eye; and though, when it was not frighted, I was able to follow the motions of some with my *Microscope*; yet if it vvere never so little startled, it posted avvay vvith such speed, and turn'd and vvinded it self so quick, that I should presently lose sight of it.

When I first observ'd the former of these Insects, or Mites, I began to conjecture, that certainly I had found out the vagabond Parents of those Mites we find in Cheeses, Meal, Corn, Seeds, musty Barrels, musty Leather, *&c.* these little Creatures, vvandring to and fro every vvhither, might perhaps, as they vvere invited hither and thither by the musty steams of several putrifying bodies, make their invasions upon those new and pleasing territories, and there spending the remainder of their life, which might be perhaps a day, or thereabouts, in very plentiful and riotous living, might leave their off-spring behind them, which by the change of the soil and Country they now inhabite, might be quite alter'd from the hew of their *primogenitors*, and, like *Mores* translated into Northern *European* Climates, after a little time, change both their skin and shape. And this seems yet more probable in these Insects, because that the soil or body they inhabit, seems to be almost half their parent, for it not only hatches and brings those little eggs, or seminal principles, to perfection, but seems to augment and nourish them also before they are hatch'd or shaped; for it is obvious enough to be observ'd, that the eggs of many other Insects, and particularly of Mites, are increas'd in bulk after they are laid out of the bodies of the Insects, and plump'd sometimes into many times their former bigness, so that the bodies they are laid in being, as it were, half their mothers, we shall not wonder that it should have such an active power to change their forms. We find by relations,

relations how much the *Negro* Women do besmeer the of-spring of the *Spaniard*, bringing forth neither white-skinn'd nor black, but tâwny hided *Mulattos*.

Now, though I propound this as probable, I have not yet been so farr certify'd by Observations as to conclude any thing, either positively or negatively, concerning it. Perhaps, some more lucky diligence may please the curious Inquirer with the discovery of this, to be a truth, which I now conjecture, and may thereby give him a satisfactory account of the cause of those creatures, whose original seems yet so obscure, and may give him cause to believe, that many other animate beings, that seem also to be the mere product of putrifaction, may be innobled with a Pedigree as ancient as the first creation, and farr exceed the greatest beings in their numerous Genealogies. But on the other side, if it should be found that these, or any other animate body, have no immediate similar Parent, I have in another place set down a conjectural *Hypothesis* whereby those *Phænomena* may likely enough be solv'd, wherein the infinite wisdom and providence of the Creator is no less rare and wonderfull.

Observ. LI. *Of the* Crab-like *Insect.*

READing one day in *Septemb.* I chanced to observe a very smal creature creep over the Book I was reading, very slowly; having a *Microscope* by me, I observ'd it to be a creature of a very unusual form, and that not less notable; such as is describ'd in the second *Figure* of the 33. *Scheme.* It was about the bigness of a large Mite, or somewhat longer, it had ten legs, eight of which, A A A A, were topt with very sharp claws, and were those upon which he walk'd, seeming shap'd much like those of a Crab, which in many other things also this little creature resembled; for the two other claws, B B, which were the formost of all the ten, and seem'd to grow out of his head, like the horns of other Animals, were exactly form'd in the manner of Crabs or Lobsters claws, for they were shap'd and jointed much like those represened in the *Scheme*, and the ends of them were furnish'd with a pair of claws or pincers, C C, which this little animal did open and shut at pleasure: It seem'd to make use of those two horns or claws both for feelers and holders; for in its motion it carried these aloft extended before, moving them to and fro, just as a man blindfolded would do his hands when he is fearfull of running against a wall, and if I put a hair to it, it would readily take hold of it with these claws, and seem to hold it fast. Now, though these horns seem'd to serve him for two uses, namely, for feeling and holding; yet he seem'd neither blind, having two small black spots, D D, which by the make of them, and the bright reflection from them seem'd to be his eyes; nor did it want other hands, having another pair of claws, E E, very neer plac'd to its mouth, and seem'd adjoining to it.

The whole body was cased over with armour-shells, as is usuall in all those

those kinds of *crustaceous* creatures, especially about their bellies, and seem'd of three kinds; the head F seem'd cover'd with a kind of scaly shell, the *thorax* with two smooth shells, or Rings, G G, and the belly with eight knobb'd ones. I could not certainly find whether it had under these last shells any wings, but I suspect the contrary; for I have not found any wing'd Insect with eight leggs, two of those leggs being always converted into wings, and, for the most part, those that have but six, have wings.

This creature, though I could never meet with more then one of them, and so could not make so many examinations of it as otherwise I would, I did notwithstanding, by reason of the great curiosity that appear'd to me in its shape, delineate it, to shew that, in all likelihood, Nature had crouded together into this very minute Insect, as many, and as excellent contrivances, as into the body of a very large Crab, which exceeds it in bulk, perhaps, some Millions of times; for as to all the apparent parts, there is a greater rather then a less multiplicity of parts, each legg has as many parts, and as many joints as a Crabs, nay, and as many hairs or brisles; and the like may be in all the other visible parts; and 'tis very likely, that the internal curiosities are not less excellent: It being a general rule in Nature's proceedings, that where she begins to display any excellency, if the subject be further search'd into, it will manifest, that there is not less curiosity in those parts which our single eye cannot reach, then in those which are more obvious.

Observ. LII. *Of the small Silver-colour'd* Book-worm.

AS among greater Animals there are many that are scaled, both for ornament and defence, so are there not wanting such also among the lesser bodies of Insects, whereof this little creature gives us an Instance. It is a small white Silver-shining Worm or Moth, which I found much conversant among Books and Papers, and is suppos'd to be that which corrodes and eats holes through the leaves and covers; it appears to the naked eye, a small glistering Pearl-colour'd Moth, which upon the removing of Books and Papers in the Summer, is often observ'd very nimbly to scud, and pack away to some lurking cranney, where it may the better protect it self from any appearing dangers. Its head appears bigg and blunt, and its body tapers from it towads the tail, smaller and smaller, being shap'd almost like a Carret.

This the *Microscopical* appearance will more plainly manifest, which exhibits, in the third *Figure* of the 33. *Scheme*, a conical body, divided into fourteen several partitions, being the appearance of so many several shels, or shields that cover the whole body, every of these shells are again cover'd or tiled over with a multitude of thin transparent scales, which, from the multiplicity of their reflecting surfaces, make the whole Animal appear of a perfect Pearl-colour.

Which

Which, by the way, may hint us the reason of that so much admired appearance of those so highly esteem'd bodies, as also of the like in mother of Pearl-shells, and in multitudes of other shelly Sea-substances; for they each of them consisting of an infinite number of very thin shells or laminated orbiculations, cause such multitudes of reflections, that the compositions of them together with the reflections of others that are so thin as to afford colours (of which I elsewhere give the reason) gives a very pleasant reflection of light. And that this is the true cause, seems likely, first, because all those so appearing bodies are compounded of multitudes of plated substances. And next that, by ordering any trasparent substance after this manner, the like *Phænomena* may be produc'd; this will be made very obvious by the blowing of Glass into exceeding thin shells, and then breaking them into scales, which any lamp-worker will presently do; for a good quantity of these scales, laid in a heap together, have much the same resemblance of Pearls. Another way, not less instructive and pleasant, is a way which I have several times done, which is by working and tossing, as 'twere, a parcel of pure crystalline glass whilst it is kept glowing hot in the blown flame of a Lamp, for, by that means, that purely transparent body will be so divided into an infinite number of plates, or small strings, with interpos'd aerial plates and *fibres*, that from the multiplicity of the reflections from each of those internal surfaces, it may be drawn out into curious Pearl-like or Silver wire, which though small, will yet be opacous; the same thing I have done with a composition of red *Colophon* and *Turpentine*, and a little Bee's Wax, and may be done likewise with Birdlime, and such like glutinous and transparent bodies: But to return to our description.

The small blunt head of this Insect was furnish'd on either side of it with a cluster of eyes, each of which seem'd to contain but a very few, in comparison of what I had observ'd the clusters of other Insects to abound with; each of these clusters were beset with a row of small brisles, much like the *cilia* or hairs on the eye-lids, and, perhaps, they serv'd for the same purpose. It had two long horns before, which were streight, and tapering towards the top, curiously ring'd or knobb'd, and brisled much like the Marsh Weed, call'd Horse-tail, or Cats-tail, having at each knot a fring'd Girdle, as I may so call it, of smaller hairs, and several bigger and larger brisles, here and there dispers'd among them: besides these, it had two shorter horns, or feelers, which were knotted and fring'd, just as the former, but wanted brisles, and were blunt at the ends; the hinder part of the creature was terminated with three tails, in every particular resembling the two longer horns that grew out of the head: The leggs of it were scal'd and hair'd much like the rest, but are not express'd in this *Figure*, the Moth being intangled all in Glew, and so the leggs of this appear'd not through the Glass which looked perpendicularly upon the back.

This Animal probably feeds upon the Paper and covers of Books, and perforates in them several small round holes, finding, perhaps, a convenient nourishment in those husks of Hemp and Flax, which have pass'd

 through

through so many scourings, washings, dressings and dryings, as the parts of old Paper must necessarily have suffer'd; the digestive faculty, it seems, of these little creatures being able yet further to work upon those stubborn parts, and reduce them into another form.

And indeed, when I consider what a heap of Saw-dust or chips this little creature (which is one of the teeth of Time) conveys into its intrals. I cannot chuse but remember and admire the excellent contrivance of Nature, in placing in Animals such a fire, as is continually nourished and supply'd by the materials convey'd into the stomach, and *fomented* by the bellows of the lungs; and in so contriving the most admirable fabrick of Animals, as to make the very spending and wasting of that fire, to be instrumental to the procuring and collecting more materials to augment and cherish it self, which indeed seems to be the principal end of all the contrivances observable in bruit Animals.

Observ. LIII. *Of a* Flea.

THe strength and beauty of this small creature, had it no other relation at all to man, would deserve a description.

For its strength, the *Microscope* is able to make no greater discoveries of it then the naked eye, but onely the curious contrivance of its leggs and joints, for the exerting that strength, is very plainly manifested, such as no other creature, I have yet observ'd, has any thing like it; for the joints of it are so adapted, that he can, as 'twere, fold them short one within another, and suddenly stretch, or spring them out to their whole length, that is, of the fore-leggs, the part A, of the 34. *Scheme*, lies within B, and B within C, parallel to, or side by side each other; but the parts of the two next, lie quite contrary, that is, D without E, and E without F, but parallel also; but the parts of the hinder leggs, G, H and I, bend one within another, like the parts of a double jointed Ruler, or like the foot, legg and thigh of a man; these six leggs he clitches up altogether, and when he leaps, springs them all out, and thereby exerts his whole strength at once.

But, as for the beauty of it, the *Microscope* manifests it to be all over adorn'd with a curiously polish'd suit of *sable* Armour, neatly jointed, and beset with multitudes of sharp pinns, shap'd almost like Porcupine's Quills, or bright conical Steel-bodkins; the head is on either side beautify'd with a quick and round black eye K, behind each of which also appears a small cavity, L, in which he seems to move to and fro a certain thin film beset with many small transparent hairs, which probably may be his ears; in the forepart of his head, between the two fore-leggs, he has two small long jointed feelers, or rather smellers, M M, which have four joints, and are hairy, like those of several other creatures; between these, it has a small *proboscis*, or *probe*, N N O, that seems to consist of a tube,


I
K
F
D
E
H
H
D
G
G
A
B
C
D
A

tube N N, and a tongue or ſucker O, which I have perceiv'd him to ſlip in and out. Beſides theſe, it has alſo two chaps or biters P P, which are ſomewhat like thoſe of an Ant, but I could not perceive them tooth'd; theſe were ſhap'd very like the blades of a pair of round top'd Scizers, and were opened and ſhut juſt after the ſame manner; with theſe Inſtruments does this little buſie Creature bite and pierce the ſkin, and ſuck out the blood of an Animal, leaving the ſkin inflamed with a ſmall round red ſpot. Theſe parts are very difficult to be diſcovered, becauſe, for the moſt part, they lye covered between the fore-legs. There are many other particulars, which, being more obvious, and affording no great matter of information, I ſhall paſs by, and refer the Reader to the Figure.

Obſerv. LIV. *Of a Louſe.*

THis is a Creature ſo officious, that 'twill be known to every one at one time or other, ſo buſie, and ſo impudent, that it will be intruding it ſelf in every ones company, and ſo proud and aſpiring withall, that it fears not to trample on the beſt, and affects nothing ſo much as a Crown; feeds and lives very high, and that makes it ſo ſaucy, as to pull any one by the ears that comes in its way, and will never be quiet till it has drawn blood: it is troubled at nothing ſo much as at a man that ſcratches his head, as knowing that man is plotting and contriving ſome miſchief againſt it, and that makes it oftentime ſculk into ſome meaner and lower place, and run behind a mans back, though it go very much againſt the hair; which ill conditions of it having made it better known then truſted, would exempt me from making any further deſcription of it, did not my faithful *Mercury*, my *Microſcope*, bring me other information of it. For this has diſcovered to me, by means of a very bright light caſt on it, that it is a Creature of a very odd ſhape; it has a head ſhap'd like that expreſt in 35. *Scheme* marked with A, which ſeems almoſt Conical, but is a little flatted on the upper and under ſides, at the biggeſt part of which, on either ſide behind the head (as it were, being the place where other Creatures ears ſtand) are placed its two black ſhining goggle eyes B B, looking backwards, and fenced round with ſeveral ſmall *cilia* or hairs that incompaſs it, ſo that it ſeems this Creature has no very good foreſight: It does not ſeem to have any eye-lids, and therefore perhaps its eyes were ſo placed, that it might the better cleanſe them with its fore-legs; and perhaps this may be the reaſon, why they ſo much avoid and run from the light behind them, for being made to live in the ſhady and dark receſſes of the hair, and thence probably their eye having a great aperture, the open and clear light, eſpecially that of the Sun, muſt needs very much offend them; to ſecure theſe eyes from receiving any injury from the hairs through which it paſſes, it has

two horns that grow before it, in the place where one would have thought the eyes ſhould be; each of theſe C C hath four joynts, which are fringed, as 'twere, with ſmall briſles, from which to the tip of its ſnout D, the head ſeems very round and tapering, ending in a very ſharp noſe D, which ſeems to have a ſmall hole, and to be the paſſage through which he ſucks the blood. Now whereas if it be plac'd on its back, with its belly upwards, as it is in the 35. *Scheme*, it ſeems in ſeveral Poſitions to have a reſemblance of chaps, or jaws, as is repreſented in the Figure by E E, yet in other poſtures thoſe dark ſtrokes diſappear; and having kept ſeveral of them in a box for two or three dayes, ſo that for all that time they had nothing to feed on, I found, upon letting one creep on my hand, that it immediately fell to ſucking, and did neither ſeem to thruſt its noſe very deep into the ſkin, nor to open any kind of mouth, but I could plainly perceive a ſmall current of blood, which came directly from its ſnout, and paſt into its belly; and about A there ſeem'd a contrivance, ſomewhat reſembling a Pump, pair of Bellows, or Heart, for by a very ſwift *ſyſtole* and *diaſtole* the blood ſeem'd drawn from the noſe, and forced into the body. It did not ſeem at all, though I viewed it a good while as it was ſucking, to thruſt more of its noſe into the ſkin then the very ſnout D, nor did it cauſe the leaſt diſcernable pain, and yet the blood ſeem'd to run through its head very quick and freely, ſo that it ſeems there is no part of the ſkin but the blood is diſpers'd into, nay, even into the *cuticula*; for had it thruſt its whole noſe in from D to C C, it would not have amounted to the ſuppoſed thickneſs of that *tegument*, the length of the noſe being not more then a three hundredth part of an inch. It has ſix legs, covered with a very tranſparent ſhell, and joynted exactly like a Crab's, or Lobſter's; each leg is divided into ſix parts by theſe joynts, and thoſe have here and there ſeveral ſmall hairs; and at the end of each leg it has two claws, very properly adapted for its peculiar uſe, being thereby inabled to walk very ſecurely both on the ſkin and hair; and indeed this contrivance of the feet is very curious, and could not be made more commodiouſly and compendiouſly, for performing both theſe requiſite motions, of walking and climbing up the hair of a mans head, then it is: for, by having the leſſer claw (a) ſet ſo much ſhort of the bigger (b) when it walks on the ſkin the ſhorter touches not, and then the feet are the ſame with thoſe of a Mite, and ſeveral other ſmall Inſects, but by means of the ſmall joynts of the longer claw it can bend it round, and ſo with both claws take hold of a hair, in the manner repreſented in the Figure, the long tranſparent Cylinder F F F, being a Man's hair held by it.

The *Thorax* ſeem'd cas'd with another kind of ſubſtance then the belly, namely, with a thin tranſparent horny ſubſtance, which upon the faſting of the Creature did not grow flaccid; through this I could plainly ſee the blood, ſuck'd from my hand, to be variouſly diſtributed, and mov'd to and fro; and about G there ſeem'd a pretty big white ſubſtance, which ſeem'd to be moved within its *thorax*; beſides, there appear'd very many ſmall milk-white veſſels, which croſt over the breaſt between


D
E
C
C
A
B
B
F
b
a
b
a
b
a
b
F

between the legs, out of which, on either side, were many small branchings, these seem'd to be the veins and arteries, for that which is analogus to blood in all Insects is milk-white.

The belly is covered with a transparent substance likewise, but more resembling a skin then a shell, for 'tis grain'd all over the belly just like the skin in the palms of a man's hand, and when the belly is empty, grows very flaccid and wrinkled; at the upper end of this is placed the stomach H H, and perhaps also the white spot I I may be the liver or *pancreas*, which, by the *peristaltick* motion of the guts, is a little mov'd to and fro, not with a *systole* and *diastole*, but rather with a thronging or justling motion. Viewing one of these Creatures, after it had fasted two dayes, all the hinder part was lank and flaccid, and the white spot I I hardly mov'd, most of the white branchings disappear'd, and most also of the redness or sucked blood in the guts, the *peristaltick* motion of which was scarce discernable; but upon the suffering it to suck, it presently fill'd the skin of the belly, and of the six scolop'd embosments on either side, as full as it could be stuft; the stomach and guts were as full as they could hold; the *peristaltick* motion of the gut grew quick, and the justling motion of I I accordingly; multitudes of milk-white vessels seem'd quickly filled, and turgid, which were perhaps the veins and arteries, and the Creature was so greedy, that though it could not contain more, yet it continued sucking as fast as ever, and as fast emptying it self behind: the digestion of this Creature must needs be very quick, for though I perceiv'd the blood thicker and blacker when suck'd, yet, when in the guts, it was of a very lovely ruby colour, and that part of it, which was digested into the veins, seemed white; whence it appears, that a further digestion of blood may make it milk, at least of a resembling colour: What is else observable in the figure of this Creature, may be seen by the 35. *Scheme*.

Observ. LV. *Of Mites.*

THe least of *Reptiles* I have hitherto met with, is a Mite, a Creature whereof there are some so very small, that the sharpest sight, unassisted with Glasses, is not able to discern them, though, being white of themselves, they move on a black and smooth surface; and the Eggs, out of which these Creatures seem to be hatch'd, are yet smaller, those being usually not above a four or five hundredth part of a well grown Mite, and those well grown Mites not much above one hundredth of an inch in thickness; so that according to this reckoning there may be no less then a million of well grown Mites contain'd in a cubick inch, and five hundred times as many Eggs.

Notwithstanding which minuteness a good *Microscope* discovers those small movable specks to be very prettily shap'd Insects, each of them furnish'd

nish'd with eight well shap'd and proportion'd legs, which are each of them joynted or bendable in eight several places, or joynts, each of which is covered, for the most part, with a very transparent shell, and the lower end of the shell of each joynt is fringed with several small hairs; the contrivance of the joynts seems the very same with that of Crabs and Lobsters legs, and like those also, they are each of them terminated with a very sharp claw or point; four of these legs are so placed, that they seem to draw forwards, the other four are placed in a quite contrary position, thereby to keep the body backwards when there is occasion.

Fig. 1. *Schem.* 36. The body, as in other larger Insects, consists of three regions or parts; the hinder or belly A, seems covered with one intire shell, the middle, or chest, seems divided into two shells B C. which running one within the other, the Mite is able to shrink in and thrust out as it finds occasion, as it can also the snout D. The whole body is pretty transparent, so that being look'd on against the light, divers motions within its body may be perceived; as also all the parts are much more plainly delineable, then in other postures, to the light. The shell, especially that which covers the back, is curiously polisht, so that 'tis easie to see, as in a *convex* Looking-glass, or *foliated* Glass-ball, the picture of all the objects round about; up and down, in several parts of its body, it has several small long white hairs growing out of its shell, which are often longer then the whole body, and are represented too short in the first and second Figures; they seem all pretty straight and plyable, save only two upon the fore-part of its body, which seem to be the horns, as may be seen in the Figures; the first whereof is a prospect of a smaller sort of Mites (which are usually more plump) as it was *passant* to and fro; the second is the prospect of one fixt on its tail (by means of a little mouth-glew rub'd on the object plate) exhibiting the manner of the growing of the legs, together with their several joynts.

This Creature is very much diversify'd in shape, colour, and divers other properties, according to the nature of the substance out of which it seems to be ingendred and nourished, being in one substance more long, in another more round, in some more hairy, in others more smooth, in this nimble, in that slow, here pale and whiter, there browner, blacker, more transparent, *&c.* I have observed it to be resident almost on all kinds of substances that are mouldy, or putrifying, and have seen it very nimbly meshing through the thickets of mould, and sometimes to lye *dormant* underneath them; and 'tis not unlikely, but that it may feed on that vegetating substance, *spontaneous Vegetables* seeming a food proper enough for *spontaneous Animals*,

But whether indeed this Creature, or any other, be such or not, I cannot positively, from any Experiment, or Observation, I have yet made, determine. But, as I formerly hinted, it seems probable, that some kind of wandring Mite may sow, as 'twere, the first seeds, or lay the first eggs, in those places, which Nature has instructed them to know convenient for the hatching and nourishing their young; and though perhaps the prime

Schem XXXVI.





prime Parent might be of a shape very differing from what the off-spring, after a little while, by reason of the substance they feed on, or the Region (as 'twere) they inhabite; yet perhaps even one of these alter'd progeny, wandering again from its native soil, and lighting on by chance the same place from whence its prime Parent came, and there settling, and planting, may produce a generation of Mites of the same shapes and properties with the first wandring Mite: And from some such accidents as these, I am very apt to think, the most sorts of Animals, generally accounted *spontaneous*, have their *origination*, and all those various sorts of Mites, that are to be met with up and down in divers putrifying substances, may perhaps be all of the same kind, and have spring from one and the same sort of Mites at the first.

Observ. LVI. *Of a small Creature hatch'd on a Vine.*

THere is, almost all the Spring and Summer time, a certain small, round, white Cobweb, as 'twere, about the bigness of a Pea, which sticks very close and fast to the stocks of Vines nayl'd against a warm wall: being attentively viewed, they seem cover'd, upon the upper side of them, with a small husk, not unlike the scale, or shell of a Wood-louse, or Hog-louse, a small Insect usually found about rotten wood, which upon touching presently rouls it self into the form of a pepper-corn: Separating several of these from the stock, I found them, with my *Microscope*, to consist of a shell, which now seemed more likely to be the husk of one of these Insects: And the fur seem'd a kind of cobweb, consisting of abundance of small filaments, or sleaves of cobwebs. In the midst of this, if they were not hatch'd, and run away before, the time of which hatching was usually about the latter end of *June*, or beginning of *July*, I have often found abundance of small brown Eggs, such as A and B in the second Figure of the 36. *Scheme*, much about the bigness of Mites Eggs; and at other times, multitudes of small Insects, shaped exactly like that in the third Figure marked with X. Its head large, almost half the bigness of its body, which is usual in the *fœtus* of most Creatures. It had two small black eyes *a a*, and two small long joynted and brisled horns *b b*. The hinder part of its body seem'd to consist of nine scales, and the last ended in a forked tayl, much like that of a *Cutio*, or Wood-louse, out of which grew two long hairs; they ran to and fro very swiftly, and were much of the bigness of a common Mite, but some of them less: The longest of them seem'd not the hundredth part of an inch, and the Eggs usually not above half as much. They seemed to have six legs, which were not visible in this I have here delineated, by reason they were drawn under its body.

If these Minute creatures were *Wood-lice* (as indeed from their own shape and frame, the skin, or shell, that grows on them, one may with great probability

bability gheſs) it affords us an Inſtance, whereof perhaps there are not many like in Nature, and that is, of the prodigious increaſe of theſe Creatures, after they are hatch'd and run about; for a common Wood-louſe, of about half an inch long, is no leſs then a hundred and twenty five thouſand times bigger then one of theſe, which though indeed it ſeems very ſtrange, yet I have obſerved the young ones of ſome Spiders have almoſt kept the ſame proportion to their Dam.

This, methinks, if it be ſo, does in the next place hint a Quæry, which may perhaps deſerve a little further examination: And that is, Whether there be not many of thoſe minute Creatures, ſuch as Mites, and the like, which, though they are commonly thought of otherwiſe, are only the *pully*, or young ones, of much bigger Inſects, and not the generating, or parent Inſect, that has layd thoſe Eggs; for having many times obſerv'd thoſe Eggs, which uſually are found in great abundance where Mites are found, it ſeems ſomething ſtrange, that ſo ſmall an Animal ſhould have an Egg ſo big in proportion to its body. Though on the other ſide, I muſt confeſs, that having kept divers of thoſe Mites incloſed in a box for a good while, I did not find them very much augmented beyond their uſual bigneſs.

What the husk and cobweb of this little white ſubſtance ſhould be, I cannot imagine, unleſs it be, that the old one, when impregnated with Eggs, ſhould there ſtay, and fix it ſelf on the Vine, and dye, and all the body by degrees ſhould rot, ſave only the husk, and the Eggs in the body: And the heat, or fire, as it were, of the approaching Sun-beams ſhould vivifie thoſe Relicts of the corrupted Parent, and out of the aſhes, as 'twere, (as it is fabled of the *Phœnix*) ſhould raiſe a new offſpring for the perpetuation of the *ſpecies*. Nor will the cobweb, as it were, in which theſe Eggs are inclos'd, make much againſt this Conjecture; for we may, by thoſe cobwebs that are carried up and down the Air after a Fog (which with my *Microſcope* I have diſcovered to be made up of an infinite company of ſmall filaments or threads) learn, that ſuch a texture of body may be otherwiſe made then by the ſpinning of a Worm.

Obſerv. LVII. *Of the* Eels *in Vinegar.*

OF theſe ſmall Eels, which are to be found in divers ſorts of Vinegar, I have little to add beſides their Picture, which you may find drawn in the third Figure of the 25. *Scheme*: That is, they were ſhaped much like an Eel, ſave only that their noſe A, (which was a little more opacous then the reſt of their body) was a little ſharper, and longer, in proportion to their body, and the wrigling motion of their body ſeem'd to be onely upwards and downwards, whereas that of Eels is onely ſide wayes: They ſeem'd to have a more opacous part about

about B, which might, perhaps, be their Gills; it seeming always the same proportionate distant from their nose, from which, to the tip of their tail, C, their body seem'd to taper.

Taking several of these out of their Pond of Vinegar, by the net of a small piece of filtring Paper, and laying them on a black smooth Glass plate, I found that they could wriggle and winde their body, as much almost as a Snake, which made me doubt, whether they were a kind of Eal or Leech.

I shall add no other observations made on this minute Animal, being prevented herein by many excellent ones already publish'd by the ingenious, Doctor *Power*, among his *Microscopical* Observations, save onely that a quantity of Vinegar repleat with them being included in a small Viol, and stop'd very close from the ambient air, all the included Worms in a very short time died, as if they had been stifled.

And that their motion seems (contrary to what we may observe in the motion of all other Insects) exceeding slow. But the reason of it seems plain, for being to move to and fro after that manner which they do, by waving onely, or wrigling their body; the tenacity, or glutinousness, and the density or resistance of the fluid *medium* becomes so exceeding sensible to their extremely minute bodies, that it is to me indeed a greater wonder that they move them so fast as they do, then that they move them no faster. For what a vastly greater proportion have they of their superficies to their bulk, then Eels or other larger Fishes, and next, the tenacity and density of the liquor being much the same to be moved, both by the one and the other, the resistance or impediment thence arising to the motions made through it, must be almost infinitely greater to the small one then to the great. This we find experimentally verify'd in the Air, which though a *medium* a thousand times more rarify'd then the water, the resistance of it to motions made through it, is yet so sensible to very minute bodies, that a Down-feather (the least of whose parts seem yet bigger then these Eels, and many of them almost incomparably bigger, such as the quill and stalk) is suspended by it, and carried to and fro as if it had no weight.

Observ. LVIII. *Of a new Property in the* Air, *and several other transparent* Mediums *nam'd* Inflection, *whereby very many considerable* Phænomena *are attempted to be solv'd, and divers other uses are hinted.*

Since the Invention (and perfecting in some measure) of *Telescopes*, it has been observ'd by several, that the Sun and Moon neer the Horizon, are disfigur'd (losing that exactly-smooth terminating circular limb, which they are observ'd to have when situated neerer the Zenith) and are bounded with an edge every way (especially upon the right and left

 sides)

ſides) ragged and indented like a Saw: which inequality of their limbs, I have further obſerv'd, not to remain always the ſame, but to be continually chang'd by a kind of fluctuating motion, not unlike that of the waves of the Sea; ſo as that part of the limb, which was but even now nick'd or indented in, is now protuberant, and will preſently be ſinking again; neither is this all, but the whole body of the Luminaries, do in the *Teleſcope*, ſeem to be depreſs'd and flatted, the upper, and more eſpecially the under ſide appearing neerer to the middle then really they are, and the right and left appearing more remote: whence the whole *Area* ſeems to be terminated by a kind of Oval. It is further obſerv'd, that the body, for the moſt part, appears red, or of ſome colour approaching neer unto it, as ſome kind of yellow; and this I have always mark'd, that the more the limb is flatted or ovalled, the more red does the body appear, though not always the contrary. It is further obſervable, that both fix'd Stars and Planets, the neerer they appear to the Horizon, the more red and dull they look, and the more they are obſerv'd to twinkle; *in ſo much*, that I have ſeen the Dog-ſtarr to vibrate ſo ſtrong and bright a radiation of light, as almoſt to dazle my eyes, and preſently, almoſt to diſappear. It is alſo obſervable, that thoſe bright ſcintillations neer the Horizon, are not by much ſo quick and ſudden in their conſecutions of one another, as the nimbler twinklings of Stars neerer the Zenith. This is alſo notable, that the Starrs neer the Horizon, are twinkled with ſeveral colours; ſo as ſometimes to appear red, ſometimes more yellow, and ſometimes blue, and this when the Starr is a pretty way elevated above the Horizon. I have further, very often ſeen ſome of the ſmall Starrs of the fifth or ſixth magnitude, at certain times to diſappear for a ſmall moment of time, and again appear more conſpicuous, and with a greater luſter. I have ſeveral times, with my naked eye, ſeen many ſmaller Starrs, ſuch as may be call'd of the ſeventh or eighth magnitude to appear for a ſhort ſpace, and then vaniſh, which, by directing a ſmall *Teleſcope* towards that part they appear'd and diſappeard in; I could preſently find to be indeed ſmall Starrs ſo ſituate, as I had ſeen them with my naked eye, and to appear twinkling like the ordinary viſible Stars; nay, in examining ſome very notable parts of the Heaven, with a three foot Tube, me thought I now and then, in ſeveral parts of the conſtellation, could perceive little twinklings of Starrs, making a very ſhort kind of apparition, and preſently vaniſhing, but noting diligently the places where they thus ſeem'd to play at boe-peep, I made uſe of a very good twelve foot Tube, and with that it was not uneaſie to ſee thoſe, and ſeveral other degrees of ſmaller Starrs, and ſome ſmaller yet, that ſeem'd again to appear and diſappear, and theſe alſo by giving the ſame Object-glaſs a much bigger aperture, I could plainly and conſtantly ſee appear in their former places; ſo that I have obſerv'd ſome twelve ſeveral magnitudes of Starrs leſs then thoſe of the ſix magnitudes commonly recounted in the Globes.

It has been obſerv'd and confirm'd by the accurateſt Obſervations of the beſt of our modern Aſtronomers, that all the Luminous bodies appear above the Horizon, when they really are below it. So that the

Sun

Sun and Moon have both been seen above the Horizon, whilst the Moon has been in an Eclipse. I shall not here instance in the great refractions, that the tops of high mountains, seen at a distance, have been found to have; all which seem to argue the Horizontal refraction, much greater then it is hitherto generally believ'd.

I have further taken notice, that not onely the Sun, Moon and Starrs, and high tops of mountains have suffer'd these kinds of refraction, but Trees, and several bright Objects on the ground: I have often taken notice of the twinkling of the reflections of the Sun from a Glass-window at a good distance, and of a Candle in the night, but that is not so conspicuous, and in observing the setting Sun, I have often taken notice of the tremulation of the Trees and Bushes, as well as of the edges of the Sun. Divers of these *Phænomena* have been taken notice of by several, who have given several reasons of them, but I have not yet met with any altogether satisfactory, though some of their conjectures have been partly true, but parly also false. Setting my self therfore upon the inquiry of these *Phænomena*, I first endeavour'd to be very diligent in taking notice of the several particulars and circumstances observable in them; and next, in making divers particular Experiments, that might cleer some doubts, and serve to determine, confirm, and illustrate the true and adæquate cause of each; and upon the whole, I find much reason to think, that the true cause of all these *Phænomena* is from the *inflection*, or *multiplicate refraction* of those Rays of light within the body of the *Atmosphere*, and that it does not proceed from a *refraction* caus'd by any terminating *superficies* of the Air above, nor from any such exactly defin'd *superficies* within the body of the *Atmosphere*.

This Conclusion is grounded upon these two Propositions:

First, that a *medium*, whose parts are unequally *dense*, and mov'd by various motions and transpositions as to one another, will produce all these visible effects upon the Rays of light, without any other *coefficient* cause.

Secondly, that there is in the Air or *Atmosphere*, such a variety in the constituent parts of it, both as to their *density* and *rarity*, and as to their divers mutations and positions one to another.

By *Density* and *Rarity*, I understand a property of a transparent body, that does either more or less refract a Ray of light (coming obliquely upon its superficies out of a third *medium*) toward its perpendicular: As I call Glass a more dense body then Water, and Water a more rare body then Glass, because of the refractions (more or less deflecting towards the perpendicular) that are made in them, of a Ray of light out of the Air that has the same inclination upon either of their superficies.

So as to the business of Refraction, spirit of Wine is a more *dense* body then Water, it having been found by an accurate Instrument that measures the angles of Refractions to Minutes that for the same refracted angle of 30°: 00' in both those *Mediums*, the angle of incidence in Water was but 41°. 3'5. but the angle of the incidence in the trial with spirit of Wine was 42°: 45'. But as to gravity, Water is a more *dense* body then

ſpirit of Wine, for the proportion of the ſame Water, to the ſame very well rectify'd ſpirit of Wine was, as 21. to 19.

So as to Refraction, Water is more Denſe then Ice; for I have found by a moſt certain Experiment, which I exhibited before divers illuſtrious Perſons of the *Royal Society*, that the Refraction of Water was greater then that of Ice, though ſome conſiderable Authors have affirm'd the contrary, and though the Ice be a very hard, and the Water a very fluid body.

That the former of the two preceding Propoſitions is true, may be manifeſted by ſeveral Experiments: As firſt, if you take any two liquors differing from one another in denſity, but yet ſuch as will readily mix: as Salt Water, or Brine, & Freſh; almoſt any kind of Salt diſſolv'd in Water, and filtrated, ſo that it be cleer, ſpirit of Wine and Water; nay, ſpirit of Wine, and ſpirit of Wine, one more highly rectify'd then the other, and very many other liquors; if (I ſay) you take any two of theſe liquors, and mixing them in a Glaſs Viol, againſt one ſide of which you have fix'd or glued a ſmall round piece of Paper, and ſhaking them well together (ſo that the parts of them may be ſomewhat diſturb'd and move up and down) you endeavour to ſee that round piece of Paper through the body of the liquors; you ſhall plainly perceive the Figure to wave, and to be indented much after the ſame manner as the limb of the Sun through a *Teleſcope* ſeems to be, ſave onely that the mutations here, are much quicker. And if, in ſteed of this bigger Circle, you take a very ſmall ſpot, and faſten and view it as the former, you will find it to appear much like the twinkling of the Starrs, though much quicker: which two *Phænomena* (for I ſhall take notice of no more at preſent, though I could inſtance in multitudes of others) muſt neceſſarily be caus'd by an *inflection* of the Rays within the terminating ſuperficies of the compounded *medium*, ſince the ſurfaces of the tranſparent body through which the Rays paſs to the eye, are not at all altered or chang'd.

This *inflection* (if I may ſo call it) I imagine to be nothing elſe, but a *multiplicate refraction*, cauſed by the unequal *denſity* of the conſtituent parts of the *medium*, whereby the motion, action or progreſs of the Ray of light is hindred from proceeding in a ſtreight line, and *inflected* or *deflected* by a *curve*. Now, that it is a *curve* line is manifeſt by this Experiment: I took a Box, ſuch as A D G E, in the firſt *Figure* of the 37. *Scheme*, whoſe ſides A B C D, and E F G H, were made of two ſmooth flat plates of Glaſs, then filling it half full with a very ſtrong ſolution of Salt, I filled the other half with very fair freſh water, then expoſing the opacous ſide, D H G C, to the Sun, I obſerv'd both the *refraction* and *inflection* of the Sun beams, I D & K H, and marking as exactly as I could, the points, P, N, O, M, by which the Ray, K H, paſſed through the compounded *medium*, I found them to be in a *curve* line; for the parts of the *medium* being continually more denſe the neerer they were to the bottom, the Ray *p f* was continually more and more deflected downwards from the ſtreight line.

This Inflection may be mechanically explained, either by Monſieur

Des

Des Cartes principles, by conceiving the Globuls of the third Element to find less and less resistance against that side of them which is downwards, or by a way, which I have further explicated in the Inquisition about Colours, to be from an obliquation of the pulse of light, whence the ruder part is continually promoted, and consequently refracted towards the perpendicular, which cuts the Orbs at right angles. What the particular Figure of the *Curve line*, describ'd by this way of light, is, I shall not now stand to examine, especially since there may be so many sorts of it as there may be varieties of the Positions of the *intermediat* degrees of *density* and *rarity* between the bottom and the top of the inflecting Medium.

I could produce many more Examples and Experiments, to illustrate and prove this first Proposition, *viz.* that there is such a constitution of some bodies as will cause inflection. As not to mention those I have observ'd in *Horn*, *Tortoise-shell*, *transparent Gums*, and *resinous Substances*: The *veins* of Glass, nay, of melted *Crystal*, found, and much complained of by Glass-grinders, and others, might sufficiently demonstrate the truth of it to any diligent Observator.

But that, I presume, I have by this Example given proof sufficient (*viz. ocular demonstration*) to evince, that there is such a modulation, or bending of the rayes of light, as I have call'd *inflection*, differing both from *reflection*, and *refraction* (since they are both made in the superficies, this only in the middle); and likewise, that this is able or sufficient to produce the effects I have ascribed to it.

It remains therefore to shew, that there is such a property in the Air, and that it is sufficient to produce all the above mentioned *Phænomena*, and therefore may be the principal, if not the only cause of them.

First, That there is such a property, may be proved from this, that the parts of the Air are some of them more condens'd, others more rarified, either by the differing heat, or differing pressure it sustains, or by the somewhat heterogeneous vapours interspers'd through it. For as the Air is more or less rarified, so does it more or less refract a ray of light (that comes out of a denser medium) from the perpendicular. This you may find true, if you make tryal of this Experiment.

Take a small Glass-bubble, made in the form of that in the second Figure of the 37. *Scheme*, and by heating the Glass very hot, and thereby very much rarifying the included Air, or, which is better, by rarifying a small quantity of water, included in it, into vapours, which will expel the most part, if not all the Air, and then sealing up the small neck of it, and letting it cool, you may find, if you place it in a convenient Instrument, that there will be a manifest difference, as to the refraction.

As if in this second Figure you suppose A to represent a small sight or hole, through which the eye looks upon an object, as C, through the Glass-bubble B, and the second sight L; all which remain exactly fixt in their several places, the object C being so cized and placed, that it may just seem to touch the upper and under edge of the hole L: and so all of it be seen through the small Glass-ball of rarified Air; then by breaking

breaking off the ſmall ſeal'd neck of the Bubble (without at all ſtirring the ſights, object, or glaſs) and admitting the external Air, you will find your ſelf unable to ſee the utmoſt ends of the object; but the terminating rayes A E and A D (which were before refracted to G and F by the rarified Air) will proceed almoſt directly to I and H; which alteration of the rayes (ſeeing there is no other alteration made in the Organ by which the Experiment is tryed, ſave only the admiſſion, or excluſion of the condens'd Air) muſt neceſſarily be cauſed by the variation of the *medium* contain'd in the Glaſs B; the greateſt difficulty in the making of which Experiment, is from the uneven ſurfaces of the bubble, which will repreſent an uneven image of the object.

Now, that there is ſuch a difference of the upper and under parts of the Air, is clear enough evinc'd from the late improvement of the *Torricellian* Experiment, which has been tryed at the tops and feet of Mountains; and may be further illuſtrated, and inquired into, by a means, which ſome whiles ſince I thought of, and us'd, for the finding by what degrees the Air paſſes from ſuch a degree of Denſity to ſuch a degree of Rarity. And another, for the finding what preſſure was requiſite to make it paſs from ſuch a degree of Rarefaction to a determinate Denſity: Which Experiments, becauſe they may be uſeful to illuſtrate the preſent Inquiry, I ſhall briefly deſcribe.

Fig. 3. I took then a ſmall Glaſs-pipe A B, about the bigneſs of a Swans quill, and about four foot long, which was very equally drawn, ſo that, as far as I could perceive, no one part was bigger then another: This Tube (being open at both ends) I fitted into another ſmall Tube D E, that had a ſmall bore juſt big enough to contain the ſmall Pipe, and this was ſeal'd up at one, and open at the other, end; about which open end I faſtned a ſmall wooden box C with cement, ſo that filling the bigger Tube, and part of the box, with Quickſilver, I could thruſt the ſmaller Tube into it, till it were all covered with the Quickſilver: Having thus done, I faſtned my bigger Tube againſt the ſide of a wall, that it might ſtand the ſteadier, and plunging the ſmall Tube cleer under the *Mercury* in the box, I ſtopt the upper end of it very faſt with cement, then lifting up the ſmall Tube, I drew it up by a ſmall pully, and a ſtring that I had faſtned to the top of the Room, and found the height of the *Mercurial Cylinder* to be about twenty nine inches.

Then letting down the Tube again, I opened the top, and then thruſt down the ſmall Tube, till I perceived the Quickſilver to riſe within it to a mark that I had plac'd juſt an inch from the top; and immediately clapping on a ſmall peice of cement that I had kept warm, I with a hot Iron ſeal'd up the top very faſt, then letting it cool (that both the cement might grow hard, and more eſpecially, that the Air might come to its temper, natural for the Day I try'd the Experiment in) I obſerv'd diligently, and found the included Air to be exactly an Inch.

Here you are to take notice, that after the Air is ſeal'd up, the top of the Tube is not to be elevated above the ſuperficies of the Quickſilver in

in the box, till the surface of that within the Tube be equal to it, for the Quicksilver (as I have elsewhere prov'd) being more heterogeneous to the Glass then the Air, will not naturally rise up so high within the small Pipe, as the superficies of the *Mercury* in the box; and therefore you are to observe, how much below the outward superficies of the *Mercury* in the box, that of the same in the Tube does stand, when the top being open, free ingress is admitted to the outward Air.

Having thus done, I permitted the *Cylinder*, or small Pipe, to rise out of the box, till I found the surface of the Quicksilver in the Pipe to be two inches above that in the box, and found the Air to have expanded it self but one sixteenth part of an inch; then drawing up the small pipe, till I found the height of the Quicksilver within to be four inches above that without, I observed the Air to be expanded only $\frac{1}{7}$ of an inch more then it was at first, and to take up the room of $1\frac{1}{7}$ inch; then I raised the Tube till the Cylinder was six inches high, and found the Air to take up $1\frac{2}{9}$ inches of room in the Pipe; then to 8, 10, 12. *&c.* the expansion of the Air that I found to each of which Cylinders are set down in the following Table; where the first row signifies the height of the *Mercurial Cylinder*; the next, the expansion of the Air; the third, the pressure of the *Atmosphere*, or the highest *Cylinder* of *Mercury*, which was then neer thirty inches; The last signifies the force of the Air so expanded, which is found by substracting the first row of numbers out of the third; for having found, that the outward Air would then keep up the Quicksilver to thirty inches, look whatever of that height is wanting must be attributed to the Elater of the Air depressing. And therefore having the Expansion in the second row, and the height of the subjacent *Cylinder* of *Mercury* in the first, and the greatest height of the *Cylinder* of *Mercury*, which of it self counterballances the whole pressure of the *Atmosphere*; by substracting the numbers of the first row out of the numbers of the third, you will have the measure of the *Cylinders* so depreſt, and consequently the force of the Air, in the several Expansions, registred.

The

The height of the Cylinder of *Mercury*, that, together with the Elater of the included Air, ballanced the pressure of the Atmosphere.	The Expansion of the Air.	The height of the *Mercury* that counterballanc'd the Atmosphere	The strength of the Elater of the expanded Air.
00	01	30	30
02	$01\frac{1}{16}$	30	28
04	$01\frac{1}{7}$	30	26
06	$01\frac{2}{9}$	30	24
08	$01\frac{1}{3}$	30	22
10	$01\frac{1}{12}$	30	20
12	$01\frac{2}{3}$	30	18
14	$01\frac{5}{6}$	30	16
16	$02\frac{2}{27}$	30	14
18	$02\frac{4}{9}$	30	12
20	03	30	10
22	$03\frac{7}{9}$	30	8
24	$05\frac{7}{18}$	30	6
25	$06\frac{2}{3}$	30	5
26	$08\frac{1}{2}$	30	4
$26\frac{1}{4}$	$09\frac{1}{2}$	30	$3\frac{3}{4}$
$26\frac{1}{2}$	$10\frac{3}{4}$	30	$3\frac{1}{2}$
$26\frac{3}{4}$	13	30	$3\frac{1}{4}$
27	$15\frac{1}{2}$	30	3

I had

I had several other Tables of my Observations, and Calculations, which I then made; but it being above a twelve month since I made them; and by that means having forgot many circumstances and particulars, I was resolved to make them over once again, which I did *August* the second 1661. with the very same Tube which I used the year before, when I first made the Experiment (for it being a very good one, I had carefully preserv'd it:) And after having tryed it over and over again; and being not well satisfied of some particulars, I, at last, having put all things in very good order, and being as attentive, and observant, as possibly I could, of every circumstance requisite to be taken notice of, did register my several Observations in this following Table. In the making of which, I did not exactly follow the method that I had used at first; but, having lately heard of Mr. *Townly's Hypothesis*, I shap'd my course in such sort, as would be most convenient for the examination of that *Hypothesis*; the event of which you have in the latter part of the last Table.

The other Experiment was, to find what degrees of force were requisite to compress, or condense, the Air into such or such a bulk.

The manner of proceeding therein was this: I took a Tube about five foot long, one of whose ends was sealed up, and bended in the form of a *Syphon*, much like that represented in the fourth Figure of the 37. *Scheme*, one side whereof A D, that was open at A, was about fifty inches long, the other side B C, shut at B, was not much above seven inches long; then placing it exactly perpendicular, I pour'd in a little Quicksilver, and found that the Air B C was $6\frac{3}{8}$ inches, or very near to seven; then pouring in Quicksilver at the longer Tube, I continued filling of it till the Air in the shorter part of it was contracted into half the former dimensions, and found the height exactly nine and twenty inches; and by making several other tryals, in several other degrees of condensation of the Air, I found them exactly answer the former *Hypothesis*.

But having (by reason it was a good while since I first made) forgotten many particulars, and being much unsatisfied in others, I made the Experiment over again, and, from the several tryals, collected the former part of the following Table: Where in the row next the left hand 24. signifies the dimensions of the Air, sustaining only the pressure of the *Atmosphere*, which at that time was equal to a *Cylinder* of *Mercury* of nine and twenty inches: The next Figure above it (20) was the dimensions of the Air induring the first compression, made by a *Cylinder* of *Mercury* $5\frac{1}{16}$ high, to which the pressure of the *Atmosphere* nine and twenty inches being added, the elastick strength of the Air so compress'd will be found $34\frac{1}{16}$, *&c.*

A Table of the Elastick power of the Air, both Experimentally and Hypothetically calculated, according to its various Dimensions.

The dimensions of the included Air.	The height of the *Mercurial Cylinder* counterpois'd by the *Atmosphere*.	The *Mercurial Cylinder* added, or taken from the former.	The sum or difference of these two *Cylinders*.	What they ought to be according to the *Hypothesis*.
12	29 +	29 =	58	58
13	29 +	$24\frac{11}{6}$ =	$53\frac{11}{16}$	$53\frac{7}{13}$
14	29 +	$20\frac{3}{16}$ =	$49\frac{3}{16}$	$49\frac{5}{7}$
16	29 +	14 =	43	$43\frac{1}{2}$
18	29 +	$9\frac{1}{8}$ =	$38\frac{1}{8}$	$38\frac{2}{3}$
20	29 +	$5\frac{3}{16}$ =	$34\frac{3}{16}$	$34\frac{4}{5}$
24	29	0 =	29	29
48	29 —	$14\frac{5}{8}$ =	$14\frac{3}{8}$	$14\frac{1}{2}$
96	29 —	$22\frac{1}{8}$ =	$6\frac{7}{8}$	$7\frac{2}{3}$
192	20 —	$25\frac{5}{8}$ =	$3\frac{3}{8}$	$3\frac{5}{8}$
384	29 —	$27\frac{2}{8}$ =	$1\frac{6}{8}$	$1\frac{7}{16}$
576	29 —	$27\frac{7}{8}$ =	$1\frac{1}{8}$	$1\frac{5}{24}$
768	29 —	$28\frac{1}{8}$ =	$0\frac{7}{8}$	$0\frac{74}{8}$
960	29 —	$28\frac{1}{8}$ =	$0\frac{5}{8}$	$0\frac{52}{8}$
1152	29 —	$28\frac{7}{16}$ =	$0\frac{9}{16}$	$0\frac{10}{16}$

From

From which Experiments, I think, we may safely conclude, that the Elater of the Air is reciprocal to its extension, or at least very neer. So that to apply it to our present purpose (which was indeed the chief cause of inventing these wayes of tryal) we will suppose a *Cylinder* indefinitely extended upwards, [I say a *Cylinder*, not a piece of a *Cone*, because, as I may elsewhere shew in the Explication of Gravity, that *triplicate* proportion of the shels of a Sphere, to their respective diameters, I suppose to be removed in this case by the decrease of the power of Gravity] and the pressure of the Air at the bottom of this *Cylinder* to be strong enough to keep up a *Cylinder* of *Mercury* of thirty inches: Now because by the most accurate tryals of the most illustrious and incomparable Mr. *Boyle*, published in his deservedly famous Pneumatick Book, the weight of Quicksilver, to that of the Air here below, is found neer about as fourteen thousand to one: If we suppose the parts of the *Cylinder* of the *Atmosphere* to be every where of an equal density, we shall (as he there deduces) find it extended to the height of thirty five thousand feet, or seven miles: But because by these Experiments we have somewhat confirm'd the hypothesis of the reciprocal proportion of the Elaters to the Extensions we shall find, that by supposing this *Cylinder* of the *Atmosphere* divided into a thousand parts, each of which being equivalent to thirty five feet, or seven geometrical paces, that is, each of these divisions containing as much Air as is suppos'd in a *Cylinder* neer the earth of equal diameter, and thirty five foot high, we shall find the lowermost to press against the surface of the Earth with the whole weight of the above mentioned thousand parts; the pressure of the bottom of the second against the top of the first to be $1000 - 1 = 999$. of the third against the second to be $1000 - 2 = 998$. of the fourth against the third to be $1000 - 3 = 997$. of the uppermost against the 999. or that next below it, to be $1000 - 999 = 1$. so that the extension of the lowermost next the Earth, will be to the extension of the next below the uppermost, as 1. to 999. for as the pressure sustained by the 999. is to the pressure sustain'd by the first, so is the extension of the first to the extension of the 999. so that, from this hypothetical calculation, we shall find the Air to be indefinitely extended: For if we suppose the whole thickness of the Air to be divided, as I just now instanced, into a thousand parts, and each of those under differing Dimensions, or Altitudes, to contain an equall quantity of Air, we shall find, that the first *Cylinder*, whose Base is supposed to lean on the Earth, will be found to be extended $35\frac{35}{999}$ foot; the second equal Division, of *Cylinder*, whose *basis* is supposed to lean on the top of the first, shall have its top extended higher by $35\frac{70}{998}$; the third $35\frac{105}{997}$; the fourth $35\frac{140}{996}$; and so onward, each equal quantity of Air having its dimensions measured by 35. and some additional number exprest alwayes in the manner of a fraction, whose numerator is alway the number of the place multipli'd by 35. and whose denominator is alwayes the pressure of the *Atmosphere* sustain'd by that part, so that by this means we may easily calculate the height of 999. divisions of those 1000. divisions, I suppos'd; whereas the uppermost

may extend it self more then as high again, nay, perhaps indefinitely, or beyond the Moon; for the Elaters and Expansions being in reciprocal proportions, since we cannot yet find the *plus ultra*, beyond which the Air will not expand it self, we cannot determine the height of the Air; for since, as we have shewn, the proportion will be alway as the pressure sustain'd by any part is to 35. so 1000. to the expansion of that part; the multiplication or product therefore of the pressure, and expansion, that is, of the two extream proportionals, being alwayes equal to the product of the means, or 35000. it follows, since that Rectangle or Product may be made up of the multiplication of infinite diversities of numbers, that the height of the Air is also indefinite; for since (as far as I have yet been able to try) the Air seems capable of an indefinite Expansion, the pressure may be decreased in *infinitum*, and consequently its expansion upwards indefinite also.

There being therefore such a difference of density, and no Experiment yet known to prove a *Saltus*, or skipping from one degree of rarity to another much differing from it, that is, that an upper part of the Air should so much differ from that immediately *subjacent* to it, as to make a distinct superficies, such as we observe between the Air and Water, &c. But it being more likely, that there is a continual increase of rarity in the parts of the Air, the further they are removed from the surface of the Earth: It will hence necessarily follow, that (as in the Experiment of the salt and fresh Water) the ray of Light passing obliquely through the Air also, which is of very different density, will be continually, and infinitely inflected, or bended, from a streight, or direct motion.

This granted, the reason of all the above recited *Phænomena*, concerning the appearance of the Celestial Bodies, will very easily be deduced. As,

First, The redness of the Sun, Moon, and Stars, will be found to be caused by the inflection of the rays within the *Atmosphere*. That it is not really in or near the luminous bodies, will, I suppose, be very easily granted, seeing that this redness is observable in several places differing in Longitude, to be at the same time different, the setting and rising Sun of all parts being for the most part red:

And secondly, That it is not meerly the colour of the Air interpos'd, will, I suppose, without much more difficulty be yielded, seeing that we may observe a very great *interstitium* of Air betwixt the Object and the Eye, makes it appear of a dead blew, far enough differing from a red, or yellow.

But thirdly, That it proceeds from the refraction, or inflection, of the rays by the *Atmosphere*, this following Experiment will, I suppose, sufficiently manifest.

Take a sphærical Crystalline Viol, such as is describ'd in the fifth Figure A B C D, and, having fill'd it with pure clear Water, expose it to the Sun beams; then taking a piece of very fine *Venice* Paper, apply it against that side of the Globe that is opposite to the Sun, as against the side

side B C, and you shall perceive a bright red Ring to appear, caus'd by the refraction of the Rays, A A A A, which is made by the Globe; in which Experiment, if the Glass and Water be very cleer, so that there be no Sands nor bubbles in the Glass, nor dirt in the Water, you shall not perceive any appearance of any other colour. To apply which Experiment, we may imagine the *Atmosphere* to be a great transparent Globe, which being of a substance more dense then the other, or (which comes to the same) that has its parts more dense towards the middle, the Sun beams that are tangents, or next within the tangents of this Globe, will be refracted or inflected from their direct passage towards the center of the Globe, whence, according to the laws of refractions made in a triangular *Prism*, and the generation of colour set down in the description of Muscovi-glass, there must necessarily appear a red colour in the *transitus* or passage of those tangent Rays. To make this more plain, we will suppose (in the sixth *Figure*) A B C D, to represent the Globe of the *Atmosphere*, E F G H to represent the opacous Globe of the Earth, lying in the midst of it, neer to which, the parts of the Air, sustaining a very great pressure, are thereby very much condens'd, from whence those Rays that are by inflection made tangents to the Globe of the Earth, and those without them, that pass through the more condens'd part of the *Atmosphere*, as suppose between A and E, are by reason of the inequality of the *medium*, inflected towards the center, whereby there must necessarily be generated a red colour, as is more plainly shewn in the former cited place; hence whatsoever opacous bodies (as vapours, or the like) shall chance to be elevated into those parts, will reflect a red towards the eye; and therefore those evenings and mornings appear reddest, that have the most store of vapours and halituous substances exhaled to a convenient distance from the Earth; for thereby the inflection is made the greater, and thereby the colour also the more intense; and several of those exhalations being opacous, reflect several of those Rays, which, through an *Homogeneous* transparent *medium* would pass unseen; and therefore we see, that when there chances to be any clouds situated in those Regions they reflect a strong and vivid red. Now, though one great cause of the redness may be this inflection, yet I cannot wholly exclude the colour of the vapours themselves, which may have something of redness in them, they being partly nitrous, and partly suliginous; both which steams tinge the Rays that pass through them, as is made evident by looking at bodies through the fumes of *Aqua fortis*, or spirit of *Nitre* [as the newly mentioned Illustrious Person has demonstrated] and also through the smoak of a Fire or Chimney.

Having therefore made it probable at least, that the morning and evening redness may partly proceed from this inflection or refraction of the Rays, we shall next shew, how the Oval Figure will be likewise easily deduced.

Suppose we therefore, E F G H in the sixth *Figure* of the 37. *Scheme*, to represent the Earth; A B C D, the *Atmospere*; E I, and E L, two Rays coming from the Sun, the one from the upper, the other from the neather

Limb,

Limb, these Rays, being by the *Atmosphere* inflected, appear to the eye at E, as if they had come from the points, N and O; and because the Ray L has a greater inclination upon the inequality of the *Atmosphere* then I, therefore must it suffer a greater inflection, and consequently be further elevated above its true place, then the Ray I, which has a less inclination, will be elevated above its true place; whence it will follow, that the lower side appearing neerer the upper then really it is, and the two *lateral* sides, *viz.* the right and left side, suffering no sensible alteration from the inflection, at least what it does suffer, does rather increase the visible Diameter then diminish it, as I shall shew by and by, the Figure of the luminous body must necessarily appear somewhat *Elliptical.*

This will be more plain, if in the seventh *Figure* of th 37. *Scheme* we suppose A B to represent the sensible Horizon; C D E F, the body of the Sun really below it; G H I K, the same appearing above it, elevated by the inflection of the *Atmosphere*: For if, according to the best observation, we make the visible Diameter of the Sun to be about three or four and thirty minutes, and the Horizontal refraction according to *Ticho* be thereabout, or somewhat more, the lower limb of the Sun E, will be elevated to I; but because, by his account, the point C will be elevated but 29. minutes, as having not so great an inclination upon the inequality of the Air, therefore I G, which will be the apparent refracted perpendicular Diameter of the Sun, will be less then C G, which is but 29. minutes, and consequently six or seven minutes shorter then the unrefracted apparent Diameter. The parts, D and F, will be likewise elevated to H and K, whose refraction, by reason of its inclination, will be bigger then that of the point C, though less then that of E; therefore will the semidiameter I L, be shorter then L G, and consequently the under side of the appearing Sun more flat then the upper.

Now, because the Rays from the right and left sides of the Sun, *&c.* have been observ'd by *Ricciolo* and *Grimaldus*, to appear more distant one from another then really they are, though (by very many Observations that I have made for that purpose, with a very good *Telescope*, fitted with a divided Ruler) I could never perceive any great alteration, yet there being really some, it will not be amiss, to shew that this also proceeds from the refraction or inflection of the *Atmosphere*; and this will be manifest, if we consider the *Atmosphere* as a transparent Globe, or at least a transparent shell, encompassing an opacous Globe, which, being more dense then the *medium* encompassing it, refracts or inflects all the entring parallel Rays into a point or focus, so that wheresoever the Observator is plac'd within the *Atmosphere*, between the focus and the luminous body, the *lateral* Rays must necessarily be more converg'd towards his eye by the refraction or inflection, then they would have been without it; and therefore the Horizontal Diameter of the luminous body must necessarily be augmented.

This might be more plainly manifest to the eye by the sixth *Figure*; but because it would be somwhat tedious, and the thing being obvious enough

enough to be imagin'd by any one that attentively considers it, I shall rather omit it, and proceed to shew, that the mass of Air neer the surface of the Earth, consists, or is made up, of parcels, which do very much differ from one another in point of density and rarity; and consequently the Rays of light that pass through them will be variously inflected, here one way, and there another, according as they pass so or so through those differing parts; and those parts being always in motion, either upwards or downwards, or to the right or left, or in some way compounded of these, they do by this their motion inflect the Rays, now this way, and presently that way.

This irregular, unequal and unconstant inflection of the Rays of light, is the reason why the limb of the *Sun*, *Moon*, *Jupiter*, *Saturn*, *Mars*, and *Venus*, appear to wave or dance; and why the body of the Starrs appear to tremulate or twinkle, their bodies, by this means, being sometimes magnify'd, and sometimes diminished; sometimes elevated, otherwhiles depress'd; now thrown to the right hand, and then to the left.

And that there is such a property or unequal distribution of parts, is manifest from the various degrees of heat and cold that are found in the Air; from whence will follow a differing density and rarity, both as to quantity and refraction; and likewise from the vapours that are interpos'd, (which, by the way, I imagine, as to refraction or inflection, to do the same thing, as if they were rarify'd Air; and that those vapours that ascend, are both lighter, and less dense, then the ambient Air which boys them up; and that those which descend, are heavier and more dense) The first of these may be found true, if you take a good thick piece of Glass, and heating it pretty hot in the fire, lay it upon such another piece of Glass, or hang it in the open Air by a piece of Wire, then looking upon some far distant Object (such as a Steeple or Tree) so as the Rays from that Object pass directly over the Glass before they enter your eye, you shall find such a tremulation and wavering of the remote Object, as will very much offend your eye: The like tremulous motion you may observe to be caus'd by the ascending steams of Water, and the like. Now, from the first of these it is manifest, that from the rarifaction of the parts of the Air, by heat, there is caus'd a differing refraction, and from the ascension of the more rarify'd parts of the Air, which are thrust up by the colder, and therefore more condens'd and heavie, is caus'd an undulation or wavering of the Object; for I think, that there are very few will grant, that Glass, by as gentle a heat as may be endur'd by ones hand, should send forth any of its parts in steams or vapours, which does not seem to be much wasted by that violent fire of the green Glass-house; but, if yet it be doubted, let Experiment be further made with that body that is accounted, by Chymists and others, the most ponderous and fix'd in the world; for by heating of a piece of Gold, and proceeding in the same manner, you may find the same effects.

This trembling and shaking of the Rays, is more sensibly caus'd by an actual flame, or quick fire, or any thing else heated glowing hot; as by a Candle, live Coal, red-hot Iron, or a piece of Silver, and the like: the same also appears very conspicuous, if you look at an Object betwixt which

which and your eye, the rising smoak of some Chimney is interpos'd; which brings into my mind what I had once the opportunity to observe, which was, the Sun rising to my eye just over a Chimney that sent forth a copious steam of smoak; and taking a short *Telescope*, which I had then by me, I observ'd the body of the Sun, though it was but just peep'd above the Horizon, to have its underside, not onely flatted, and press'd inward, as it usually is when neer the Earth; but to appear more protuberant downwards then if it had suffered no refraction at all; and besides all this, the whole body of the Sun appear'd to tremble or dance, and the edges or limb to be very ragged or indented, undulating or waving, much in the manner of a flag in the Wind.

This I have likewise often observ'd in a hot Sunshiny Summer's day, that looking on an Object over a hot stone, or dry hot earth, I have found the Object to be undulated or shaken, much after the same manner. And if you look upon any remote Object through a *Telescope* (in a hot Summer's day especially) you shall find it likewise to appear tremulous. And further, if there chance to blow any wind, or that the air between you and the Object be in a motion or current, whereby the parts of it, both rarify'd and condens'd, are swiftly remov'd towards the right or left, if then you observe the Horizontal ridge of a Hill far distant, through a very good *Telescope*, you shall find it to wave much like the Sea, and those waves will appear to pass the same way with the wind.

From which, and many other Experiments, 'tis cleer that the lower Region of the Air, especially that part of it which lieth neerest to the Earth, has, for the most part, its constituent parcels variously agitated, either by heat or winds, by the first of which, some of them are made more rare, and so suffer a less refraction; others are interwoven, either with ascending or descending vapours; the former of which being more light, and so more rarify'd, have likewise a less refraction; the latter being more heavie, and consequently more dense, have a greater.

Now, because that heat and cold are equally diffus'd every way; and that the further it is spread, the weaker it grows; hence it will follow, that the most part of the under Region of the Air will be made up of several kinds of *lentes*, some whereof will have the properties of *Convex*; others of *Concave glasses*; which, that I may the more intelligibly make out, we will suppose in the eighth *Figure* of the 37. *Scheme*, that A represents an ascending vapour, which, by reason of its being somewhat *Heterogeneous* to the ambient Air, is thereby thrust into a kind of Globular form, not any where terminated, but gradually finished, that is, it is most rarify'd in the middle about A, somewhat more condens'd about B B, more then that about C C; yet further, about D D, almost of the same density with the ambient Air about E E; and lastly, inclosed with the more dense Air F F, so that from A, to F F, there is a continual increase of density. The reason of which will be manifest, if we consider the rising vapour to be much warmer then the ambient heavie Air; for by the coldness of the ambient Air, the shell E E will be more refrigerated then D D, and that then C C, which will be yet more then B B, and that more

more then A; so that from F to A, there is a continual increase of heat, and consequently of rarity; from whence it will necessarily follow, that the Rays of light will be inflected or refracted in it, in the same manner as they would be in a *Concave-glase*; for the Rays *GKI*, *G K I* will be inflected by *G K H*, *G K H*, which will easily follow from what I before explained concerning the inflection of the *Atmosphere*.

On the other side, a descending vapour, or any part of the air included by an ascending vapour, will exhibit the same effects with a *Convex lens*; for, if we suppose, in the former Figure, the quite contrary constitution to that last describ'd; that is, the ambient Air F F being hotter then any part of that matter within any circle, therefore the coldest part must necessarily be A, as being fartheſt remov'd from the heat, all the intermediate spaces will be gradually discriminated by the continuall mixture of heat and cold, so that it will be hotter at E E, then D D, in D D then C C, in C C then B B, and in B B then A. From which, a like refraction and condensation will follow; and consequently a lesser or greater refraction, so that every included part will refract more then the including, by which means the Rays, G K I, G K I, coming from a Starr, or some remote Object, are so inflected, that they will again concurr and meet, in the point M. By the interposition therefore of this descending vapour the visible body of the Star, or other Object, is very much augmented, as by the former it was diminished.

From the quick consecutions of these two, one after another, between the Object and your eye, caused by their motion upwards or downwards, proceeding from their levity or gravity, or to the right or left, proceeding from the wind, a Starr may appear, now bigger, now less, then really it would otherwise without them; and this is that property of a Starr, which is commonly call'd twinkling, or scintillation.

The reason why a Star will now appear of one colour, now of another, which for the most part happens when 'tis neer the Horizon, may very easily be deduc'd from its appearing now in the middle of the vapour, other whiles neer the edge; for if you look against the body of a Starr with a *Telescope* that has a pretty deep *Convex* Eye-glass, and so order it, that the Star may appear sometimes in one place, and sometimes in another of it; you may perceive this or that particular colour to be predominant in the apparent Figure of the Starr, according as it is more or less remote from the middle of the *Lens*. This I had here further explain'd, but that it does more properly belong to another place.

I shall therefore onely add some few Quæries, which the consideration of these particulars hinted, and so finish this Section.

And the first I shall propound is, Whether there may not be made an artificial transparent body of an exact Globular Figure that shall so inflect or refract all the Rays, that, coming from one point, fall upon any *Hemisphere* of it; that every one of them may meet on the opposite side, and cross one another exactly in a point; and that it may do the like also with all the Rays that, coming from a *lateral* point, fall upon any other *Hemisphere*; for if so, there were to be hoped a perfection of *Dioptricks*;

 and

and a transmigration into heaven, even whil'st we remain here upon earth in the flesh, and a descending or penetrating into the center and innermost recesses of the earth, and all earthly bodies; nay, it would open not onely a cranney, but a large window (as I may so speak) into the Shop of Nature, whereby we might be enabled to see both the tools and operators, and the very manner of the operation it self of Nature; this, could it be effected, would as farr surpass all other kind of perspectives as the vast extent of Heaven does the small point of the Earth, which distance it would immediately remove, and unite them, as 'twere, into one, at least, that there should appear no more distance between them then the length of the Tube, into the ends of which these Glasses should be inserted: Now, whether this may not be effected with parcels of Glass of several densities, I have sometimes proceeded so farr as to doubt (though in truth, as to the general, I have wholly despair'd of it) for I have often observ'd in Optical Glasses a very great variety of the parts, which are commonly called Veins; nay, some of them round enough (for they are for the most part, drawn out into strings) to constitute a kind of *lens*.

This I should further proceed to ope, had any one been so inquisitive as to have found out the way of making any transparent body, either more dense or more rare; for then it might be possible to compose a Globule that should be more dense in the middle of it, then in any other part, and to compose the whole bulk, so as that there should be a continual gradual transition from one degree of density to another; such as should be found requisite for the desired inflection of the *transmigrating* Rays; but of this enough at present, because I may say more of it when I set down my own Trials concerning the melioration of *Dioptricks*, where I shall enumerate with how many several substances I have made both *Microscopes*, and *Telescopes*, and by what and how many, ways: Let such as have leisure and opportunity farther consider it.

The next Quæry shall be, whether by the same collection of a more dense body then the other, or at least, of the denser part of the other, there might not be imagin'd a reason of the apparition of some new fix'd Stars, as those in the Swan, *Cassiope's Charr*, *Serpentarius*, *Piscis*, *Cetus*, &c.

Thirdly, Whether it be possible to define the height of the *Atmosphere* from this inflection of the Rays, or from the Quicksilver Experiment of the rarifaction or extension of the Air.

Fourthly, Whether the disparity between the upper and under Air be not sometimes so great, as to make a reflecting superficies; I have had several Observations which seem to have proceeded from some such cause, but it would be too long to relate and examine them. An Experiment, also somewhat analogous to this, I have made with Salt-water and Fresh, which two liquors, in most Positions, seem'd the same, and not to be separated by any determinate superficies, which separating surface yet in some other Positions did plainly appear.

And if so, Whether the reason of the equal bounding or *terminus* of the under parts of the clouds may not proceed from this cause; whether, secondly,

secondly, the Reason of the apparition of many Suns may not be found out, by considering how the Rays of the Sun may so be reflected, as to describe a pretty true Image of the body, as we find them from any regular Superficies. Whether also this may not be found to cause the apparition of some of those *Parelii*, or counterfeit Suns, which appear coloured, by refracting the Rays so, as to make the body of the Sun appear in quite another place then really it is. But of this more elsewhere.

5. Whether the *Phænomena* of the Clouds may not be made out by this diversity of density in the upper and under parts of the Air, by supposing the Air above them to be much lighter then they themselves are, and they themselves to be yet lighter then that which is subjacent to them, many of them seeming to be the same substance with the Cobwebs that fly in the Air after a Fog.

Now that such a constitution of the Air and Clouds, if such there be, may be sufficient to perform this effect, may be confirm'd by this Experiment.

Make as strong a Solution of Salt as you are able; then filling a Glass of some depth half full with it, fill the other half with fresh Water, and poyse a little Glass-bubble, so as that it may sink pretty quick in fresh Water, which take and put into the aforesaid Glass, and you shall find it to sink till it comes towards the middle, where it will remain fixt, without moving either upwards or downwards. And by a second Experiment, of poising such a bubble in water, whose upper part is warmer, and consequently lighter, then the under, which is colder and heavier; the manner of which follows in this next Quærry, which is,

6. Whether the rarifaction and condensation of Water be not made after the same manner, as those effects are produc'd in the Air by heat; for I once pois'd a seal'd up Glass-bubble so exactly, that never so small an addition would make it sink, and as small a detraction make it swim, which suffering to rest in that Vessel of Water for some time, I always found it about noon to be at the bottom of the Water, and at night, and in the morning, at the top: Imagining this to proceed from the Rarifaction of the Water, caus'd by the heat, I made tryal, and found most true; for I was able at any time, either to depress, or raise it, by heat and cold; for if I let the Pipe stand for some time in cold water, I could easily raise the Bubble from the bottom, whither I had a little afore detruded it, by putting the same Pipe into warm Water. And this way I have been able, for a very considerable time, to keep a Bubble so poys'd in the Water, as that it should remain in the middle, and neither sink, nor swim: For gently heating the upper part of the Pipe with a Candle, Coal, or hot Iron, till I perceived the Bubble begin to descend, then forbearing, I have observed it to descend to such or such a station, and there to remain suspended for some hours, till the heat by degrees were quite vanished, when it would again ascend to its former place. This I have also often observed naturally performed by the heat of the Air, which being able to rarifie the upper parts of the Water sooner then the lower, by reason of its immediate contact, the heat of the Air

has sometimes so slowly increased, that I have observed the Bubble to be some hours in passing between the top and bottom.

7. Whether the appearance of the *Pike* of *Tenerif*, and several other high Mountains, at so much greater a distance then seems to agree with their respective heights, be not to be attributed to the *Curvature* of the visual Ray, that is made by its passing obliquely through so differingly *Dense* a Medium from the top to the eye very far distant in the Horizon: For since we have already, I hope, made it very probable, that there is such an *inflection* of the Rays by the differing density of the parts of the Air; and since I have found, by several Experiments made on places comparatively not very high, and have yet found the pressure sustain'd by those parts of the Air at the top and bottom, and also their differing Expansions very considerable: Insomuch that I have found the pressure of the *Atmosphere* lighter at the top of St. *Paul*'s Steeple in *London*, (which is about two hundred foot high) then at the bottom by a sixtieth or fiftieth part, and the expansion at the top greater then that at the bottom by neer about so much also; for the *Mercurial Cylinder* at the bottom was about 39. inches, and at the top half an inch lower; the Air also included in the Weather-glass, that at the bottom fill'd only 155. spaces, at the top fill'd 158. though the heat at the top and bottom was found exactly the same with a seal'd *Thermometer*: I think it very rational to suppose, that the greatest Curvature of the Rays is made nearest the Earth, and that the inflection of the Rays, above 3. or 4. miles upwards, is very inconsiderable, and therefore that by this means such calculations of the height of Mountains, as are made from the distance they are visible in the Horizon, from the supposal that that Ray is a straight Line (that from the top of the Mountain is, as twere, a Tangent to the Horizon whence it is seen) which really is a *Curve*, is very erroneous. Whence, I suppose, proceeds the reason of the exceedingly differing Opinions and Assertions of several Authors, about the height of several very high Hills.

8. Whether this Inflection of the Air will not very much alter the supposed distances of the Planets, which seem to have a very great dependence upon the Hypothetical refraction or inflection of the Air, and that refraction upon the hypothetical height and density of the Air: For since (as I hope) I have here shewn the Air to be quite otherwise then has been hitherto suppos'd, by manifesting it to be, both of a vast, at least an uncertain, height, and of an unconstant and irregular density; It must necessarily follow, that its inflection must be varied accordingly: And therefore we may hence learn, upon what sure grounds all the Astronomers hitherto have built, who have calculated the distance of the Planets from their Horizontal *Parallax*; for since the Refraction and *Parallax* are so nearly ally'd, that the one cannot be known without the other, especially by any wayes that have been yet attempted, how uncertain must the *Parallax* be, when the Refraction is unknown? And how easie is it for Astronomers to assign what distance they please to the Planets, and defend them, when they have such a curious *subterfuge* as that of Refraction, wherein a very little variation will allow them liberty enough to place the Celestial Bodies at what distance they please.

If

If therefore we would come to any certainty in this point, we must go other wayes to work; and as I have here examined the height and refractive property of the Air by other wayes then are usual, so must we find the Parallax of the Planets by wayes not yet practised; and to this end, I cannot imagine any better way, then the Observations of them by two persons at very far distant parts of the Earth, that lye as neer as may be under the same Meridian, or Degree of longitude, but differing as much in latitude, as there can be places conveniently found: These two persons, at certain appointed times, should (as near as could be) both at the same time, observe the way of the *Moon*, *Mars*, *Venus*, *Jupiter*, and *Saturn*, amongst the fixt Stars, with a good large *Telescope*, and making little Iconismes, or pictures, of the small fixed Stars, that appear to each of them to lye in or near the way of the Center of the Planet, and the exact measure of the apparent Diameter; from the comparing of such Observations together, we might certainly know the true distance, or Parallax, of the Planet. And having any one true Parallax of these Planets, we might very easily have the other by their apparent Diameters, which the *Telescope* likewise affords us very accurately. And thence their motions might be much better known, and their Theories more exactly regulated. And for this purpose I know not any one place more convenient for such an Observation to be made in, then in the Island of St. *Helena*, upon the Coast of *Africk*, which lyes about sixteen degrees to the Southwards of the Line, and is very near, according to the latest Geographical Maps, in the same Meridian with *London*; for though they may not perhaps lye exactly in the same, yet their Observations, being ordered according to what I shall anon shew, it will not be difficult to find the true distance of the Planet. But were they both under the same Meridian, it would be much better.

And because Observations may be much easier, and more accurately made with good *Telescopes*; then with any other Instruments, it will not, I suppose, seem impertinent to explain a little what wayes I judge most fit and convenient for that particular. Such therefore as shall be the Observators for this purpose, should be furnished with the best *Telescopes* that can be had, the longer the better, and more exact will their Observations be, though they are somewhat the more difficultly manag'd. These should be fitted with a *Rete*, or divided Scale, plac'd at such a distance within the Eye-glass, that they may be distinctly seen, which should be the measures of minutes and seconds; by this Instrument each Observator should, at certain prefixt times, observe the Moon, or other Planet, in, or very near, the Meridian; and because it may be very difficult to find two convenient stations that will happen to be just under the same Meridian, they shall, each of them, observe the way of the Planet, both for an hour before, and an hour after, it arrive at the Meridian; and by a line, or stroke, amongst the small fixed Stars, they shall denote out the way that each of them observ'd the Center of the Planet to be mov'd in for those two hours: These Observations each of them shall repeat for many dayes together, that both it may happen, that both of them

them may sometimes make their Observations together, and that from divers Experiments we may be the better assured of what certainty and exactness such kind of Observations are like to prove. And because many of the Stars which may happen to come within the compass of such an *Iconism*, or Map, may be such as are only visible through a good *Telescope*, whose Positions perhaps have not been noted, nor their longitudes, or latitudes, any where remarked; therefore each Observator should indeavour to insert some fixt Star, whose longitude, and latitude, is known; or with his *Telescope* he shall find the Position of some notable *Telescopical* Star, inserted in his Map, to some known fixt Star, whose place in the *Zodiack* is well defin'd.

Having by this means found the true distance of the Moon, and having observed well the *apparent Diameter* of it at that time with a good *Telescope*, it is easie enough, by one single Observation of the apparent Diameter of the Moon with a good Glass, to determine her distances in any other part of her *Orbit*, or *Dragon*, and consequently, some few Observations will tell us, whether she be mov'd in an *Ellipsis*, (which, by the way, may also be found, even now, though I think we are yet ignorant of her true distance) and next (which without such Observations, I think, we shall not be sure of) we may know exactly the bigness of that *Ellipsis*, or Circle, and her true velocity in each part, and thereby be much the better inabled to find out the true cause of all her Motions. And though, even now also, we may, by such Observations in one station, as here at *London*, observe the *apparent Diameter* and motion of the Moon in her *Dragon*, and consequently be inabled to make a better ghess at the *Species* or kind of Curve, in which she is mov'd, that is, whether it be sphærical, or *elliptical*, or neither, and with what proportional velocities she is carried in that Curve; yet till her true *Parallax* be known, we cannot determine either.

Next, for the true distance of the Sun, the best way will be, by accurate Observations, made in both these forementioned stations, of some convenient Eclipse of the Sun, many of which may so happen, as to be seen by both; for the *Penumbra* of the Moon may, if she be sixty Semidiameters distant from the Earth, and the Sun above seven thousand, extend to about seventy degrees on the Earth, and consequently be seen by Observators as far distant as *London*, and St. *Helena*, which are not full sixty nine degrees distant. And this would much more accurately, then any way that has been yet used, determine the Parallax, and distance, of the Sun; for as for the Horizontal Parallax I have already shewn it sufficiently uncertain; nor is the way of finding it by the Eclipse of the Moon any other then hypothetical; and that by the difference of the true and apparent quadrature of the Moon is less not uncertain, witness their Deductions from it, who have made use of it; for *Vendelinus* puts that difference to be but 4′. 30″. whence he deduces a vast distance of the Sun, as I have before shewn. *Riccioli* makes it full 30′. 00″. but *Reinoldus*, and *Kircher*, no less then three degrees. And no wonder, for if we examine the *Theory*, we shall find it so complicated with uncertainties.

First,

First, From the irregular surface of the Moon, and from several Parallaxes, that unless the *Dichotomy* happen in the *Nonagesimus* of the *Ecliptick*, and that in the Meridian, *&c.* all which happen so very seldom, that it is almost impossible to make them otherwise then uncertainly. Besides, we are not yet certain, but that there may be somewhat about the Moon *analogus* to the Air about the Earth, which may cause a refraction of the light of the Sun, and consequently make a great difference in the apparent *dichotomy* of the Moon. Their way indeed is very rational and ingenious; and such as is much to be preferr'd before the way by the Horizontal Parallax, could all the uncertainties be remov'd, and were the true distance of the Moon known.

But because we find by the Experiments of *Vendiline*, *Reinoldus*, &c. that Observations of this kind are very uncertain also: It were to be wisht, that such kind of Observations, made at two very distant stations, were promoted. And it is so much the more desirable, because, from what I have now shewn of the nature of the Air, it is evident, that the refraction may be very much greater then all the Astronomers hitherto have imagined it: And consequently, that the distance of the Moon, and other Planets, may be much lesse then what they have hitherto made it.

For first, this Inflection, I have here propounded, will allow the shadow of the Earth to be much shorter then it can be made by the other *Hypothesis* of refraction, and consequently, the Moon will not suffer an Eclipse, unless it comes very much nearer the Earth then the Astronomers hitherto have supposed it.

Secondly, There will not in this *Hypothesis* be any other shadow of the Earth, such as *Kepler* supposes, and calls the *Penumbra*, which is the shadow of the refracting *Atmosphere*; for the bending of the Rays being altogether caus'd by *Inflection*, as I have already shewn, all that part which is ascribed by *Kepler*, and others after him, to the *Penumbra*, or dark part, which is without the *umbra terræ*, does clear vanish; for in this *Hypothesis* there is no refracting surface of the Air, and consequently there can be no shadows, such as appear in the ninth Figure of the 37. *Scheme*, where let A B C D represent the Earth, and E F G H the *Atmosphere*, which according to *Keplers* supposition, is like a Sphære of Water terminated with an exact surface E F G H, let the lines M F, L B, I D, K H, represent the Rays of the Sun; 'tis manifest, that all the Rayes between L B, and I D, will be reflected by the surface of the Earth B A D, and consequently, the conical space B O D would be dark and obscure; but, say the followers of *Kepler*, the Rays between M F, and L B, and between I D, and K H, falling on the *Atmosphere*, are refracted, both at their ingress and egress out of the *Atmosphere*, nearer towards the Axis of the spærical shadow C O, and consequently, inlighten a great part of that former dark Cone, and shorten, and contract, its top to N. And because of this Reflection of these Rays, say they, there is superinduc'd another shell of a dark Cone F P H, whose Apex P is yet further distant from the Earth: By this *Penumbra*, say they, the Moon

is

is Eclipsed, for it alwayes passes between the lines 1 2, and 3 4.

To which I say, That if the Air be such, as I have newly shewn it to be, and consequently cause such an inflection of the Rays that fall into it, those dark *Penumbra's* F Y Z Q, H X V T, and O R P S, will all vanish. For if we suppose the Air indefinitely extended, and to be no where bounded with a determinate refracting surface, as I have shewn it uncapable of having, from the nature of it; it will follow, that the Moon will no where be totally obscured, but when it is below the Apex N, of the dark blunt Cone of the Earth's shadow: Now, from the supposition, that the Sun is distant about seven thousand Diameters, the point N, according to calculation, being not above twenty five terrestrial Semidiameters from the Center of the Earth: It follows, that whensoever the Moon eclipsed is totally darkned, without affording any kind of light, it must be within twenty five Semidiameters of the Earth, and consequently much lower then any Astronomers have hitherto put it.

This will seem much more consonant to the rest of the secundary Planets; for the highest of *Jupiter's* Moons is between twenty and thirty *Jovial Semidiameters* distant from the Center of *Jupiter*; and the Moons of *Saturn* much about the same number of *Saturnial Semidiameters* from the Center of that Planet.

But these are but conjectures also, and must be determin'd by such kind of Observations as I have newly mention'd.

Nor will it be difficult, by this *Hypothesis*, to salve all the appearances of Eclipses of the Moon, for in this *Hypothesis* also, there will be, on each side of the shadow of the Earth, a *Penumbra*, not caus'd by the Refraction of the Air, as in the *Hypothesis* of *Kepler*; but by the faint inlightning of it by the Sun: For if, in the sixth Figure, we suppose E S Q, and G S R, to be the Rays that terminate the shadow from either side of the Earth; E S Q coming from the upper limb of the Sun, and G S R from the under; it will follow, that the shadow of the Earth, within those Rays, that is, the Cone G S E, will be totally dark. But the Sun being not a point, but a large *area* of light, there will be a secondary dark Cone of shadow E P G, which will be caus'd by the earth's hindring part of the Rays of the Sun from falling on the parts G P R, and E P Q. of which halved shadow, or *Penumbra*, that part will appear brightest which lyes neareſt the terminating Rayes G P, and E P, and those darker that lye neareſt to G S, and E S: when therefore the Moon appears quite dark in the middle of the Eclipse, she must be below S, that is, between S and F; when she appears lighter near the middle of the Eclipse, she must pass some where between R Q and S; and when she is alike light through the whole Eclypse, she must pass between R Q, and P.

Observ.

Obſerv. LIX. *Of multitudes of ſmall* Stars *diſcoverable by the* Teleſcope.

HAving, in the laſt Obſervation, premis'd ſome particulars obſervable in the *medium*, through which we muſt look upon *Cœleſtial* Objects, I ſhall here add one Obſervation of the Bodies themſelves; and for a *ſpecimen* I have made choice of the *Pleiades*, or ſeven Stars, commonly ſo called (though in our time and Climate there appear no more then ſix to the naked eye) and this I did the rather, becauſe the deſervedly famous *Galileo*, having publiſht a Picture of this *Aſteriſme*, was able, it ſeems, with his Glaſs to diſcover no more then thirty ſix, whereas with a pretty good twelve foot *Teleſcope*, by which I drew this 38 *Iconiſm*, I could very plainly diſcover ſeventy eight, placed in the order they are ranged in the Figure, and of as many differing Magnitudes as the *Aſterisks*, wherewith they are Marked, do ſpecifie; there being no leſs then fourteen ſeveral Magnitudes of thoſe Stars, which are compris'd within the draught, the biggeſt whereof is not accounted greater then one of the third Magnitude; and indeed that account is much too big, if it be compared with other Stars of the third Magnitude, eſpecially by the help of a *Teleſcope*; for then by it may be perceiv'd, that its ſplendor, to the naked eye, may be ſomewhat augmented by the three little Stars immediately above it, which are near adjoyning to it. The *Teleſcope* alſo diſcovers a great variety, even in the bigneſs of thoſe, commonly reckon'd, of the firſt, ſecond, third, fourth, fifth, and ſixth Magnitude; ſo that ſhould they be diſtinguiſh'd thereby, thoſe ſix Magnitudes would, at leaſt, afford no leſs then thrice that number of Magnitudes, plainly enough diſtinguiſhable by their Magnitude, and brightneſs; ſo that a good twelve foot Glaſs would afford us no leſs then twenty five ſeveral Magnitudes. Nor are theſe all, but a longer Glaſs does yet further, both more nicely diſtinguiſh the Magnitudes of thoſe already noted, and alſo diſcover ſeveral other of ſmaller Magnitudes, not diſcernable by the twelve foot Glaſs: Thus have I been able, with a good thirty ſix foot Glaſs, to diſcover many more Stars in the *Pleiades* then are here delineated, and thoſe of three or four diſtinct Magnitudes leſs then any of thoſe ſpots of the fourteenth Magnitude. And by the twinkling of divers other places of this *Aſteriſme*, when the Sky was very clear, I am apt to think, that with longer Glaſſes, or ſuch as would bear a bigger *aperture*, there might be diſcovered multitudes of other ſmall Stars, yet inconſpicuous. And indeed, for the diſcovery of ſmall Stars, the bigger the *aperture* be, the better adapted is the Glaſs; for though perhaps it does make the ſeveral ſpecks more radiant, and glaring, yet by that means, uniting more Rays very near to one point, it does make many of thoſe radiant points conſpi-

 cuous,

cuous, which, by putting on a less *aperture*, may be found to vanish; and therefore, both for the discovery of the fixt Star, and for finding the *Satellites* of *Jupiter*, before it be out of the day, or twilight, I alwayes leave the Object-glass as clear without any *aperture* as I can, and have thereby been able to discover the *Satellites* a long while before; I was able to discern them, when the smaller *apertures* were put on; and at other times, to see multitudes of other smaller Stars, which a smaller *aperture* makes to disappear.

In that notable *Asterism* also of the Sword of *Orion*, where the ingenious Monsieur *Hugens van Zulichem* has discovered only three little Stars in a cluster, I have with a thirty six foot Glass, without any *aperture* (the breadth of the Glass being about some three inches and a half) discover'd five, and the twinkling of divers others up and down in divers parts of that small milky Cloud.

So that 'tis not unlikely, but that the meliorating of *Telescopes* will afford as great a variety of new Discoveries in the Heavens, as better *Microscopes* would among small terrestrial Bodies, and both would give us infinite cause, more and more to admire the omnipotence of the Creator.

Observ. LX. *Of the* Moon.

HAving a pretty large corner of the Plate for the ~~seven~~ Starrs, void, for the filling it up, I have added one small *Specimen* of the appearance of the parts of the Moon, by describing a small spot of it, which, though taken notice of, both by the Excellent *Hevelius*, and called *Mons Olympus* (though I think somewhat improperly, being rather a vale) and represented by the Figure X, of the 38. *Scheme*, and also by the Learn'd *Ricciolus*, who calls it *Hipparchus*, and describes it by the Figure Y, yet how far short both of them come of the truth, may be somewhat perceiv'd by the draught, which I have here added of it, in the Figure Z, (which I drew by a thirty foot Glass, in *October* 1664. just before the Moon was half inlightned) but much better by the Reader's diligently observing it himself, at a convenient time, with a Glass of that length, and much better yet with one of threescore foot long; for through these it appears a very spacious Vale, incompassed with a ridge of Hills, not very high in comparison of many other in the Moon, nor yet very steep. The Vale it self ABCD, is much of the figure of a Pear, and from several appearances of it, seems to be some very fruitful place, that is, to have its surface all covered over with some kinds of vegetable substances; for in all positions of the light on it, it seems to give a much fainter reflection then the more barren tops of the incompassing Hills, and those a much fainter then divers other cragged, chalky, or rocky Mountains of the Moon. So that I am not unapt to think, that the Vale may have

Vegetables

Vegetables *analogus* to our Grass, Shrubs, and Trees; and most of these incompassing Hills may be covered with so thin a vegetable Coat, as we may observe the Hills with us to be, such as the short Sheep pasture which covers the Hills of *Salisbury* Plains.

Up and down in several parts of this place here describ'd (as there are multitudes in other places all over the surface of the Moon) may be perceived several kinds of pits, which are shap'd almost like a dish, some bigger, some less, some shallower, some deeper, that is, they seem to be a hollow *Hemisphere*, incompassed with a round rising bank, as if the substance in the middle had been digg'd up, and thrown on either side. These seem to me to have been the effects of some motions within the body of the Moon, *analogus* to our Earthquakes, by the eruption of which, as it has thrown up a brim, or ridge, round about, higher then the Ambient surface of the Moon, so has it left a hole, or depression, in the middle, proportionably lower; divers places resembling some of these, I have observ'd here in *England*, on the tops of some Hills, which might have been caus'd by some Earthquake in the younger dayes of the world. But that which does most incline me to this belief, is, first, the generality and diversity of the Magnitude of these pits all over the body of the Moon. Next, the two experimental wayes, by which I have made a representation of them.

The first was with a very soft and well temper'd mixture of Tobacco-pipe clay and Water, into which, if I let fall any heavy body, as a Bullet, it would throw up the mixture round the place, which for a while would make a representation, not unlike these of the Moon; but considering the state and condition of the Moon, there seems not any probability to imagine, that it should proceed from any cause *analogus* to this; for it would be difficult to imagine whence those bodies should come; and next, how the substance of the Moon should be so soft; but if a Bubble be blown under the surface of it, and suffer'd to rise, and break; or if a Bullet, or other body, sunk in it, be pull'd out from it, these departing bodies leave an impression on the surface of the mixture, exactly like these of the Moon, save that these also quickly subside and vanish. But the second, and most notable, representation was, what I observ'd in a pot of boyling Alabaster, for there that powder being by the eruption of vapours reduc'd to a kind of fluid consistence, if, whil'st it boyls, it be gently remov'd besides the fire, the Alabaster presently ceasing to boyl, the whole surface, especially that where some of the last Bubbles have risen, will appear all over covered with small pits, exactly shap'd like these of the Moon, and by holding a lighted Candle in a large dark Room, in divers positions to this surface, you may exactly represent all the *Phænomena* of these pits in the Moon, according as they are more or less inlightned by the Sun.

And that there may have been in the Moon some such motion as this, which may have made these pits, will seem the more probable, if we suppose it like our Earth, for the Earthquakes here with us seem to proceed from some such cause, as the boyling of the pot of Ala-

baſter, there ſeeming to be generated in the Earth from ſome ſubterraneous fires, or heat, great quantities of vapours, that is, of expanded aerial ſubſtances, which not preſently finding a paſſage through the ambient parts of the Earth, do, as they are increaſed by the ſupplying and generating principles, and thereby (having not ſufficient room to expand themſelves) extreamly condens'd, at laſt overpower, with their *elaſtick* properties, the reſiſtence of the incompaſſing Earth, and lifting it up, or cleaving it, and ſo ſhattering of the parts of the Earth above it, do at length, where they find the parts of the Earth above them more looſe, make their way upwards, and carrying a great part of the Earth before them, not only raiſe a ſmall brim round about the place, out of which they break; but for the moſt part conſiderable high Hills and Mountains, and when they break from under the Sea, divers times, mountainous Iſlands; this ſeems confirm'd by the *Vulcans* in ſeveral places of the Earth, the mouths of which, for the moſt part, are incompaſſed with a Hill of a conſiderable height, and the tops of thoſe Hills, or Mountains, are uſually ſhap'd very much like theſe pits, or diſhes, of the Moon: Inſtances of this we have in the deſcriptions of *Ætna* in *Sicily*, of *Hecla* in *Iceland*, of *Tenerif* in the *Canaries*, of the ſeveral *Vulcans* in *New-Spain*, deſcrib'd by *Gage*, and more eſpecially in the eruption of late years in one of the *Canary* Iſlands. In all of which there is not only a conſiderable high Hill raiſed about the mouth of the *Vulcan*, but, like the ſpots of the Moon, the top of thoſe Hills are like a diſh, or baſon. And indeed, if one attentively conſider the nature of the thing, one may find ſufficient reaſon to judge, that it cannot be otherwiſe; for theſe eruptions, whether of fire, or ſmoak, alwayes rayſing great quantities of Earth before them, muſt neceſſarily, by the fall of thoſe parts on either ſide, raiſe very conſiderable heaps.

Now, both from the figures of them, and from ſeveral other circumſtances; theſe pits in the Moon ſeem to have been generated much after the ſame manner that the holes in Alabaſter, and the *Vulcans* of the Earth are made. For firſt, it is not improbable, but that the ſubſtance of the Moon may be very much like that of our Earth, that is, may conſiſt of an earthy, ſandy, or rocky ſubſtance, in ſeveral of its ſuperficial parts, which parts being agitated, undermin'd, or heav'd up, by eruptions of vapours, may naturally be thrown into the ſame kind of figured holes, as the ſmall duſt, or powder of Alabaſter. Next, it is not improbable, but that there may be generated, within the body of the Moon, divers ſuch kind of internal fires and heats, as may produce ſuch Exhalations; for ſince we can plainly enough diſcover with a *Teleſcope*, that there are multitudes of ſuch kind of eruptions in the body of the Sun it ſelf, which is accounted the moſt noble Ætherial body, certainly we need not be much ſcandaliz'd at ſuch kind of alterations, or corruptions, in the body of this lower and leſs conſiderable part of the univerſe, the Moon, which is only ſecundary, or attendant, on the bigger, and more conſiderable body of the Earth. Thirdly, 'tis not unlikely, but that ſuppoſing ſuch a ſandy or mouldring ſubſtance to be

Schem: XXXVIII

Pleiades. p. 245.

Fig: 21



Stellarum magnitudines



Fig: X



Fig: Y.

be there found, and supposing also a possibility of the generation of the internal *elastical* body (whether you will call it air or vapours) 'tis not unlikely, I say, but that there is in the Moon a principle of gravitation, such as in the Earth. And to make this probable, I think, we need no better Argument, then the roundness, or globular Figure of the body of the Moon it self, which we may perceive very plainly by the *Telescope*, to be (bating the small inequality of the Hills and Vales in it, which are all of them likewise shap'd, or levelled, as it were, to answer to the center of the Moons body) perfectly of a Sphærical figure, that is, all the parts of it are so rang'd (bating the comparitively small ruggedness of the Hills and Dales) that the outmost bounds of them are equally distant from the Center of the Moon, and consequently, it is exceedingly probable also, that they are equidistant from the Center of gravitation; and indeed, the figure of the superficial parts of the Moon are so exactly shap'd, according as they should be, supposing it had a gravitating principle as the Earth has, that even the figure of those parts themselves is of sufficient efficacy to make the gravitation, and the other two suppositions probable: so that the other suppositions may be rather prov'd by this considerable Circumstance, or Observation, then this suppos'd Explication can by them; for he that shall attentively observe with an excellent *Telescope*, how all the Circumstances, notable in the shape of the superficial parts, are, as it were, exactly adapted to suit with such a principle, will, if he well considers the usual method of Nature in its other proceedings, find abundant argument to believe it to have really there also such a principle; for I could never observe, among all the mountainous or prominent parts of the Moon (whereof there is a huge variety) that any one part of it was plac'd in such a manner, that if there should be a gravitating, or attracting principle in the body of the Moon, it would make that part to fall, or be mov'd out of its visible posture. Next, the shape and position of the parts is such, that they all seem put into those very shapes they are in by a gravitating power: For first, there are but very few clifts, or very steep declivities in the ascent of these Mountains; for besides those Mountains, which are by *Hevelius* call'd the *Apennine* Mountains, and some other, which seem to border on the Seas of the Moon, and those only upon one side, as is common also in those Hills that are here on the Earth; there are very few that seem to have very steep ascents, but, for the most part, they are made very round, and much resemble the make of the Hills and Mountains also of the Earth; this may be partly perceived by the Hills incompassing this Vale, which I have here describ'd; and as on the Earth also, the middlemost of these Hills seems the highest, so is it obvious also, through a good *Telescope*, in those of the Moon; the Vales also in many are much shap'd like those of the Earth, and I am apt to think, that could we look upon the Earth from the Moon, with a good *Telescope*, we might easily enough perceive its surface to be very much like that of the Moon.

Now whereas in this small draught, (as there would be multitudes if the whole Moon were drawn after this manner) there are several little

Ebullitions,

Ebullitions, or Dishes, even in the Vales themselves, and in the incompassing Hills also; this will, from this supposition, (which I have, I think, upon very good reason taken) be exceeding easily explicable; for, as I have several times also observ'd, in the surface of Alabaster so ordered, as I before describ'd, so may the later eruptions of vapours be even in the middle, or on the edges of the former; and other succeeding these also in time may be in the middle or edges of these, *&c.* of which there are Instances enough in divers parts of the body of the Moon, and by a boyling pot of Alabaster will be sufficiently exemplifi'd.

To conclude therefore, it being very probable, that the Moon has a principle of gravitation, it affords an excellent distinguishing Instance in the search after the cause of gravitation, or attraction, to hint, that it does not depend upon the diurnal or turbinated motion of the Earth, as some have somewhat inconsiderately supposed and affirmed it to do; for if the Moon has an attractive principle, whereby it is not only shap'd round, but does firmly contain and hold all its parts united, though many of them seem as loose as the sand on the Earth, and that the Moon is not mov'd about its Center; then certainly the turbination cannot be the cause of the attraction of the Earth; and therefore some other principle must be thought of, that will agree with all the secundary as well as primary Planets. But this, I confess, is but a probability, and not a demonstration, which (from any Observation yet made) it seems hardly capable of, though how successful future indeavours (promoted by the meliorating of Glasses, and observing particular circumstances) may be in this, or any other, kind, must be with patience expected.

FINIS.

THE TABLE.

Pag.

1 Obſervat. 1. Of the point of a Needle.

2 A *Deſcription of it: what other Bodies have the ſharpeſt points: of the ruggedneſs of poliſht Metal. A*
3 *deſcription of a printed point. Of very ſmall writing, and the uſe of it for ſecret intelligence: the cauſe of the courſneſs of printed lines and points.*

4 Obſerv. 2. Of the Edge of a Razor.

A deſcription of it: the cauſes of
5 *its roughneſs: of the roughneſs of very well poliſht Optick Glaſſes.*

Obſer. 3. Of fine Lawn.

A deſcription of it: A ſilken Flax mention'd, an attempt to explicate the
6 Phænomena *of it, with a conjecture at the cauſe of the gloſs of Silk.*

Obſerv. 4.. Of Tabby.

A ſhort deſcription of it. A conje-
7 *cture about the reaſon why Silk is ſo ſuſceptible of vivid colours: and why Flax and Hair is not. A conjecture, that it may perhaps be poſſible to ſpin a kind of artificial Silk out of ſome glutinous ſubſtance that may equalize natural Silk.*

8 Obſerv. 5. Of water'd Silks.

The great unaccurateneſs of artifi-
cial works. A deſcription of a piece of
9 *water'd Silk; an Explication of the cauſe of the* Phænomena: *the way by which that operation is perform'd: ſome other* Phænomena *mention'd* 10
depending on the ſame cauſe.

Obſerv. 6. Of Glaſs-Canes.

The exceeding ſmalneſs of ſome of
theſe Bodies. By what means the hol-
lowneſs of theſe ſmall pipes was diſco-
ver'd: ſeveral Phænomena *of it men-* 11
tion'd. An attempt to explicate them
from the congruity and incongruity of 12
Bodies: what thoſe proprieties are. A 13
hypothetical explication of fluidity: of
the fluidity of the air, and ſeveral other 14
Phænomena *of it: of congruity & in-* 15
congruity; illuſtrated with ſeveral Ex- 16
periments: what effects may be aſcrib'd 17
to theſe properties: an explication of 18
the roundneſs of the ſurface of fluid
Bodies: how the ingreſs of fluid bodies 19
into a ſmall hole of an heterogenious 20
body is hindred by incongruity; a
multitude of Phænomena *explicable* 21
hereby. Several Quaries propounded;
1. Concerning the propagation of light
through differing mediums. 2. Con- 22
cerning Gravity. 3. Concerning the
roundneſs of the Sun, Moon, and Pla-
nets. 4. Concerning the roundneſs of
Fruits, Stones, and divers artificial
Bodies. His Highneſs Prince Rupert's 23
way of making Shot. Of the roundneſs 24
of Hail. Of the grain of Kettering
Stone, and of the Sparks of fire. 5. Con- 25
cerning ſpringineſs and tenacity.
6. Concerning the original of Foun- 26
tains; ſeveral Hiſtories and Experi-
ments relating thereto. 7. Concerning 27
the diſſolution of Bodies in Liquors.
8. Concerning the univerſality of this 28
Principle: what method was taken in
making and applying experiments. The

explication

explication of filtration, and several
29 *other* Phænomena; *such as the motion of Bodies on the surface of Liquors; se-*
30 *veral Experiments mention'd to this purpose. Of the height to which the water may rise in these Pipes; and a conje-*
31 *cture about the juices of Vegetables, & the use of their pores. A further explication of Congruity: And an attempt of solving the* Phænomena *of the strange Experiment of the suspension of the*
32 Mercury *at a much greater height then thirty inches. The efficacy of immediate contact, and the reason of it.*

33 Observ. 7. Of Glass drops.

Several Experiments made with
34 *these small Bodies. The manner of the breaking and flawing of them, expli-*
35 *cated by Figures. What other bodies will be flawed much in the same manner: some other tryals, and a description of the Drops themselves: some conjectures at the cause of the* Phænomena, *indeavoured to be made pro-*
36 *bable by several Arguments and Experiments. An Experiment of the expansion of Water by heat, and shrinking by cold: the like Proprieties suppos'd in*
37 *Glass drops, and what effects proceed from them: the seven Propositions on which the conjectures are grounded. Experiments to shew, that bodies ex-*
38 *pand by heat. The manner of making* Thermometers, *and the Instrument*
39 *for* graduating *them. The manner of* graduating *them, and their use: Other Experiments to prove the expan-*
40 *sion of bodies by heat. Four experimental Arguments to prove the expansion*
41 *of Glass by heat: further prov'd by the Experiment of boyling Alabaster; which is explicated. An explication of the contracting of heated Glass up-*
42 *on cooling. An explication how the parts of the Glass become bent by sudden cold, and how kept from extricating themselves by the contignation of the Glass drop; which is further explicated by another Experiment made with a hollow Glass ball: the reason of* 43
the flying asunder of the parts further explicated: that 'tis probable these bodies may have many flaws, though not visible, and why: how a gradual heating and cooling does put the parts of 44
Glass, and other hardned bodies, into a looser texture.

Observ. 8. Of Fiery Sparks.

The occasion and manner of making this Experiment: divers Observations set down in order to the find- 45
ing out the reasons: some conjectures concerning it, which are endeavoured to be explicated and confirm'd by several Experiments and Reasons: the 46
Hypothesis *a little further explicated. Some Observations about the* 47
Globular Figure: and an Experiment of reducing the filings of Tin or Lead to exactly round Globules.

Observ. 9. Of Fantastical Colours.

The texture of Muscovy *Glass; its Figures: what other Bodies are like it:* 48
that it exhibits several colours, and how: several Observations and Experiments about those colours: the reason why on this occasion the nature of co- 49
lours is inquir'd into. A conjecture at the reason of these colours explicated 50
by several Experiments and Reasons: First, by continual cleaving the Body, till it become colour'd. Secondly, by producing all kinds of colours with two flat Plates of Glass. Thirdly, by blowing Glass so thin in the Lamp, till it produce the same effect. Fourthly, by 51
doing the same with Bubbles of divers other transparent Bodies: the reasons of the colours on nealed Steel, where by the way the causes of the 52
hardning

52 *hardning and tempering of Steel, endeavour'd to be shewn and explicated by several Reasons and Experiments: the reason of the colours on*
53 *Lead, Brass, Copper, Silver,* &c. *other Instances of such colour'd bodies in animal substances: several other distinguishing Observations.* Des Cartes
54 Hypothesis *of Colours examin'd. An* Hypothesis *for the explication of light by motion, indeavoured to be explicated and determined by seve-*
55 *ral Reasons and Experiments: three distinguishing Properties of the moti-*
56 *on of light. The distinguishing Properties of a trasparent* Medium [*that there seems to be no Experiment that proves the Instantaneous motion of*
57 *light*] *the manner of the propagation of light through them. Of the* homogeniety *and* heterogeniety *of transparent* Mediums, *and what effects they cause on the Rayes of light, explicated by a Figure: an Exami-*
58 *nation of the refraction of the Rays by a plain Surface, which causes Colours. An Examination of the like ef-*
59 *fects produced by a spherical Surface: the use that may be made of these Experiments, for the examination of several* Hypotheses *of Colours.* Des
60 Cartes Hypothesis *examin'd. Some*
61 *Difficulties taken notice of in it. What seems most likely to be the cause of colour: that propriety is indeavoured*
92 *to be shewn in a Glass ball: that the reflection is not necessary to produce*
63 *Colours nor a double refraction: the* Hypothesis *further examined, both in*
64 *the* pellucid Medium *and in the Eye. The definitions of Colours; and a fur-*
65 *ther explication and examination of*
66 *the Proprieties of* laminated *Bodies;*
67 *by what means they conduce to the production of Colours.*

Observ. 10. Of Metalline Colours.

68 *That all Colours seem to be caus'd by refraction. An* Hypothesis *consonant hereunto, explicated by Figures. How* 69
several Experiments, of the sudden changing of Colours by Chymical Li-
quors, may be hereby explicated: how 70
many wayes such Chymical Liquors may alter the colours of Bodies. Objections made against this Hypo- 71
thesis *of two colours only, indeavour-*
ed to be answer'd, by several Reasons and Experiments. The reason why 72
some Colours are capable of being di-
luted, others not: what those are: that probably the particles of most metal-
line Colours are transparent; for this several Arguments and Observations are recited: how Colours become in- 73
capable of diluting, explicated by a Similitude. An Instrument, by which 74
one and the same coloured Liquor at once exhibited all the degrees of co-
lours between the palest yellow and deepest red: as likewise another that exhibited all varieties of blues: se-
veral Experiments try'd with these Boxes. An Objection drawn from the 75
nature of Painters colours answered: that diluting and whitening a colour are different operations; as are deepening and blackening: why some may be diluted by grinding, and some other by being tempered with Oyl:
several Experiments for the explica- 76
ting of some former Assertions: why 77
Painters are forced to make use of many colours: what those colours are: and how mixt. The conclusion, that 78
most coloured Bodies seem to consist of transparent particles: that all co- 79
lours dissoluble in Liquors are capable of diluting: some of mixing, what a strange variety may thereby be produc'd.

Observ. 11. Of the Figures of Sand.

Of the substances and shapes of 80
common

common and other Sands: a description of a very small Shell.

81 Observ. 12. Of Gravel in Urine.

A description of such Gravel, and
82 *some tryals made with it, and conjectures at its cause.*

Obser. 13. Of Diamonds in Flints.

A description and examination of some of them, explicated further by
83 *Cornish Diamonds: several Observations about reflection and refraction: and some deductions therefrom; as an explication of whiteness; that the Air has a stronger reflection then Wa-*
84 *ter. How several Bodies may be made transparent: an explication of the*
85 Phænomena *of* Oculus Mundi. *Of the regular Geometrical Figures of*
86 *several Bodies: an hypothetical expli-*
87 *cation mentioned: the method of prosecuting this inquiry.*

88 Observ 14. Of frozen Figur e.

The Figures of hoar Frost, and the
89 *Vortices on windows: several Observations on the branched Figures of*
90 *Urine: the Figures of* Regulus Mar-
91 tis stellatus, *and of Fern. Of the Fi-*
92 *gures of Snow. Of frozen water.*

Observ. 15. Of Kettering Stone.

93 *A description of the Figure of the*
94 *Particles, and of the Pores, and of the*
95 *Contexture. Several Observations and*
96 *Considerations thereupon: some Conjectures about the* medium *and pro-*
97 *pagation of light, and the constitution of fluid and transparent Bodies. Se-*
98 *veral Experiments to prove the porousness of Marble, and some other Stones. An account of some Experiments to this purpose made on an* Oculus Mundi: *some other Considerations and Experiments about the* 99
porousness of Bodies: some other Con- 100
siderations about the propagation of light and refraction.

Observ. 16. Of Charcoal.

Of two sort of Pores to be found 101
in all Woods and Vegetables; the shape of them; the number, thickness, manner and use of these Pores. An explication of the Phænomena 102
of Coals. The manner of charring Wood, or any other body. What part of Wood is combustible. An Hypo- 103
thesis *of fire explicated in twelve* 104
particulars, wherein the Action of the Air, as a Menstruum, *in the dissolution of all sulphureous bodies, is very particularly explicated, and* 105
some other Considerations about the Air proposed: the examination of a piece of Lignum fossile *sent from* 106
Rome, *and some Conclusions thence deduc'd.*

Observ. 17. Of Wood, and other 107
Bodies, petrified.

Several Observations of divers kinds of these substances. A more par- 108
ticular examination and explication of one very notable piece of petrified Wood; and some Conjectures about the cause of those productions: several Observations made on other 109
petrified Bodies, as Shells, &c. *And* 110
some probable Conclusions thence de- 111
duc'd, about the original cause of 112
those Bodies.

Observ. 18. Of the Pores of Cork, 113
and other Bodies.

Several Observations and Considerations about the nature of Cork: 114
the number of Pores in a cubical Inch,

Inch, and several Considerations about Pores. 115 *Several Experiments and Observations about the nature of Cork: the Texture and Pores of the Pith of an Elder, and several other Trees: of the Stalks of Burdocks, Teasels, Daisies, Carret, Fennel,* 116 *Ferne, Reeds,* &c. *of the frothy texture of the Pith of a Feather: some Conjectures about the probability of values in these Pores. Argued also from the* Phænomena *of the sensible and humble Plant:* 117 *some Observations on which are inserted.* 120

121 Observ. 19. Of a Vegetable growing on blighted Leaves.

122 *Several Observations and Examinations made of them:* 123 *several Considerations about spontaneous* 124 *generation arising from the putrefaction of Bodies.* 125

Observ. 20. Of Blew Mould and Mushromes.

126 *The description of several kinds of Moulds.* 127 *The method of proceeding in natural Inquiries. Several Considerations about the nature of Mould and Mushromes. 1. That they may be produc'd without seed. 2. That they seem to have none. 3. That Salts,* &c. *are shap'd into as curious figures without a seed.* 128 *4. Of a kind of Mushrome growing in a Candle: A more particular explication of this last sort of Mushromes. 5. Of the figure and manner of the production of petrified Icicles:* 129 *several deductions from these Considerations, about the nature of the vegetation of Mould and Mushromes.* 130

131 Observ. 21. Of Moss.

132 *The description of several sorts of Mosses; upon this occasion several Conjectures, about the manner of the production of these kinds of Bodies, are hinted, and some of them explicated by a Similitude taken from a* 133 *piece of Clock-work. The vast difference of the bigness of vegetable Bodies;* 134 *and the probability that the least may comprehend as curious contrivances as the greatest. Of multitudes of other Moulds, Mosses, and* 135 *Mushromes, and other vegetating Principles, in Water, Wood,* &c.

Observ. 22. Of Sponges, and other fibrous Bodies.

Several Observations and Conjectures about the making of these Bodies; 136 *and several Histories out of Authors. Scarce any other Body hath* 137 *such a texture;* 138 *the fibrous texture of Leather, Spunk,* &c. *(which are* 139 *there describ'd) come nearest to it. That upon tryal with a piece of Spunge and Oyl the necessity of respiration could not be alter'd.* 140

Observ. 23. Of the Form of Sea-weed.

From the curiously shap'd Surface of this Sea-weed, and some others, is conjectured the possibility of 141 *multitudes of the like.*

Observ. 24. Of the Surfaces of some Leaves.

The description, 1. Of the bald Surfaces of Leaves. 2. Of the downy Surfaces of several others. 3. Of the gummous exsudation, or small transparent Pearls, discovered 142 *with a* Microscope *in several others. An Instance of all which is afforded in a Rosemary Leaf.*

Observ.

The TABLE.

Obſerv. 25. Of the ſtinging Points of a Nettle.

143 *A deſcription of the Needles and ſeveral other contrivances in the leaf*
144 *of a Nettle: how the ſtinging pain is created: upon this ſeveral conſiderations about poyſoning Darts are ſet down. An Experiment of killing Effs, and Fiſhes with Salt. Some conjectures at the efficacy of Baths; the uſe that may be made of injecting into the*
145 *Veins. A very remarkable Hiſtory out of* Bellonius; *and ſome Conſiderations about ſtaining and dying of Bodies.*

Obſerv. 26. Of Cowage.

The deſcription of it out of Parkin-
146 ſon: *an Experiment made of it: a deſcription, and ſome conjectures at the cauſe of the* Phænomena.

Obſerv. 27. Of the Beard of a wild Oat.

147
148 *The deſcription of its ſhape and*
149 *properties: the manner of making a*
150 Hygroſcope *with it; and a Conje-*
151 *cture at the cauſes of theſe motions,*
152 *and of the motions of the Muſcles.*

Obſerv. 28. Of the Seeds of *Venice* Looking-glaſs.

153 *The deſcription of them.*

Obſer. 29. Of the Seeds of Time.

154 *A deſcription of them. A digreſſion about Natures method.*

Obſerv. 30. Of Poppy Seeds.

155 *The deſcription and uſe of them.*

Obſerv. 31. Of Purſlane Seeds. 156

A deſcription of theſe and many other Seeds.

Obſerv. 32. Of Hair. 157

The deſcription of ſeveral ſorts of 158
Hair; their Figures and Textures:
the reaſon of their colours, A deſcripti- 159
on of the texture of the ſkin, and of 160
Spunk and Sponges: by what paſ- 161
ſages and pores of the ſkin tranſpiration ſeems to be made. Experiments to prove the porouſneſs of the ſkin of Vegetables.

Obſerv. 33. Of the Scales of a Soale. 162

A deſcription of their beauteous form.

Obſerv. 34. Of the Sting of a Bee. 163

A deſcription of its ſhape, mecha- 164
niſme, and uſe.

Obſerv. 35. Of Feathers. 165
166
A deſcription of the ſhape and cu- 167
rious contexture of Feathers: and ſome conjectures thereupon.

Obſer. 36. Of Peacocks Feathers.

A deſcription of their curious form 168
and proprieties; with a conjecture at 169
the cauſe of their variable colours.

Obſer. 37. Of the Feet of Flyes, and other Inſects.

A deſcription of their figure, parts, 170
and uſe; and ſome conſiderations 171
thereupon.

Obſerv.

172 Obser. 38. Of the Wings of Flyes.

After what manner, and how swiftly the wings of Insects move. A description of the Pendulums under the wings; and their motion: the shape and structure of the parts of the wing. 173 174

175 Obser. 39. Of the Head of a Fly.

1. All the face of a Drone-fly is nothing almost but eyes. 2. Those are of two magnitudes. 3. They are Hemispheres, and very reflective and smooth. 4. Some directed towards every quarter. 5. How the Fly cleanses them. 6. Their number. 7. Their order: divers particulars observ'd in the dissecting a head. That these are very probably the eyes of the Creature; argued from several Observations and Experiments, that Crabs, Lobsters, Shrimps, seem to be water Insects, and to be framed much like Air Insects. Several Considerations about their manner of vision. 176 177 178 179 180

Obser. 40. Of the Teeth of a Snail.

181 *A brief description of it.*

Observ. 41. Of the Eggs of Silk-worms.

182 *Several Observables about the Eggs of Insects.*

183 Observ. 42. Of a blue Fly.

184 *A description of its outward and inward parts. Its hardiness to indure freezing, and steeping in Spirit of wine.* 185

Observ. 43. Of a water Insect.

186 *A description of its shape, transparency, motion, both internal and progressive; and transformation. A History somewhat* Analogus *cited out of* Piso. *Several Observations about the various wayes of the generations of Insects: by what means they act so seemingly wisely and prudently. Several Queries propounded. Postscript, containing a relation of another very odd way of the generation of Insects. An Observation about the fertility of the Earth of our Climate in producing Insects, and of divers other wayes of their generation.* 187 188 189 190 191 192 193

Observ. 44. Of the tufted Gnat.

Several Observables about Insects, and a more particular description of the parts of this Gnat. 194

Ob. 45. Of the great belly'd Gnat. 195

A short description of it.

Obser. 46. Of a white Moth.

A description of the feathers and wings of this, and several other Insects. Divers Considerations about the wings, and the flying of Insects and Birds. 196 197 198

Obs. 47. Of the Shepherd Spider.

A description of its Eyes: and the sockets of its long legs: and a Conjecture of the mechanical reason of its fabrick; together with a supposition, that 'tis not unlikely, but Spiders may have the make of their inward parts exactly like a Crab, which may be call'd a water Spider. 199 200

Obser. 48. Of the hunting Spider.

A short description of it: to which is annext an excellent History of it, made by Mr. Evelyn. *Some further* 201

202 *Observations on other Spiders, and their Webs, together with an examination of a white Substance flying up and down in the Air after a Fog.*

Obser. 49. Of an Ant.

203 *That all small Bodies, both Vegetable and Animal, do quickly dry and wither. The best remedy I found to hinder it, and to make the Animal lye still*
204 *to be observ'd. Several particulars related of the actions of this Creature;*
205 *and a short description of its parts.*

Obs. 50. Of the wandring Mite.

206 *A description of this Creature, and of another very small one, which usu-*
207 *ally bore it company. A Conjecture at the original of Mites.*

Observ. 51. Of a Crab-like Insect.

208 *A brief description of it.*

Observ. 52. Of a Book-worm.

209 *A description of it; where by the way is inserted a digression, experimentally explicating the* Phænome-
210 na *of Pearl. A consideration of its digestive faculty.*

Observ. 53. Of a Flea.

211 *A short description of it.*

Observ. 54. Of a Louse.

212 *A description of its parts, and some*
213 *notable circumstances.*

Observ. 55. Of Mites.

The exceeding smalness of some Mites, and their Eggs. A description
214 *of the Mites of Cheese: and an intimation of the variety of forms in other Mites, with a Conjecture at the Ca-* 215
son.

Ob. 56. Of small Vine-Mites.

A description of them; a ghess at their original; their exceeding smal-
ness compar'd with that of a Wood- 216
louse, from which they may be suppos'd to come.

Observ. 57. Of Vinegar-worms.

A description of them, with some 217
considerations on their motions.

Obs. 58. Of the Inflection of the Rays of Light in the Air.

A short rehearsal of several Phæ- 218
nomena. *An attempt to explicate* 219
them: the supposition founded on two Propositions, both which are indeavoured to be made out by several Experiments. What density and rarity is in respect of refraction: the refraction of Spirit of Wine compared with that of common Water: the refraction 220
of Ice. An Experiment of making an Undulation of the Rays by the mixing of Liquors of differing density. The explication of inflection, *mechani-* 221
cally and hypothetically: what Bodies have such an inflection. Several Experiments to shew that the Air has this propriety; that it proceeds from 222
the differing density of the Air: that the upper and under part of the Air are of differing density: some Experi- 223
ments to prove this. A Table of the strength of the spring of the Air, an-swering to each degree of extension; when first made, and when repeated. 224
Another Experiment of compressing 225
the Air. A Table of the strength of the 226
Air, answering to each compression and expansion; from which the height

of

227 *of the Air may be suppos'd indefinite;*
228 *to what degree the Air is rarifi'd at any distance above the Surface of the Earth: how, from this, Inflection is*
229 *inferr'd; and several* Phænomena
230 *explain'd. That the Air near the Earth is compos'd of parts of differing*
231 *density; made probable by several*
232 *Experiments and Observations; how this propriety produces the effects of the waving and dancing of Bodies; and of the twinkling of the Stars.*
233 *Several* Phænomena *explicated. Some Queries added.*

1. *Whether this Principle may not be made use of, for perfecting Optick*
234 *Glasses? What might be hoped from it if it were to be done?*

2. *Whether from this Principle the apparition of some new Stars may not be explicated?*

3. *Whether the height of the Air may be defin'd by it?*

4. *Whether there may not sometimes be so great a disparity of density between the upper and under parts of the Air, as to make a reflecting Surface?*

5. *Whether, if so, this will not ex-*
235 *plicate the* Phænomena *of the Clouds. An Experiment to this purpose?*

7. *Whether the Rayes from the*
236 *top of Mountains are not bended into Curve-lines by inflection? An Argument for it, taken from an Experiment made on St.* Paul's *Steeple.*

8. *Whether the distance of the Planets will not be more difficult to*
237 *be found? What wayes are most likely to rectifie the distance of the Moon: the way of fitting* Telescopes *for such Observations. How to make the*
238 *Observations, and how from them to find the true distance of the Moon at any time. How the distance of the Sun may be found by two Observators. The*
739 *way by the Dicotomy of the Moon uncertain. That the distance of the Moon may be less then it has been hitherto suppos'd.* Kepler's *Supposition not so probable: the explication of* 240
the Phænomena *by another* Hypothesis.

Observ. 59. Of the fixt Stars. 241

Of the multitudes of Stars discoverable by the Telescope, *and the variety of their magnitudes: 78. Stars distinguisht in the* Pleiades: *that there are degrees of bigness even in the Stars accounted of the same magnitude: the longer the Glasses are, and the bigger apertures they will indure, the more fit they are for these discoveries: that 'tis probable, longer Glasses would yet make greater discoveries. 5. Stars* 242
discover'd in the Galaxie *of* Orion's *Sword.*

Observ. 60. Of the Moon.

A description of a Vale in the Moon; what call'd by Hevelius *and* Ricciolus, *and how describ'd by them: with what substances the hills of the* 243
Moon may be cover'd. A description of the pits of the Moon, and a conjecture at their cause: two Experiments that make it probable, that of the surface of boyl'd Alabaster dust seeming 244
the most likely to be resembled by eruptions of vapours out of the body of the Moon: that Earthquakes seem to be generated much the same way, and their effects seem very similar. An Argument that there may be such variations in the Moon, because greater have been observ'd in the Sun: because 245
the substance of the Moon and Earth seem much alike: and because 'tis probable the Moon has a gravitating principle: this is argued from several particulars. The reason why several 246
pits are one within another. The use that may be made of this Instance of a gravity in the Moon.

ERRATA.

ERRATA.

IN the Preface, Page 7. line 18. read *feet* : line 24. read *Gilbert*, *Harvy*.

Page 13. line ult. read *taste* : p. 34. l. 18. r. *small lens* : l. penult. r. *that proceeds from* : p. 40. l. 44. r. *when you*: p. 48. l. 34. r. *broadest*: p. 57. l. 39. dele *be*: p. 62. l. 36. r. *water-drop* : p. 64. l. 9. r. *duction of G A C H* : l. 35. r. *impressions* : p. 96. l. 33. r. *compose* : p. 100. l. 11. r. *Mersennus* : p. 106. l. 8. r. *extreamly* : p. 110. l. 8. r. *as* : l. 12. r. *those* : p. 112. l. 32. r. *Aldronandus*, *Wormius* : p. 121. l. 9. dele *of* : p. 128. l. 43, dele *from*: p. 129. l. 18. r. *fifth place* : p. 130. l. 29. r. *Aerial menstruum* : p. 136. l. 39. r. *knew how* : p. 144. l. 2. r. *parts of the* : p. 147. l. 36. r. *look'd on* : p. 161. l. 13. r. *body* : p. 162. l. 17. dele *only* : p. 166. l. 11. r. 22 : l. 12. dele the Semicolon : l. 27. r. *place* : p. 167. l. 40. r. 22 ; p. 172. l. 18. r. *and first for the* : p. 198. l. 17. r. *and an artific.* p. 215. l. ult. r. *and from the* : p. 221. l. 4. r. *whence the under* : p. 234. l. 18. r. *to hope* : p. 238. l. 42. r. *is not less* : p. 240. l. 19. r. *Moon*.